

PRICE BID

Name of Work : Misc. Civil & Repair Works at BHEL Township in Sector-17, Noida.

NIT No. : NIT No.26: AA: NOI: ADMN: MCR Works: 112: 2016-17 Date: 02.11.2016

S. No.	Description of Item	Unit	Qty.	DSR 2014 Rate	Amount (Rs)
(1)	(2)	(3)	(4)	(5)	(6)=(5)X(4)
1	<i>Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.</i>	<i>sqm</i>	<i>1000.00</i>	<i>20.05</i>	<i>20050.00</i>
2	<i>Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.</i>	<i>cum</i>	<i>2.50</i>	<i>1302.30</i>	<i>3255.75</i>
3	<i>Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, Chajjas, lintels, bands, plain window sills, staircases and spiral stair cases up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:2:4 (1cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size).</i>	<i>cum</i>	<i>2.50</i>	<i>6778.20</i>	<i>16945.50</i>
4	<i>Centering and shuttering including strutting, propping etc. and removal of form for suspended floors, roofs, landings, balconies and access platform</i>	<i>sqm</i>	<i>10.00</i>	<i>401.65</i>	<i>4016.50</i>
5	<i>Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level -Thermo-Mechanically Treated bars</i>	<i>Kg</i>	<i>1000.00</i>	<i>68.10</i>	<i>68100.00</i>

6	<p>Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after .The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge .The elevational area of the scaffolding shall be measured for payment purpose .The payment will be made once irrespective of duration of scaffolding. Note: - This item to be used for maintenance work judiciously, necessary deduction for scaffolding in the existing item to be done.</p>	sqm	50.00	159.9	7995.00
7	<p>Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground within 50 metres lead : With cement mortar 1:4 (1cement: 4 coarse sand)</p>	Sqm	2000.00	259.15	518300.00
8	<p>Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.</p>	sqm	1500.00	89.65	134475.00
9	<p>Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : Old work (one or more coats)</p>	sqm	2000.00	32.00	64000.00

10	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade, two or more coats on new work.	sqm	100.00	74.40	7440.00
11	Carriage of material by mechanical transport including loading, unloading and stacking Lime, moorum, building rubbish upto 5 Km.	cum	100.00	122.46	12246.00
12	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in- charge. 15.2.1 Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix	cum	25.00	892.70	22317.50
13	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed :	100 sqm	2	5044.15	10088.30
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size	cum	20	5466.3	109326
15	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size	cum	40.00	4301.15	172046.00
16	Dry brick pitching half brick thick in drains including supply of bricks and preparing the surface complete with common burnt clay F.P.S. (non modular) bricks of class designation 7.5	sqm	200.00	438.40	87680.00
17	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	25.00	4677.25	116931.25

18	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design. With common burnt clay F.P.S. (non-modular) bricks of class designation 7.5	each	100.00	1571.25	157125.00
19	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	Kg	2000.00	73.95	147900.00
20	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	sqm	500.00	602.20	301100.00
21	Total Estimated Amount (inclusive of all excluding Service Tax) in Rs.				1981337.80
22	Percentage Above (+)/Below (-) / at par with S.No. 21				
23	Total Quoted Amount after applying percentage (S.No. 22) (inclusive of all excluding Service Tax) in Rs.				
24 a	In case, as per the current status the party (service provider) is an Individual, HUF, or partnership firm including AOP	Service Tax (on 70 % of total quoted amount of S. No. 23) to be payable by party (.....%) (Rs)			
24 b		Service Tax (on 70 % of total quoted amount of S. No. 23) to be payable by BHEL (.....%) (Rs)			
25	In case, as per the current status the party is a Private or Public limited Company	Service Tax (on 70 % of total quoted amount of S. No. 23) to be payable by party (.....%) (Rs)			
26	Total Amount inclusive of Service Tax	In case of Individual, HUF, or partnership firm including AOP (Total of 23+24 a+24 b) (Rs)			
		In case of Private or Public limited Company (Total of 23+25) (Rs)			
Total Offer Value in Words : Rupees					



उज्ज्वल तोमर

अभियंता (भा. सं.- टीएफएस)

Ujjwal Tomar

Engineer (HR-TAX)

(Signature & seal of the contractor)