

!



भारत हेवी इलेक्ट्रिकल्स लिमिटेड

(भारत सरकार का उपक्रम)

Bharat Heavy Electricals Limited

(A Govt. Of India Undertaking)

**CENTRALISED STAMPING UNIT & FABRICATION PLANT
INDUSTRIAL AREA, JAGDISHPUR, DISTRICT- AMETHI (UP)**

Phone: 05361-224128, FAX: 05361-224166

TENDER ENQUIRY

TENDER FOR FENCING WORKS AT CSU BHEL JAGIDSHPUR

Tender Enquiry No: BHE/CSU/CVL/16-17/08

SECTION-III

BILL OF QUANTITIES & PRICE SCHEDULE

भारत हेवी इलेक्ट्रिकल्स लिमिटेड

(भारत सरकार का उपक्रम)

सीएसयू एवं एफ़पी जगदीशपुर, जनपद- अमेठी

SECTION-III



TE. No. BHE/CSU/CVL/16-17/08

SECTION-III: BOQ & PRICE SHEDULE FOR FENCING WORKS AT CSU JAGDISHPUR

S. No.	DESCRIPTION OF WORK	UNIT	QTY.	Rate Quoted (Rs.)		Quoted Amount (Rs.)
				In Figures	In words	
1	Peroviding and fixing Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earth work and concrete work to be paid for separately) With G.I. barbed wire	RM	693.00			
2	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately).	RM	850.00			
3	Earthwork in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 Sqm on plain) including dressing of sides and ramming of bottom, lift up to 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50m. All kinds of soil	Cum	1.88			
4	Supplinying and filling in plinth with jamuna sand including watering, raming consolidating, dressing complete	Cum	0.38			

भारत हेवी इलेक्ट्रिकल्स लिमिटेड

(भारत सरकार का उपक्रम)

सीएसयू एवं एफ़पी जगदीशपुर, जनपद- अमेठी

SECTION-III



TE. No. BHE/CSU/CVL/16-17/08

SECTION-III: BOQ & PRICE SHEDULE FOR FENCING WORKS AT CSU JAGDISHPUR

S. No.	DESCRIPTION OF WORK	UNIT	QTY.	Rate Quoted (Rs.)		Quoted Amount (Rs.)
				In Figures	In words	
5	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work up to plinth level 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size).	Cum	0.38			
6	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. up to floor five level, excluding cost of centering, shuttering, finishing and reinforcement :size).1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm nominal size)	Cum	1.88			
7	Centring and shuttering including strutting, propping etc. and removal of form work for Lintels, beams, plinth beams, girders, bressumers and cantilevers.	Sqm	15.00			
8	Providing and Fixing Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg	112.50			
9	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. All kinds of soil.	Sqm	161.00			

Total (Exclusive of Service Tax)=

Note: Service tax shall be paid extra as applicable.

(Sign & Seal of the contractor)