



# TENDER DOCUMENT

(PRICE BID FORMAT)

## PART - B

---

**Name of the work:**

***Works Contract for Acoustic & Aesthetic Works related to SCR***

---



Annexure – II

**Price Bid Format (Part B)**

Name of the work: **Works Contract for Acoustic and Aesthetic Works related to SCR.**

<b>Sl. No.</b>	<b>Item</b>	<b>Unit</b>	<b>Quantity</b>	<b>Percentage allocation</b>
1.00	GLASS WOOL CLADDING: Providing and fixing thermal insulation with Resin Bonded Fibre glass wool having density 24 kg/m <sup>3</sup> , 50 mm thick, wrapped in 200G Virgin Polythene Bags fixed to wall with screw, rawel plug & washers and held in position by criss crossing GI wire etc. complete as per directions of Engineer-in-Charge.	sqm	450	3.23
2.00	ROCK WOOL CLADDING: Providing and fixing thermal insulation with Resin Bonded rock wool conforming to IS: 8183, having density 48 kg/m <sup>3</sup> , 50 mm thick, wrapped in 200 G Virgin Polythene Bags fixed to wall with screw, rawel plug & washers and held in position by criss crossing GI wire etc. complete as per directions of Engineer-in-Charge.	sqm	450	2.89
3.00	PERFORATED STEEL TILES: Supplying and fixing perforated powder coated steel tile with a back sheet of NRC 0.6. Colour of tiles - off white/ ivory and tile thickness 0.5mm, perforation dia. 2.5mm - 16% open space. The cost includes labour, material (GI tiles, back sheet, grid, accessories, screws etc.) complete.	sqm	870	24.07
4.00	WOODEN FLOORING: Providing and fixing Armstrong make wooden flooring Ambience Plus 8mm AC-4, 15 Warranty of size (192mmx1214mmx8mm) or (192mmx1286mmx8mm) or equivalent (after sample approval) Fixed as per specification provided by Engineer In charge including the cost of all materials, labour, transporting etc. complete.	sft.	2098.98	6.97
5.00	75MM SKIRTING FOR WOODEN FLOORING: Providing and fixing Armstrong or equivalent make 75mm width skirting. Fixed as per specification provided by M/s Armstrong including the cost of all materials, labour, transportation etc. complete.	RFT.	367.47	0.81
6.00	50MM DOOR PROFILE FOR WOODEN FLOORING: Providing and fixing Armstrong or equivalent make 50mm wide Door profile. Fixed as per specification provided by M/s Armstrong including the cost of all materials, labour, transportation et complete.	RFT.	31.5	0.07
7.00	METAL SHEET OUTER CLADDING: Supplying and fixing powder coated plain steel tiles 0.5mm thick of assorted colours and size 300mm x 1200mm including cost of all labour, material (Tiles, grid, Accessories screws etc.), transportation etc. complete.	sqm	306	10.45



8.00	METAL SHEET INNER CLADDING: Supplying and fixing powder coated plain steel tiles 0.5mm thick of assorted colours and size 600mm x 600mm including cost of all labour, material (Tiles, grid, Accessories screws etc.), transportation etc complete.	sqm	141	3.78
9.00	PVC LAMINATED GYPSUM TILE FALSE CEILING: Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main T at 600 mm center to center to form a grid of 1200x600 mm and T at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main T runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.	sqm	195	8.32



10.00	ACP CLADDING: Designing, fabricating, testing, installing and fixing in position Curtain Wall with Aluminium Composite Panel Cladding for all heights and all levels etc. including: Providing, fabricating and supplying and fixing panels of aluminium composite panel cladding metallic colour of approved shades made out of 4mm thick aluminium composite panel material consisting of 3mm thick FR grade mineral core sandwiched between two Aluminium sheets (each 0.5mm thick) and shade as per selection of Engineer Incharge. The item includes cost of all material & labour component, the cost of all mock ups at site, including aluminium base frame works. Including filling up joints using silicon sealant of matching pigment. Including the cost of all labour, materials, scaffolding and transportation etc complete.	sqm	131	12.81
11.00	GLASS DOORS: Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double action hydraulic floor spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-incharge (Door handle, lock and stopper etc.to be paid separately).	sqm	15.12	1.53
12.00	GLASS PARTITIONS: Providing and fixing 12 mm thick frameless toughened glass door shutter of approved brand and manufacture, including providing and fixing top & bottom pivot & double action hydraulic floor spring type fixing arrangement and making necessary holes etc. for fixing required door fittings, all complete as per direction of Engineer-incharge (Door handle, lock and stopper etc.to be paid separately).	sqm	128.88	8.62
13.00	Designing supplying and fixing frosted glass stickers to the glass including cost of labor, transportation complete, 3M make or similar	sqm	72.00	1.62



14.00	ALUMINIUM WORKS FOR FIXED PORTIONS: Providing and fixing aluminium work for partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) <b>Powder coated aluminium (minimum thickness of powder coating 50 micron) Wastages will not be measured and paid.</b>	kg	459	4.75
15.00	ALUMINIUM WORKS FOR DOORS, WINDOWS & VENTILATORS: Providing and fixing aluminium work for doors, windows & ventilators including providing and fixing hinges/ pivots and making provisions for fixing of fittings wherever required including with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) Wastages will not be measured and paid.	Kg	196.8	2.44
16.00	12MM THICK PARTICLE BOARD: Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows Shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer in- charge. -- Pre-laminated particle board with decorative lamination on one side and balancing lamination on other side.	sqm	118.8	2.69



17.00	5MM THICK PLAIN GLASS GLAZING: Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. ---With float glass panes of 5 mm thickness of make Saint Gobin or Modi Float(weight not less than 12.50 kg/ sqm).	sqm	79.20	2.33
18.00	OPENING FOR KITCHEN SINK: Providing opening of required size & shape for wash basin/ kitchen sink in working platform, vanity counter and similar location in marble/ Granite/ stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	each	5.00	0.08
19.00	SS KITCHEN WITHOUT DRAIN BOARD: Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required ---Kitchen sink without drain board of size 610x510mm bowl depth 200mm.	each	5.00	0.41
20.00	WARDROBE FRAME & SHUTTERS: Providing and fixing cabinet (Frame & Shutter only) with specifications as mentioned, including cost of labour, material, transportation etc. Frame & Shutters: Made of 19mm BWP grade ply board / block board complying with IS- 710. Laminate: 1mm Texture Wood finish for exterior & 0.8mm frosty white for interior finish. Hardware: Hettich / Haffele / Ebco hinge with 2 hinges on each shutter. Edge Banding: Rehau Germany (2mm for shutter & 0.8mm for caracase, done with mechanized edge bander) Adhesive: Pidilite Fevicol.	sft	86.08	1.64
21.00	Providing and fixing 2mm thick venyl flooring of make, shade and size as approved by Engineer In charge including the cost of all materials, labour, transportation, fixing charges etc. complete.	sqm	90	0.49

Total amount quoted in figures:

Rs. \_\_\_\_\_

Total Amount quoted in words:

Rupees \_\_\_\_\_

Bidder has to quote their Total amount as a whole for carrying out above subject work in the space provided above both in figures and words.

Accordingly, item wise rates will be arrived based on percentage allocation of total amount to each items respectively.

Bidder **should not** quote individual rate for above said items.

Signature of Contractor along with name & address.