

Bharat Heavy Electricals Limited
High Pressure Boiler Plant
Tiruchirappalli – 620 014. India
Civil Engineering Department (Factory)

TENDER DOCUMENT (PRCE BID)

Name of work	:	Repair & Renovation of existing facilities at Puthayiram Poonga Park located in BHEL Township, Kailasapuram, Trichy – 14
Value of work	:	Rs 2.02 Lakhs + Applicable GST
Tender Notice No.	:	CT:TN:005/18-19
Tender Schedule No.	:	CT:TS:017/18-19
Period of Contract	:	01 Month
EMD	:	Rs 4,200.00/-
Issued to	:	

BHARAT HEAVY ELECTRICALS LIMITED
TIRUCHIRAPALLI - 620 014
SCHEDULE - A

Name of Work: : Repair & Renovation of existing facilities at Puthayiram Poonga Park located in BHEL Township, Kailasapuram, Trichy – 14

I / We _____ have read the condition of tender attached hereto and agree to abide by such conditions. I/We offer to execute the works in **T.S No. CT:TS:017/18-19 for a period of 1 Month** at the percentage below / at par / above the rates contained in Bill of Quantities appended **below from Page 03**

I / We further agree to sign an Agreement Bond to abide by the General Conditions of Contract and to carryout all works according to the specifications for materials and works of Bharat Heavy Electricals Limited, Tiruchirapalli-620 014. In case of acceptance of the tender by the BHEL, I/We bind myself/ourselves to execute the contract documents within 7 days after notice that my/our tender has been accepted and this contract has been awarded to me/us and thus failing which I/We shall have no objection to the forfeiture of the Earnest Money amount to **Rs.4,200/-** lodged with Bharat Heavy Electricals Limited, Tiruchirapalli-620 014.

I / We further agree to include all tools & plants and consumables required for the work in my / our scope but required power and water will be provided at one point by BHEL at free of cost and based on this, we have quoted our percentage.

Note: Details & Quantities of each item of work shown in the BILL OF QUANTITIES are only approximate and the same is appended below. They are given as a guide for the purpose of tendering only and are liable to variation and alteration of the Competent Authority. The work under each item as executed shall be measured and priced at the rates provided in Bill of Quantities appended below.

**BHEL / TRICHY-620 014
CIVIL ENGINEERING DEPARTMENT-FACTORY**

BILL OF QUANTITIES

Name of work : Repair & Renovation of existing facilities at Puthayiram Poonga Park located in BHEL Township, Kailasapuram, Trichy – 14

S.No	Quantity	Item Description	Unit	Rate	Amount
1	1	Wave Slide - Replacement of the sliding Piece with FRP chute – 3 sloping chute and one small horizontal chute – fixed to suit the existing structure. The connection between landing platform at top and sliding chute to be made smooth.	set		
2	1	See Saw - Replacement of the 4 Wooden Seat and one T shaped handle and fixed to suit the existing structure	set		
3	1	Chair Type Merry Go Round -Replacement of the Bearing Shaft Unit and fixing the Merry Go Round and to make it functional	set		
4	1	Wave Slide - Replacement of 3 rd FRP sliding Piece from one piece of Item 01, Patch working on small horizontal chute and fixed to suit the existing structure. The connection between landing platform at top and sliding chute to be made smooth	set		
5	1	Duck Type Merry Go Round -Replacement of the 4 FRP Duck and fixing on the Merry Go Round and to make it functional	set		
6	1	Tubular Slide - Replacement of 4 FRP Long Chute with top Closure and Bottom one Piece and fixed to suit the existing structure. 12 Nos of Steps on the ladder also needs to be replaced. The connection between landing platform at top and sliding chute to be made smooth	set		
7	1	Family Swing - Providing Wooden Seating of Size 4 feet x 1 feet with back rest and supported by necessary chain and suitably clamping to the top bar of the existing frame. The frame to be checked for load capacity and it was earlier used as swing with a tyre hanging from centre.	set		

CONTRACTOR

3

ACCEPTING OFFICER

S.No	Quantity	Item Description	Unit	Rate	Amount
8	1	Spiral Slide - Patch work on the FRP chutes of the Spiral slide and making it fit for use. 11 Nos of steps on the ladder side needs to be replaced. The connection between landing platform at top and sliding chute to be made smooth.	set		
9	1	Duck Type Merry Go Round -Replacement of the 4 FRP Duck with foot rest on the existing frame and fixing on the stub shown in the figure with suitable bearing and to make it functional. The frame on which the duck is fixed is available.	set		
10	1	Wave Slide -Patch working on third FRP Chute and the small horizontal chute. The connection between landing platform at top and sliding chute to be made smooth	set		
GRAND TOTAL (Including all Taxes including GST)					

The above rate inclusive of GST.

S.No	Note:
1	Please make a visit to puthairam poonga situated at Kailasapuram BHEL Township to ascertain the condition of the above items
2	The rate should include Inspection, removal of damaged parts without disturbing adjacent parts, cost of supply of spares, attending to repair works, consumables, leading, Transportation, Lubrication and Labour Charges
3	The quoted rate shall be inclusive of all taxes ,GST ,Transportation charges,incidental charges etc complete
4	The quoted rate will be firm and will not be changed under any circumstances towards any reason
5	The work should be carried out as per standard specification and as per the instruction of Engineer in charge
6	If any item is later found to be not fit for reuse or beyond repair, then payment will not be made for the same.
7	If any structure needs to be modified, then the same including fixing on ground to be taken care in the scope of supply.
8	Payment shall be made on actual completion of work and accepted by Engineer In charge in line with BHEL terms and conditions

CONTRACTOR

4

ACCEPTING OFFICER