

1X660 MW UPRVUNL PANKI TPS, EXTENSION

***TECHNICAL SPECIFICATION
FOR
LUBE OIL TRANSFER PUMPS***

SPECIFICATION NO.- PE-TS-426-567-A001



**BHARAT HEAVY ELECTRICALS LIMITED
POWER SECTOR
PROJECT ENGINEERING MANAGEMENT
NOIDA (INDIA)**



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATIONS FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

CONTENTS

This Technical specification consists of two sections:

SECTION – I

SECTIONS	TITLE	PAGE NO.
SUB-SECTION-A	INTENT OF SPECIFICATION	1
SUB-SECTION-B	PROJECT INFORMATION WITH WIND AND SEISMIC DESIGN CRITERIA	5
SUB-SECTION-C	TECHNICAL SPECIFICATIONS	13
SUB-SECTION-C1A	SPECIFIC TECHNICAL REQUIREMENT – MECHANICAL	14
SUB-SECTION-C1B	GENERAL TECHNICAL REQUIREMENT	17
SUB-SECTION-C1C	QUALITY ASSURANCE AND INSPECTION REQUIREMENT	49
SUB-SECTION-C1D	MASTER DRAWING LIST WITH SUBMISSION SCHEDULE	58
SUB-SECTION-C1E	PAINTING SPECIFICATION	61
SUB-SECTION-C1F	LIST OF MAKES OF SUB-VENDOR ITEMS	75
SUB-SECTION-C2	SPECIFIC TECHNICAL SPECIFICATION - ELECTRICAL PORTION	78
SUB-SECTION-C3	DATASHEET	106
SUB-SECTION-C3A	DATASHEET-A-FOR LUBE OIL TRANSFER PUMPS	107
SUB-SECTION-C3B	DATASHEET-C-FOR LUBE OIL TRANSFER PUMPS	108
SUB-SECTION-D	FORMAT FOR OPERATION AND MANITENANCE	114

SECTION – II –DOCUMENTS TO BE SUBMITTED BY BIDDER

SUB SECTIONS	TITLE	Page No
ANNEXURE-I	LIST OF DOCUMENTS TO BE SUBMITTED WITH BID	118
ANNEXURE-II	COMPLIANCE CUM CONFIRMATION CERTIFICATE	119
ANNEXURE-III	PRE BID CLARIFICATION SCHEDULE	121
ANNEXURE-IV	SCHEDULE OF TECHNICAL DEVIATION	122
ANNEXURE-V	ELECTRICAL LOAD DATA	124



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-A

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

INTENT OF SPECIFICATION



TITLE:
1X660 MW UPRVNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATIONS FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-A

REV. 00

DATE: JULY 2019

SHEET : 1 OF 3

1.0 **SCOPE OF ENQUIRY/ INTENT OF SPECIFICATION**

- 1.1 The specification covers design (i.e. Preparation and submission of drawing /documents including “As Built” drawings and O&M manuals), engineering, manufacture, fabrication, assembly, inspection / testing at vendor's & sub-vendor's works, painting, maintenance tools & tackles (as applicable), fill of lubricants & consumables along with spares for erection, start up and commissioning as required, forwarding, proper packing, shipment and delivery at site complete with all accessories for the total scope defined as per BHEL NIT & tender technical specification as specified, amendment & agreements till placement of order, demonstration testing and handing over to BHEL's customer of Lube Oil Transfer Pumps as per details in different sections / volumes of this specification and various pre-award agreements for 1X660 MW UPRVNL PANKI TPS, EXTENSION.
- 1.2 The contractor shall be responsible for providing all material, equipment & services, which are required to fulfil the intent of ensuring operability, maintainability, reliability and complete safety of the complete work covered under this specification, irrespective of whether it has been specifically listed herein or not. Omission of specific reference to any component / accessory necessary for proper performance of the equipment shall not relieve them of the responsibility of providing such facilities to complete the supply, erection and commissioning of **Lube Oil Transfer Pumps** within quoted price.
- 1.3 It is not the intent to specify herein all the details of design and manufacture. However, the equipment / system shall conform in all respects to high standards of design, engineering and workmanship and shall be capable of performing the required duties in a manner acceptable to purchaser who will interpret the meaning of drawings and specifications and shall be entitled to reject any work or material which in his judgement is not in full accordance herewith.
- 1.4 The extent of supply under the contract includes all items shown in the drawings, notwithstanding the fact that such items may have been omitted from the specification or schedules. Similarly, the extent of supply also includes all items mentioned in the specification and /or schedules, notwithstanding the fact that such items may have been omitted in the drawing.
- 1.5 Items though not specifically mentioned but needed to make the system complete as stipulated under these specifications are also to be furnished unless otherwise specifically excluded.
- 1.6 The general terms and conditions, instructions to tenderer and other attachment referred to elsewhere are hereby made part of the tender specifications. The equipment / material and works covered by this specification is subject to compliance to all the attachments referred in the specification. The tenderer shall be responsible for adherence to all requirements stipulated herein.
- 1.7 While all efforts have been made to make the specification requirement complete & unambiguous, it shall be bidders' responsibility to ask for missing information, ensure completeness of specification, to bring out any contradictory / conflicting requirement in different sections of the specification and within a section itself to the notice of BHEL and to seek any clarification on specification requirement in the format enclosed under Sec.-III of the specification within 10 days of receipt of tender documents. In absence of any such



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATIONS FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-A

REV. 00

DATE: JULY 2019

SHEET : 2 OF 3

clarifications, in case of any contradictory requirement, the more stringent requirement as per interpretation of Purchaser/Customer shall prevail and shall be complied by the bidder without any commercial implication on account of the same. Further in case of any missing information in the specification not brought out by the prospective bidders as part of pre-bid clarification, the same shall be furnished by Purchaser/ Customer as and when brought to their notice either by the bidder or by purchaser/ customer themselves. However, such requirements shall be binding on the successful bidder without any commercial & delivery implication.

- 1.8 Deviations, if any, should be very clearly brought out clause by clause in the enclosed schedule otherwise, it will be presumed that the vendor's offer is strictly in line with NIT specification.
- 1.9 In case all above requirements are not complied with, the offer may be considered as incomplete and would become liable for rejection.
- 1.10 Unless specified otherwise, all through the specification, the word contractor shall have same meaning as successful bidder/vendor and Customer/Purchaser/Employer will mean BHEL and/or Customer as interpreted by BHEL in the relevant context. Please refer GCC/SCC for better clarity.
- 1.11 The equipment covered under this specification shall not be dispatched unless the same have been finally inspected, accepted and dispatch release issued by BHEL/Customer.
- 1.12 BHEL's Customer's representative shall be given full access to the shop in which the equipment's are being manufactured or tested and all test records shall be made available to him.
- 1.13 Various codes and standards to be used shall be as indicated in various parts of the specification. In case bidder uses any standard other than those indicated in the specification, the onus of establishing equivalence of the same with the specified standards will rest with the bidder and acceptance of the same shall be sole prerogative of customer. The bidder will also arrange for BHEL a copy of the standards in ENGLISH language. The cost of such service will be deemed to have been included by the bidder in the total cost of the package. BHEL will not entertain any additional cost on account of the same.
- 1.14 All text/ numeric in the document / drawings to be generated by the successful bidder will be in English language only.
- 1.15 The bidder's offer shall not carry any sections like clarification, interpretations and /or assumptions.

Note:

Bidder to note that BHEL reserves the right for drawing/document submission through web based Document Management System. Bidder would be provided access to the DMS for drawing/document approval and adequate training for the same. Detailed methodology would be finalized during the kick-off meeting. Bidder to ensure following at their end.

- Internet explorer version – Minimum Internet Explorer 7.



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATIONS FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-A

REV. 00

DATE: JULY 2019

SHEET : 3 OF 3

- Internet speed – 2 mbps (Minimum preferred).
- Pop ups from our external DMS IP (124.124.36.198) should not be blocked.
- Vendor's internal proxy setting should not block DMS application's link (<http://dmsserver.bhelpem.com/Wrench%20Web%20Access/Login.aspx>).



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-A

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

PROJECT INFORMATION WITH WIND AND SEISMIC DESIGN CRITERIA

SECTION-I, SUB-SECTION-A : GENERAL PROJECT INFORMATION

1.0 PROJECT INFORMATION

1.1	Owner	:	UTTAR PRADESH RAJYA VIDYUT UTPADAN NIGAM LIMITED, LUCKNOW	
1.2	Project Title	:	Panki Thermal Power Station (1x660MW)	
1.3	Owner's Engineer	:	DEVELOPMENT CONSULTANTS PVT. LTD	
1.4	Project Site Location	:	Place	Panki
		:	District	Kanpur
		:	State	Uttar Pradesh
		:	Country	India
1.5	Latitude & Longitude of project site	:	North	N26°28'20"
		:	East	E 80°14'32"
1.6	Nearest Railway Station	:	Panki	5 km
1.7	Nearest Town	:	Kanpur	16km
1.8	Nearest Highway	:	National Highway - 25	
1.9	Nearest Airport	:	Kanpur	25 km
		:	Lucknow	80 Km
1.10	Nearest Commercial Airport	:	Delhi	140 km
1.11	Nearest Water Body	:	Lower Ganga Canal, adjacent to site	
1.12	Land	:	Land is in possession of UPRVUNL.	
1.13	Station Graded Level Elevation from Mean sea level (MSL)	:	Plant FGL → RL(+) 126.0M → EI(-) 0.500M Plant FFL → RL(+) 126.5M → EI(+/-) 0.000M	
1.14	Water	:		
1.14.1	Nearest Water Source	:	Lower Ganga Canal system running adjacent for project site	
1.14.2	Water Requirement for station	:	~ 1927 m ³ /hr considering closed cooling cycle with NDCT. Additional 700m ³ /hr for ash slurry preparation during emergency ash disposal to ash dyke.	
1.14.3	Raw Water Analysis from Upper Ganga Canal	:	Refer Appendix - I	
1.15	Site Ambient Condition	:		
1.15.1	Monthly mean (DBT)	:	Maximum	44.4 °C
		:	Minimum	3.8 °C
1.15.2	Extreme Recorded (DBT)	:	Maximum	47.3 °C
		:	Minimum	-0.9 °C
1.15.3	Monthly mean (WBT)	:	Maximum	27.3 °C
		:	Minimum	9.2 °C
1.15.4	Relative Humidity	:	Maximum	84 %
		:	Minimum	28 %
1.15.5	Average relative humidity	:	Annual Average	65 %
1.15.6	Rainfall	:	Annual average	832.6 mm

			Heaviest fall recorded in 24 hrs	247.4 mm
1.15.7	Basic Wind Speed	:	47.00 m/s	As per IS: 875 part – III
			For wind resistance design of structure & equipment refer relevant civil section	
1.15.8	Climatic condition	:	For detailed information refer attached Climatological data as published by IMD for Kanpur station.	
1.16	Seismic data	:	Zone – III	As per IS: 1893
			For earthquake resistance design of structure & equipment refer relevant civil section	
1.17	Fuel Data			
1.17.1	Coal Source	:	Coal requirement for this stage of the project is estimated as 2.99 million tones/annum considering 660 MW capacity, GCV of blended coal 4030 kcal/kg, Heat Rate as 2317 kcal/kwh and 90% PLF as per CERC operative norms effective from 1/4/2009.	
1.17.2	Coal Transportation	:	Thru BOXN wagons of Indian Railways System	
1.17.3	Coal Analysis	:	Refer Appendix – II	
1.17.4	Support Fuel (HFO / LDO) transportation	:	Support fuel will be transported by road tankers or by Railway system. Start-up / support fuel for the proposed project will be LDO/HFO.	
1.17.5	Support Fuel (HFO / LDO) analysis	:	Refer Appendix - II	

Appendix – I: Raw Water Analysis (Source - Lower Ganga Canal)

S. No.	Description	Unit	Parameter
1	Physical characteristics		
	pH at 25°C	-	8.00
	Turbidity	Silica Scale	500
	Total Suspended solids	ppm	250
	Total Dissolved solids	ppm	241
	Colour	Hazen	< 5
2	Cations		
	Calcium Hardness	ppm as CaCO ₃	80
	Magnesium Hardness	ppm as CaCO ₃	40
	Sodium + Potassium	ppm as CaCO ₃	36
	Iron	ppm as CaCO ₃	1.5
	Total Cations	ppm as CaCO ₃	157.5
3	Anions		
	Bicarbonate	ppm as CaCO ₃	100
	Carbonate	ppm as CaCO ₃	0.95

S. No.	Description	Unit	Parameter
	Hydroxyl Chlorides	ppm as CaCO ₃	0.05
	Sulphate	ppm as CaCO ₃	20
	Nitrate	ppm as CaCO ₃	36
	Total Anions	ppm as CaCO ₃	0.5
			157.5
4	Carbon Di-oxide as CO ₂	ppm	1.97
5	Dissolved Silica	ppm as SiO ₂	10.0
6	Colloidal Silica	ppm as SiO ₂	0.5
7	Organic Matter	ppm as O ₂	4.0

Appendix – II : Coal Quality Parameter

Sl.No.	Particulars	Unit	Performance / Design Fuel	Worst Fuel	Best Fuel
1.0.	Proximate Analysis (As Received Basis)	By Weight			
1.1.	Moisture	%	10.5	12	12
1.2.	Ash	%	35	43	32
1.3.	Volatile Matter	%	26	19	27
1.4.	Fixed Carbon	%	28.5	26	29
1.5.	Total	%	100	100	100
1.6.	Gross Calorific Value	kcal/kg	3700	3200	4200
2.0.	Ultimate Analysis (As Received Basis)				
2.1.	Moisture	%	10.5	12	12
2.2.	Ash	%	35	43	32
2.3.	Carbon	%	42	33.5	44
2.4.	Hydrogen	%	2.0	2.4	2.77
2.5.	Nitrogen	%	1.6	1.3	1.5
2.6.	Sulfur	%	0.46	0.45	0.5
2.7.	Oxygen	%	8.44	7.35	7.23
2.8.	Total	%	100	100	100
3.0.	Hard Groove Index		53	50	55
4.0.	Ash Fusion Range				
a)	Initial Deformation Temperature	^o C	1200	1154	1165
b)	Hemispherical Temperature	^o C	1350	1300	>1350

Sl.No.	Particulars	Unit	Performance / Design Fuel	Worst Fuel	Best Fuel
c)	Fusion Temperature	°C	>1400	>1400	>1400

Source: Saharpur Jamarpani Coal Mine, Jharkhand
Imported Coal

Sl. No.	Item	Unit	Design Coal
1.	Gross heating Value	Kcal/kg	5500

Source: Indonesia / South African coal

Amendment
Light Diesel Oil (LDO): As per
IS : 15770 : 2008.

Appendix – III : Light Diesel Oil (LDO)
As per IS: 1460-2000

S.No.	Property	Unit	Value
1.0	Ash content (max)	% by mass	0.02
2.0	Carbon residue (Rams Bottom) max	% by mass	0.2
3.0	Cetane number (Min)	-	-
4.0	Pour Point (max)		
	a) Winter	°C	12
	b) Summer		21
5.0	Flash Point (min)		
	a) Abel	°C	--
	b) Pensky0Martens		68
6.0	Kinematic Viscosity at 38 deg	Cst	2.5 to 15.7
7.0	Sediments (max)	% by mass	0.1
8.0	Sulphur Content (max)	% by mass	1.8
9.0	Water Content (max)	% by volume	---
10.0	Gross Calorific Value (GCV), approx	kCal/kg	10,000
11.0	Density at 15°C	Kg/m ³	850 to 870

Appendix – IV : Heavy Fuel Oil (HFO)
As per IS: 1593-1982

S.No.	Property	Unit	Value
1.0	Viscosity at 50 °C	Cst	370
2.0	Density at 15°C (approx)	Kg/m ³	890 to 950
3.0	Flash Point (min)	°C	66
4.0	Pour Point (max)	°C	20
5.0	Water Content (max)	% by volume	1
6.0	Sediments (max)	% by weight	0.25
7.0	Sulphur Content (max)	% by weight	4.5
8.0	Ash content (max)	% by weight	0.1
9.0	Gross Calorific Value (GCV), approx	kCal/kg	10,000

2.0 Access to Site

The nearest town Kanpur is about 16 km from site. It is easily accessible by Railway/Road.

Dedicated railway link is available for the transportation of coal and fuel oil for the power plant. No problem is envisaged in accessibility and transportation of heavy equipment to site by road or rail.

3.0 Plant Rating, Capacity, Availability, PLF

Plant continuous rating will be 660 MW at generator terminals based on the following site conditions.

- Ambient air temperature
- Condenser cooling water inlet temperature of 33°C and 10°C temperature rise across the condenser.
- Generator power factor of 0.85 (zero point eight-five).
- Fuel specification as given elsewhere.
- Design temperature for electrical equipment is 50°C.

The VWO capacity of the steam turbine 660 MW will be 105% or 693 MW and the Boiler maximum Continuous Rating (MCR) will be established to match the steam requirement at VWO conditions. The capacity of the unit is selected so as to deliver the rated output even after ageing that will occur between overhauls, as a result of deposition of salts in turbine blades, wear and tear etc.

4.0 Power Evacuation

The power generated from the proposed project will be evacuated over the 400 KV through a 400 KV open switchyard. Further to Switchyard distribution will be by UPTRANSCO. Interconnection of proposed 400 KV Switchyard with existing 220 kV switchyard shall be done as specified elsewhere in specification.

जलवायवी सारणी CLIMATOLOGICAL TABLE

1951 से 1976 तक के प्रेक्षणीय आँकड़ों पर आधारित
BASED ON OBSERVATIONS FROM 1951 TO 1976

स्थान : कानपुर (U)
STATION : Kanpur (A)

अक्षांश : 26°26' N
LAT 26°26' N

देशान्तर : 80°22' E
LONG 80°22' E

ऊँचाई : 120 मीटर
HEIGHT ABOVE M. S. L. 120 METRES

STATION : Kanpur (A)																			
LAT 26°26' N LONG 80°22' E																			
HEIGHT ABOVE M.S.L.																			
वर्षा																			
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									
वायु तापमान										वर्षा									

स्टेशन :कानपुर (ए)
STATION: Kanpur (A)

Page 12 of 125



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

TECHNICAL SPECIFICATION



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1A

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

SPECIFIC TECHNICAL REQUIREMENT – MECHANICAL



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1A

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

1.0 SCOPE OF WORK

- 1.1** Design, engineering, manufacturing, inspection and testing at manufacturer's works, painting, supply/delivery duly packed at project site for pump & motor set duly coupled and unitised on a common base frame with coupling guard, foundation bolts, flanges, companion flanges with nuts bolts and gaskets, drip pan with plugged draining arrangement, strainer with flanges, companion flanges, nuts, bolts & gaskets, foundation bolts etc along with commissioning spares and all accessories as indicated in the **pump Datasheet-A and Datasheet-C under SUB-SECTION -C3A.& C3B**

The scope of equipment (Quantity, Capacity, Head and the type of strainer) to be supplied shall be as per Data sheet-A (PE-DC-426-100-N137) given under SUB-SECTION- 3CA.

- 1.2 Mandatory spares: Not Applicable**

2.0 TERMINAL POINT

- a) Suction strainer nozzle counter flange (suction side)
- b) Pump discharge nozzle's counter flange.

- 2.1** For electrical system, bidder's scope shall terminate at motor terminal box complete with cable glands/ lugs for power cabling. Also refer electrical scope between BHEL & Vendor given under **Electrical portion** of specification under SUB-SECTION-C2.

3.0 EXCLUSIONS

- 3.1 Power Cable
- 3.2 Motor starter in MCC
- 3.3 Local Push Button Station
- 3.4 Feeder for motor
- 3.5 Earthing of Pumps. However, earthing conductor is to be provided by the bidder.
- 3.6 Foundation & associated civil works.

4.0 CORROSION PROTECTION/ PAINTING SCHEDULE

- 4.1 Painting shall be in line with the painting specification covered under Sub-Section-C1E.
- 4.2 Make of paints shall be as Asian Paints, Berger paints or Good lass Nerolac.

5.0 QUALITY REQUIREMENTS

- a) Bidder should maintain excellent quality of works; all supply items shall meet the relevant quality Standards.



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1A

REV. 00

DATE: JULY 2019

SHEET : 2 OF 1

- b) The successful bidder shall furnish Quality Plans/ Inspection Check Lists for various item for the package in line with minimum requirement indicated in specification during detail engineering for Customer's approval.
- c) For other items for which any specific inspection requirement is not indicated in the specification but the same included in scope of work, vendor specific QPs/ CLs shall be furnished by the successful bidder for Customer/Consultant's review and approval. All comments made by customer/ consultant shall be incorporated by the successful bidder without any commercial and delivery implication.

6.0 DRAWINGS AND DOCUMENTS TO BE SUBMITTED WITH THE BID

The drawings and documents to be submitted with the bid shall be as per list given under SECTION-II.

7.0 DRAWINGS AND DOCUMENTS REQUIRED DURING DETAIL ENGINEERING

List of drawings / documents required during detail engineering along with submission Schedule is given under SUB-SECTION-C1D.

8.0 SUB-VENDOR ITEMS

The makes of sub-vendor items indicated under SUB-SECTION-C1G of specification are subject to acceptance by customer without any additional commercial implication to BHEL.



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1B

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

GENERAL TECHNICAL REQUIREMENT

1.0 INTRODUCTION

This part covers technical requirements, which will form an integral part of the Contract. The following provisions shall supplement all the detailed technical requirements brought out in the Technical Specifications and the Technical Data Sheets.

2.0 BRAND NAME

Whenever a material or article is specified or described by the name of a particular brand, manufacturer or vendor, the specific item mentioned shall be understood to be indicative of the function and quality desired, and not restrictive; other manufacturer's products may be considered provided sufficient information is furnished to enable the Owner to determine that the products proposed are equivalent or superior to those named.

3.0 BASE OFFER & ALTERNATE PROPOSALS

The Bidder's proposal shall be based upon the use of equipment and material complying fully with the requirements specified herein. It is recognized that the Bidder may have standardized on the use of certain components, materials, processes or procedures different than those specified herein. Alternate proposals offering similar equipment based on the manufacturer's standard practice may also be considered, provided the base offer is in line with technical specifications and such proposals meet the specified design standards and performance requirement and are acceptable to the Owner. Sufficient amount of information for justifying such proposals shall be furnished to Owner along with the bid to enable the Owner to determine the acceptability of these proposals.

4.0 COMPLETENESS OF FACILITIES

- 4.1 Bidders may note that this is a contract inclusive of the scope as indicated elsewhere in the specification. Plant shall be engineered and designed in accordance with the specification requirement. All engineering and associated services are required to ensure that a completely engineered plant is provided.
- 4.2 All equipments furnished by the Bidder shall be complete in every respect, with all mountings, fittings, fixtures and standard accessories normally provided with such equipment and/or those needed for erection, completion and safe operation & maintenance of the equipment and for the safety of the operating personnel, as required by applicable codes, though they may not have been specifically detailed in the respective specifications, unless included in the list of exclusions.
- 4.3 All similar standard components/ parts of similar standard equipment provided shall be interchangeable with one another.

5.0 Codes & Standards

- 5.1 In addition to the codes and standards specifically mentioned in the relevant technical specifications for the equipment / plant / system, all equipment parts, systems and works covered under this specification shall comply with all currently applicable statutory regulations and safety codes of the Republic of India as well as of the locality where they will be installed, including the following:

- (a.) Bureau of Indian Standards (BIS)
- (b.) Indian Electricity Act (2003)
- (c.) Indian Electricity Rules
- (d.) Indian Explosives Act
- (e.) Indian Factories Act and State Factories Act
- (f.) Indian Boiler Regulations (IBR)
- (g.) Regulation of Central Electricity Authority
- (h.) Regulations of the Central Pollution Control Board, India
- (i.) Regulations of the Ministry of Environment & Forest (MoEF), Government of India
- (j.) Pollution Control Regulations by Department of Environment, Government of India
- (k.) State Pollution Control Board.
- (l.) Building and other construction workers (Regulation of Employment and Conditions of services) Central Rules, 1998
- (m.) Explosive Rules, 1983
- (n.) Petroleum Rules, 1976,
- (o.) Gas Cylinder Rules, 1981
- (p.) Static and Mobile Pressure Vessels (Unified) Rules, 1981
- (q.) Workmen's Compensation Rules, 1924
- (r.) Rules for Electrical installation by Tariff Advisory Committee (TAC) and appropriate Electrical Inspectorate.
- (s.) Owner's Safety Policy
- (t.) Any other statutory codes / standards / regulations, as may be applicable.

5.2 Unless covered otherwise by Indian codes & standards and in case nothing to the contrary is specifically mentioned elsewhere in the specifications, the latest editions (as applicable as on date of bid opening), of the codes and standards given below shall also apply:

- (a.) British Standards (BS)
- (b.) Japanese Industrial Standards (JIS)
- (c.) American National Standards Institute (ANSI)
- (d.) American Society of Testing and Materials (ASTM)
- (e.) American Society of Mechanical Engineers (ASME)
- (f.) American Petroleum Institute (API)
- (g.) Standards of the Hydraulic Institute, U.S.A.
- (h.) International Organisation for Standardization (ISO)
- (i.) Tubular Exchanger Manufacturer's Association (TEMA)
- (j.) American Welding Society (AWS)
- (k.) Cooling Tower Institute (CTI)
- (l.) National Electrical Manufacturers Association (NEMA)
- (m.) National Fire Protection Association (NFPA)
- (n.) International Electro-Technical Commission (IEC)
- (o.) Expansion Joint Manufacturers Association (EJMA)
- (p.) Heat Exchange Institute (HEI)
- (q.) IEEE standard
- (r.) JEC standard

5.3 Other International/ National standards such as DIN, VDI, BS, etc. shall also be accepted for only material codes and manufacturing standards, subject to the Owner's approval, for which the Bidder shall furnish, along with the offer, adequate information to justify that these standards are equivalent or superior to the standards mentioned above. In all such cases the Bidder shall furnish

specifically the variations and deviations from the standards mentioned elsewhere in the specification together with the complete word to word translation of the standard that is normally not published in English.

- 5.4 As regards highly standardized equipments such as Steam Turbine and Generator, National /International standards such as JIS, DIN, VDI, ISO, SEL, SEW, VDE, IEC & VGB shall also be considered as far as applicable for Design, Manufacturing and Testing of the respective equipment. In addition, these standards shall be referred for the design of machine foundations, wherever specifically mentioned in the specifications. However, for those of the above equipment not covered by these National / International standards, established and proven standards of manufacturers shall also be considered.
- 5.5 In the event of any conflict between the codes and standards referred to in the above clauses and the requirement of this specification, the requirement of Technical Specification shall govern.
- 5.6 Two (2) English language copies of all-national and international codes and/or standards used in the design of the plant, equipment, civil and structural works shall be provided by the Bidder to the Owner within two calendar months from the date of the Notification of Award.
- 5.7 In case of any change in codes, standards & regulations between the date of bid opening and the date when vendors proceed with fabrication, the Owner shall have the option to incorporate the changed requirements or to retain the original standard. It shall be the responsibility of the Bidder to bring to the notice of the Owner such changes and advise Owner of the resulting effect.

6.0 EQUIPMENT FUNCTIONAL GUARANTEE

- 6.1 The Equipment and Auxiliaries shall be capable of continuous operation in frequency range of 47.5 to 51.5 Hz.
- 6.2 The functional guarantees of the equipment under the scope of the Contract shall be as per "Chapter 8 - Functional Guarantee & LD", Volume-II. These guarantees shall supplement the general functional guarantee provisions covered under General Conditions of Contract.
- 6.3 Liquidated damages for shortfall in meeting functional guarantee(s) during the performance and guarantee tests shall be assessed and recovered from the Bidder as specified elsewhere in this specification.

7.0 DESIGN OF FACILITIES / MAINTENANCE & AVAILABILITY CONSIDERATIONS

7.1 Design of Facilities

- 7.1.1 All the design procedures, systems and components proposed shall have already been adequately developed and shall have demonstrated good reliability under similar conditions elsewhere.
- 7.1.2 The Bidder shall be responsible for the selection and design of appropriate equipments to provide the best co-ordinate performance of the entire system. The basic requirements are detailed out in various clauses of the Technical Specifications. The design of various components, assemblies and subassemblies shall be done so that it facilitates easy field assembly and dismantling. All the

rotating components shall be so selected that the natural frequency of the complete unit is not critical or close to the operating range of the unit.

7.2 Maintenance and Availability Considerations

- 7.2.1 Equipment/facilities offered shall be designed for high availability, low maintenance and ease of maintenance. The Bidder shall specifically state the design features incorporated to achieve high degree of reliability/ availability and ease of maintenance. The Bidder shall also furnish details of availability records in the reference plants stated in his experience list.
- 7.2.2 Bidder shall state in his offer the various maintenance intervals, spare parts and man-hour requirement during such operation. The intervals for each type of maintenance namely inspection of the furnace, inspection of the entire hot gas path and the minor and major overhauls shall be specified in terms of fired hours, clearly defining the spare parts and man-hour requirement for each stage.
- 7.2.3 Lifting devices i.e. hoists and chain pulley jacks, etc. shall be provided by the Bidder for handling of any equipment or any of its part having weight in excess of 500 Kgs during erection and maintenance activities.
- 7.2.4 Lifting devices like lifting tackles, slings, etc. to be connected to hook of the hoist / crane shall be provided by the Bidder for lifting the equipment and accessories covered under the specification.

8.0 DOCUMENTS, DATA AND DRAWINGS TO BE FURNISHED BY BIDDER

- 8.1 Plant and equipment shall be fully integrated, engineered and designed to perform in accordance with the technical specification. All engineering and technical services required ensuring a completely engineered plant shall be provided in respect of mechanical, electrical, control & instrumentation, civil & structural works as per the scope.

The Contractor shall furnish engineering data/drawings in accordance with the schedule of information as specified in Technical Specification and data sheets.

A comprehensive engineering and quality coordination procedure shall be finalized with the successful bidder covering salient features as described in this section of specifications.

- 8.2 The number of copies/prints/CD-ROMs/manuals to be furnished for various types of documents is given in Annexure-I attached with Chapter 5, Volume-II.
- 8.3 The documentation that shall be provided by the Bidder is indicated in various sections of specification. The documentation shall include but not be limited to the following:

8.3.1 Basic Engineering Documentation

Prior to commencement of the detailed engineering work, the Bidder shall furnish a Plant Definition Manual within 4-6 weeks from the date of the Notification of Award. This manual shall contain the following as a minimum:-

- 1) System description of all the mechanical, electrical, control & instrumentation & civil systems.

- 2) Technology scans for each system / sub-system & equipment.
- 3) Selection of appropriate technology / schemes for various systems/ subsystems including techno-economic studies between various options.
- 4) Optimization studies including thermal cycle optimization.
- 5) Sizing criteria of all the systems, sub-systems including various piping systems/ equipments/ structures/ equipment foundations along with all calculations justifying and identifying the sizing and the design margins.
- 6) Schemes and Process & Instrumentation diagrams for the various systems/ sub-system with functional write-ups.
- 7) Operation Philosophy and the control philosophy of the Main Plant and other plants.
- 8) General Layout plan of the power station incorporating all facilities in Bidder's as well as those in the Owner's scope. This drawing shall also be furnished in native (Word, Excell, ACAD etc) in the form of CD discs to the Owner for engineering of areas not included in Bidder's scope.
- 9) Basic layouts and cross sections of the main plant building (various floor elevations), boiler, fuel oil area and other areas included in the scope of the Bidder.
- 10) Documentation in respect of Quality Assurance System as listed out elsewhere in this specification.

The successful bidder shall furnish within three (3) weeks from the date of Notification of Award, a list of contents of the Plant Definition Manual (PDMs) including techno-economic studies, which shall then be mutually discussed & finalised with the Owner.

After approval of Plant Definition Manual / Design Basis Report, Bidder shall furnish detailed technical specification of all system / packages of the Plant.

8.3.2 Detailed Engineering Documentation

- 1) Layouts, general arrangements, elevations and cross-sections drawings for all the equipment and facilities of the plant.
- 2) Flow diagrams, Process & Instrumentation Diagrams along with write-up and system description.
- 3) Start-up curves for turbine, boiler and both turbine and boiler combined together as a unit for various start-ups, viz. cold, warm and hot start-up.
- 4) Piping isometric, composite layout and fabrication drawings.
- 5) Piping engineering diagrams, pipe and fittings schedules, valve schedules, hanger and support schedules, insulation schedules.
- 6) Technical data sheets for all bought out and manufactured items. Bidder shall use the specifications as a base for placement of orders on their sub-vendors.

- 7) Detailed design calculations for components, system/sub-system, piping etc., wherever applicable including sizing calculations for all auxiliaries as per criteria specified elsewhere in specification.
- 8) Boiler pressure part schedule and sizing calculations. Boiler performance data and boiler design dossier.
- 9) Transient, hydraulic and thermal stress analysis of piping and system wherever applicable & input and output data along with stress analysis isometrics showing nodes.
- 10) Thermal cycle information (heat balance diagrams, boiler performance calculations, condenser and heat exchanger thermal calculations etc.).
- 11) Characteristic Curves/ Performance Correction Curves. Hydraulic & Mechanical design calculations for condensers & heaters.
- 12) Model Studies/ CFD analysis for ESP, CW sump etc and furnishing report with recommendations.
- 13) Characteristic Curves/ Performance Correction Curves and thermal design calculations for Cooling Tower.
- 14) Composite Water Balance for total Plant.
- 15) Hydraulic calculation/profile for Water Treatment Plant.
- 16) Comprehensive list of all terminal points which interface with Owner's facilities giving details of location, terminal pressure, temperature, fluid handled & end connection details, forces, moments etc.
- 17) Power supply single line diagram, block logics, control schematics, electrical schematics, etc.
- 18) Protection systems diagrams and relay settings. Load Flow study.
- 19) Interconnection diagrams.
- 20) Cable routing plan.
- 21) Instrument schedule, measuring point list, I/O list, Interconnection & wiring diagram, functional write-ups, installation drawings for field mounted instruments, logic diagrams, control schematics, wiring and tubing diagrams of panels and enclosures etc. Drawings for open loop and close loop controls (both hardware and software). Motor list and valve schedule including type of actuator etc.
- 22) Alarm and annunciation list and alarms & trip set points.
- 23) Sequence and protection interlock schemes.
- 24) Type test reports and power system stability study report.
- 25) Control system configuration diagrams and card circuit diagrams and maintenance details.

- 26) Detailed software manuals & source software listing.
- 27) Detailed flow chart for digital control system.
- 28) Mimic diagram layout.
- 29) Civil Task drawings (for the Engineering by Owner), Design and Drawings for the Civil & Structural works in the scope of the Bidder.
- 30) Model study reports wherever applicable.
- 31) Functional & guarantee test procedures and test reports.
- 32) Documentation in respect of Quality Assurance System as listed out elsewhere in this specification.
- 33) Documentation in respect of commissioning as listed out elsewhere in this specification.

The Bidder while submitting the above documents / drawings for approval / reference as the case may be, shall mark on each copy of submission the reference letter along with the date vide which the submissions are made.

8.3.2 Instruction Manuals

The Bidder shall submit to the Owner, draft Instruction Manuals for all the equipments covered under the Contract by the end of one year from the date of his acceptance of the Letter of Award. The Instruction manuals shall contain full details required for erection, commissioning, operation and maintenance of each equipment. The manual shall be specifically compiled for this project. After finalization and approval of the Owner the Instruction Manuals shall be submitted as indicated in Annexure-IV. The Contract shall not be considered to be completed for purposes of taking over until the final Instructions manuals have been supplied to the Owner. The Instruction Manuals shall comprise of the following.

A) Erection Manuals

The erection manuals shall be submitted at least three (3) months prior to the commencement of erection activities of particular equipment/system. The erection manual should contain the following as a minimum.

- 1) Erection strategy.
- 2) Sequence of erection.
- 3) Erection instructions.
- 4) Critical checks and permissible deviation/tolerances.
- 5) List of tool, tackles, heavy equipments like cranes, dozers, etc.
- 6) Bill of Materials
- 7) Procedure for erection.

- 8) General safety procedures to follow during erection/installation.
- 9) Procedure for initial checking after erection.
- 10) Procedure for testing and acceptance norms.
- 11) Procedure / Check list for pre-commissioning activities.
- 12) Procedure / Check list for commissioning of the system.
- 13) Safety precautions to be followed in electrical supply distribution during erection

B) Operation & Maintenance Manuals

- a) The manual shall be a two rim PVC bound stiff sided binder able to withstand constant usage or where a thicker type is required it shall have locking steel pins, the size of the manual shall not be larger than international size A3. The cover shall be printed with the Project Name, Services covered and Volume / Book number Each section of the manual shall be divided by a stiff divider of the same size as the holder. The dividers shall clearly state the section number and title. All written instructions within the manual not provided by the manufacturers shall be typewritten with a margin on the left hand side.

- b) The arrangement and contents of O&M manuals shall be as follows :

1) Chapter 1 - Plant Description :

To contain the following sections specific to the equipment/system supplied

- i.) Description of operating principle of equipment / system with schematic drawing / layouts.
- ii.) Functional description of associated accessories / controls. Control interlock protection writes up.
- iii.) Integrated operation of the equipment alongwith the intended system. (The is to be given by the supplier of the Main equipment by taking into account the operating instruction given by the associated suppliers).
- iv.) Exploded view of the main equipment, associated accessories and auxiliaries with description. Schematic drawing of the equipment alongwith its accessories and auxiliaries.
- v.) Design data against which the plant performance will be compared.
- vi.) Master list of equipments, Technical specification of the equipment/ system and approved data sheets.
- vii.) Identification system adopted for the various components, (it will be of a simple process linked tagging system).

- viii.) Master list of drawings (as built drawing - Drawings to be enclosed in a separate volume).

2) Chapter 2.0 - Plant Operation:

To contain the following sections specific to the equipment supplied

- i.) Protection logics provided for the equipment alongwith brief philosophy behind the logic, Drawings etc.
- ii.) Limiting values of all protection settings.
- iii.) Various settings of annunciation/interlocks provided.
- iv.) Start-up and shut down procedure for equipment alongwith the associated systems in step mode.
- v.) Do's and Don'ts related to operation of the equipment
- vi.) Safety precautions to be taken during normal operation. Emergency instruction on total power failure condition/lubrication failure/any other conditions.
- vii.) Parameters to be monitored with normal value and limiting values.
- viii.) Equipment isolating procedures.
- ix.) Trouble shooting with causes and remedial measures.
- x.) Routine testing procedure to ascertain healthiness of the safety devices alongwith schedule of testing.
- xi.) Routine Operational Checks, Recommended Logs and Records
- xii.) Change over schedule if more than one auxiliary for the same purpose is given.
- xiii.) System/plant commissioning procedure.
- xiv.) Preservation procedure on long shut down.

3) Chapter 3.0 - Plant Maintenance

To contain the following sections specific to the equipment supplied

- i.) Exploded view of each of the equipments. Drawings alongwith bill of materials including name, code no. & population.
- ii.) Exploded view of the spare parts and critical components with dimensional drawings (In case of Electronic cards, the circuit diagram to be given) and spare parts catalogue for each equipment
- iii.) List of Special T/ P required for Overhauling /Trouble shooting including special testing equipment required for calibration etc

- iv.) Stepwise dismantling and assembly procedure clearly specifying the tools to be used, checks to be made, records to be maintained etc. Clearance to be maintained etc.
- v.) Preventive Maintenance schedules linked with running hours/calendar period alongwith checks to be carried out
- vi.) Overhauling schedules linked with running hours/calendar period alongwith checks to be done
- vii.) Long term maintenance schedules
- viii.) Consumables list alongwith the estimated quantity required during normal running and during maintenance like Preventive Maintenance and Overhauling
- ix.) List of lubricants with their Indian equivalent, Lubrication Schedule including charts showing lubrication checking, testing and replacement procedure to be carried daily, weekly, monthly & at longer intervals to ensure trouble free operation and quantity required for complete replacement
- x.) Tolerance for fitment of various components
- xi.) Details of sub vendors with their part no. in case of bought out items
- xii.) List of spare parts with their Part No, total population, life expediency & their interchange ability with already supplied spares to OWNER.
- xiii.) List of mandatory and recommended spare list along with manufacturing drawings, material specification & quality plan for fast moving consumable spares.
- xiv.) Lead time required for ordering of spares from the equipment supplier, instructions for storage and preservation of spares
- xv.) General information on the equipment such as modification carried out in the equipment from its inception, equipment population in the country / foreign country and list of utilities where similar equipments have been supplied.

8.3.2.2 After finalization and approval of the Employer, the O & M Manuals shall be submitted as indicated in Annexure-VI. The Contract shall not be considered to be completed for purposes of taking over until the final Instructions manuals (both erection and O & M manuals have been supplied to the Employer.

8.3.2.3 If after the commissioning and initial operation of the plant, the instruction manuals (Erection and /or O&M manuals) require modifications/additions/ changes, the same shall be incorporated and the updated final instruction manuals shall be submitted by the Contractor to the Employer for records and number of copies shall be as mentioned in Annexure-VI.

--INTENTIONALLY KEPT VOID--

11.0 Equipment Bases

A cast iron or welded steel base plate shall be provided for all rotating equipment which is to be installed on a concrete base, unless otherwise specifically agreed to by the Owner. Each base plate which support the unit and its drive assembly, shall be of a neat design with pads for anchoring the units, shall have a raised lip all around, and shall have threaded drain connections.

12.0 Protective Guards

Suitable guards shall be provided for protection of personnel on all exposed rotating and/or moving machine parts. All such guards shall be designed for easy installation and removal for maintenance purpose.

13.0 Lubricants, Servo Fluids and Chemicals

13.1 The Bidder's scope includes all the first fill and one year's topping, requirements of consumables such as oils, lubricants including grease, servo fluids, gases and essential chemicals etc. Consumption of all these consumables during the initial operation and final filling after the initial operation shall also be included in the scope of the Bidder. Bidder shall also supply a quantity not less than 10% of the full charge of each variety of lubricants, servo fluids, gases, chemicals etc. used which is expected to be utilised during the first year of operation. This additional quantity shall be supplied in separate Containers.

13.2 As far as possible lubricants marketed by the Indian Oil Corporation shall be used. The variety of lubricants shall be kept to a minimum possible.

Detailed specifications for the lubricating oil, grease, gases, servo fluids, control fluids, chemicals etc. required for the complete plant covered herein shall be furnished. On completion of erection, a complete list of bearings/ equipment giving their location and identification marks shall be furnished to the Owner along with lubrication requirements.

14.0 Lubrication & Chemicals

Equipment shall be lubricated by systems designed for continuous operation. Lubricant level indicators shall be furnished and marked to indicate proper levels under both standstill and operating conditions.

14.1 Chemicals for Water System

Bidder's scope include Chemical required for complete water system up to final handing over EPC package and further two (2) months plant operational requirement.

15.0 Material of Construction

All materials used for the construction of the equipment shall be new and shall be in accordance with the requirements of this specification. Materials utilized for various components shall be those which have established themselves for use in such applications.

16.0 Rating Plates, Name Plates & Labels

- 16.1 Each main and auxiliary item of plant including instruments shall have permanently attached to it in a conspicuous position, a rating plate of non-corrosive material upon which shall be engraved manufacturer's name, equipment, type or serial number together with details of the ratings, service conditions under which the item of plant in question has been designed to operate, and such diagram plates as may be required by the Owner.
- 16.2 Each item of plant shall be provided with nameplate or label designating the service of the particular equipment. The inscriptions shall be approved by the Owner or as detailed in appropriate section of the technical specifications.
- 16.3 Such nameplates or labels shall be of white non-hygroscopic material with engraved black lettering or alternately, in the case of indoor circuit breakers, starters, etc. of transparent plastic material with suitably coloured lettering engraved on the back. The name plates shall be suitably fixed on both front and rear sides.
- 16.4 Items of plant such as valves, which are subject to handling, shall be provided with engraved chromium plated nameplate or label with engraving filled with epoxy. The name plates for valves shall be marked in accordance with MSS standard SP-25 and ANSI B 16.34 as a minimum.
- 16.5 Hanger/ support numbers shall be marked on all pipe supports, anchors, hangers, snubbers and restraint assemblies. Each constant and variable spring support shall also have stamped upon it the designed hot and cold load which it is intended to support. Suitable scale shall also be provided to indicate load on support/hanger.

- 16.6 Valves, steam traps and strainers shall be identified by Owner's tag number of a metal tap permanently attached to non pressure parts such as the yoke by a stainless steel wire. The direction of flow shall also be marked on the body.
- 16.7 Safety and relief valves shall be provided with the following:
- a) Manufacturer's identification.
 - b) Nominal inlet and outlet sizes in mm.
 - c) Set pressure in Kg/cm² (abs).
 - d) Blowdown and accumulation as percentage of set pressure.
 - e) Certified capacity in Kg of saturated steam per hour or in case of liquid certified capacity in litres of water per minute.
- 16.8 All such plates, instruction plates, etc. shall be bilingual with Hindi inscription first, followed by English. Alternatively, two separate plates one with Hindi and the other with English inscriptions may be provided.
- 16.9 All segregated phases of conductors or bus ducts, indoor or outdoor, shall be provided with coloured phase plates to clearly identify the phase of the system

17.0 Tools and Tackles

The Bidder shall supply with the equipment one complete set of all special tools and tackles and other instruments required for the erection, assembly, disassembly and proper maintenance of the plant and equipment and systems (including software). These special tools will also include special material handling equipment, jigs and fixtures for maintenance and calibration / readjustment, checking and measurement aids etc. A list of such tools and tackles shall be submitted by the Bidder alongwith the offer.

The price of each tool / tackle shall be deemed to have been included in the total bid price. These tools and tackles shall be separately packed and sent to site. The Bidder shall also ensure that these tools and tackles are not used by him during erection, commissioning and initial operation. For this period the Bidder should bring his own tools and tackles. All the tools and tackles shall be of reputed make acceptable to the Owner.

18.0 Welding

- 18.1 If the manufacturer has special requirements relating to the welding procedures for welds at the terminals of the equipments to be performed by others the requirements shall be submitted to the Owner in advance of commencement of erection work.

19.0 Colour Code for all Equipments/ Piping/ Pipe Services

- 19.1 All equipment/ piping/ pipe services are to be painted by the Bidder in accordance with Owner's standard colour coding scheme, which will be furnished to the Bidder during detailed engineering stage.

20.0 Protection and Preservative Shop Coating

20.1 Protection

All coated surfaces shall be protected against abrasion, impact, discoloration and any other damages. All exposed threaded portions shall be suitably protected with either metallic or a non-metallic protection device. All ends of all valves and piping and conduit equipment connections shall be properly sealed with suitable devices to protect them from damage. The parts which are likely to get rusted, due to exposure to weather, should also be properly treated and protected in a suitable manner. All primers/paints/coatings shall take into account the hot humid, corrosive & alkaline, subsoil or over ground environment as the case may be. The requirements for painting specification shall be complied with as detailed out in Chapter 9, Volume II.

20.2 Preservative Shop Coating

- 20.2.1 All exposed metallic surfaces subject to corrosion shall be protected by shop application of suitable coatings. All surfaces which will not be easily accessible after the shop assembly, shall be treated beforehand and protected for the life of the equipment. All surfaces shall be thoroughly cleaned of all mill scales, oxides and other coatings and prepared in the shop. The surfaces that are to be finish-painted after installation or require corrosion protection until installation, shall be shop painted with at least two coats of primer.
- 20.2.2 Transformers and other electrical equipments if included shall be shop finished with one or more coats of primer and two coats of high grade epoxy. The finished colours shall be as per manufacturer's standards, to be selected and specified by the Owner at a later date.
- 20.3 Shop primer for all steel surfaces which will be exposed to operating temperature below 95 degrees Celsius shall be selected by the Bidder after obtaining specific approval of the Owner regarding the quality of primer proposed to be applied. Special high temperature primer shall be used on surfaces exposed to temperature higher than 95 degrees Celsius and such primer shall also be subject to the approval of the Owner.
- 20.4 All other steel surfaces which are not to be painted shall be coated with suitable rust preventive compound subject to the approval of the Owner.
- 20.5 All piping shall be cleaned after shop assembly by shot blasting or other means approved by the Owner. Lube oil piping or carbon steel shall be pickled.
- 20.6 Painting for Civil structures shall be done as per relevant part of technical specification.

21.0 QUALITY ASSURANCE PROGRAMME

To ensure that the equipment and services under the scope of contract whether manufactured or performed within the Contractor's works or at his sub-contractor's premises or at the Employer's site or at any other place of work are in accordance with the specifications, the Contractor shall adopt suitable quality assurance program to control such activities at all points, as necessary. Such programs shall be outlined by the Contractor and shall be finally accepted by the Employer/authorised representative after discussions before the award of the contract. The QA program shall be generally in line

with ISO-9001/IS-14001. A quality assurance program of the contractor shall generally cover the following:

- a) His organization structure for the management and implementation of the proposed quality assurance program
- b) Quality System Manual
- c) Design Control System
- d) Documentation and Data Control System
- e) Qualification data for bidder's key personnel.
- f) The procedure for purchase of materials, parts, components and selection of sub-Bidder's services including vendor analysis, source inspection, incoming raw-material inspection, verification of materials purchased etc.
- g) System for shop manufacturing and site erection controls including process, fabrication and assembly.
- h) Control of non-conforming items and system for corrective actions and resolution of deviations.
- i) Inspection and test procedure both for manufacture and field activities.
- j) Control of calibration and testing of measuring testing equipment.
- k) System for Quality Audits.
- l) System for identification and appraisal of inspection status.
- m) System for authorising release of manufactured product to the Owner.
- n) System for handling, storage and delivery.
- o) System for maintenance of records, and
- p) Furnishing of quality plans for manufacturing and field activities detailing out the specific quality control procedure adopted for controlling the quality characteristics relevant to each item of equipment/component as per formats enclosed as Annexure-I and Annexure-II respectively.

22.0 General Requirements - Quality Assurance

22.1 All materials, components and equipment covered under this specification shall be procured, manufactured, erected, commissioned and tested at all the stages, as per a comprehensive Quality Assurance Programme. An indicative programme of inspection/tests to be carried out by the Bidder for some of the major items is given in the respective technical specification. This is, however, not intended to form a comprehensive programme as it is the Bidder's responsibility to draw up and implement such programme duly approved by the Owner. The detailed Quality Plans for manufacturing and field activities shall be drawn up by the Bidder and will be submitted to Owner for approval. Schedule

of finalisation of such quality plans will be finalised before award. Monthly progress reports on MQP/FQP submission/approval shall be furnished.

- 22.2 Manufacturing Quality Plan will detail out for all the components and equipment, various tests/inspection, to be carried out as per the requirements of this specification and standards mentioned therein and quality practices and procedures followed by Bidder's/ Sub-Bidder's/ sub-supplier's Quality Control Organisation, the relevant reference documents and standards, acceptance norms, inspection documents raised etc., during all stages of materials procurement, manufacture, assembly and final testing/performance testing. The Quality Plan shall be submitted on electronic media e.g. CD or E-mail in addition to hard copy, for review and approval. After approval the same shall be submitted in compiled form on CD-ROM.
- 22.3 Field Quality Plans will detail out for all the equipment, the quality practices and procedures etc. to be followed by the Bidder's "Site Quality Control Organisation", during various stages of site activities starting from receipt of materials/equipment at site.
- 22.4 The Bidder shall also furnish copies of the reference documents/plant standards/acceptance norms/tests and inspection procedure etc., as referred in Quality Plans along with Quality Plans. These Quality Plans and reference documents/standards etc. will be subject to Owner's approval without which manufacturer shall not proceed. These approved documents shall form a part of the contract. In these approved Quality Plans, Owner shall identify customer hold points (CHP), i.e. test/checks which shall be carried out in presence of the Owner's Project Manager or his authorised representative and beyond which the work will not proceed without consent of Owner in writing. All deviations to this specification, approved quality plans and applicable standards must be documented and referred to Owner along with technical justification for approval and dispositioning.
- 22.5 No material shall be despatched from the manufacturer's works before the same is accepted, subsequent to predespatch final inspection including verification of records of all previous tests/inspections by Owner's Project Manager/Authorised representative and duly authorised for despatch by issuance of Material Despatch Clearance Certificate (MDCC).
- 22.6 All material used for equipment manufacture including casting and forging etc. shall be of tested quality as per relevant codes/standards. Details of results of the tests conducted to determine the mechanical properties; chemical analysis and details of heat treatment procedure recommended and actually followed shall be recorded on certificates and time temperature chart. Tests shall be carried out as per applicable material standards and/or agreed details.
- 22.7 The Bidder shall submit to the Owner Field Welding Schedule for field welding activities in the format enclosed at Annexure-V. The field welding schedule shall be submitted to the Owner along with all supporting documents, like welding procedures, heat treatment procedures, NDT procedures etc. at least ninety days before schedule start of erection work at site.
- 22.8 All welding and brazing shall be carried out as per procedure drawn and qualified in accordance with requirements of ASME Section IX/BS-4870 or other International equivalent standard acceptable to the Owner.

- 22.9 All welding/brazing procedures shall be submitted to the Owner or its authorised representative for approval prior to carrying out the welding/brazing.
- 22.10 All brazers, welders and welding operators employed on any part of the contract either in Bidder's/sub-Bidder's works or at site or elsewhere shall be qualified as per ASME Section-IX or BS-4871 or other equivalent International Standards acceptable to the Owner.
- 22.11 Welding procedure qualification & Welder qualification test results shall be furnished to the Owner for approval. However, where required by the Owner, tests shall be conducted in presence of Owner/authorised representative.
- 22.12 For all pressure parts and high pressure piping welding, the latest applicable requirements of the IBR (Indian Boiler Regulations) shall also be essentially complied with. Similarly, any other statutory requirements for the equipment/systems shall also be complied with. On all back-gauged welds MPI/LPI shall be carried before seal welding.
- 22.13 Unless otherwise proven and specifically agreed with the Owner, welding of dissimilar materials and high alloy materials shall be carried out at shop only.
- 22.14 No welding shall be carried out on cast iron components for repair.
- 22.15 All the heat treatment results shall be recorded on time temperature charts and verified with recommended regimes.
- 22.16 All non-destructive examination shall be performed in accordance with written procedures as per International Standards, The NDT operator shall be qualified as per SNT-TC-IA (of the American Society of non-destructive examination). NDT shall be recorded in a report, which includes details of methods and equipment used, result/evaluation, job data and identification of personnel employed and details of co-relation of the test report with the job.
- 22.17 All plates of thickness above 40mm & all bar stock/Forging above 40mm dia shall be ultrasonically tested. For pressure parts, plate of thickness equal to or above 25mm shall be ultrasonically tested.
- 22.18 The Bidder shall list out all major items/ equipment/ components to be manufactured in house as well as procured from sub-contractors bought out items (BOI). All the sub-Bidder proposed by the Bidder for procurement of major bought out items including castings, forging, semi-finished and finished components/equipment etc., list of which shall be drawn up by the Bidder and finalised with the Owner, shall be subject to Owner's approval. The Bidder's proposal shall include vendor's facilities established at the respective works, the process capability, process stabilization, QC systems followed, experience list, etc. along with his own technical evaluation for identified sub-contractors enclosed and shall be submitted to the Owner for approval within the period agreed at the time of pre-awards discussion and identified in review category prior to any procurement. Monthly progress reports on sub-Bidder detail submission / approval shall be furnished. Such vendor approval shall not relieve the Bidder from any obligation, duty or responsibility under the contract.
- 22.19 For components/equipment procured by the contractors for the purpose of the contract, after obtaining the written approval of the Owner, the Bidder's

purchase specifications and inquiries shall call for quality plans to be submitted by the suppliers. The quality plans called for from the sub-Bidder shall set out, during the various stages of manufacture and installation, the quality practices and procedures followed by the vendor's quality control organisation, the relevant reference documents/standards used, acceptance level, inspection of documentation raised, etc. Such quality plans of the successful vendors shall be finalised with the Owner and such approved Quality Plans shall form a part of the purchase order/contract between the Bidder and sub-Bidder. Within three weeks of the release of the purchase orders /contracts for such bought out items /components, a copy of the same without price details but together with the detailed purchase specifications, quality plans and delivery conditions shall be furnished to the Owner on the monthly basis by the Bidder along with a report of the Purchase Order placed so far for the contract.

- 22.20 Owner reserves the right to carry out quality audit and quality surveillance of the systems and procedures of the Bidder's or their sub-Bidder's quality management and control activities. The Bidder shall provide all necessary assistance to enable the Owner carry out such audit and surveillance.
- 22.21 The Bidder shall carry out an inspection and testing programme during manufacture in his work and that of his sub-Bidder's and at site to ensure the mechanical accuracy of components, compliance with drawings, conformance to functional and performance requirements, identity and acceptability of all materials parts and equipment. Bidder shall carry out all tests/inspection required to establish that the items/equipment conform to requirements of the specification and the relevant codes/standards specified in the specification, in addition to carrying out tests as per the approved quality plan.
- 22.22 Quality audit/surveillance/approval of the results of the tests and inspection will not, however, prejudice the right of the Owner to reject the equipment if it does not comply with the specification when erected or does not give complete satisfaction in service and the above shall in no way limit the liabilities and responsibilities of the Bidder in ensuring complete conformance of the materials/equipment supplied to relevant specification, standard, data sheets, drawings, etc.
- 22.23 For all spares and replacement items, the quality requirements as agreed for the main equipment supply shall be applicable.
- 22.24 Repair/rectification procedures to be adopted to make the job acceptable shall be subject to the approval of the Owner/ authorised representative.

22.25 Environmental Stress Screening

All solid state electronic system / equipment / sub assembly shall be free from infant mortile components. For establishing the compliance to this requirement, the contractor / sub – contractor should meet the following

- 1) The Contractor / Sub – contractor shall furnish the established procedure being followed for eliminating infant mortile components. The procedure followed by the Contractor / Sub – contractor should be substantiated along with the statistical figures to validate the procedure being followed. The necessary details as required under this clause shall be furnished at the stage of QP finalization.

OR

In case the Contractor / Sub – contractor do not have any established procedure to eliminate infant mortile components then two number or 10% whichever is less, most densely populated Panels shall be tested for Elevated Temperature Cycle Test as per the following procedure.

Elevated Temperature Test Cycle

During the elevated temperature test which shall be for 48 hours of the total 168 hours of testing, the ambient temperature shall be maintained at 50 deg.C. The equipment shall be interconnected with devices which will cause it to repeatedly perform all operations it is expected to perform in actual service with load on various components being equal to those which will be experienced in actual service.

During the elevated temperature test the cubicle doors shall be closed (or shall be in the position same as they are supposed to be in the field) and inside temperature in the zone of highest heat dissipating components/modules shall be monitored. The temperature rise inside the cubicle should not exceed 10 deg.C above the ambient temp. at 50 deg.C.

In case of any failure during the test cycle, the further course of action should be mutually discussed for demonstrating the intent of the above requirement.

2) Burn in Test Cycle

The 48 hours elevated temperature test shall be followed by 120 hours of burn in test as above except that the temperature shall be reduced to the ambient temperature prevalent at that time.

During the above tests, the process I/O and other load on the system shall be simulated by simulated inputs and in the case of control systems, the process which is to be controlled shall also be simulated. Testing of individual components or modules shall not be acceptable.

In case the Bidder/ sub-Bidder is having any alternate established procedure of eliminating infant mortile components, the detail procedures followed by the Bidder/ sub- Bidder along with the statistical figures to validate the alternate procedure to be forwarded.

- 22.26 The Bidder/Sub-Bidder shall carry out routine test on 100% item at Bidder/sub-Bidder's works. The quantum of check/test for routine & acceptance test by Owner shall be generally as per criteria/sampling plan defined in referred standards. Wherever standards have not been mentioned quantum of check/test for routine / acceptance test shall be as agreed during detailed engineering stage.

23.0 QA Documentation Package

- 23.1 The Bidder shall be required to submit the QA Documentation in two hard copies and two CD ROMs, as identified in respective quality plan with tick (√) mark.

- 23.1.1 Each QA Documentation shall have a project specific Cover Sheet bearing name & identification number of equipment and including an index of its contents with page control on each document.

The QA Documentation file shall be progressively completed by the Supplier's sub-supplier to allow regular reviews by all parties during the manufacturing.

The final quality document will be compiled and issued at the final assembly place of equipment before despatch. However CD-Rom may be issued not later than three weeks.

- 23.2 Typical contents of QA Documentation are as below:-

- a) Quality Plan
- b) Material mill test reports on components as specified by the specification and approved Quality Plans.
- c) Manufacturer / works test reports/results for testing required as per applicable codes and standard referred in the specification and approved Quality Plans.
- d) Non-destructive examination results /reports including radiography interpretation reports. Sketches/drawings used for indicating the method of traceability of the radiographs to the location on the equipment.
- e) Heat Treatment Certificate/Record (Time- temperature Chart)
- f) All the accepted Non-conformance Reports (Major/Minor) / deviation, including complete technical details / repair procedure).
- g) CHP / Inspection reports duly signed by the Inspector of the Owner and Bidder for the agreed Customer Hold Points.
- h) Certificate of Conformance (COC) wherever applicable.
- i) MDCC

- 23.3 Similarly, the Bidder shall be required to submit two sets (two hard copies and two CD ROMs), containing QA Documentation pertaining to field activities as per Approved Field Quality Plans and other agreed manuals/ procedures, prior to commissioning of individual system.

- 23.4 Before despatch / commissioning of any equipment, the Supplier shall make sure that the corresponding quality document or in the case of protracted phased deliveries, the applicable section of the quality document file is completed. The supplier will then notify the Inspector regarding the readiness of the quality document (or applicable section) for review.

- a) If the result of the review carried out by the Inspector is satisfactory, the Inspector shall stamp the quality document (or applicable section) for release.
- b) If the quality document is unsatisfactory, the Supplier shall endeavor to correct the incompleteness, thus allowing to finalize the quality

document (or applicable section) by time compatible with the requirements as per contract documents. When it is done, the quality document (or applicable section) is stamped by the Inspector.

- c) If a decision is made despatch, whereas all outstanding actions cannot be readily cleared for the release of the quality document by that time. The supplier shall immediately, upon shipment of the equipment, send a copy of the quality document Review Status signed by the Supplier Representative to the Inspector and notify of the committed date for the completion of all outstanding actions & submission. The Inspector shall stamp the quality document for applicable section when it is effectively completed. The submission of QA documentation package shall not be later than 3 weeks after the despatch of equipment.

-----INTENTIONALLY KEPT VOID-----

25.0 Inspection, Testing and Inspection Certificates

- 25.1 The word 'Inspector' shall mean the Project Manager and/or his authorized representative and/or an outside inspection agency acting on behalf of the Owner to inspect and examine the materials and workmanship of the works during its manufacture or erection.
- 25.2 The Project Manager or his duly authorized representative and/or an outside inspection agency acting on behalf of the Owner shall have access at all reasonable times to inspect and examine the materials and workmanship of the works during its manufacture or erection and if part of the works is being manufactured or assembled on other premises or works, the Bidder shall obtain for the Project Manager and for his duly authorized representative permission to inspect as if the works were manufactured or assembled on the Bidder's own premises or works.
- 25.3 The Bidder shall give the Project Manager/Inspector fifteen (15) days written notice of any material being ready for testing. Such tests shall be to the Bidder's account except for the expenses of the Inspector's. The Project Manager/Inspector, unless the witnessing of the tests is virtually waived and confirmed in writing, will attend such tests within fifteen (15) days of the date on which the equipment is noticed as being ready for test/inspection failing which the Bidder may proceed with test which shall be deemed to have been made in the inspector's presence and he shall forthwith forward to the inspector duly certified copies of test reports in two (2) copies.
- 25.4 The Project Manager or Inspector shall within fifteen (15) days from the date of inspection as defined herein give notice in writing to the Bidder, or any objection to any drawings and all or any equipment and workmanship which is in his opinion not in accordance with the contract. The Bidder shall give due consideration to such objections and shall either make modifications that may be necessary to meet the said objections or shall inform in writing to the Project Manager/Inspector giving reasons therein, that no modifications are necessary to comply with the contract.
- 25.5 When the factory tests have been completed at the Bidder's or sub-Bidder's works, the Project Manager /Inspector shall issue a certificate to this effect fifteen (15) days after completion of tests but if the tests are not witnessed by the Project Manager /Inspectors, the certificate shall be issued within fifteen (15) days of the receipt of the Bidder's test certificate by the Project Manager /Inspector. Project Manager /Inspector to issue such a certificate shall not prevent the Bidder from proceeding with the works. The completion of these tests or the issue of the certificates shall not bind the Owner to accept the equipment should it, on further tests after erection be found not to comply with the contract.
- 25.6 In all cases where the contract provides for tests whether at the premises or works of the Bidder or any sub-Bidder, the Bidder, except where otherwise specified shall provide free of charge such items as labour, material, electricity, fuel, water, stores, apparatus and instruments as may be reasonably demanded by the Project Manager /Inspector or his authorized representatives to carry out effectively such tests on the equipment in accordance with the

Bidder and shall give facilities to the Project Manager/Inspector or to his authorized representative to accomplish testing.

- 25.7 The inspection by Project Manager / Inspector and issue of Inspection Certificate thereon shall in no way limit the liabilities and responsibilities of the Bidder in respect of the agreed Quality Assurance Programme forming a part of the contract.
- 25.8 To facilitate advance planning of inspection in addition to giving inspection notice as specified at clause no 9.05.03 of this chapter, the Bidder shall furnish quarterly inspection programme indicating schedule dates of inspection at Customer Hold Point and final inspection stages. Updated quarterly inspection plans will be made for each three consecutive months and shall be furnished before beginning of each calendar month.
- 25.9 All inspection, measuring and test equipment used by Bidder shall be calibrated periodically depending on its use and criticality of the test/measurement to be done. The Bidder shall maintain all the relevant records of periodic calibration and instrument identification, and shall produce the same for inspection by the Owner. Wherever asked specifically, the Bidder shall re-calibrate the measuring/test equipment in the presence of Project Manager/Inspector.

-----INTENTIONALLY KEPT VOID-----

30.0 Noise level

The equivalent 'A' weighted sound pressure level measured at a height of 1.0 m above floor level in elevation and at a distance of one (1) meter horizontally from the nearest surface of any equipment / machine, furnished and installed under these specifications, expressed in decibels to a reference of 0.0002 microbar, shall not exceed 85 dBA except for

- a) Safety valves and associated vent pipes for which it shall not exceed 105 dBA.
- b) Regulating drain valves in which case it shall be limited to 90 dBA.
- c) TG unit in which case it shall not exceed 90 dBA.
- d) For HP-LP bypass valves and other intermittently operating control valves, the noise level shall be within the limit of 85 dBA.
- e) Mill noise which will be limited to 85-90 dBA.

31.0 PACKAGING AND TRANSPORTATION

All the equipments & spares shall be suitably protected, coated, covered or boxed and crated to prevent damage or deterioration during transit, handling and storage at Site till the time of erection. Each spare shall be clearly marked or labelled on the outside of the packing with its description. When more than one spare part is packaged in a single case, a general description of the contents shall be shown on the outside of such a case and other packages must be suitably marked and numbered for the purpose of identification. All cases, containers or packages, are liable to be opened for such examination as may be considered reasonable by the Engineer. In case of equipment supplied with grease/lubricants from imported origin, the supplied shall clearly indicate the indigenous equivalent of the grease/lubricant and source of supply so as to enable the Owner to procure these items from indigenous sources. While packing all the materials, the limitation from the point of view of the sizes of railway wagons available in India should be taken account of. The Bidder shall be responsible for any loss or damage during transportation, handling and storage due to improper packing. The Bidder shall ascertain the availability of Railway wagon sizes from the Indian Railways or any other agency concerned in India well before effecting dispatch of equipment. Before dispatch it shall be ensured that complete processing and manufacturing of the components is carried out at shop, only restricted by transport limitation, in order to ensure that site works like grinding, welding, cutting & pre-assembly to bare minimum. The Owner's Inspector shall have right to insist for completion of works in shops before dispatch of materials for transportation.

32.0 ELECTRICAL EQUIPMENTS/ENCLOSURES

All electrical equipments and devices, including insulation, heating and ventilation devices shall be designed for ambient temperature and a maximum relative humidity as specified elsewhere in the specification.

ANNEXURE-I

MFGR.'s LOGO	MANUFACTURER'S NAME AND ADDRESS		MANUFACTURING QUALITY PLAN				PROJECT : PACKAGE : CONTRACT NO. : MAIN-SUPPLIER :								
			ITEM :		QP NO.: REV.NO: DATE: PAGE: ... OF....										
SL. NO	COMPONENT & OPERATIONS	CHARACTERI STICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK		REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		AGENCY			REMARKS	
					M	C/N					M	C	N		
1.	2.	3.	4.	5.	6.		7.	8.	9.	D*	** 10.			11.	
				LEGEND: * RECORDS, IDENTIFIED WITH "TICK" (✓) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION.** M: MANUFACTURER/SUB-SUPPLIER C: SUPPLIER/NOMINATED INSPECTION AGENCY, N: THE OWNER P: PERFORM W: WITNESS AND V: VERIFICATION. AS APPROPRIATE, CHP: THE OWNER SHALL IDENTIFIED IN COLUM "N"				 		DOC. NO.: REV..... CAT.....					
MANUFACTURER/ SUB-SUPPLIER		MAIN- SUPPLIER						FOR THE OWNER USE							
SIGNATURE															
								REVIEWED BY		APPROVED BY		APPRO VAL SEAL			

ANNEXURE-II

SUPPLIER'S LOGO		SUPPLIER'S NAME AND ADDRESS		FIELD QUALITY PLAN			PROJECT : PACKAGE : CONTRACT NO. : MAIN-SUPPLIER:				
				ITEM :		QP NO.:					
				SUB-SYSTEM :		REV.NO.:					
						DATE:					
						PAGE: OF....					
S. N O	ACTIVITY AND OPERATION	Characteristics / instruments		CLASS# OF CHECK	TYPE OF CHECK	QUANTU M OF CHECK	REFERENC E DOCUMENT	ACCEPTA NCE NORMS	FORMAT OF RECORD		REMARK S
1.	2.	3.		4.	5.	6.	7.	8.	9.	D*	10.
				LEGEND: * RECORDS , INDENTIFIED WITH "TICK" (✓) SHALL BE ESSENTIALLY INCLUDED BY SUPPLIER IN QA DOCUMENTATION. LEGEND TO BE USED: CLASS #: A = CRITICAL, B=MAJOR, C=MINOR; 'A' SHALL BE WITNESSED BY THE OWNER FQA, 'B' SHALL BE WITNESSED BY OWNER'S ERECTION / CONSTRUCTION DEPTT. AND 'C' SHALL BE WITNESSED BY ERECTION SUPPLIER (A & B CHECK SHALL BE OWNER CHP STAGE)			 DOC. NO.: REV.....				
MANUFACTURER/ SUB-SUPPLIER		MAIN- SUPPLIER									
SIGNATURE							FOR THE OWNER USE		REVIEWED BY		APPRO VED BY

ANNEXURE-IV

[illegible]

ANNEXURE-V

		Project : Stage :		FIELD WELDING SCHEDULE (To be raised by the Bidder)								DOC. NO.:				
		Bidder :		Welding Code:								REV. NO.:				
		Bidder No. :										DATE :				
		System :										PAGE : OF				
Sl. No.	DRG No. for Weld Location and Identification mark	Description of parts to welded	Matl. Spec.	Dimensions		Process of welding	Type of Weld	Electrode filler spec.	WPS. No.	Min. pre-heat	Heat treatment		NDT method/Quantum	REF		Remarks
											Temp.	Holding time		Spec. No.	ACC Norm Ref.	
NOTES:																
SIGNATURE																

ANNEXURE-VI
DOCUMENTS DISTRIBUTION SCHEDULE

S.No.	Description of Document	DESEIN				UPRVUNL			
		HO		SITE		HO		SITE	
		HC	CC	HC	CC	HC	CC	HC	CC
1.	Drawings, Data Sheets, Calculation, all equipment / Instrument Schedule, BOM etc. a) For Approval b) Resubmission c) For Information	6*	1	-	-	2	1	-	-
2.	Final Approved Documents	2	1 + 1 CD	1	1	1	1 + 2 CD	4	1 + 1 CD
3.	Drawings / Documents 'As Built'	2	1 + 1 CD	1	1	2	1 + 2 CD	4	1 + 1 CD
4.	Type Test Reports (Initial)	4*	1 + 1 CD	-	-	2	1 + 2 CD	-	-
5.	Type Test Report (Final)	2	1 + 1 CD	1	1	2	1 + 2 CD	4	1 + 1 CD
6.	Piping / Equipment Analysis (Transient) etc., Model Study Report (Draft) including Input / Output date etc.	4*	1	-	-	2	1 + 1 CD	-	-
7.	Piping / equipment Analysis (Transient) etc. Model Study Report (Final Approval) including Input / Output date	2	1 + 1 CD	-	-	2	1 + 2 CD	2	1 + 1 CD
8.	Erection Manual (Draft)	3*	1CD	-	-	1	1CD	-	-

S.No.	Description of Document	DESEIN				UPRVUNL			
		HO		SITE		HO		SITE	
		HC	CC	HC	CC	HC	CC	HC	CC
9.	Erection Manual 'Final'	1	1CD	1	-	1	1CD	2	1CD
10.	O&M Manual 'Draft'	3*	1CD	+	-	1	1CD	-	-
11.	O&M Manual 'Final'	1	1CD	1	-	1	1CD	2	2CD
12.	Commissioning Procedure 'Draft'	3*	1CD	-	-	1	1CD	-	-
13.	Commissioning Procedure 'Final'	1	1CC	1	-	1	1CD	2	1CD
14.	PG Test Procedure "Draft"	3*	1	-	-	1	1	-	-
15.	PG Test Procedure 'Final'	1	1 + 1 CD	1	-	2	1 + 1 CD	2	1 + 1 CD
16.	Progress Report	3	1CD	1	-	2	1CD	1	1CD
17.	PG Test Report for Approval	4*	1	-	-	2	1 + 1 CD	-	-
18.	Approved PG Test Report	1	1 + 1 CD	1	-	2	1 + 1 CD	4	1 CD
19.	Project Completion Report	1	1 + 1 CD	1	-	1	1CD	1	1CD
20.	Vendor Details in respect of proposed vendors including Contractor's evaluation Report	1	1CD	-	-	1	1CD	-	-
21.	Monthly Vendor / QP Approval Status	1	1	-	-	2	1	1	1
22.	Manufacturing QPs, Field QPs for review / comments	6*	1	-	-	2	1CD	-	-
23.	Manufacturing QPs, Field QP, Final	1	1CD	1	-	2	1CD	2	1CD
24.	QA documents Package for equipment / field activities etc.	1	1CD	1	-	1	1CD	1	1CD

- * - Consultant will return one (1) commented document to Vendor and CE (UPRVUNL), Lucknow
- HC - Hard Copy
- CC - Soft Copy thru e-mail
- CD - CD ROM
- HO - Head Office of Consultant / UPRVUNL



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1C

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

QUALITY ASSURANCE AND INSPECTION REQUIREMENT

 MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR		STANDARD QUALITY PLAN						PROJECT					
		ITEM : LUBE OIL PUMPS SUB-SYSTEM: CLEAN/ DIRTY/ RETURN OIL PUMPS			QP NO. PE:QP: STD:567:A001 DATE 07/07/07 REV. 00 PAGE 1 of 5			PACKAGE LUBE OIL PUMPS CONTRACT NO PO NO.		CONTRACTOR BHARAT HEAVY ELECTRICALS LTD.			
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		AGENCY** 10			REMARKS
1	2	3	4	5	6	7	8	9	D*	M	C	N	11
1.0	RAW MATERIALS & BOUGHT OUTS CONTROL												
1.1	PUMP CASING (Pump Body)	Physical Properties	Major	Physical Test	1/Cast	Appd Drg. /Data-sheet	Appd Drg. /Data-sheet	Lab Reports	D*	P	V	V	
		Chemical Properties	Major	Chemical Test	1/Cast	-do-	-do-	Lab Report	D*	P	V	V	
1.2	END COVERS	Physical Properties	Major	Physical Test	1/Cast	- do -	- do -	Lab Reports	D*	P	V	V	
		Chemical Properties	Major	Chemical Test	1/Cast	- do -	- do -	Lab Reports	D*	P	V	V	
1.3	SHAFTS	Physical Properties	Major	Physical Test	1/ Bar	- do -	- do -	Lab Reports	D*	P	V	V	
		Chemical Properties	Major	Chemical Test	1/Bar	- do -	- do -	Lab Reports	D*	P	V	V	
		Sub surface defects	Major	UT	100%	ASTM A 388 100% back wall echo	Fall in back wall echo 20% Max. Defect Echo 20% Max of B.W.E.	Inspection Report	D*	P	V	V	
		Hardness	Major	Hardness	100%	Appd Drg/ Datasheet	Appd Drg/ Datasheet	Lab Rprt.	D*	P	V	V	
1.4	GEARS (DRIVING AND DRIVEN)	Physical Properties	Major	Physical Test	1/ Bar	Appd Drg./ Datasheet	Appd Drg./ Datasheet	Lab Report	D*	P	V	V	
		Chemical Properties	Major	Chemical test	1/ Bar	Appd Drg./ Datasheet	Appd Drg./ Datasheet	Lab Report	D*	P	V	V	
				Heat Treatment	100%	-do-	-do-	HT Chart	D*	P	V	V	

		LEGEND : * RECORDS IDENTIFIED WITH “D” SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: CUSTOMER/ CONSULTANT INDICATE ‘P’-PERFORM, ‘W’-WITNESS AND ,‘V’-VERIFICATION AS APPROPRIATE, ‘CHP’ SHALL BE IDENTIFIED IN COLUMN “REMARKS” BY CUSTOMER/ CONSULTANT	FOR CUST/CONSUL USE	DOC.NO.:	
MANUFACTURER / SUBCONTRACTOR	CONTRACTOR				
SIGNATURE			REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY	

		MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR	STANDARD QUALITY PLAN					PROJECT					
			ITEM : LUBE OIL PUMPS SUB-SYSTEM: CLEAN/ DIRTY/ RETURN OIL PUMPS			QP NO.	PE:QP:	PACKAGE LUBE OIL PUMPS					
						DATE	07/07/07	CONTRACT NO					
						REV.	00	PO NO.					
						PAGE	2 of 5	CONTRACTOR		BHARAT HEAVY ELECTRICALS LTD.			
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD	AGENCY**	10			REMARKS
1	2	3	4	5	6	7	8	9	D*	M	C	N	11
1.5	Relief Valve Body	Sub surface defects	Major	UT	100%	ASTM A 388	Fall in back wall echo 20% Max. Defect Echoe 20% Max of B.W.E.	Inspection Report	D*	P	V	V	
		Hardness Test	Major	Hardness	100%	Appd Dwg/ Data sheet	Appd Dwg/ Data sheet	Lab Rprt.	D*	P	V	V	
		Physical Properties	Major	Physical Test	1/Bar	Appd Drg/Data sheet	Appd Drg/Data sheet	Lab Reports	D*	P	V	V	
1.6	Flanges (Companion)	Chemical Properties	Major	Chemical Test	1/Bar	-do-	-do-	Lab Reports	D*	P	V	V	
		Physical Properties	Major	Physical Test	1/ Heat	-do-	-do-	Lab Reports	D*	P	V	V	
1.7	Bearings, Oil Seals, Mechanical Seals	Chemical Properties	Major	Chemical Test	1/Heat	-do-	-do-	Lab Reports	D*	P	V	V	
		Make, size, Bearing number, finish, fitment	Major	Visual, Fitment	100%	Manufacturing Drawing	Manufacturing drawing	Log book		P	V	-	
1.8	Electric Motors	Review of Routine test certificate	Major	Review	100%	IS 325/IEC –34 for export job	Appd Drg/Data sheet	Routine test report	D*	P	V	V	
2.0	IN PROCESS CONTROL												
2.1	All components	1. Workmanship &	Major	Visual Measure-	100%	Mfg. Drawing	Mfg. Drawing	Log book		P	V	-	

		LEGEND : * RECORDS IDENTIFIED WITH “D” SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: CUSTOMER/ CONSULTANT INDICATE ‘P’-PERFORM, ‘W’-WITNESS AND ,‘V’-VERIFICATION AS APPROPRIATE, ‘CHP’ SHALL BE IDENTIFIED IN COLUMN “REMARKS” BY CUSTOMER/ CONSULTANT	FOR CUST/CONSUL USE	DOC.NO.:	
MANUFACTURER / SUBCONTRACTOR	CONTRACTOR				
SIGNATURE			REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY	

		MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR		STANDARD QUALITY PLAN				PROJECT					
				ITEM : LUBE OIL PUMPS SUB-SYSTEM: CLEAN/ DIRTY/ RETURN OIL PUMPS		QP NO.	PE:QP: STD:567:A001	PACKAGE LUBE OIL PUMPS		CONTRACT NO		PO NO.	
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD		AGENCY** 10			REMARKS
1	2	3	4	5	6	7	8	9	D*	M	C	N	11
2.2	Pump Casing, Covers, Relief Valve Housing & Curing of Pump Casing Gaskets	Finish 2. Dimensions Leak tightness	Critical	ment Hydro test at 2 x maximum allowable working pressure for 30 mins.	100%	Data Sheets / Technical Specifications	No leakages, No deformation	Inspection Report.	D*	P	W	V	Pump to be tested with oil of viscosity closest to lube oil @ rated viscosity for Pressure, @ lowest
2.3	Gears/ Screws & Shaft	Surface Defects	CR	PT	100%	ASME E 165	No surface defects	Inspection Report	D*	P	V	V	
2.4	Gears/ Screws – Induction Hardening	Hardness	Major	Hardness Measurement	100%	Appd Dwg/ Data sheet	Appd Dwg/ Data sheet	Inspection Report	D*	P	V	V	
3.0	SUB ASSEMBLY / ASSEMBLY CONTROL FINAL INSPECTION AND TESTING												
3.1	Rotor Assembly	Static, residual dynamic balancing	CR	Static, dynamic Balancing	100%	ISO-1940	IS)-1940 G 6.3	Inspection Report	D*	P	V	V	
3.2	Pump Assembly	Completeness	Major	Visual, Measurement	100%	Manufacturing Drawing	Manufacturing Drawing	Check List/ Card	D*	P	V	V	
3.3	Complete Pump with Unit Motor	1. Performance for H v/s Q, H v/s P, H v/s Pump eff. 2. Vibration / Noise 3. Relief Valve set	CR	Performance Test	100%	Hydraulic Institute Standards of USA. Tech Specn, Appd. Data	Hydraulic Institute Standards of USA. Tech Specn, Appd. Data	Test Report	D*	P	W	W	

		LEGEND : * RECORDS IDENTIFIED WITH “D” SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: CUSTOMER/ CONSULTANT INDICATE ‘P’-PERFORM, ‘W’-WITNESS AND ,‘V’-VERIFICATION AS APPROPRIATE, ‘CHP’ SHALL BE IDENTIFIED IN COLUMN “REMARKS” BY CUSTOMER/ CONSULTANT	FOR CUST/CONSUL USE	DOC.NO.:	
MANUFACTURER / SUBCONTRACTOR	CONTRACTOR				
SIGNATURE			REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY	

		MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR		STANDARD QUALITY PLAN				PROJECT					
				ITEM : LUBE OIL PUMPS SUB-SYSTEM: CLEAN/ DIRTY/ RETURN OIL PUMPS		QP NO. PE:QP: STD:567:A001 DATE 07/07/07 REV. 00 PAGE 4 of 5		PACKAGE LUBE OIL PUMPS CONTRACT NO PO NO. CONTRACTOR BHARAT HEAVY ELECTRICALS LTD.					
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD	AGENCY** 10			REMARKS	
1	2	3	4	5	6	7	8	9	D*	M	C	N	11
3.4	Cleaning, protection, painting & packing	pressure 4. Leakage 5. Temp rise. 6. Over all dimensions 7. Orientation 8. Strip Test	Major Major Critical	Measurement Visual Visual	100%	sheets Approved GA Drgs. No visible damage	sheets Vibration Level = 50 Microns ,max. Noise Level = 85 dB max. No visible damage	Inspection Report	D*	P	V	V	viscosity for capacity , @ highest viscosity for power Strip test in case of abnormal noise only.
		Activity compliance	MI	Visual	100%	Tech / Mfg. Specn for packing; Appd dwg for cleaning, protection & painting including shade	Tech / Mfg. Specn for packing; Appd dwg for cleaning, protection & painting including shade						

LEGEND

MI: Minor Characteristics affecting appearance.

MA: Major characteristics affecting performance , redution in life , large down time etc.

		LEGEND : * RECORDS IDENTIFIED WITH "D" SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: CUSTOMER/ CONSULTANT INDICATE 'P'-PERFORM, 'W'-WITNESS AND , 'V'-VERIFICATION AS APPROPRIATE, 'CHP' SHALL BE IDENTIFIED IN COLUMN "REMARKS" BY CUSTOMER/ CONSULTANT	FOR CUST/CONSUL USE	DOC.NO.:	
MANUFACTURER / SUBCONTRACTOR	CONTRACTOR				
SIGNATURE			REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY	

	MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR		STANDARD QUALITY PLAN					PROJECT				
			ITEM : LUBE OIL PUMPS SUB-SYSTEM: CLEAN/ DIRTY/ RETURN OIL PUMPS			QP NO. PE:QP: DATE STD:567:A001 REV. 07/07/07 PAGE 00 5 of 5		PACKAGE LUBE OIL PUMPS CONTRACT NO PO NO. CONTRACTOR BHARAT HEAVY ELECTRICALS LTD.				
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD	AGENCY**	REMARKS		
1	2	3	4	5	6	7	8	9	D*	M	C	N

CR: Critical Characteristics affecting safety of equipment & personnel.
P: Agency which performs the test inspection
W: Agency which witness the test inspection.
V: Agency which verifies test certificates, inspection reports and carries out audit check of component/operation.
M: Manufacturer/ Sub-Contractor.
C: Contractor nominated inspection agency / BHEL.
N: Customer/ Consultant
CHP: Customer/ consultant hold point

		LEGEND : * RECORDS IDENTIFIED WITH "D" SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: CUSTOMER/ CONSULTANT INDICATE 'P'-PERFORM, 'W'-WITNESS AND , 'V'-VERIFICATION AS APPROPRIATE, 'CHP' SHALL BE IDENTIFIED IN COLUMN "REMARKS" BY CUSTOMER/ CONSULTANT	FOR CUST/CONSUL USE	DOC.NO.:	
MANUFACTURER / SUBCONTRACTOR	CONTRACTOR				
SIGNATURE			REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY	

	MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR		STANDARD QUALITY PLAN					PROJECT					
			ITEM : BASKET (SIMPLEX/DUPLEX) OIL STRAINER SUB-SYSTEM: LUBE OIL			QP NO. PE:QP:STD:567:A0 012 DATE 07/07/07 REV. 00 PAGE 1 of 3		PACKAGE LUBE OIL PUMPS CONTRACT NO LOI No. CONTRACTOR BHARAT HEAVY ELECTRICALS LTD.					
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD	AGENCY** 10				REMARKS
1	2	3	4	5	6	7	8	9	D*	M	C	N	11
1.0	RAW MATERIALS & BOUGHT OUT CONTROL												
1.1	STRAINER BODY , FLANGE, BOTTOM PLATE, TOP COVER	Physical Properties	Major	Physical Test	1sample /Heat	Appd Drg. /Data-sheet	Appd Drg. /Data-sheet	Lab Reports	D*	P	V	-	FOR DUPLEX STRAINER ONLY
		Chemical Properties	Major	Chemical Test	1sample /Heat	-do-	-do-	Lab Report	D*	P	V	-	
1.2	3 WAY VALVE HOUSING CASTING, BACKING PLATE	Physical Properties	Major	Physical Test	1/Cast	- do -	- do -	Lab Reports	D*	P	V	-	
		Chemical Properties	Major	Chemical Test	1/Cast	- do -	- do -	Lab Reports	D*	P	V	-	
1.3	SCREEN	Chemical composition	Major	Chemical Test	1/Sample	- do -	- do -	Lab Reports	D*	P	V	-	
2.0	IN PROCESS CONTROL												
2.1	Welding Procedure	Correctness/ Welding parameters	Major	Review	100%	ASME, SEC-IX	ASME, SEC-IX	QW 482	D*	P	V	-	
2.2	PQR & Welders Qualification	Weld Soundness	Major	Physical test/ RT	100%	ASME, SEC-IX	ASME, SEC-IX	QW 483 & QW 484	D*	P	V	-	
2.3	Weld Fit ups	Dimension & Alignment Orientation	Major	Measurement/ Visual	100%	Appd WPS/ Appd dwg	Appd WPS	QW 482	D*	P	V	-	
2.4	Weldments- Root & Final Run (As applicable)	Weld defects	Major	Penetrant test	100%	ASME- E 165	No defect	Mfr test reports	D*	P	V	-	
		LEGEND :					FOR DVB/NTPC USE	DOC.NO.:					
MANUFACTURER / SUBCONTRACTOR		* RECORDS IDENTIFIED WITH "TICK" SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: DVB/NTPC INDICATE 'P'-PERFORM, 'W'-WITNESS AND 'V'-VERIFICATION AS APPROPRIATE, 'CHP' SHALL BE IDENTIFIED IN COLUMN "REMARKS" BY DVB/NTPC											
SIGNATURE							REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY					

		MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR		STANDARD QUALITY PLAN				PROJECT						
				ITEM : BASKET (SIMPLEX/DUPLEX) OIL STRAINER SUB-SYSTEM: LUBE OIL		QP NO. PE:QP:STD:567:A0 012 DATE 07/07/07 REV. 00 PAGE 2 of 3		PACKAGE LUBE OIL PUMPS CONTRACT NO LOI No. CONTRACTOR BHARAT HEAVY ELECTRICALS LTD.						
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD	AGENCY** 10				REMARKS	
1	2	3	4	5	6	7	8	9	D*	M	C	N	11	
2.5	Assembly of internal basket	Orientation & fittings of internal	Major	Visual & Proper Fitment	100%	Appd Drawing/ Data Sheet	Appd dwgs & manufacturing standards	Inspection Report	D*	P	V	-		
3.0	FINAL INSPECTION AND TESTING													
3.1	Cleaning, protection, painting & packing	Completeness Cleanliness Dimension of screen & other parts Leaktightness	Major	Visual Measurement	100%	Appd Dwg	Appd Dwg/ Data Sheet/ Mfr standard	Inspection Report	D*	P	V	V		
3.2		Flow v/s pressure drop test	Major	Hydrotest at 1.5 times the design pressure ; holding time 30 minutes	100%	Appd Drg & Data Sheet	Appd Dwg/ Data Sheet/ Mfr standard	Inspection Report	D*	P	V	V		
3.3		Activity compliance	MI	Visual	100%	Tech / Mfg. Specn for packing; Appd dwg for cleaning, protection & painting including	Tech / Mfg. Specn for packing; Appd dwg for cleaning, protection & painting including	Inspection Report	D*	P	V	V		
3.4														
		LEGEND :					FOR DVB/NTPC USE	DOC.NO.:						
MANUFACTURER / SUBCONTRACTOR		* RECORDS IDENTIFIED WITH "TICK" SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: DVB/NTPC INDICATE 'P'-PERFORM, 'W'-WITNESS AND, 'V'-VERIFICATION AS APPROPRIATE, 'CHP' SHALL BE IDENTIFIED IN COLUMN "REMARKS" BY DVB/NTPC												
SIGNATURE							REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY						

	MANUFACTURER'S NAME & ADDRESS BHEL APPROVED VENDOR		STANDARD QUALITY PLAN					PROJECT				
			ITEM : BASKET (SIMPLEX/DUPLEX) OIL STRAINER SUB-SYSTEM: LUBE OIL			QP NO. PE:QP:STD:567:A0 012 DATE 07/07/07 REV. 00 PAGE 3 of 3		PACKAGE LUBE OIL PUMPS CONTRACT NO LOI No. CONTRACTOR BHARAT HEAVY ELECTRICALS LTD.				
SR. NO.	COMPONENT & OPERATIONS	CHARACTERISTICS	CLASS	TYPE OF CHECK	QUANTUM OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORMS	FORMAT OF RECORD	AGENCY**			REMARKS
1	2	3	4	5	6	7	8	9	D*	M	C	N
						shade	shade					

LEGEND

- MI:** Minor Characteristics affecting appearance.
MA: Major characteristics affecting performance , redution in life , large down time etc.
CR: Critical Characteristics affecting safety of equipment & personnel.
P: Agency which performs the test inspection
W: Agency which witness the test inspection.
V: Agency which verifies test certificates, inspection reports and carries out audit check of component/operation.
M: Manufacturer/ Sub-Contractor.
C: Contractor nominated inspection agency / BHEL.
N: Customer/ Consultant
CHP: Customer/ consultant hold point

		LEGEND : * RECORDS IDENTIFIED WITH "TICK" SHALL BE ESSENTIALLY INCLUDED BY CONTRACTOR IN QA DOCUMENTATION ** M: MANUFACTURER/SUB CONTRACTOR ,C: CONTRACTOR /NOMINATED INSPECTION AGENCY ,N: DVB/NTPC INDICATE 'P'-PERFORM, 'W'-WITNESS AND 'V'-VERIFICATION AS APPROPRIATE, 'CHP' SHALL BE IDENTIFIED IN COLUMN "REMARKS" BY DVB/NTPC	FOR DVB/NTPC USE	DOC.NO.:	
MANUFACTURER / SUBCONTRACTOR	CONTRACTOR				
SIGNATURE			REVIEWED BY	NAME & SIGN OF APPROVING AUTHORITY	



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1D

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

MASTER DRAWING LIST WITH SUBMISSION SCHEDULE



TITLE:

**TECHNICAL SPECIFICATION
LUBE OIL TRANSFER PUMPS
1X660 MW UPRVUNL PANKI TPS, EXTENSION**

SPEC. NO.: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1D

REV. NO.: 00

DATE JULY 2019

DRAWINGS/ DOCUMENTS REQUIRED DURING DETAIL ENGINEERING

The successful bidder shall submit the following drawings / documents during detail engineering for approval / information / reference (as the case may be):-

Sl. No.	BHEL Drawing / Document No.	Title	Schedule Date	Resubmission after incorporating comments
1	PE-V0-417-567-A001	Data sheet & GA of LOP	4 weeks from LOI	Within 1 week
2	PE-V0-417-567-A002	Data sheet & GA of Strainer	4 weeks from LOI	Within 1 week
3	PE-V0-417-567-A003	Data sheet & GA of lube oil pump motor	4 weeks from LOI	Within 1 week
4	PE-V0-417-567-A004	QAP of Lube oil pump and strainer	4 weeks from LOI	Within 1 week
5	PE-V0-417-567-A005	O & M Manual of lube oil pumps	8 weeks from LOI	Within 1 week



TITLE:

**TECHNICAL SPECIFICATION
LUBE OIL TRANSFER PUMPS
1X660 MW UPRVUNL PANKI TPS, EXTENSION**

SPEC. NO.: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1D

REV. NO.: 00

DATE JULY 2019

NOTE : Drwg/ Document shall be uploaded by the successful bidder on WRENCH /DMS.Procedure for the same will be informed after award of contract.

COMPANY SEAL

SIGNATURE : _____

NAME : _____

DESIGNATION: _____

COMPANY: _____

DATE: _____



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1E

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

PAINTING SPECIFICATION

SUB-SECTION-C1E: PAINTING

1.0 SCOPE

This section covers the painting requirements for the power plant equipment, structures, piping etc. and any other surface required to be painted. The painting system should ensure optimal protection of the installation with minimum need for maintenance, environmental friendly & easy to apply.

2.0 CODES AND STANDARDS

Painting of equipment shall be carried out as per the specifications indicated below and shall conform to the relevant IS contract for the material and workmanship.

The following Indian Standards may be referred to for carrying out the painting job:

IS: 5	:	Colours for ready mixed paints and enamels
IS: 101	:	All Parts and Sections for paint testing
IS: 1303	:	Glossary of terms relating to paints
IS: 2379	:	Colour code for identification of pipelines
IS: 1477	:	Code of practice for painting of ferrous metals in buildings (Parts I & II)
IS: 2524	:	Code of practice for painting of non-ferrous metals in buildings (Parts I & II)
IS: 6278	:	Code of practice for white washing and colour Washing
IS: 13183	:	Aluminium Paint, heat Resistant specification
IS: 158	:	Ready mixed paint, brushing, bituminous, black, Lead free, acid, alkali, water and heat resisting
IS: 2074	:	Ready mixed paint, air drying, red Oxide Zinc Chrome, priming
IS: 104	:	Ready mixed paint, brushing, Zinc Chrome, priming
IS: 2932	:	Enamel, synthetic, exterior (a) undercoating (b) finishing.
IS: 2629	:	Recommended Practice for Hot Dip Galvanising
BS EN ISO 14713	:	Code of practice for protection of iron & steel structure against corrosion
ISO 8501-1	:	Preparation of steel substrates before application of paint & related Products. Part-1: Rust grades & preparation grades of uncoated steel substrates & steel substrates after overall removal of previous coatings
ISO 8502-3	:	Assessment of dust on steel surface prepared for painting (Pressure sensitive tape method)
ISO 12944 (Part 1 to 7)	:	Corrosion protection of steel structures by Protective paint systems
SSPC	:	US Specifications of Steel Structures Painting Council, SSPC Volumes I and II
SSPC-SP-08	:	Surface preparation by Pickling
NORSOK M-501	:	Surface preparation & Protective coating
ISO 20340	:	Pre-Qualification test
ASTM	:	American Standard Test Method for paints and coatings
AWWA	:	American Water Works Association

In the event of conflict between the Codes and Standards referred to in the specification and the requirement of this specification, the latter shall govern. Statutory and Local regulations shall be strictly followed in selection and application of paint.

3.0 GENERAL

- 3.1 This specification covers the surface preparation, method of application and material to be used for all coating of equipment, steel structures and piping. Steel material subjected to surface preparation on shop/site shall have minimum requirements in accordance with Rust Grade B (SSPC/SSPM Volume-2).
- 3.2 Coating materials according to SSPC, EN ISO, ASTM, BIS or DIN standards, shall be used. The paint shall comply with applicable laws, regulations, ordinances etc., of the local authority, state or the nation pertains to the work. The materials shall be matched with each other so that they are compatible. Coatings deviating this specification shall be subject to approval. Standards of surface preparation and painting shall give a time to first maintenance of 10 years.
- 3.3 The paint to be applied shall be approved by Customer / Engineer.
- 3.4 All paints & paint material used shall be procured from approved manufacturers. Paint shall be supplied in manufacturers original containers with the description of content, specification No., colour, ref no, date of manufacture, shelf life expiry date & pot life.
- 3.5 The paint manufacturers shall provide coating system data sheet for each coating system to be used containing the following information:
1. Surface preparations
 2. Film thickness (min and max)
 3. Min and max recoating intervals at relevant temperatures
 4. Mixing ratio, thinner details and coating repair systems
- 3.6 The sample for testing the paint being used may be taken by the customer at any time.
- 3.7 In general Shop fabricated equipment will be delivered to the site coated with a shop applied system or the manufacturer's standard finish in accordance with the requirements of this specification.
- 3.8 For equipment that has received shop prime coat, touch-up prime coat and additional coats shall be applied in accordance with the coating schedule. It is responsibility of the vendor to ensure compatibility between shop and field applied paint systems.
- 3.9 Necessary precautions shall be provided to all equipment, structures to protect other surfaces from abrasive blasting, coating over spray and spatter. Damage to other surfaces or equipment shall be repaired by the vendor.
- 3.10 The Contractor shall submit the following for review and approval by the Customer:

1. Manufacturer's recommended paint scheme for the project
2. Latest published product & instructions for application data,
3. Procedures for surface preparation and application.
4. Pre qualification for equipments and blasting materials, product, procedure and personnel qualifications for the paint and painting systems.
5. Painting repair procedures

Painting records shall contain:

- Equipment/components/location painted
- Date of painting
- Paint details such as specification No, colour, date of manufacture, shelf life, expiry date
- Application equipments
- Ambient conditions at the time of painting
- Surface temperature
- Drying time between coating, DFT and number of coatings
- Appropriate work plan for painting.

- 3.11 The supply of all necessary equipments, weather protection, and scaffolding for painting to ensure work is carried out in accordance with the specification and agreed programme.
- 3.12 Maintenance of the paint work until completion of the contract, this shall include repair of any damaged areas caused by third party.
- 3.13 Disposal of painting waste resulting from painting, shall comply with applicable laws, regulations, ordinances etc., of the local authority, state or the nation pertains to the work and coating materials.
- 3.14 It is a mandatory requirement that all operatives working to this procedure take full cognizance and implement necessary safety precautions.

4.0 PREPARATION OF SURFACES

- 4.1 All surfaces to be painted shall be thoroughly cleaned of all grease, oil, loose mill scale, dust, rust, weld spatters, sharp edges and any other foreign matter. Removal of grease and oil contamination shall be in accordance with SSPC-SP1 prior to cleaning process described below.
- 4.2 Mechanical cleaning by power tool and scrapping with steel wire brushes shall be adopted to clear the surfaces. However, in certain locations where power tool cleaning cannot be carried out, hand scrapping may be permitted with steel wire brushes and/or abrasive paper. Cleaning with solvents shall be resorted to only in such areas where other methods specified above have not achieved the desired results. Cleaning with solvents shall be adopted only after written approval of the Engineer.
- 4.3 The blast cleaned surface shall be checked for signs of salt contamination as per ISO 8502-6 & 9. The maximum allowable level of contamination shall be 20 mg/m². Surfaces that do not meet these criteria shall be reprocessed.

Mechanical Cleaning:

Manual/power tool cleaning shall be done as per grade St-2 or St-3, of ISO 8504-3. This method to be used for repair painting or on already painted

surface and in case of usage on new construction painting prior approval may be obtained from purchaser/engineer.

	Condition of surface	ISO 8504-3	SIS 055900	SSPC
Hand tool cleaning	Rusted	C St2	C St2	SP2
	Rusted and pitted	D St2	D St2	SP2
Power tool cleaning	Rusted	C St3	C St3	SP3
	Rusted and pitted	D St3	D St3	SP3

- i) Grade St-2: Thorough scraping and wire brushing, machine brushing, grinding etc. This grade of preparation shall remove loose mill scale, rust and foreign matter. Finally the surface is to be cleaned with a vacuum cleaner or with clean compressed air or with clean brush. After preparation, the surface should have a faint metallic sheen. The appearance shall correspond to the prints designated St-2.
- ii) Grade St-3: very thorough scraping and wire brushing, machine brushing, grinding etc. After preparing the surface, it should have a pronounced metallic sheen and correspond to the prints designated St-3.

Blast cleaning:

Compressors: Compressed air supply for blast cleaning shall be free of water and oil. Air compressors shall not be allowed to deliver air at 110deg C. The blasting activity shall be performed at ambient temperatures above 5°C and relative humidity less than 85%. Steel temperature shall be 3°C above dew point. Necessary safety precautions for equipment and operator shall be adhered to.

Abrasives: Abrasives used for blast cleaning carbon steel and alloy steel shall be as per ISO 8504-2 and SSPC painting manual. Suggested abrasives may be chilled iron grit or shot steel and malleable iron grit and shots non metallic abrasive (aluminium oxide, copper slag, garnet etc.).

Removal of mill scale and rust using abrasives such as grit or shot under high pressure. The grade of blasting performed in line with the approved painting scheme.

Surfaces to be coated shall be free of all grease, oil, loose rust, and loose mill scale. Rust, mill scale, weld spatter, flux, shall be removed by the methods indicated in the Coating Schedule. Oil and grease shall be removed by solvent cleaning method as outlined in SSPC - SP - 1 prior to blasting.

The quality and grain size of abrasives and the parameter of their use are to be chosen to obtain the surface profile depth and cleanliness. Abrasives shall comply with applicable laws, regulations, ordinances etc., of the local authority, state or the nation pertaining to the work.

Profile measurements for abrasive blast cleaned surface shall be made with a Profile comparator and permanent record shall be maintained with Testex Press-O-Film.

Surfaces prepared for coating shall be coated the same day and before any visible rusting occurs (the time elapsed between blast cleaning and

commencement of painting shall under no circumstances exceed 4 hours, but in any case must commence before signs of degradation occur).

After blasting cleaning, depending on production flow, a weldable, inorganic ethyl zinc silicate shop primer of minimum dry film thickness 25 mm may be used.

The grades of surface finish:

	ISO 8501-1	SIS 055900	SSPC	NACE
White metal	Sa3	Sa3	SP5	1
Near White metal	Sa 2½	Sa 2½	SP10	2
Commercial blast	Sa2	Sa2	SP6	3
Brush off blast	Sa1	Sa1	SP7	4

Paint Application

General:

Paints and other coating materials shall be applied in accordance with the paint manufacturer's instructions. The surface preparation and painting system shall be as described in ANNEXURE with the following exceptions:

- Nameplates, code stampings and push buttons
- Concrete brickwork, tile, and glass unless specified by the Purchaser / Engineer
- Non-ferrous materials
- Austenitic stainless steel
- Plastic and / or plastic coated materials
- Insulated surface of equipment and pipes except colour coating wherever required
- Any surface specified by the Purchaser / Engineer not to be painted.

Paint Application Requirements

The paint shall be applied in accordance with the paint manufacturer's product data sheet, which shall include the mix ratio, the method of application, and the use of thinners and over coating times.

Paint application shall be by brush, roller or spray gun. Local regulations regarding spray and roller coating shall be observed. A smooth uniform film shall be applied to the surfaces to be coated.

Painting shall be performed when the temperature of the surface is greater than 3°C above the dew point of the surrounding air and relative humidity of the air is less than 85% unless local conditions dictate otherwise and the Customer is in agreement. Guidance on the estimation of the probability of condensation can be found in ISO 8502-4. The measurement of these conditions is the responsibility of the Vendor.

In addition, paints shall not be applied under the following conditions:

- When the surface temperature is greater than 60 °C (unless a higher temperature is agreed by the paint manufacturer)
- When the air temperature is less than approximately 5°C, (depending on local conditions)

- When there is the likelihood of an unfavourable change in weather conditions within two hours after painting
- When there is a deposition of moisture in the form of rain, condensation, frost, etc., on the surface.
- When the available light is less than 500 lux.

Paints shall not be applied within 50 mm of edges which will later have to be welded. Such weld areas shall be taped/one coat of weldable primer for distance of 50 mm either side of the weld line.

When zinc rich primers are used, care shall be taken to mask to avoid any possibility of over spraying onto duplex, austenitic stainless steels; nickel alloys or 9% nickel steel components.

Two pack coatings like Air drying epoxy, Polyurethane coatings etc shall be mixed in the ratio recommended by manufacturer to ensure proper and complete curing of the coatings. The base and hardener are to be separately mixed first to obtain a homogenous mixture. The hardener is to be added to the base slowly, with continuous mixing / agitation and not the reverse. Power agitation is preferred over hand mixing.

Any addition of thinner to achieve the application viscosity should be made only after the components are thoroughly mixed. Excess thinner is not recommended, as increase in volume, leads to lower DFT, sagging, longer curing time, etc.

Coating containing heavy or metallic pigments that have a tendency to settle shall be kept in suspension by continuous use of a mechanical agitator whilst being applied, to ensure uniformity over the surface area (e.g., zinc MIO's pigmented materials).

Transport and erection of painted structures shall be carried out only after the drying time specified by the paint manufacturer has elapsed. Handling & packing of painted material shall be appropriate to avoid damage to painting, such as the use of non-metallic slings, etc for handling and by minimising handling after painting. All steel equipment shall be provided with priming or coating system to protect the steel surface during transport, storage, installation and construction.

Spray Application

Airless or pneumatic spray applications are preferred methods of application. Spraying shall be carried out keeping the spray gun at the minimum suitable distance from the work piece and consistently at 90° to the surface being painted.

Approval of Purchaser / Engineer shall be obtained during spray painting which may cause interference to other works. If spray painting is to be carried out, the following shall be taken into account:

The correct spray tips, air pressures, etc, as recommended by the equipment supplier, shall be used.

Conventional air spray equipment is used, the correct combination of air volume, air pressure and fluid flow to give good atomisation to be ensured to

get a defect free painted surface. The major disadvantage of conventional air spray is that high build coatings can generally not be applied by this method as most paints have to be thinned to a suitable viscosity for satisfactory atomisation, and so lose their high build properties. Vendor shall follow manufacture's instruction.

Air spray (pressure pot) is recommended in cases where large quantities of paint are to be applied as paint in the tank can be prevented from settling, reduces application time and also enables the gun to be turned to any angle to coat objects effectively without spilling paint.

Airless spray is recommended as high build coatings can be applied without thinning, very rapid application is possible, giving an economic advantage, compared to conventional spray, overspray and bounce-back are reduced, leading to reduced losses of material and less dust and fume hazards.

Each coat shall be applied uniformly and completely over the entire surface. All runs and sags shall be brushed out immediately or the paint shall be removed and the surface re-sprayed.

Very complex structures should be painted by brush instead of spray gun to avoid overspray, dry spray and unacceptable paint losses.

Brush application

Brush application may be used under the following circumstances:

- When areas cannot be properly coated by spraying for reasons such as material or environmental considerations
- For the initial coat of paint to corners, edges, crevices, holes, welds or irregular surface prior to spray application
- For "touch up" or repairs to localize damaged paint or areas of incorrectly applied paint
- Where the paint manufacturer considers the coating material suitable for brush application.

Brushes shall be of a style and quality that will permit the proper application of paint.

Brush applications should be done in two passes that are perpendicular to each other 'wet on wet' so that a smooth coat, as near uniform in thickness as possible, is obtained thereby avoiding running and droplets. There should be no deep or detrimental brush marks. Paint shall be worked into all crevices and corners. Runs and sags shall be brushed out.

During the application of each coat, all areas such as corners, edges, welds, small brackets, bolts, nuts and interstices shall receive additional paint to ensure that these areas have at least the minimum specified dry film thickness and to ensure continuity of coating.

Roller application

Roller application shall only be used on relatively large surface areas and only if spraying is not an option. Roller application shall only be used if the first or priming coat of paint has been applied by brush. Roller application shall be in accordance with the paint Manufacturer's instructions.

Coating materials

The selected coating materials shall be suitable for the intended use and shall be selected after an evaluation of all relevant aspects such as

- Corrosion protective properties
- Requirements to health, safety and environment
- Properties related to application conditions, equipment and personnel
- Experience with the coating materials and coating system.

All coating materials and solvents shall be protected from ignition sources and shall remain within storage temperatures and storage conditions recommended by the coating manufacturer. All coating materials and solvents shall be stored in the original container bearing the manufacturer's label and instructions. Performance standard as listed below shall be established by paint manufacturer the records shall be submitted for review.

- Adhesion test (pull off test)
- Flexibility test
- Salt spray test (min 1000 Hrs)
- Water absorption test
- UV resistance test (external coating)
- Cathodic disbonding test (internal coating)
- Abrasion test (internal coating)
- Impact resistance test
- Sea water immersion test (structures in tidal, splash zone and conveying sea water)

Each product shall have a batch number showing year and month of manufacture and giving full traceability of production. Shelf life shall be included in the technical data sheet. All coating materials and solvents shall be stored in the original container bearing the manufacturer's label and instructions.

The composition of the paint shall be at the discretion of the manufacturer, provided that the finished product meets the requirements of, State or Local regulatory bodies for the products. All vehicle components for use in the manufacture of paints and enamels shall meet the ASTM/ ISO Specification except as otherwise stated coating systems shall be selected as per corrosivity category listed in the table below. Coating systems are tabulated in ANNEXURE and shall be pre-qualified in accordance with specification. Coating systems/ alternative coating systems may be re-subjected to pre-qualification, at the discretion of OWNER/ ENGINEER. The specified coating systems, the number of coats and the coating film thicknesses given in Annexure are minimum requirements Top coat colors should be in accordance with Annexure.

Gratings and step threads

- i) Surface preparation

Gratings and step threads shall be cleaned by acid pickling as per SSPC-SP-08.

- ii) Hot dip galvanising

The hot dip galvanising shall be done as per IS 2629 .The average mass of coating shall be 610 gms/m².

- iii) Post galvanising treatment

Immediately after galvanising, post treatment such as chromating shall be applied to retard white rust attack.

- iv) Touch up mechanical damages

The repair of damages coatings shall be done as per the recommended practice ASTM A 780.

CORROSIVITY OF ENVIRONMENTS

Corrosivity category		Mass loss per unit surface (per year of exposure)	
		Mass loss g/mm ²	Thickness loss μ m
C2	Low	>10 to 100	>1.30 to 25
C3	Medium	200-400 g/m ²	(25-50 μ m)
C4	High	400-650 g/m ²	(50-80 μ m)
C5	Very High Industrial & marine	650-1500g/m ²	(80-200 μ m)

Tests required for evaluation of acceptance of coating materials:

TABLE -1

PERFORMANCE TEST OF PAINT

SL. No.	Test	ASTM TEST METHOD
1.0	Abrasion Resistance: (topcoat only)	ASTM D4060
2.0	Adhesion:	ASTM D4541
3.0	Dry Heat Resistance:	ASTM D2485
4.0	Flexibility: (topcoat only)	ASTM D522, 180° bend
5.0	Pencil Hardness: (topcoat only)	ASTM D3363
6.0	Salt Fog Resistance:	ASTM B117, 1000 hours
7.0	Weather Resistance:	ASTMG23 Type D
8.0	Test	ASTM Test Method
9.0	Density	D 1475
10.0	Dipping properties	D 823
11.0	Drying time	D 1640
12.0	Flexibility	D 1737/D 522
13.0	Hardness	D 3363
14.0	Adhesion (pull off test)	D 4541
15.0	Abrasion resistance	D 968/D 4060
16.0	DFT/Coat	As per SSPC Guidelines
17.0	Storage Stability	D 1849
18.0	Resistance to	
	i) Humidity for 2000 hrs.	D 2247
	ii) Salt Spray for 2000 hrs.	B 117
	iii) Accelerated Weathering	D 822

INSPECTION:

Inspection will be performed by an inspector authorised by Purchaser / Engineer. Paint materials including primers and thinners brought to site by contractor for application shall be procured directly from manufactures as per specification and shall be accompanied by manufacturer's test certificates.

The painting work shall be subjected to inspection by purchaser / engineer at all times. The vendor shall offer following stage of inspection:

- Surface preparation
- Primer application
- Subsequent coats
- Paint qualification test

Vendor shall provide the expert technical services of the paint manufactures as and when required by purchaser / engineer to ensure both the surface preparation and applications are carried out as per their recommendations. This service shall be provided without any obligation to purchaser.

The following coating inspection & test shall be carried out:

1. Ambient and steel temperature, relative humidity and dew point min twice in a shift.
2. Surface finish & profile check each component or once per 10 m2 after surface preparation.
3. Salt contamination test - Free from salt contamination.
4. Dry Film Thickness as per ISO 2808 No.6.
5. Holiday Test as per ASTM D 5162/ NACE RP 0188.
6. Adhesion Test as per ISO 2409 for cross-cut test, or a pull-off test as per ISO 4624/ ASTM D 4541.

6.0 SUGGESTED COLOUR CODES FOR PAINTING:

Sl. No.	Item/Service	Colour	IS-5	Colour (Band)	IS-5
1.0	Structures, platforms, ladders and handrails	Dark Admiralty Grey	632		
2.0	Boiler casing, ESP and ducting	Nut Brown	413		
3.0	Fans, pumps, motors,	Light Grey	631		
4.0	Tanks (without insulation and cladding)				
4.1	Outdoor	Aluminium			
4.2	Indoor	Light grey	631		
5.0	Vessels & all other proprietary equipment (without insulation & cladding)	Light grey	631		
6.0	Switchgear	Light grey	631		
7.0	Control & relay panels	Light grey	631 78 of IS1650		
8.0	Turbine	Golden	356		

Sl. No.	Item/Service	Colour	IS-5	Colour (Band)	IS-5
		Yellow			
9.0	Generator & exciter	Light grey	631		
10.0	Transformers	Aluminium			
11.0	Machinery guards	Signal red	537		
12.0	Crane				
12.1	Crane structure	Golden Yellow	356		
12.2	Trolley and hook	Crimson	540		
13.0	Piping (without insulation and cladding)				
13.1	Water System				
13.1.1	Boiler feed	Sea green	217		
13.1.2	Condensate	Sea green	217	Light brown	410
13.1.3	Bearing cooling water	Sea green	217	French blue	166

Notes:

1. This colour code basically refers to IS: 2379 for piping with necessary modifications.
2. Where band colour is specified, same shall be provided at 30 meter intervals on long uninterrupted lines and also adjacent to valves and junctions.

PAINTING SCHEME FOR C2 AMD C3 ENVIRONMENT

S. No	Description	Surface Preparation	Primer			Intermediate paint			Finish coat			Total DFT
			Paint	No. of coats	DFT	Paint	No. of coats	DFT	Paint	No. of coats	DFT	Min.
1.	Boiler structure, un-insulated ducts, suspensions, hangers temperature <120°C	Sa 2 ½	In organic Zn silicate	2	80 µ	HB MIO epoxy	1	120 µ	Poly urethane	2		260µ
2.	Indoor structure	Sa 2 ½	HB Zn Phosphate	2	80 µ	HB MIO epoxy	1	120 µ	--	--	--	260µ
3.	Insulated parts exposed to temp >120°C	Sa 2 ½	In organic Zn silicate	2	60 µ							60µ
4.	Work shop	Sa 2 ½	HB Zn Phosphate	2	80 µ	HB MIO epoxy	1	120 µ	--	--	--	260µ
5.	Water Treatment Plant (external)	Sa 2 ½	Zn rich epoxy	2	80 µ	HB MIO epoxy	2	200 µ	Aliphatic poly urethane	2	80 µ	360µ
6.	Coal Handling Plant	Sa 2 ½	In organic Zn silicate	2	80 µ	HB MIO epoxy	1	120 µ	poly urethane	2	60 µ	260µ
7.	Fuel pipings	Sa 2	Ehthy Zn silicate	1	40 µ				HR aluminium paint	2	40 µ	80µ
8.	Un insulated silencer, steel stacks >120°C	Sa 2 ½	Ehthy Zn Silicate	1	40 µ				HR silicone aluminium paint	2	40 µ	80µ
9.	Above ground piping	Sa 2 ½	In organic Zn silicate	2	80 µ	HB MIO epoxy	1	120 µ	Poly urethane	2	60 µ	260µ
10.	Burried piping (External)	Sa 2 ½	Coal tar primer, coal tar enamel, inner wrap of fibre glass, final outer wrap of enamel impregnated fibre									4.0m m
11.	Burried piping (Internal)	Sa 2 ½	Solid rigid poly urethane 500 µ									500µ
12.	Storage tanks (external)	Sa 2 ½	In organic Zn silicate	2	80 µ	HB MIO epoxy	1	120 µ	Poly urethane	2	60 µ	260µ
13.	Storage tanks (internal)	Sa 2 ½	3 coats of amine adducts									400µ

14.	DM water piping (internal)	Sa 2 ½	Hard rubber lining min 4 mm thickness									4. mm
15.	DM water tank (internal)	Sa 2 ½	In organic Zn silicate	2	80 μ	HB MIO epoxy	1	150 μ	HB coal tar epoxy	1	150 μ	380μ
16.	Fuel oil tanks (internal)	Sa 2 ½	In organic Zn silicate	2	80 μ	HB MIO epoxy	1	150 μ	HB coal tar epoxy	1	150 μ	380μ
17.	Insulated parts continuously exposed to condensing water	Sa 2 ½	In organic Zn silicate	2	75 μ							75μ
18.	For insulated piping <125°C	Sa 2 ½	Polyamide cured epoxy coating	2	250 μ							250μ
19.	Electrical parts, control panels, valves, pumps & motors (indoor)*	Sa 2 ½	Zn phosphate epoxy	2	80 μ				Chlorinated rubber	2	80 μ	160μ
20.	Electrical parts, control panels, valves, pumps & motors (outdoor)*	Sa 2 ½	Zn phosphate epoxy	2	80 μ				Chlorinated rubber	2	100 μ	180μ
21.	Switch yard, floor grills walk ways	Sa 2 ½	Hot dip galvanising 80μ									80μ

* Note: Manufacturer to specify details of painting system capable of withstanding environmental conditions for a period of 10 years before first maintenance



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C1F

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

LIST OF MAKES OF SUB-VENDOR ITEMS

	TECHNICAL SPECIFICATION FOR LUBE OIL TRANSFER PUMPS SUB-VENDOR LIST		SPECIFICATION NO:PE-TS-426-567-A001
			SECTION IA
			REVISION 00
			JULY 2019

4	III	PAINT	NGEF	BANDALORE / HUBLI
	III		LHP	SOLAPUR
	III		ASIAN PAINT	
	III		BERGER	
	III		KANSAI NEROLAC	
	III		JOTUN	
	III		SHALIMAR	
	III		JENSON & NICHOLSON (I) LTD	
	III		CDC CARBOLINE (I) LTD.	
	III		ADDISON PAINTS LTD	
	III		GRAND POLYCOAT	
	III		BOMBAY PAINTS	
	III		HEMPLE PAINTS (SINGAPORE)	
	III		AKZONOBEL COATINGS	
	NOTES	INSPECTION CATEGORIZATION		
	1	CAT I :INSPECTION BY OWNER, BHEL/BHEL NOMINATED TPJA & VENDOR .MDCC WILL BE ISSUED BASED ON INSPECTION REPORT IN LINE ITH APPROVED QAP.		
	2	CAT II: INSPECTION BY BHEL/BHEL NOMINATED TPJA & VENDOR. MDCC WILL BE ISSUED BASED ON INSPECTION REPORT IN LINE ITH APPROVED QAP.		
	3	CAT III: MDCC WILL BE ISSUED BASED COC & MTC ISSUED BY VENDOR AND VERIFICATION BY BHEL/OWNER IN LINE WITH APPROVED QAP/CHECK LIST		

The make of Sub-vendor items shall be generally as indicated above which is subject to customer / BHEL approval during detail engineering.

Make of any unlisted items shall be subject to customer / BHEL approval during detail engineering. For such items, bidder to furnish list of sub-vendors during detail engineering stage for Customer / BHEL's review and approval. Bidder shall furnish following supporting documentation within 1 month of placement of LOI. Thereafter no request for additional sub-vendor shall be entertained.

- Documentation to show that the equipment /system has been supplied for a plant of similar or higher capacity.
- Documentation in the form of certificate that the equipment/system has been operating satisfactorily for two years as on the scheduled date of bid opening.

The successful bidder will get the makes of all items approved from Customer/ Consultant during detail engineering within two months of placement of LOI. The complete list will be necessarily be submitted within one month of placement of LOI to ensure timely placement of order for BOIs

Bidder to assess the capability of their proposed sub-vendors in terms of preparation of drawings, calculations, documents, quality assurance, supply of material etc. as per project schedule before placing the order on them.

Dealers are not acceptable for any item of the package. Bidder shall procure all items including plates, structural, flanges; counter flanges etc. from approved sub vendor only.

SUB-VENDOR LIST FOR ELECTRICAL ITEMS

ITEM DESCRIPTION	SL NO.	VENDOR NAME
CABLE GLANDS	1	ALLIED TRADERS & EXPORTERS
	2	ARUP ENGG & FOUNDRY WORKS
	3	BALIGA LIGHTING EQPT.PVT.LTD.
	4	COMMET BRASS PRODUCTS
	5	DOWELLS
	6	ELECTROMAC INDUSTRIES
	7	INCAB
CABLE LUGS	1	DOWELLS
	2	UNIVERSAL MACHINES LTD.
LV MOTORS (NON FLAME PROOF)	1	ABB
	2	BHARAT BIJLEE LTD.
	3	CROMPTON GREAVES
	4	GE-POWER
	5	KIRLOSKAR ELECTRIC CO LTD.
	6	LAXMI HYDRAULICS PVT. LTD
	7	MARATHON
	8	NGEF
	9	RAJINDRA ELECT INDUSTRIES
	10	SIEMENS

**TELANGANA STATE POWER GENERATION
CORPORATION LTD
TELANGANA STATE, INDIA**

1x660 MW UPRVUNL PANLI TPS, EXTENSION

SECTION-I, SUB-SECTION – C2

**LUBE OIL TRANSFER PUMP TECHNICAL
SPECIFICATION
(ELECTRICAL PORTION)**



**BHARAT HEAVY ELECTRICALS LIMITED
POWER SECTOR
PROJECT ENGINEERING MANAGEMENT,
NOIDA, U.P., INDIA**



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C2

REV. 00

DATE: JULY 2019

SHEET :

CONTENTS

TITLE	NO. OF SHEETS
COVER SHEET	1
CONTENT	1
CUSTOMER (M/s DCPL) SPECIFICATION FOR MOTORS	20
ELECTRICAL SCOPE BETWEEN BHEL & VENDOR	1
DATASHEET (ANNEXURE- I)	1
DATASHEET-C	2
ELECTRICAL LOAD DATA FORMAT	1
QUALITY PLAN (FOR MOTORS BELOW 55 KW)	2
TOTAL	29

CHAPTER 17 : AC & DC MOTORS**1.00 MOTORS****1.1 SCOPE**

This specification is intended to cover design, manufacture, assembly and testing of AC Squirrel Cage Induction Motors for use in Thermal Power Plants and is supplement to the driven equipment specifications under which these motors are being procured for the project.

SITE CONDITIONS

Site conditions are covered in 'Project Data', contained in specification of the driven equipment.

1.2 Gases, Fumes & Dust Particles

1.2.01 General - Sulphur dioxide and/or trioxide fumes mildly present. Climate is tropical, conducive to fungus growth.

1.2.02 Dust Particles

1 Outdoor locations - Heavily dusty with abrasive dust and coal particles of size five (5) to hundred (100) microns present in atmosphere in large quantity.

2 Indoor Locations.

2.1 Coal conveyors - As for outdoor as per clause 1.02.02.1 above.

2.2 Other locations - Lightly dusty with abrasive dust and coal particles of size five (5) to twenty (20) microns present in atmosphere.

1.2.03 Special Fumes

1 Water treatment plant and acid cleaning room - Acid and alkali fumes present.

2 Fuel oil pumping areas & Hydrogen generation plant - Explosive fumes (flameproof motors required).

1.2.04 For the purpose of design of equipment/systems, an ambient temperature of 50 deg. Centigrade and relative humidity of 95% (at 40 deg C) shall be considered. The equipment shall operate in a highly polluted environment.

1.3 LOCATION OF MOTOR - As required

1.4 **SPECIFICATIONS & STANDARDS**.....Motors shall comply with the latest revisions of all relevant standards of BIS (IS-325, IS-900, IS-996, IS-1231, IS-1885, IS-2148, IS-2223, IS-2253, IS-2254, IS-2848, IS-3202, IS-4029, IS-4691, IS-4722, IS-4728, IS-4889, IS-6362, IS-7816, IS-8223, IS-8789, IS: 12615, IS:3177 and IEC : 60034 3Φ Induction motor) except as modified herein or in driven equipment specification.

Motors conforming to BS or IEC Publications, which ensure equivalent quality shall also be acceptable. In case of any difference between IS Specification/International Standards (IEC; NEMA etc.), this motor specification prevails.

1.5 TYPE

1.5.1 AC Motors:

- a) Squirrel cage induction motor suitable for direct-on-line starting.
- b) Continuous duty LT motors upto 160 KW Output rating (at 50 deg. C ambient temperature), shall be **Efficiency class-IE2**, conforming to IS 12615, or IEC:60034-30.
- c) Crane duty motors shall be slip ring/ squirrel cage Induction motor as per the requirement.

1.5.2 DC Motors Shunt wound.

1.6 VOLTAGE (NOMINAL)

1.6.1 LV Motors

For motors upto and including 200 KW - Four hundred fifteen (415) V.

1.6.2 MV MOTORS

For motors above 200kW upto and including 1500kW, Three point three (3.3) kV.

For CHP conveyors motor above 160 kW, 3.3 kV, AC supply is to be used. However all the motors on stacker reclaimer shall be on 415 V AC only.

1.6.3 HV Motors

For motors above 1500kW - eleven(11) KV

1.6.4 All motors are to be designed for system grounding described in "System Particulars" under site information of the Driven Equipment Specification.

1.7 FREQUENCY (NOMINAL) - fifty (50) Hertz

1.8 NUMBER OF PHASES - Three (3)

1.9 SPEED - As required by the driven equipment

1.10 TYPE OF STARTING :

Direct on-line (VFD/Soft-starter/star/delta starting in special cases)

1.11 DUTY

1.11.1 Continuous motor rating shall be arrived at considering 15% margin over the duty point input or 10% over the maximum demand of the driven equipment,



whichever is higher, considering highest system frequency and voltage variation. Crane motors shall be rated for S4 duty, 40% cyclic duration factor. If however, a higher margin is stipulated in the accompanying driven equipment specification, the higher stipulated margin shall prevail.

- 1.11.2 All HT motors shall have vibration pads for mounting vibration detectors.
- 1.11.3 All motors shall be designed to withstand hundred twenty (120) percent of rated speed without any mechanical damage for two (2) minutes.
- 1.11.4 Motors shall be designed to keep torsional and rotational natural frequencies of vibration of the motor and driven equipment atleast twenty five (25) percent above or below, preferably above the motor operating speed (to avoid resonance in vibration over the operating speed) range.
- 1.11.5 All LV motors rated 0.37kW and higher with S1 duty shall be compulsorily be of energy efficiency level IE 2 as per IS 12615:2011.
- Motors rated above 37kW shall have efficiency higher than 0.92 and high power factor of atleast 0.88.

1.12 **SUPPLY VARIATIONS**

Motors shall be capable of running continuously at full load under following variations in power supply:

- 1.12.1 All equipments shall be suitable for rated frequency of 50 Hz with a variation of (+) 3% and (-)5%, voltage variation of ($\pm$) 6% for 11 kV & 3.3 kV and ($\pm$)10% for 415V and 10% (absolute sum) combined variation of voltage and frequency unless specifically brought out in the specification.

1.13 **ABNORMAL CONDITIONS CAPABILITY**

Motor shall have following capabilities as specified design ambient temperature:

- 1.13.1 The motors shall also be capable of running up again after voltage collapse to about 40% for approximate duration of 0.5 sec. Subsequent rise in voltage to 70% and further to 80% and 100%, the total duration not exceeding 20 sec.

1.13.2 Low Voltage Running :

Motor shall be capable of running satisfactorily at seventy five (75) percent nominal voltage for five (5) minutes.

1.13.3 Momentary Low Voltage Withstanding :

Motor, when running at full load, shall not stall when voltage drops down to seventy (70) percent nominal voltage for one (1) minute.

1.14 **STARTING CAPABILITY**

1.14.1 Low Voltage Starting :

Motor shall be capable of starting and accelerating to full speed at full load (including loaded equipment e.g. mills and conveyors etc) at eighty (80)

percent nominal voltage at motor terminals. Mill motors may be permitted to start with terminal voltage not below 90%.

1.14.2 Cold Motor Starting Under specified voltage variations two (2) starts in quick succession and third start five (5) minutes thereafter, all with full load (including loaded equipment eg mills and conveyors etc) of driven equipment. No additional start will be made till lapse of further thirty (30) minutes.

1.14.3 Hot Motor Starting Under specified voltage variations, one (1) immediate and two (2) fifteen (15) minutes interval starts all with full load (including loaded equipment e.g. mills and conveyors etc) of driven equipment. No additional start will be made till lapse of further thirty (30) minutes.

1.14.4 Motor shall also be suitable for three (3) equally spread starts per hour when the motor is under normal service condition.

1.14.5 Break-away Starting Current Breakaway starting current as percent of full load current for various motor ratings shall not exceed the values given below:

1.14.5.1 Motors above 1500 KW upto 4000kW 600% without any positive tolerance except for ID Fan Motor.

1.14.5.2 Motors above 4000 KW 450%. Not subject to any positive tolerance.

1.14.5.3 For D.C. Motors the starting current shall be limited to 2 times full load current.

1.14.5.3 **Starting voltage requirement**

a) All Motors (except Mill Motors)

- 80% of rated voltage for Motors upto 4000 kW
- 75% of rated voltage for Motors above 4000 kW

b) For Mill Motors:

- 85% of rated voltage for Motors above 1000 kW
- 90% of rated voltage for Motors below 1000 kW

Except AOP & JOP motors running on D.G emergency supply, starting voltage shall be 80%.

1.14.5.4 **Starting Time**

1.14.5.4.1 For motors with starting time upto 20 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be at least 2.5 secs. more than starting time.

1.14.5.4.2 For motors with starting time more than 20 secs. and upto 45 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be at least 5 secs. more than starting time.

1.14.5.4.3 For motors with starting time more than 45 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be more than starting time by at least 10% of the starting time.



1.14.5.5 Torque Requirements:-

- 1.14.5.5.1 Accelerating torque at any speed with the lowest permissible starting voltage shall be at least 10%. Motor full load torque.
- 1.14.5.5.2 Pull out torque at rated voltage shall not be less than 205% of full load torque. It shall be 275% for crane duty Motors.

1.15 SAFE STALL TIME

- 1.15.1 To avoid problem in selecting standard protective relays without using speed switches, safe stall time under hot conditions (corresponding to 110% nominal voltage at motor terminals) shall be more than the accelerating time (corresponding to 80% nominal voltage at motor terminals) by the following minimum values :
- 1.15.1.01 Two (2) seconds, where accelerating time (at 80% nominal voltage) does not exceed 20 seconds.
- 1.15.1.02 Three (3) seconds, where accelerating time (at 80% nominal voltage) exceeds 20 seconds.
- 1.15.1.03 At no stage, speed switch shall be provided to achieve the above requirements mentioned under Clause No. 1.14.5.4

1.16 CLASS OF INSULATION

- 1.16.1 LV Motors Class F.
- 1.16.2 MV & HV Motors Class F
- 1.16.03 However temperature rise shall be restricted to limits corresponding to Class 'B' insulation for both HT & LT motors. The temperature under abnormal running conditions shall be limited to 5°C above class 'B' limits.
- 1.16.04 The value of the polarization index for motors above 200kW should not be less than 2 when determined according to IS: 7816.
- 1.17 **TEMPERATURE RISE UNDER NORMAL CONDITIONS.....** Temperature rise over specified design ambient temperature when motor is running with full load at nominal supply voltage & frequency shall not exceed the values given below:

S.No.	Specified Design Ambient Temperature	Thermometer Method	Resistance Method
1.17.01	50°C	60°C	70°C
1.17.02	45°C	65°C	75°C
1.17.03	40°C	70°C	80°C

1.18 BUS TRANSFER WITHSTAND CAPABILITY

Motors will be connected to an automatic bus transfer system and hence may be subjected to one hundred and fifty (150) percent of the nominal voltage during changeover of buses due to the vector difference between the residual voltage and incoming supply voltage and the duration of this condition may be one second. Motors shall be capable of withstanding the voltage and torque stresses developed under such conditions without damage. The manufacturer/vendor shall indicate the special precautions taken to meet the above requirements and confirm.

- 1.18.01 That about 5000 bus transfers, in lifetime of motor, shall not puncture its insulation.
- 1.18.02 That motor shall be capable of withstanding heavy inrush transient current caused by such bus transfers without damage.
- 1.18.03 That the motor windings shall be adequately braced to satisfactorily withstand mechanical stresses under these conditions.
- 1.18.04 The motor and driven equipment shafts shall be adequately sized to satisfactorily withstand transient torques under these conditions.

1.19 TYPE OF ENCLOSURE

- 1.19.01 Outdoor Motors IP 55 (Additional canopy to be provided by EPC contractor.
- 1.19.02 Indoor Motors IP 55
- 1.19.03 IP-55 degree of protection shall be achieved without application of any compound, putty etc.
- 1.19.04 Motor located in hazardous area shall have flameproof enclosure conforming to IS: 2148 /Equiv. as detailed below:
- a) Fuel Oil area : Group IIB
 - b) Hydrogen generation plant area : Group IIC (or Group-I, Div-II as per NEC or Class-1, Gr-B, Div-II as per NEMA/IEC60034).

1.20 METHOD OF COOLING

- 1.20.1 Method of cooling shall be IC 411 (TEFC), IC 511 (TETV) or IC 611 (CACA). However, motors rated 3000kW or above can be closed air circuit water cooled (CACW).
- 1.20.2 Large capacity motors not available with above types of cooling may be accepted with IC 81 W for IC 91 W (CACW) cooling subject to the approval of the Owner.

1.21 TYPE OF MOUNTING As required for the driven equipment.**1.21 MAXIMUM MECHANICAL VIBRATIONS**

- 1.21.01 Noise level for all the motors shall be limited to 85dB(A) except for BFP motor for which the maximum limit shall be 90dB(A). Vibration shall be limited within the limits

prescribed in IS: 12075 / IEC 60034-14. Motors shall withstand vibrations produced by driven equipment. HT motor bearing housings shall have flat surfaces, in both X and Y directions, suitable for mounting 80mmX80mm vibration pads.

1.21.02 Noise level

The noise level of motors shall not exceed 85 db (A) at 1m from operating motor measured in accordance with IS: 10265.

1.21.03 Motor body shall have two earthing points on opposite sides.

1.21.04 11 KV motors shall be offered with Separate Insulated Connector (Elastimould or Equivalent make) as per IEEE 386. The offered Elastimould terminations shall be provided with protective cover and trifurcating sleeves. Elastimould termination kit shall be suitable for fault level of 25 KA for 0.17 seconds.

1.21.05 3.3 KV motors shall be offered with dust tight phase separated double walled (metallic as well as insulated barrier) Terminal box. Suitable termination kit shall be provided for the offered Terminal box. The offered Terminal Box shall be suitable for fault level of 250 MVA for 0.12 sec. Removable gland plates of thickness 3 mm (hot/cold rolled sheet steel) or 4 mm (non magnetic material for single core cables) shall be provided.

1.21.06 The spacing between gland plate & centre of terminal stud shall be as per Table-I.

TABLE - I

DIMENSIONS OF TERMINAL BOXES FOR LV MOTORS

Motor MCR in KW	Minimum distance between centre of stud and gland plate in mm
UP to 3 KW	As per manufacturer's practice.
Above 3 KW - upto 7 KW	85
Above 7 KW - upto 13 KW	115
Above 13 KW - upto 24 KW	167
Above 24 KW - upto 37 KW	196
Above 37 KW - upto 55 KW	249
Above 55 KW - upto 90 KW	277
Above 90 KW - upto 125 KW	331

Above 125 KW-upto 200 KW 203

For HT motors the distance between gland plate and the terminal studs shall not be less than 500 mm.

1.21.07 All motors shall be so designed that maximum inrush currents and locked rotor and pullout torque developed by them at extreme voltage and frequency variations do not endanger the motor and driven equipment.

1.21.08 For motors rated 1500 KW & above, neutral current transformers of PS class shall be provided on each phase in a separate neutral terminal box.

1.21.09 The ratio of locked rotor KVA at rated voltage to rated KW shall not exceed the following (without any further tolerance) except for BFP motor.

(a)	Below 110KW	:	10.0
(b)	From 110 KW & upto 200 KW	:	9.0
(c)	Above 200 KW & upto 1000KW	:	10.0
(d)	From 1001KW & upto 4000KW	:	9.0
(e)	Above 4000KW	:	6 to 6.5

1.22 WINDING & INSULATION

- (a) Type : Non-hygroscopic, oil resistant, flame resistant
- (b) Starting duty : Two hot starts in succession, with motor initially at normal running temperature.
- (c) 11kV & 3.3 kV : Thermal class 155 (F) insulation.
AC motors
The winding insulation process shall be total Vacuum Pressure Impregnated i.e resin poor method. The lightning Impulse & interturn insulation surge withstand level shall be as per IEC-60034 part-15
- (d) 240VAC, 415V : Thermal Class(B) or better
AC & 220V
DC motors

1.23 DIRECTION OF ROTATION

1.23.1 As needed by driven equipment.

1.23.2 The 3 phase motor shall, however, be suitable for operation in both directions of rotation. A plate showing direction of rotation as determined by the phase sequence on the terminals marking shall be screwed at non-driving end of the body of the motor.

1.23.3 If, in the case of HT motors, fan is suitable for only one direction of rotation, the fan shall be so designed that with the slight modification work, it can be made suitable for other direction of rotation also. No extra material shall be required for doing above modification work.

1.24 BEARINGS



- 1.24.1 General Greased ball, roller and/or sleeve bearing shall be rated for minimum standard life of 20,000 hours taking bearing and driven equipment loads into account. Loss of grease shall be scarce and it shall not creep along shaft into motor housing.
- Bearing shall be effectively sealed against dust ingress and shall be pressure grease gun lubricated.
- If the bearings are oil lubricated, a drain plug shall be provided for draining residual oil and oil level gauge shall be provided to show precisely oil level required under standstill and running conditions.
- Unless otherwise approved, bearing lubricating system shall be such that no external forced oil or water is necessary to maintain required oil supply to keep bearing temperature within design limits.
- For MV & HV motors, the bearings shall be insulated wherever necessary to prevent damage to motor bearings from shaft current.
- When pressure oiling is required for horizontal motors, bearings shall be sleeve type arranged for pressure oiling supplied from lubrication system of driven machine, with ring oiling for starting and emergency duty. Ring oiling system shall be adequate for starting and continuous operation of motor for at least half an hour, without pressure oiling system in operation. Oil sight flow gauges shall be provided to indicate oil flow through each bearing.
- Lubricants shall be selected for prolonged storage and normal use of motors in tropical climate and shall contain corrosion and oxidation inhibitors. Greases shall have suitable bleeding characteristics to minimize setting. The selected lubricants shall be indigenously available.
- Sleeve bearings for use with motors having flexible coupling with limited end play, shall have adequate axial end play to prevent transmission of thrust from driven equipment to motor bearings.
- Bearings shall be of reputed make subject to the approval of the Owner/Consulting Engineer.
- 1.24.2 Large motors Large motors shall preferably have spherically seated babitted, ring forced, feed lubricated, water-cooled bearings. If anti-friction bearings are provided, these shall be roller bearings rated for a minimum standard life of 30000 hours taking all bearing and driven equipment loads into account.
- 1.25 **SHAFT EXTENSION** Key slotted bare shaft extension of required length with key on driving end.
- 1.26 **DRAIN HOLES** Two (2) drain holes with plugs, one (1) on either end of motor at the bottom most point.
- 1.27 **LIFTING DEVICES** Motors shall be provided with eyebolts, lugs or other means to facilitate safe lifting.
- 1.28 **DOWEL PINS**..... It shall be possible to drill holes vertically inclined through motor feet or mounting flange for installing dowel pins after assembling motor and driven equipment, before despatch (for completed driving + driven

equipment assembly) or at site after erection (for separate supplies of above equipment).

1.29 **CENTERING SPIGOT**..... Flange mounted motor shall have centering spigot to match driven equipment socket.

1.30 **EASE OF MAINTENANCE**..... Motor shall be so constructed that it can be de-assembled and reassembled with ease.

1.31 **NAMEPLATES**..... Motor shall have nameplate(s) showing diagram of connections, all particulars as per IS: 325 and following additional information:

In addition, an arrow block shall be screwed on to the body of motor on the non-driving end to indicate direction of rotation of motor.

1.31.1 Temperature rise under normal/abnormal conditions.

1.31.2 Type of bearing and recommended lubricants.

1.32 **FINISH**..... Motor shall have glossy, light grey finish No. 631 as per IS: 5 for withstanding site conditions as per Clause 1.00 above.

All sharp edges and scales shall be removed from the surface, which shall then be thoroughly degreased, de-rusted and given two (2) coats of primer and two (2) coats of finish paint. It is preferred that a phosphate coat is given to motor prior to application of primer coat. Motors for water treatment plant shall have Zinc Chromate base with acid resistant Epilex 4 paint.

1.33 **TERMINAL BOXES**

1.33.1 GeneralMotors shall be provided with separate terminal boxes for main, space heaters, embedded temperature detectors, bearing temperature indicators and moisture detectors terminals. When it is not possible to provide LT motors with separate terminal box for space heater terminals, space heater terminals shall be adequately segregated from the main terminals in the single box. Terminal boxes shall be weatherproof and water-tight confirming to minimum IP-55 degree of protection with removable front cover for making connections. IP-55 degree of protection shall be achieved without application of compound. Space between and around terminals shall be adequate for easily connecting aluminium conductor cables. Terminal box arrangement shall be to the approval of the Owner /Consulting Engineer. All terminal boxes shall be suitable for proper termination of the type and tentative size of cables specified in Clause 1.34 below, however, exact size of cables shall be furnished by Owner during engineering stage.

The terminal boxes shall be complete with cable glands and termination accessories as required. Suitable non-magnetic material construction shall be adopted for terminal boxes where single core cables are to be terminated. All HT motors shall be provided with phase segregated terminal box.

Terminal bushings and clamps shall be non-absorbent, non- inflammable, insulated material for connecting with cable.

1.33.2 **Main Terminal Box**



1.33.2.1 LV Motors Main terminal box shall be capable of being turned through 360 degrees in steps of 90 degrees.

1.33.2.2 MV & HV Motors Motor shall be provided with two (2) terminal boxes for stator terminals. One (1) terminal box shall be for phase terminals while other one for forming star connection. These should be interchangeable to facilitate cable routing.

Neutral terminal box for HT motors rated above 1500 KW shall be suitable for mounting of three (3) Nos. wound/bar primary/ring type cast resin insulated current transformers for differential protection. These transformers shall be supplied and mounted in the motor terminal box. In addition to above, 3 Nos. of identical current transformers shall be supplied loose for mounting in the switchgear. Stator phase terminal box may either be phase segregated or standard terminal box suitable for both top and bottom entry of cables (i.e. they should be capable of being turned through 180 Degrees). The terminal box shall be designed for termination of XLPE cables using heat shrinkable or push on type terminating Kit. Terminal leading shall be stud type or leading wire type.

1.33.2.3 Cable End Boxes.....Terminal Boxes shall be provided with cable end boxes having cable lugs and cable glands for cables of sizes as specified in Clause 1.34 below.

Cable box shall be suitable for glanding the cables; and shall have adequate space between cable glands terminating studs to allow suitable bends of cable inside the cable box for all 3 phases of relevant cable sizes specified.

1.33.2.4 The terminal boxes shall be capable of withstanding at the terminals the system fault level (as indicated below) without rupture for a duration of atleast 0.25 seconds.

Min. fault level for MV Motors - 40 KA

Min. fault level for LV & HV Motors - 50 KA

1.33.2.5 **PHASE TO PHASE/ PHASE TO EARTH AIR CLEARANCE:**

NOTE: Minimum inter-phase and phase-earth air clearances for LT motors with lugs installed shall be as follows:

Motor MCR in KW	Clearance
UP to 110 KW	10mm
Above 110 KW and upto 150 KW	12.5mm
Above 150 KW	19mm

1.33.2.6 Terminal Accessories.....Each terminal end shall be furnished with bimetallic washers, spring washers, nuts and crimp type aluminium (preferably tinned) lugs suitable for cables of sizes as specified in Clause 1.34 below.

1.34 **TYPE AND SIZE OF CABLES**

1.34.1 **Space Heaters**



- 1.34.1.1 For LV Motors: Two point five (2.5) mm², two (2) core copper conductor PVC insulated, armoured and FRLS PVC sheathed heavy duty 650/1100 V grade cable to IS: 1554 (Part-I).
- 1.34.1.2 For MV & HV Motors: Six (6) mm² two core aluminium conductor PVC insulated armoured and FRLS PVC sheathed heavy duty 650/1100V grade cable to IS: 1554 (Part-I).
- 1.34.2 For Embedded Temperature Detectors two sets of six (6) Twisted triad 0.5 mm² ATC copper conductor armoured, shielded cable, 650/1100 V Grade IS: 1554 (Part-I). For bearing temperature, RTDS, two (2) sets of four (4) twisted triad 0.5 mm², ATC copper conductor armoured shielded 650/1100 V Grade, IS: 1554 (Part-I).
- 1.34.3 Bearing Temperature Indicators - For each indicator, 0.5 mm² six (6) tarnished triad ATC copper conductor, PVC insulated, shielded armoured and FRLS PVC sheathed heavy duty 650/1100 V grade cable as per IS: 1554 Part-I. Two (2) cables one (1) for each bearing temperature indicator.
- 1.34.4 For Moisture Detectors.....As for space heaters as per Clause 33.01.01 above.
- 1.34.5 **For Main Terminals**

LT Motors

1. Three (3) core cablesStranded aluminium conductor, XLPE insulated, colour coded, laid up, PVC sheathed, GI wire / strip armoured, FRLS PVC jacketed overall, 650 / 1100V grade, heavy-duty cables as per IS: 1554 (Part-I).
2. Single core cablesStranded aluminium conductor, XLPE insulated, hard drawn aluminium wire/ strip armoured FRLS PVC jacketed overall, 650 / 1100V grade, heavy duty cable as per IS: 1554 (Part-I).

HT Motors

1. Three (3) core cables stranded aluminium conductor, XLPE insulated, screened colour coded, laid up, PVC sheathed, GI wire/strip armoured FRLS PVC jacketed overall, 6.6 KV / 11 KV grade, heavy duty cables as per requirement for unearthed system as per IS: 7098 (Part-II).

The size and no. of cable to be intimated to the successful bidder during detailed engineering and the contractor shall provide terminal box, cable gland and lugs suitable for the same.

Cable size may be increased in some cases because of large number of cables in under-ground ducts or because of voltage drop consideration. The supplier shall supply with terminal box and cable accessories suitable for higher size of cable at no extra cost.

1.35 **EARTHING**

- 1.35.01 General..... Two (2) grounding terminals one (1) on either side at the bottom suitable for connecting mild steel/GI flat/GI wire grounding conductor, size of grounding conductor shall be decided during detailed engineering.

- 1.35.02 LV Motors.....At each earthing point, two (2) drilled and tapped holes with hexagonal head bolts, plain washers, spring washers and tinned lugs (for motors upto 5.5 KW) for size of conductor specified shall be provided.
- 1.35.03 MV & HV Motors.....Non-corrodible metallic grounding pad shall be welded or brazed at each earthing point. The size of grounding pad shall be 75x65x25 mm. Grounding pad shall have 40 mm apart two (2) drilled and tapped holes with hexagonal head bolts, plain washers and spring washers for size of conductor specified. In addition, one suitable earthing terminal shall be provided inside the stator phase terminal box for earthing metallic shield of XLPE cables.
- 1.36 **EMBEDDED TEMPERATURE DETECTORS**.....HT motor shall be provided with six (6) Nos. duplex resistance temperature detectors (RTDs) embedded in stator winding at locations where high temperatures are expected. In addition one (1) duplex type RTD shall be provided in each bearing. The RTDs shall be 3 wire duplex platinum resistance type having a value of 100 ohms at 0 Deg.C
- 1.37 **BEARINGS TEMPERATURE INDICATORS**..... HT motors shall be provided with dial type two (2) bearing temperature indicators and will have two (2) sets of contacts, each set having 2 NO + 2 NC contacts rated for 5A at 240V AC and 0.5A at 220V DC. One set will be set to operate at lower value to give alarm and other set at a higher value to trip the motor.
- 1.38 **SPACE HEATERS**.....Valve / Damper actuator motors; and Motors above 30 KW shall be provided with one (1) or two (2) space heaters suitable for 240V, 50 Hertz single phase AC supply and of adequate capacity to maintain motor internal temperature above dew point to prevent moisture condensation or deterioration of insulation during shut down. Heaters shall be mounted inside the motor in accessible locations so that their removal and replacement is simple. Motors upto 30 kW shall have stator windings suitable for connections to 24V, 50 Hz AC supply for space heating.
- Motors upto 30 kW shall have stator windings suitable for connection to 24V, 50 Hz ac supply for space heating
- The terminals of space heaters shall be brought out to a separate totally enclosed dust proof and weatherproof terminal box.
- 1.39 **HOT AIR TEMPERATURE DETECTOR**
- If the motor is of CACA or CACW enclosure, a thermometer with alarm contracts in hot air circuit shall be provided.
- 1.40 **WATER FLOW INDICATOR**
- If the motor is of CACW enclosure a provision shall be made for visual indication of water flow and flow switch shall also be provided with alarm contacts. Thermometers shall be provided in water inlet and outlet circuits.
- 1.41 **MOISTURE DETECTORS**.....Motors with type of cooling 1C 81W or 1C 91 W shall be provided with moisture detectors for raising alarm in the event of water tube failure.

1.42 **BED PLATE**.....Whenever motor is supplied with driven equipment the Supplier shall ensure that bed plate suits both motor and driven equipment and is adequately braced to keep vibration and misalignment within allowable limits to the approval of driven equipment and motor manufacturers.

1.43 **OTHER ACCESSORIES**..... Motor shall be supplied with all accessories and parts other than those, specified above which are necessary and/or useful for efficient operation.

1.44 **TYPE TEST**

1.44.01 **HT MOTORS**

- a) The contractor shall carry out the type tests as listed in this specification on the equipment to be supplied under this contract. The bidder shall indicate the charges for each of these type tests separately. The type tests charges shall be paid only for the test(s) actually conducted successfully under this contract.
- b) The type tests shall be carried out in presence of the Purchaser's representative, for which minimum 15 days notice shall be given by the contractor. The contractor shall obtain the Purchaser's approval for the type test procedure before conducting the type test. The type test procedure shall clearly specify the test set-up, instruments to be used, procedure acceptance norms, recording of different parameters, interval of recording, precautions to be taken etc. for the type test(s) to be carried out.
- c) In case the contractor has conducted such specified type test(s) within last five years as on the date of bid opening, he may submit during detailed engineering the type test reports to the Purchaser's for waiver of conductance of such test(s). These reports should be for the tests conducted on the equipment similar to those proposed to be supplied under this contract and test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. The Purchaser's reserves the right to waive conducting of any or all the specified type test(s) under this contract. In case type tests are waived, the type test charges shall not be payable to the contractor.
- d) Further the Contractor shall only submit the reports of the type tests as listed in "LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED" and carried out within last five years from the date of bid opening. These reports should be for the test conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. However if the contractor is not able to submit report of the type test(s) conducted within last five years from the date of bid opening, or in the case of type test report(s) are not found to be meeting the specification requirements, the contractor shall conduct all such tests under this contract at no additional cost to the Purchaser's either at third party lab or in presence of client representative and submit the reports for approval.

e) **LIST OF TYPE TESTS TO BE CONDUCTED**



The following type tests shall be conducted on each type and rating of HT motor

- i) No load saturation and loss curves upto approximately 115% of rated voltage
- ii) Measurement of noise at no load.
- iii) Momentary excess torque test (subject to test bed constraint).
- iv) Full load test(subject to test bed constraint)
- v) Temperature rise test at rated conditions. During heat run test, bearing temp., winding temp., coolant flow and its temp. shall also be measured. In case the temperature rise test is carried at load other than rated load, specific approval for the test method and procedure is required to be obtained. Wherever ETD's are provided, the temperature shall be measured by ETD's also for the record purpose.

f) LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED

The following type test reports shall be submitted for each type and rating of HT motor

- i) Degree of protection test for the enclosure followed by IR, HV and no load run test.
- ii) Terminal box-fault level withstand test for each type of terminal box of HT motors only.
- iii) Lightning Impulse withstand test on the sample coil shall be as per clause no. 4.3 IEC-60034, part-15
- iv) Surge-withstand test on interturn insulation shall be as per clause no. 4.2 of IEC 60034, part-15

1.44.02

LT Motors

- a) LT Motors supplied shall be of type tested design. During detailed engineering, the contractor shall submit for Purchaser's approval the reports of all the type tests as listed in this specification and carried out within last five years from the date of bid opening. These reports should be for the test conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client.
- b) However if the contractor is not able to submit report of the type test(s) conducted within last five years from the date of bid opening, or in the case of type test report(s) are not found to be meeting the specification requirements, the Purchaser's shall conduct all such tests under this contract at no additional cost to the Purchaser either at third party lab or in presence of client representative and submit the reports for approval.

1.44.03

LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED

1 x 660 MW – Panki Thermal Power Station

Bidding Doc. No. 14A14-SPC-G-0001
Page 351 of 593

Page 94 of 125

The following type test reports shall be submitted for each type and rating of LT motor of above 50 KW only

- i) Measurement of resistance of windings of stator and wound rotor.
- ii) No load test at rated voltage to determine input current power and speed.
- iii) Open circuit voltage ratio of wound rotor motors (in case of Slip ring motors)
- iv) Full load test to determine efficiency power factor and slip .
- v) Temperature rise test.
- vi) Momentary excess torque test.
- vii) High voltage test.
- viii) Test for vibration severity of motor.
- ix) Test for noise levels of motor(Shall be limited as per clause no 1.21.01 of this section)
- x) Test for degree of protection and
- xi) Over speed test.
- xii) Type test reports for motors located in fuel oil area having flame proof enclosures as per IS 2148 / IEC 60079-1

1.44.04 All acceptance and routine tests as per the specification and relevant standards shall be carried out. Charges for these shall be deemed to be included in the equipment price.

1.45 INFORMATION WITH PROPOSAL

1.45.1 AC Motor Data Sheet.

1.45.2 Dimension Drawing/Foundation load details of motor and driven equipment.
1.45.03 Manufacturer's catalogue showing constructional details.

1.46.00 **INFORMATION ON AWARD OF CONTRACT**.....Within six (6) weeks from the date of award of the Contract, following shall be furnished:

1.46.01 Motor Data Sheet.

1.46.02 Certified binding dimension drawing of motor complete with all accessories and fittings specifically showing terminal boxes, terminal spacing and sizes, earthing connections and sizes thereof, mounting details, lifting lugs, final foundation loads and dimensions with tolerances of centering spigot (where needed), shaft extension and key.

1.46.03 Following characteristics curves:

1.46.03.01 Torque-speed curves for motor at eighty (80), hundred (100) and hundred ten (110) percent rated voltage as well as torque-speed curve for driven equipment.

1.46.03.02 Current-speed curves at eight (80), hundred (100) and hundred ten (110) percent rated voltage

1.46.03.03 Current-time curves at eighty (80), hundred (100) and hundred ten (110) percent rated voltage.

1.46.03.04 Thermal withstand curves for hot and cold at eighty (80), hundred (100) and hundred ten (110) percent rated voltage.

- 1.46.03.05 Efficiency, power factor, current and speed versus power output curves.
- 1.46.03.06 Speed-time curves at eight (80), hundred (100) and hundred ten (110) percent rated voltage.
- 1.46.03.07 Negative phase sequence current withstand characteristics.

1.47 COMMISSIONING CHECK LIST (HT MOTORS)

A PRELIMINARY CHECKS

Check the following:

1. Check the name plate details according to specification. Discrepancies, if any, to be satisfactorily resolved.
2. Check tightness of all bolts, clamps and connecting terminals.
3. Check body earthing
4. Check whether bearing lubrication is adequate
5. Check clearance inside terminal box
6. Checking stator (motor air gap) Check – Grease lubrication (for ball or roller bearing) is adequate if the motor was in storage for very long period replace the grease, by fresh grease after flushing the bearing clean. Excess grease in the bearing (housing ... is overheat of bearings) Check the free rotation of the rotor in decoupled condition. Check the air gap between stator and rotor at four positions 90o apart at driving and non-driving end. Compare the recorded values with factory results. For slip ring motors : with starting resistances.
 - a) Check the variation of resistance
 - b) Check brush lifting and slip ring short.

B COMMISSIONING CHECKS

1. Meggar tests of motor winding and cables
2. Continuity check of motor windings control and power cables
3. Measure resistance of motor winding (in case of large motors)
4. Control and interlocks should be checked
5. Motor protection relay to be calibrated
6. Phase sequence and direction of rotation
7. Other than DOL scheme to be checked example trafo starts
9. Measure starting current starting timer and no load current
10. On load operations starting and running currents (observed vibrations, temperatures of bearings and body)
11. On load operation, starting and running currents (observed vibrations, temperatures of bearings and body)
12. In case of forced water cooling of start or check winding temperatures as ready by built in RTDs.
13. Water level (start up cooling) low to be checked for limit switch operation.

1.48 COMMISSIONING CHECK LIST (LT MOTORS)**A PRELIMINARY CHECKS**

Check the following:

1. Check the name plate details according to specification. Discrepancies, if any, to be satisfactorily resolved.
2. Check tightness of all bolts, clamps and connecting terminals.
3. Check body earthing
4. Check whether bearing lubrication is adequate
5. Check clearance inside terminal box

B COMMISSIONING CHECKS

1. Meggar tests of motor winding and cables
2. Continuity check of motor windings control and power cables
3. Over load and short circuit relay tests and settings
4. Control and interlocks should be checked
5. Phase sequence and direction of rotation
6. Operation of timer in case of star delta starting
7. Measure starting current starting timer and no load current
8. On load operations starting and running currents

1.49 DC MOTOR SPECIFICATION

DC Motor will be of continuous duty type totally enclosed fan cooled (TEFC) having IP-54 degree of protection suitable for 220 V DC supply. DC motor will be shunt wound type having high torque characteristic suitable for Bi-directional rotation at rated speed and output. The general constructional features and details of DC motor will be in line with details/ particulars stipulated in the specification for AC squirrel cage induction motors.

Contractor will furnish the data in respect of DC motors.

DATASHEET

	Auxiliary power supply	
1.1	HV supply	
	11kV, 3Φ, 3W, 50 Hz non effectively earthed	Motors rated above 1500 kW
	Fault level	50 kA for 1 second
1.2	MV supply	
	3.3kV, 3Φ, 3W, 50 Hz non effectively earthed	Motors above 200kW upto and including 1500kW
	Fault level	40 kA for 1 second
1.3	LV supply	
	415V, 3Φ, 3W, 50 Hz effectively earthed	Motors below and including 200kW
	Fault level	50kA for 1 second
	110V, 1Φ, 2W, 50 Hz effectively earthed	Lighting, space heating, AC control and protective devices
1.4	DC supply	
	220V, 2W, unearthed	DC alarm, control and protective devices.
	Fault level	25 kA for 1 second
2	Range of variation	As indicated in the specification
2.1	AC supply	
	voltage	-----
	Frequency	-----
	Combined voltage & frequency	-----
2.2	DC supply	198 to 240 V
Note: During starting of largest motor, the voltage may drop to 80% of the rated voltage for a period of 60 seconds. All electrical equipment while running shall successfully ride over such period without affecting system performance.		

STANDARD ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR (FOR EPC PROJECTS)
PACKAGE: LUBE OIL TRANSFER PUMP (Supply Package)

PROJECT: 1X660 MW UPRVUNL PANKI TPS, EXTENSION

<u>S.NO</u>	<u>DETAILS</u>	<u>SCOPE SUPPLY</u>	<u>SCOPE E&C</u>	<u>REMARKS</u>
1	415 V MCC	BHEL	BHEL	240 V AC (supply feeder)/415 V AC (3 PHASE 4 WIRE) supply shall be provided by BHEL based on load data provided by vendor at contract stage for all equipment supplied by vendor as part of contract. Any other voltage level (AC/DC) required will be derived by the vendor.
2	Local Push Button Station (for motors)	BHEL	BHEL	Located near the motors.
3	Power cables, control cables and screened control cables	BHEL	BHEL	Incoming cable from BHEL supplied MCC will be informed by BHEL. Screened control cable between DCS & field equipment will also be informed by BHEL. Vendor shall provide lugs & glands accordingly.
4	Cable trays, accessories & cable trays supporting system	BHEL	BHEL	
5	Cable glands and lugs for equipment's supplied by Vendor	Vendor	BHEL	1. Double compression Ni-Cr plated brass cable glands 2. Solder less crimping type heavy duty tinned copper lugs for power and control cables.
6	Conduit and conduit accessories for cabling between equipment's supplied by vendor	BHEL	BHEL	
7	Equipment grounding & lightning protection	BHEL	BHEL	
8	Below grade grounding	BHEL	BHEL	
9	LT Motors with base plate and foundation hardware	Vendor	BHEL	Makes shall be subject to BHEL approval at contract stage.
10	Mandatory spares	Vendor	-	Vendor to quote as per specification.
11	Recommended O & M spares	Vendor	-	As per specification
12	Any other equipment/material/service required for completeness of system but not specified above (to ensure trouble free and efficient operation of the system).	Vendor	BHEL	
13	Electrical equipment GA drawing	Vendor	-	For necessary interface review.

NOTES:

1. Make of all electrical equipments/items supplied shall be reputed make & shall be subject to approval of BHEL after award of contract.
2. All QPs shall be subject to approval of BHEL after award of contract without any commercial implication.

DATASHEET (ANNEXURE- I)

1.0	Design ambient temperature	:	50 °C
2.0	Maximum acceptable kW rating of LV motor	:	≤200KW
3.0	Installation (Indoors/ Outdoors)	:	As required
4.0	Degree Of Protection (Indoor/Outdoor)	:	IP55
5.0	Type of Cooling	:	Refer clause 1.20 of Customer Motor Specification.
6.0	Details of supply system		
	a) Rated voltage (with variation)	:	415V ± 10%
	b) Rated frequency (with variation)	:	50 Hz (Variation: +3% TO –5%)
	c) Combined voltage & freq. variation	:	10%
	d) System fault level at rated voltage	:	50 kA for 1 sec
	e) Short time rating for terminal boxes		
	○ 90kW & Above (Breaker controlled)	:	50 kA for 1 sec
	○ Below 90kW (MCCB Contactor controlled)	:	50 KA for 01 sec.
	f) LV System grounding	:	Solidly
7.0	Class of insulation	:	Refer clause 1.16 of Customer Motor Specification
8.0	Minimum voltage for starting (As percentage of rated voltage)	:	Refer clause 1.14.5.3 & 4 of Customer Motor Specification
9.0	Power cables data	:	Shall be given during Detailed engg.
10.0	Earth Conductor Size & Material	:	Shall be given during Detailed engg.
11.0	Space heater supply	:	240 V, 1Φ , 50 Hz
12.0	Rating up to which Single phase motor	:	Acceptable upto 0.20 kW
13.0	Tests	:	Refer clause 1.44.02 of Customer Motor Specification
14.0	Energy efficient/ Flame proof motor	:	As per Customer spec. requirement

- **Also detail Customer spec. for Motors to be referred as enclosed with the specification.**

DATASHEET -C

S. No.	Description		Data to be filled by successful bidder
A.	General		
1	Manufacturer & country of origin		
2	Motor type		
3	Type of starting		
4	Name of the equipment driven by motor & Quantity		
5	Maximum Power requirement of driven equipment		
6	Rated speed of Driven Equipment		
7	Design ambient temperature		
B.	Design and Performance Data		
1	Frame size & type designation		
2	Type of duty		
3	Rated Voltage		
4	Permissible variation for		
5	a	Voltage	
6	b	Frequency	
7	c)	Combined voltage & frequency	
8	Rated output at design ambient temp (by resistance method)		
9	Synchronous speed & Rated slip		
10	Minimum permissible starting voltage		
11	Starting time in sec with mechanism coupled		
12	a) At rated voltage		
13	b) At min starting voltage		
14	Locked rotor current as percentage of FLC (including IS tolerance)		
15	Torque		
	a) Starting		
	b) Maximum		
16	Permissible temp rise at rated output over ambient temp & method		
17	Noise level at 1.0 m (dB)		
18	Amplitude of vibration		
19	Efficiency & P.F. at rated voltage & frequency		
	a) At 100% load		
	c) At 75% load		

S. No.	Description	Data to be filled by successful bidder
	c) At starting	
C.	Constructional Features	
1	Method of connection of motor driven equipment	
2	Applicable Standard	
3	DOP of Enclosure	
4	Method of cooling	
5	Class of insulation	
6	Main terminal box	
	a) Type	
	b) Power Cable details (Conductor, size, armour/unarmour)	
	c) Cable Gland & lugs details (Size, type & material)	
	d) Permissible Fault level (kArms & duration in sec)	
7	Space heater details (Voltage & watts)	
8	Flame proof motor details (if applicable)	
	a) Enclosure	
	b) suitability for hazardous area	
	i Zone	O / I / II
	ii Group	IIA / IIB / IIC
9	No. of Stator winding	
10	Winding connection	
11	Kind of rotor winding	
12	Kind of bearings	
13	Direction of rotation when viewed from NDE	
14	Paint Shade & type	
15	Net weight of motor	
16	Outline mounting drawing No (To be enclosed as annexure)	
D.	Characteristic curves/ drawings (To be enclosed for motors of rating $\geq 55\text{KW}$)	
	a) Torque speed characteristic	
	b) Thermal withstand characteristic	
	c) Current vs time	
	d) Speed vs time	

		QUALITY PLAN SHEET 1 OF 2		CUSTOMER :		PROJECT			SPECIFICATION :			
				BIDDER/ :		TITLE			NUMBER :			
				VENDOR		QUALITY PLAN NUMBER PED-506-00-Q-006, REV-01			SPECIFICATION TITLE			
		SYSTEM		ITEM AC ELECT. MOTORS BELOW 55KW (LV)			SECTION			VOLUME III		
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
1	2	3	4	5	6	7	8	9	P	W	V	11
1.0	ASSEMBLY	1.WORKMANSHIP	MA	VISUAL	100%	MANUF'S SPEC	MANUF'S SPEC	-DO-	2	-	-	
		2.DIMENSIONS	MA	-DO-	-DO-	MFG. DRG./ MFG. SPEC.	MFG. DRG./ MFG. SPEC.	-DO-	2	-	-	
		3.CORRECTNESS COMPLETENESS TERMINATIONS/ MARKING/COLOUR CODE	MA	VISUAL	100%	MFG.SPEC./ RELEVANT IS	MFG.SPEC. RELEVANT IS	-DO-	2	-	-	
2.0	PAINTING	1.SHADE	MA	VISUAL	SAMPLE	MANUFR'S SPEC/BHEL SPEC./RELEVANT STANDARD	BHEL SPEC. SAME AS COL.7	LOG BOOK	2	-	-	
3.0	TESTS	1.ROUTINE TEST INCLUDING SPECIAL TEST AS PER BHEL SPEC.	MA	-DO-	100%	IS-325/ BHEL SPEC./ DATA SHEET	SAME AS COL.7	TEST REPORT	2	1		
		2.OVERALL DIMENSIONS & ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/DATA SHEET	APPROVED DRG/DATA SHEET & RELEVANT IS	INSPN. REPORT	2	1	-	NOTE -1 & NOTE-3
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									

		QUALITY PLAN		CUSTOMER :		PROJECT TITLE			SPECIFICATION : NUMBER :			
				BIDDER/ : VENDOR		QUALITY PLAN NUMBER PED-506-00-Q-006, REV-01			SPECIFICATION : TITLE :			
		SHEET 2 OF 2		SYSTEM		ITEM AC ELECT. MOTORS BELOW 55KW (LV)			SECTION		VOLUME III	
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
1	2	3	4	5	6	7	8	9	P	W	V	11
		3.NAMEPLATE DETAILS	MA	VISUAL	100%	IS-325 & DATA SHEET	IS-325 & DATA SHEET	INSPN. REPORT	2	1	-	
NOTES: 1 ROUTINE TESTS ON 100% MOTORS SHALL BE DONE BY THE VENDOR. HOWEVER, BHEL SHALL WITNESS ROUTINE TESTS ON RANDOM SAMPLES. THE SAMPLING PLAN SHALL BE MUTUALLY AGREED UPON 2 WHERE EVER CUSTOMER IS INVOLVED IN INSPECTION, (1) SHALL MEAN BHEL AND CUSTOMERS BOTH TOGETHER. 3 FOR EXHAUST/VENTILATION FAN MOTORS OF RATING UPTO 1.5KW , ONLY ROUTINE TEST CERTIFICATES SHALL BE FURNISHED FOR SCRUTINY. <u>Legends for Inspection agency</u> 1. BHEL/CUSTOMER 2. VENDOR (MOTOR MANUFACTURER) 3. SUB-VENDOR (RAW MATERIAL/COMPONENTS SUPPLIER) P. PERFORM W. WITNESS V. VERIFY												
BHEL			PARTICULARS		BIDDER/VENDOR							
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C3

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

DATASHEET

SECTION-I, SUB-SECTION-C3A: DATASHEET-A-FOR LUBE OIL TRANSFER PUMPS

BHEL PEM	DATA SHEET FOR LUBE OIL PUMPS		DOC. NO. PE-DC-426-100-N137
			SHEET NO. 01 OF 01
	PROJECT TITLE : 1X660 MW PANKI TPS		
1.0	SERVICE IDENTIFICATION	CLEAN OIL PUMP	DIRTY OIL PUMP
2.0	DRAWING NO.	PE-DG-426-100-N108	PE-DG-426-100-N108
3.0	SYSTEM	CENTRAL LUBE OIL SYSTEM	CENTRAL LUBE OIL SYSTEM
4.0	TYPE	ROTARY POSITIVE DISPLACEMENT	ROTARY POSITIVE DISPLACEMENT
5.0	NUMBER REQUIRED	ONE (01) NO.	ONE (01) NO.
6.0	FLOW RATE (MAX.)	6600 LPH	6600 LPH
7.0	DISCHARGE PRESSURE	2.0 KG/CM ² (g)	2.0 KG/CM ² (g)
8.0	SUCTION CONDITION	FLOODED (MAX -4 MLC TO BE CONSIDERED)	FLOODED (MAX -4 MLC TO BE CONSIDERED)
9.0	LOCATION OF INSTALLATION	INDOOR	INDOOR
10.0	LIQUID PUMPED	TURBINE LUBE OIL (TURBINOL-46-HPC / SERVOPRIME 46-IOC)	TURBINE LUBE OIL (TURBINOL-46-HPC / SERVOPRIME 46-IOC)
11.0	PROPERTIES OF FLUID	DENSITY- 0.9 GM/CC AT 15°C FLASH POINT - 210 °C VISCOSITY -28 CST AT 50 °C / 48 CST AT 37.8°C / 140 CST AT 20°C	DENSITY- 0.9 GM/CC AT 15°C FLASH POINT - 210 °C VISCOSITY -28 CST AT 50 °C / 48 CST AT 37.8°C / 140 CST AT 20°C
12.0	TEMPERATURE NORMAL / MAX	AMBIENT / 70 ⁰ C	AMBIENT / 70 ⁰ C
13.0	SUCTION / DISCHARGE PIPING CONNECTION	OD 88.9 X 5.49 / OD 88.9 X 5.49	OD 88.9 X 5.49 / OD 88.9 X 5.49
14.0	RELIEF VALVE	BUILT-IN ON EACH PUMP	BUILT-IN ON EACH PUMP
15.0	SUCTION STRAINER	DUPLEX TYPE STRAINER WITH CHANGE-OVER VALVE, SS ELEMENT MESH SIZE 20 & BLOW DOWN VALVE	DUPLEX TYPE STRAINER WITH CHANGE-OVER VALVE, SS ELEMENT MESH SIZE 20 & BLOW DOWN VALVE
16.0	MATERIALS OF CONSTRUCTION CASING GEARS SHAFT	CAST IRON - IS 210 - FG260 EN-8/9 EN-8/9	CAST IRON - IS 210 - FG260 EN-8/9 EN-8/9
17.0	APPLICABLE CODES / STATUTORY REGULATIONS	AS APPLICABLE API STDS	AS APPLICABLE API STDS
18.0	DRIVE TYPE	INDUCTION MOTOR 415 V, 50 Hz	INDUCTION MOTOR 415 V, 50 Hz
19.0	INSTRUMENTS	NA	NA
NOTE : ALL OTHER GENERAL TECHNICAL REQUIREMENTS / ACCESSORIES & SPARES IN LINE WITH CUSTOMER SPEC.			



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-C3B

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

DATASHEET-C- FOR LUBE OIL TRANSFER PUMPS



TITLE	SPECIFICATION NO. PE-TS-426-167-A001	
	DATA SHEET FOR LUBE OIL PUMPS	
	SUB- SECTION: C3B	
	REV 00	DATE :JULY 2019
SHEET 1 of 5		

“*” marked details will be furnished by the bidder for review and approval by customer

1.00 Project Information

1.01	Enquiry No.	*
1.02	Project	*

2.00 Service Condition

2.01	Service	Clean Oil/ Dirty Oil/Drain Oil (*bidder to tick mark the applicable service)
2.02	No. of units	*
2.03	Location	Indoor
2.04	Duty	Intermittent

3.00 Operating Condition

3.01	Liquid to be pumped	Turbine Lube Oil
3.02	Pumping Temperature	Ambient/70°C
3.03	Viscosity	
	a) Highest	140cSt @20°C
	b) Lowest	28cSt @50°C
	c) Normal	48cSt @37.8°C
3.04	Design Viscosity of oil (cSt)	28cSt for capacity , 140cSt for power consumption
3.05	Specific Gravity	0.9
3.06	Suction Conditions available	Flooded
3.07 i)	Rated capacity (LPM)	*
ii)	Pump Maximum flow (LPM) & corresponding head (kg/cm ² (g))	*
3.08	Rated head – kg/cm ² (g)	*
3.09	R..V.Press.Setting	*

4.00 Pump

4.01	Manufacturer	*
4.02	Type	External gear with herringbone gears
4.03	Model No.	*
4.04 (i)	Design & Manufacturing Standard	API 676
4.04 (ii)	Testing Standard	HIS (ANSI/HI-3.6-2000 / VDMA 24284 , Accuracy Class-2, Group-II

	TITLE DATA SHEET FOR LUBE OIL PUMPS		SPECIFICATION NO. PE-TS-426-167-A001	
			SUB- SECTION: C3B	
			REV 00	DATE :JULY 2019
SHEET 2 of 5				
(* Bidder to tick the standard adopted)				
4.05	Rotation (Viewed from pump shaft end)	*		
4.06	Shut off head, if applicable	Not applicable		
4.07	Suction flange	Size 80 NB Standard ANSI B 16.5 Rating 150 lb Facing RF Location (as viewed from drive end) -*(Bidder to tick the applicable) Top End Side		
4.08	Discharge flange	Size 80 NB Standard ANSI B 16.5 Rating 150 lb Facing RF Location (as viewed from drive end) -*(Bidder to tick the applicable)		
4.09	Timing Gear	Not applicable for gear pumps		
4.10	Relief Valve	Built-in		
	a) Manufacturer	Pump manufacturer (OEM)		
	b) Type	*		
	c) Size (NB)	*		
	d) Capacity, litre/min	110% of the pump max. flow		
	e) Valve, setting pressure adjustable & range of adjustability, in case adjustable	Yes/No (* bidder to indicate the applicable) - *		
	f) Material			
	g) Spring, Material	Spring Steel		
	h) Relief valve cover-Material	Same as MOC of pump body		
	i) Bonnet-Material	Same as MOC of pump body		
4.11	Shaft Sealing	Mechanical seal		
4.12	Bearing			
	a) Type	*		
	b) Nos. Provided	*		
	c) Method of lubrication	*		
	d) Temperature rise over oil temperature	*		
4.13	Type of Coupling	*		

	TITLE DATA SHEET FOR LUBE OIL PUMPS	SPECIFICATION NO. PE-TS-426-167-A001	
		SUB- SECTION: C3B	
		REV 00	DATE :JULY 2019
		SHEET 3 of 5	
4.14	Type of Impeller	External gear- Herringbone profile	
4.15	BHP consumed at Rated viscosity (at pump shaft)	*	
4.16	BHP consumed at Max. viscosity (at pump shaft)	*	
4.17	BHP consumed at Min. viscosity (at pump shaft)	*	
4.18	BHP consumed at the R.V. Set Pressure (at pump shaft) @ 48 cSt at maximum value of set pressure range	*	
4.19	Pump Efficiency at rated condition @ 48 cSt		
	a) Mechanical	*	
	b) Volumetric	*	
	c) Overall	*	
4.20	Recommended motor rating at 50 ° C ambient (kw)	*	
4.21	Motor RPM	*	
4.22	Design pressure of the pump body and end covers - kg/cm ² (g)- * (Should be at least 6 kg/cm ² (g))		
5.00	Material of Construction		
5.01	Casing and End covers	CAST IRON IS210 FG 260	
5.02	VOID		
5.03	Rotor/Gear	EN-8 BS 970 Part-I	
5.04	Shaft/Shaft Sleeve	Hardness- * SS 316	
5.05	Seal	*	
5.06	Gasket	GRAFOIL/ Any other asbestos free material subject to customer acceptance (* bidder to indicate)	
5.07	Bearing	*	
5.08	Relief Valve Components	*	
5.09	Base Plate	MS to IS 2062	
6.00	Spares		
6.01	Commissioning Spares	1 set of gaskets/1 no. gasket compound tube 1 No. mechanical seal	
6.02	Essential Spares for Pump, if applicable	* (Project specific)	

Page 111 of 125



TITLE

**DATA SHEET
FOR LUBE OIL PUMPS**

SPECIFICATION NO. PE-TS-426-167-A001

SUB- SECTION: C3B

REV 00

DATE :JULY 2019

SHEET 4 of 5

6.03	Essential Spares for Motor, if applicable	* (Project specific)
6.04	Recommended Spares for Pump for 3 Years	*
6.05	Recommended Spare for Motor for 3 Years	*
7.00	Weight of	
7.01	Pump	*
7.02	Motor	*
7.03	Base plate	*
7.04	Other Accessories (Please specify)	*
8.00	Strainer/Filter	
8.01	Manufacturer Bhatia Engineering Company/ Filtration Engineers (I) Pvt.Ltd / Jaypee Industries Pvt. Ltd./Multitex Filtration Engineers/ Otoklin Plants & Equipment Ltd/ OEM subject to condition that strainer of similar type & capacity have been working satisfactorily at least two plants. (Bidder to tick the make considered)	*
8.02	Type & Size	* (Type -Project specific; size –to match pump suction)
8.03	Nos. provided	* (Project specific)
8.04	Size of Screen mesh & wire dia (min)	40 mesh & 34 SWG
8.05	Design Pressure (kg/cm ²) (Should be at least 4 kg/cm ²)	*
8.06	Capacity (LPM)	To match pump flow
8.07	Design Viscosity	140cSt @ 20 °C
8.08	End Connection	Flanged ANSI B 16.5, Class –150 lb
8.09	Maximum Pressure drop at design viscosity (kg/cm ²)	



TITLE

**DATA SHEET
FOR LUBE OIL PUMPS**

SPECIFICATION NO. PE-TS-426-167-A001

SUB- SECTION: C3B

REV 00

DATE :JULY 2019

SHEET 5 of 5

	a) Clean	*
	b) Dirty (50% clogged)	*
8.10	Material of construction	
	a) Strainer body	*
	b) Screen	SS316
	c) Gaskets	GRAFOIL/ Any other asbestos free material subject to customer acceptance (* bidder to indicate)
8.10	a) Inlet pipe Area	*
	b) Free straining area	*
	c) Ration of Free straining area to inlet pipe area (should be $\geq 6:1$)	*
9.00	Accessories to be provided	
	Common base plate plate	Yes- MS fabricated from IS 2062
		Common for pump & motor
	Coupling & Coupling Guard	Yes
	Foundation bolts & nuts	Yes
	Flanges & Companion flanges	Yes, Class 150 lb, RF to ANSI B 16.5
	Nuts, bolts & gaskets	Yes
	Lifting lugs, Eye bolts etc	Yes
	Name plate for all the equipment	Yes



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-I, SUB-SECTION-D

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

FORMAT FOR OPERATION AND MANITENANCE

Format for Operation & Maintenance Manual

Project name :

Project number :

Package Name :

PO reference :

Document number :

Revision number :

Sl.no. & Sections	Description	Tick (√)if included in Manual			Remarks
		Yes	No	Not Applicable	
1.	Cover page				
1.1	Project Name				
1.2	Customer/consultant Name				
1.3	Name of Package				
1.4	Supplier details with phone, FAX ,email address , Emergency Contact number				
1.5	Name and sign of prepared by , checked by & approved by				
1.6	Revision history with approval Details				
2.0	Index				
2.1	showing the sections & related page nos All the pages should be numbered section wise				
3.0	Description of Plant/System				
3.1	Description /write up of operating principle of system equipment/ associated sub-systems & accessories/controls system , operating conditions, performance parameters under normal , start up and special cases				
3.2	Equipment list and basic parameter with Tag numbers				
3.3	Data sheets approved by Customer/for information and catalogues provided by original manufacturer				
3.4	Associated other packages and Interface /terminal points				
3.5	P&ID & Process Diagrams				
3.6	GA Layout drawings, As-built drawings , Actual photograph of items/system (Drawings of A2 & bigger sizes are to be attached in the last)				
3.7	Single line/wiring diagrams				
3.8	Control philosophy /control write-ups				

4.0	Commissioning Activities (if not covered in separate document i.e. erection manual, commissioning manual)				
4.1	Pre-Commissioning Checks				
4.2	handling of items at site				
4.3	Storage at site				
4.4	Unpacking & Installation procedure				
5.0	Operation Guidelines for plant personal/user/operator				
5.1	Interlock & Protection logic along with the limiting values of protection settings for the equipment along with brief philosophy behind the logic, drawings etc. to be provided.				
5.2	Start up, normal operation and shut down procedure for equipments along with the associated systems in step by step mode. Valve sequence chart, step list, interlocks etc. with Equipment isolating procedures to be mentioned.				
5.3	Do's & Don't of the equipments.				
5.4	Safety precautions to be taken during normal operation. Safety symbols, Emergency instructions on total power failure condition/lubrication failure/any other condition				
5.5	Parameters to be monitored with normal values and limiting values				
5.6	Trouble shooting with causes and remedial measures				
5.7	Routine operational checks, recommended logs & records				
5.8	Changeover schedule if more than one auxiliary for the same purpose is given				
5.9	Painting requirement and schedule				
5.10	Inspection, repair , Testing and calibration procedures				
6.0	Maintenance guidelines for plant personal				
6.1	List of Special Tools and Tackles required for Overhaul/Trouble shooting including special testing equipment required for calibration etc.				
6.2	Stepwise dismantling and re-assembly procedure clearly specifying the tools to be used, checks to be made, records to be maintained, clearances etc. to be mentioned. Tolerances for fitment of various components to be given.				

6.3	Preventive Maintenance & Overhauling schedules linked with running hours/calendar period along with checks to be given				
6.4	Long term maintenance schedules especially for structural, foundations etc.				
6.5	Consumable list along with the estimated quantity required during commissioning, normal running and during maintenance like Preventive Maintenances and Overhaul. Storage/handling requirement of consumables/self-life.				
6.6	List of lubricants with their Indian equivalent, Lubrication Schedule, Quantity required for each equipment for complete replacement is to be given				
6.7	List of vendors & Sub-vendors with their latest addresses, service centres ,Telephone Nos., Fax Nos., Mobile Nos., e-mail IDs etc.				
6.8	List of mandatory and recommended spare parts list				
6.9	Tentative Lead time required for ordering of spares from the equipment supplier				
6.10	Guarantee and warranty clauses				
7.0	Statutory and other specific requirements considerations.				
8.0	List of reference documents				
9.0	Binding as per requirement				



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-II, ANNEXURE-I

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

LIST OF DOCUMENTS TO BE SUBMITTED WITH THE BID

- a. Pre-bid clarification schedule as per format given under Section-II, Annexure-III, in case of any clarifications.
- b. Deviation schedule as per format given under Section-II, Annexure--IV, in case of any deviations by bidder.
- c. Compliance cum confirmation certificate as given under Section-II, Annexure-II.
- d. Unpriced price schedule.
- e. Signed and stamped copy of the electrical load data (Section-II, Annexure-V).
- f. In addition to the above, docs required along with bid given under electrical portion of specification shall be furnished by bidder.



TITLE:

**TECHNICAL SPECIFICATION
1X660 MW UPRVUNL PANKI TPS, EXTENSION
COMPLIANCE CUM CONFIRMATION
CERTIFICATE**

SPEC. NO.: PE-TS-426-567-A001

SECTION: II, ANNEXURE-II

REV. NO. 0 DATE

SHEET 1 OF 2

COMPLIANCE CUM CONFIRMATION CERTIFICATE

The bidder shall confirm compliance with following by signing/ stamping this compliance certificate (every sheet) and furnish same with the offer.

- a) The scope of supply, technical details, construction features, design parameters etc. shall be as per technical specification & there are no exclusions other than those mentioned under "exclusion" and those resolved as per 'Schedule of Deviations', if applicable, with regard to same.
- b) There are no other deviations w.r.t. specifications other than those furnished in the 'Schedule of Deviations'. Any other deviation, stated or implied, taken elsewhere in the offer stands withdrawn unless specifically brought out in the 'Schedule of Deviations'.
- c) Bidder shall submit QP in the event of order based on the guidelines given in the specification & QP enclosed therein. QP will be subject to BHEL/ CUSTOMER approval & customer hold points for inspection/ testing shall be marked in the QP at the contract stage. Inspection/ testing shall be witnessed as per same apart from review of various test certificates/ Inspection records etc. This shall be within the contracted price with no extra implications to BHEL after award of the contract.
- d) All drawings/ data-sheets/ calculations etc. submitted along with the offer shall be considered for reference only, same shall be subject to BHEL/ CUSTOMER approval in the event of order.
- e) The offered materials shall be either equivalent or superior to those specified in the specification & shall meet the specified/ intended duty requirements. In case the material specified in the specifications is not compatible for intended duty requirements then same shall be resolved by the bidder with BHEL during the pre - bid discussions, otherwise BHEL/ Customer's decision shall be binding on the bidder whenever the deficiency is pointed out.

For components where materials are not specified, same shall be suitable for intended duty, all materials shall be subject to approval in the event of order.

- f) The commissioning spares shall be supplied on 'As Required Basis' & prices for same included in the base price itself.
- g) All sub vendors shall be subject to BHEL/ CUSTOMER approval in the event of order.
- h) Guarantee for plant/equipment as applicable, shall be as per relevant clause of GCC /SCC /Other Commercial Terms & Conditions.
- i) In the event of order, all the material required for completing the job at site shall be supplied by the bidder within the ordered price even if the same are additional to approved billing break up, approved drawing or approved Bill of quantities. This clause will apply in case during site commissioning additional requirements emerges due to customer and/ or consultant's comments. No extra claims shall be put on this account.
- j) Schedule of drawings submissions, comment incorporations & approval shall be as stipulated in the specifications. The successful bidder shall depute his design personnel to BHEL's/ Customer's/ Consultant's office for across the table resolution of issues and to get documents approved in the stipulated time.



TITLE:

**TECHNICAL SPECIFICATION
1X660 MW UPRVUNL PANKI TPS, EXTENSION
COMPLIANCE CUM CONFIRMATION
CERTIFICATE**

SPEC. NO.: PE-TS-426-567-A001

SECTION: II, ANNEXURE-II

REV. NO. **0** DATESHEET **2** OF **2**

- k) As built drawings shall be submitted as and when required during the project execution.
- l) The bidder has not tempered with this compliance cum confirmation certificate and if at any stage any tempering in the signed copy of this document is noticed then same shall be treated as breach of contract and suitable actions shall be taken against the bidder.

SIGNATURE: _____

NAME : _____

DESIGNATION: _____

COMPANY: _____

DATE: _____

COMPANY SEAL



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-II, ANNEXURE-III

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

PRE-BID CLARIFICATION SCHEDULE

S. No.	Section/Clause/Page No.	Statement of the referred clause	Clarification Required

The bidder hereby certifies that above mentioned are the only clarifications required on the technical specification for the subject package.

SIGNATURE: _____

NAME: _____

DESIGNATION: _____

COMPANY: _____

DATE: _____

COMPANY SEAL



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-II, ANNEXURE-IV

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

SCHEDULE OF TECHNICAL DEVIATION

DEVIATION SHEET (COST OF WITHDRAWAL)**PACKAGE:- LUBE OIL TRANSFER PUMPS****TENDER ENQUIRY REFERENCE:-****NAME OF VENDOR:-**

SL NO	VOULME/ SECTION	PAGE NO.	CLAUSE NO.	TECHNICAL SPECIFICATION/ TENDER DOCUMENT	COMPLETE DESCRIPTION OF DEVIATION	COST OF WITHDRAWAL OF DEVIATION	REFERENCE OF PRICE SCHEDULE ON WHICH COST OF WITHDRAWAL OF DEVIATION IS APPLICABLE	NATURE OF COST OF WITHDRAWAL OF DEVIATION (POSITIVE/ NEGATIVE)	REASON FOR QUOTING DEVIATION
-------	-----------------	----------	------------	--	-----------------------------------	---------------------------------	--	--	------------------------------

TECHNICAL DEVIATIONS

COMMERCIAL DEVIATIONS

PARTICULARS OF BIDDERS/ AUTHORISED REPRESENTATIVE

NAME	DESIGNATIONS	SIGN & DATE	
------	--------------	-------------	--

NOTES:

- For self manufactured items of bidder, cost of withdrawal of deviation will be applicable on the basic price (i.e. excluding taxes, duties & freight) only.
- For directly dispatchable items, cost of withdrawal of deviation will be applicable on the basic price including taxes, duties & freight.
- All the bidders have to list out all their Technical & Commercial Deviations (if any) in detail in the above format.
- Any deviation not mentioned above and shown separately or found hidden in offer, will not be taken cognizance of.
- Bidder shall submit duly filled unpriced copy of above format indicating "quoted" in "cost of withdrawal of deviation" column of the schedule above along with their Techno-commercial offer, wherever applicable.
- Bidder shall furnish price copy of above format along with price bid.
- The final decision of acceptance/ rejection of the deviations quoted by the bidder shall be at discretion of the Purchaser.
- Bidders to note that any deviation (technical/commercial) not listed in above and asked after Part-I opening shall not be considered.
- For deviations w.r.t. Payment terms, Liquidated damages, Firm prices and submission of E1/ E2 forms before claiming 10% payment, if a bidder chooses not to give any cost of withdrawal of deviation loading as per Annexure-VIII of GCC, Rev-06 will apply. For any other deviation mentioned in un-priced copy of this format submitted with Part-I bid but not mentioned in priced copy of this format submitted with Priced bid, the cost of withdrawal of deviation shall be taken as NIL.
- Any deviation mentioned in priced copy of this format, but not mentioned in the un-priced copy, shall not be accepted.
- All techno-commercial terms and conditions of NIT shall be deemed to have been accepted by the bidder, other than those listed in unpriced copy of this format.
- Cost of withdrawal is to be given separately for each deviation. In no event bidder should club cost of withdrawal of more than one deviation else cost of withdrawal of such deviations which have been clubbed together shall be considered as NIL.
- In case nature of cost of withdrawal (positive/negative) is not specified it shall be assumed as positive.
- In case of discrepancy in the nature of impact (positive/ negative), positive will be considered for evaluation and negative for ordering.



TITLE:
1X660 MW UPRVUNL PANKI TPS, EXTENSION
TECHNICAL SPECIFICATION FOR
LUBE OIL TRANSFER PUMPS

SPECIFICATION No: PE-TS-426-567-A001

SECTION-II, ANNEXURE-V

REV. 00

DATE: JULY 2019

SHEET : 1 OF 1

ELECTRICAL LOAD DATA

LOAD TITLE	RATING (KW / A)		UNIT (U)/STN (S)	Nos.		VOLTAGE CODE*	FEEDER CODE**	EMER. LOAD (Y)	CONT.(C)/ INTT.(I)	STARTING TIME >5 SEC (Y)	LOCATION	BOARD NO.	CABLE		BLOCK CABLE DRG. No.	CONTROL CODE	REMARKS	LOAD No.
	NAME PLATE	MAX. CONT. DEMAND (MCR)		RUNNING	STANDBY								SIZE CODE	NOS				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
CLEAN OIL TRANSFER PUMP	3.7 KW		-	1	-	D	U	-	-	-	TG hall							
DIRTY OIL TRANSFER PUMP	3.7 KW		-	1	-	D	U	-	-	-	TG hall							

Note:

- Bidder to confirm that the system provided by them would be catered by the above loads considered by BHEL. In case there is any variation; the same should be clearly stated in the technical offer. No changes would be admissible during detailed engineering stage.
- Bidder to note that for the system being supplied by them, only the above loads will be provided. In case any other load is required the same would be derived /multiplied by bidder on their own from these feeders only.

NOTES:

1. COLUMN 1 TO 12 & 18 SHALL BE FILLED BY THE REQUISITIONER (ORIGINATING AGENCY); REMAINING COLUMNS ARE TO BE FILLED UP BY PEM (ELECTRICAL)

2. ABBREVIATIONS : * VOLTAGE CODE (7):- (ac) A=11 KV, B=6.6 KV, C=3.3 KV, D=415 V, E=240 V (1 PH), F=110 V (cc): G=220 V, H=110 V, J=48 V, K=+24V, L=-24 V

: ** FEEDER CODE (8):- U=UNIDIRECTIONAL STARTER, B=BI-DIRECTIONAL STARTER, S=SUPPLY FEEDER, D=SUPPLY FEEDER (CONTACTER CONTROLLED)

	LOAD DATA (ELECTRICAL)	JOB NO.	ORIGINATING AGENCY		PEM (ELECTRICAL)		
		PROJECT TITLE	1X660 MW UPRVUNL PANKI TPS, EXTN	NAME			
		SYSTEM	LUBE OIL PUMPS	SIGN.			
		DEPTT. / SECTION	ELECTRICAL	SHEET 1 OF 1	REV. 00	DATA FILLED UP ON	
				DATA ENTERED ON			
				DE'S SIGN. & DATE		Page 125 of 125	