



भारत हेवी इलेक्ट्रिकल्स लिमिटेड
(भारत सरकार का उपक्रम)
सेंट्रलाइज्ड स्टेपिंग एवं फेब्रिकेशन प्लांट
औद्योगिक क्षेत्र जगदीशपुर, जिला- अमेठी (उ०प्र०)-227817

Tender For RCC Approach For Weigh Bridge & Misc Works at CS&FP BHEL Jagdishpur

Tender Enquiry No: BHE/CS&FP/CVL/18-19/01

BOQ & Priced Bid (Section - III)

This Document shall also consists of following sections: -

- **Annexure PB – I**
- **Annexure PB – II**

BHARAT HEAVY ELECTRICALS LIMITED

(A GOVERNMENT OF INDIA UNDERTAKING)

CS & FP Industrial Area,

Jagdishpur, Amethi (UP) 227817



Centralised Stamping & Fabrication Plant (CS & FP), BHEL Jagdishpur

Name of Work : RCC Approach For Weigh Bridge & Misc Works at CS&FP BHEL Jagdishpur

Annexure PB - I

Bill of Quantities & Price Schedule

S.No.	DESCRIPTION OF WORK	UNIT	Total Qty	% Weightage of Item Amount against Total Amount
1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kinds of soil.	Sqm	1850.00	5.935
2	P & L in position cement concrete (PCC) of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	Cum	19.42	19.997
3	Providing and laying in position specified grade of reinforced cement concrete , excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size).	Cum.	28.65	40.953
4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar	Cum	5.87	1.137
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	1.00	1.284
6	Painting Interior / Exterior to give an even shade old work (Paint & Other Finishing Material Shall be provided by BHEL Free of cost)	Sqm	224.00	1.106
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level (Thermo-Mechanically Treated bars of grade Fe-500D or more)	Kg.	1335.00	17.378
8	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	Sqm.	14.00	0.042
9	Hiring Hydraulic Excavator of 1 cum bucket including cost of Driver and Fuel.	Hours	24.00	5.078
10	Hiring Tractor with trolley with Fuel and Driver	Per Day	8.00	2.300
11	Hiring Manpower for misc. finishing works	Man Days	40.00	4.791
			Total %	100.00
Note : GST Payable extra as applicable				



Centralised Stamping & Fabrication Plant (CS & FP), BHEL Jagdishpur
Name of Work : RCC Approach For Weigh Bridge & Misc Works at CS&FP BHEL
Jagdishpur

Annexure PB - II
Summary of Price Schedule

Details of ANNEXURE PB-I	Total Amount (in ₹)
Total Amount (Rupees in Figures) :	
Total Amount (Rupees in Words) :	

Note:

- 1 Total price of the package to be quoted by the bidders which shall form the basis of comparison for deciding lowest bid.**
- 2 In case of any discrepancy between 'Total Quoted Amount (in Figures)' and 'Total Quoted Amount (in Words)', lower of the two 'Amounts' shall be considered for evaluation purpose**
- 3 For further processing & award total quoted Amount for the package by the L1 (lowest) bidder shall be used for deriving Individual item rate by BHEL based on % (percentage) weightage specified at BOQ & Price Schedule (Annexure PB-I).**
- 4 GST Payable extra as applicable**

Signature BHEL

Signature & Seal of Bidder