

**PRICE BID (PART-B)**

**NIT No. 22:AA:NOI:ADMN:BMC:112:2018-19 DATED 26.07.2018**

**Sub:- Renovation of Badminton court in BHEL Township Noida**

S.N.	Item Description	Unit	Rate Rs.	Qty.	Amount (Rs.)
1	Surface dressing of the ground including removing vegetation and equalities not exceeding 15 cm deep and disposal of rubbish, lead up to 50 m and lift up to 1.5 m. All kind of soil.	Sqm.	12.28	1000	12276.00
2	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	Cum.	807.62	8.00	6460.96
3	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:	Cum.	4041.75	7.50	30313.14
4	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq. meters and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls complete, including disposal of rubbish to the dumping ground, all complete as per directions of Engineer-In-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	Sqm.	241.82	20.00	4836.48
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 40 mm thick with 20 mm nominal size stone aggregate	Sqm.	319.09	270	86153.76
6	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	Sqm.	49.02	180.00	8822.88
7	CEMENT CONCRETE (CAST IN SITU) 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size)	Cum.	3940.77	15.00	59111.58
8	12 mm cement plaster finished with a floating coat of neat cement of mix : 1:4 (1 cement: 4 fine sand)	Sqm.	188.50	40.00	7539.84
9	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes (size 50x25x2 mm of MS Hollow box section)	KG	79.42	150.00	11913.00
10	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. One or more coats on old work	Sqm.	45.14	62.00	2798.93
11	Providing and Laying of High-Impact Synthetic Polypropylene Interlocking Modular Tiles of 15.0 mm thick with Game Line Marking with suitable edge strip as colour & sample approved by the Engineer in charge. Minimum size of tile 300x300 mm	Sqft.	165.60	1152	190771.20
12	<b>Total Estimated Expenditure (Excluding GST)in Rs.</b>	<b>420998</b>			
13	Percentage Above(+)/ Below(-) at par with S. No. 12 ( To be quoted)				
14	Total Quoted Amount after applying percentage (S. No. 13) (excluding of GST) in Rs.				
15	GST @ _____ (in Rs.)				
16	<b>Total Amount (all inclusive) in (Rs.)</b>				
	<b>Total (In Words) -</b>				

**Note:-** All the above rates and quantities are fixed & firm. Bidder has to quote % Above (+)/ Below (-) the mentioned estimated value in Sr. No. 13 only. Based on the value entered in sr. no. 13, subsequent rows, i.e. serial no. 14 to 16 should be filled by the bidder. On opening of price bid, if any deviation is found from the above mentioned criteria to fill the price bid, it shall be considered deviation from Tender Terms & the bid shall be rejected.

Signature and seal of bidder


**विकास कुमार गर्ग**  
 उप प्रबंधक (आ. वं.-टीएलएस)  
**Varun Kumar Garg**  
 Dy. Manager (HR-T&X)  
 भारती भारी इलेक्ट्रिकल्स लि., एस्टेट कार्यालय, सेक्टर-17, नोएडा  
 Bharat Heavy Electricals Ltd., Estate Office, Sector-17, Noida