

PART B

PRICE BID

कार्य का नाम / Name of Work:

बी एच ई एल उपनगरी, सेक्टर - 17, नोएडा में सड़कों के शोल्डर पर पेंटर टाइल बिछाने का कार्य।

Laying of Paver Tiles Over Road Shoulders in BHEL Township, Sector- 17, Noida

निविदा संख्या/NIT No.: 02:AA:NOI:ADMN:PT:112:2019-20 दिनांक/DATED: 19.04.2019

Sl. No.	Description of Item	unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., disposal of unserviceable material to the dumping ground, for which payment shall be made separately and stacking of serviceable material within 50 metre lead as per direction of Engineer-in-Charge.	sqm	800	47.48	37980.80
2	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including disposal of excavated earth upto 50 m and lift upto 1.5 m, disposed soil to be levelled and neatly dressed : All kinds of soil .	sqm	2000	46.64	93280.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	cum	200	3940.77	788154.40
4	Providing and laying 75 mm thick compacted bed of dry brick aggregate of 40 mm thick nominal size including spreading, well ramming, consolidating and grouting with jamuna sand, including finishing smooth etc. complete as per direction of Engineer-in-charge.	cum	200	124.39	24877.60
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in :Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	80	4912.91	393032.64
6	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand)	Sqm	600	148.06	88836.00
7	Neat cement punning.	Sqm	600	37.49	22492.80
8	Providing and laying 60mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-charge.	sqm	2800	541.82	1517084.80
9	Total Basic Amount (excluding GST) in Rs.				2965739.04
10	Percentage Above(+)/ Below(-) at par with S. No. 9 in Rs.				
11	Total Quoted Amount after applying percentage (S.N. 10) (excluding GST) in Rs.				
12	GST @ _____ % of Total in Rs.				
13	Total Amount inclusive of GST (in Rs.)				

Signature & Seal of Bidder


BHEL
वरुण कुमार गर्ग
उप प्रबंधक (म. सं.-टीएएल)
Varun Kumar Garg
Dr. Manager (HR-TAX)
भारत हेवी इलेक्ट्रिकल्स लि., संस्था कार्यालय, सेक्टर-17, नोएडा
Bharat Heavy Electricals Ltd., Estate Office, Sector-17, Noida