

BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM :: HYDERABAD-32
TOWNSHIP ADMINISTRATION
Schedule - A - Price bid

Tender Notice NO: HY/TA/OT-03/2019-20

Date: 12.06.2019

Name of Work: Construction of Boundary wall along the periphery of BHEL RC Puram lands in clear lengths

S.No	Description	Ref. Code	Total Qty	unit	Unit Rate (Rs.)	Total Amount (Rs.)
1	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30cm measured at a height of 1m above ground level. The rate quoted shall include the cost of cutting, cleaning, loading, conveyance within a lead of 2 KM to places as directed by Engineer-in-Charge.	code 2.31	20000.00	Sq.m	6.42	128400.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed, in all kinds of soil.	code 2.6.1	8614.23	Cu.m	155.60	1340374.19
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.	2.8/p-72	10000.00	Cu.m	157.50	1575000.00
4	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed. hard rock (blasting prohibited) all as directed by the Engineer-in-charge.	2.7.3/ P.72	1081.11	Cu.m	618.10	668234.09
5	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means for hard rock including disposal of excavated earth, lead up to 50 m and lift up to 1.5 m, disposed earth to be levelled and neatly dressed all as directed by the Engineer-in-charge. (Hard rock requiring blasting)	2.7.2	500.00	Cu.m	418.15	209075.00
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size). as directed by engineer-in-charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue	code 4.1.8	57.20	Cu.m	3911.23	223722.36
7	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering. All work up to plinth level. 1:5:10 (1 cement 5 fine sand 10 graded stone aggregate 40 mm nominal size). All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	4.1.11/P.85	866.69	Cu.m	3404.78	2950888.78
8	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement. All work up to plinth level/above ground level 1:2:4 (1 cement 2 coarse sand 4 grade stone aggregate 20mm nominal size). All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	5.1.3 P 96	1729.96	Cu.m	5186.54	8972506.74
9	Providing and laying cement concrete of grade 1:2:4 in retaining walls return walls (any thickness) including attached pilasters, columns piers abutments pillars posts struts buttresses string or lacing courses parapets coping bed blocks anchor blocks plain window sills fillets etc. upto floor five level excluding the cost of centering shuttering and finishing. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	4.2.3/ P.85	48.54	Cu.m	5910.64	286902.47

Schedule - A - Price bid

Tender Notice NO: HY/TA/OT-03/2019-20

Date: 12.06.2019

Name of Work: Construction of Boundary wall along the periphery of BHEL RC Puram lands in clear lengths

S.No	Description	Ref. Code	Total Qty	unit	Unit Rate (Rs.)	Total Amount (Rs.)
10	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering, shuttering, finishing and reinforcement including consolidation by vibrations for all works up to plinth level with 1:1.5:3(1cement 1.5 coarse sand 3 grade stone aggregate 20mm nominal size). All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	5.1.2 P 96	40.00	Cu.m	5625.89	225035.50
11	Reinforcement for RCC work including straightening, cutting bending placing in position and binding including cost of all materials etc, all complete above plinth level. Hot rolled deformed bars. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	5.22A.4	237400.40	Kgs	60.60	14386464.24
12	Coursed rubble masonry in second sort with hard stone in foundation & above plinth with cement mortar 1:6 (1 cement :6 coarse sand), complete as directed by engineer-in-charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	code 7.7.1	5981.83	Cu.m	3917.22	23432144.11
13	Plastering in CM 1:6 , 20 mm thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete -Upto 10.00 M level. Complete as directed by engineer-in-charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	code 13.3.2	10336.00	Sq.m	198.69	2053670.18
14	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90 m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4 m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core (2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape (0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately) All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	code 16.53	10463.30	Rmt	248.71	2602327.34
15	Pointing on stone work with cement mortar 1:3 (1 cement : 3 fine sand) :Raised and cut pointing. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	code 13.33.2	30483.51	Sq.m	254.12	7746347.63
16	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift up to 1.5 m .	2.25/p.75	4575.01	Cu.m	112.40	514231.12
17	Centring and shuttering including strutting, propping etc and removal of form. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.		0.00			
a	For foundations, footings, bases of columns, etc For mass concrete.	5.9.1	1670.83	Sq.m	73.16	122237.92
b	For columns, pillars, piers, abutments, posts and struts.	5.9.6	6908.65	Sq.m	374.67	2588463.90
c	For Lintels, Beams, plinth beams, girders, bressumers and cantilevers.	5.9.5	5395.10	Sq.m	320.23	1727670.18
d	Column for gates	5.9.6	280.00	Sq.m	374.67	104907.60

Schedule - A - Price bid

Tender Notice NO: HY/TA/OT-03/2019-20

Date: 12.06.2019

Name of Work: Construction of Boundary wall along the periphery of BHEL RC Puram lands in clear lengths

S.No	Description	Ref. Code	Total Qty	unit	Unit Rate (Rs.)	Total Amount (Rs.)
18	Providing hoisting and fixing upto floor five level precast reinforced cement concrete in vertical and horizontal fines individually or forming box louvers setting in cement mortar 1:2 (1cement 2 coarse sand) including the cost of required centring shuttering and finishing smooth with 6mm thick cement plaster 1:3 (1 cement 3 fine sand) on exposed surfaces complete but excluding the cost of reinforcement with 1:2:4 (1 cement 2 coarse sand 4 graded stone aggregate 20 mm nominal size) with strength M 30, the pre-casting has to be done in specially designed moulds and compacted with mechanical vibrator complete all as directed by engineer in charge. BHEL letters to be embossed as shown in the drg/ as directed by Engineer In charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	5.17 P- 98	1535.26	Cu.m	7177.85	11019865.99
19	Grouting of bolt pockets and column groove in cement mortar 1:1 including cost of all materials,labour,curing,for all leads and lifts etc, complete. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	BQ & Cement coefficient DSR-3.1	32.62	Cu.m	8800.00	287056.00
20	Finishing walls with acrylic smooth exterior paint of required shade. New work (two or more coat applied @ 1.67 ltr/ 10 sqm) over and including base coat of water proofing cement paint applied @ 2.20kg/ 10sqms. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	13.46.1	38314.46	Sq.m	31.71	1214951.53
21	Supply and Errection of 40mm GI pipes to be fixed in position to the CRS wall as directed by Engineer In charge. All the materials are in contractor scope including necessary fittings, BHEL Will not give any Material FREE Issue.	(1549 P-172)	8428.40	Rmt	220.00	1854248.00
22	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron / steel work. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	13.50.3	1053.55	Sq.m	21.33	22472.22
23	Painting with aluminium paint of approved brand and manufacture to give an even shade including cost of all materials etc,complete.One or more coats. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	14.55	1053.55	Sq.m	30.68	32322.91
24	Brick work with modular bricks of class designation 75 in foundation, plinth and upto floor five level in cement mortar 1:6(1cement :6 coarse sand) All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	6.2.2	47.10	Cu.m	4076.51	192003.62
25	Plastering in cement mortar 1:6, 12 mm thick including curing, cost of all materials etc, complete all as directed by Engineer-in-charge All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	13.1.2	553.24	Sq.m	98.90	54715.44
26	Supply and apply Distempering with 1st quality acrylic washable distemper (ready mixed) of approved manufacture and of required shade and colour complete as per manufacturer specification. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	13.42	236.80	Sq.m	35.19	8332.99

Schedule - A - Price bid

Tender Notice NO: HY/TA/OT-03/2019-20

Date: 12.06.2019

Name of Work: Construction of Boundary wall along the periphery of BHEL RC Puram lands in clear lengths

S.No	Description	Ref. Code	Total Qty	unit	Unit Rate (Rs.)	Total Amount (Rs.)
27	Supplying and fixing of Unplasticised Poly Vinyl Chloride (UPVC) openable doors with openable shutters duly manufactured using UPVC reinforced profiles of 60 mm x 55 mm x 2.0 mm for outer frames, 70 mm x 60 mm x 2.25 mm for mullion sections as per the need and 102 mm x 60 mm x 2.0 mm for openable shutter frame capable of mounting single glazing system structurally reinforced with hot dip galvanized up to 50 microns of minimum thickness of 1.2 mm prefabricated & welded through fusion welding the window sash shall be fitted with 5 mm thick clear float glass of reputed make duly fixed with TPV Gaskets/ EPDM weathering seal resistant and accessories for openable door hinges of stainless steel grade 304- 3 Nos., per shutter handle with mazak alloy casting 1 No. per shutter, locking system suitably concealed 1 No., with raiser wedges for smooth operation and the system is to be installed at the site using anchor fasteners, silicon rubber sealant, easy glazing/ deglazing at site etc., including cost and conveyance of all materials, accessories, labour charges for transportation, erection at site with templates for casement sizing complete for finished item of work. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	APSSR 14-15 BMT-N.63	16.00	Sq.m	6807.65	108922.40
28	Supplying and fixing of Unplasticised Poly Vinyl Chloride (UPVC) sliding windows two track sliding duly manufactured using UPVC reinforced profiles of 62 mm x 60 mm x 2.25 mm for outer frames, 66 mm x 38 mm x 2.25 mm for sliding shutter frames capable of mounting single glazing system, structurally reinforced with hot dip galvanized up to 50 microns of minimum thickness of 1.2 mm prefabricated & welded through fusion welding the window sash shall be fitted with 5 mm thick clear float glass of reputed make duly fixed with EPDM weathering seal resistant accessories like clipping locking system made of aluminium 1 No., per set of sashes and the system is to be installed at the site using anchor fasteners, silicon rubber sealant, easy glazing/deglazing at site etc., including cost and conveyance of all materials, accessories, labour charges for transportation, erection at site with templates for casement sizing complete for finished item of work. Note: In no case the dimensions shall not be less than the specified in the spec. Actual size of window shall be as directed by Engineer In charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	BHEL approved rate/ BQ	48.00	Sq.m	3873.45	185925.60
29	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade. Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture cost of all materials. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	13.62.1	3508.00	Sq.m	62.27	218443.16
30	Supply & installation of Boom Barrer 3 meter width. Boom built from highly stable Aluminium alloy to produce rectangular profile of 100 x 55 x 1.6 mm or 80 x 38 x 1.6 mm. If the boom length is more than 3 meters end support is required. Power supply: Power supply 230 V \pm 10% 50/60 Hz single - phase Motor revolutions: 1400 rpm. Absorbed power: 250 W Capacitor : 15uF. Absorbed current : 1 A Manual manoeuvre : Personalized release key - knob No. of manoeuvres in 24 h : continuous service Thermal protection : 110 ° C Environmental conditions : 15 ° C to + 60 °C. Degree of protection : IP 53 Insulation class : F Reduction gear : Erg oil. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	BQ	4.00	Nos	76000.00	304000.00

Schedule - A - Price bid

Tender Notice NO: HY/TA/OT-03/2019-20

Date: 12.06.2019

Name of Work: Construction of Boundary wall along the periphery of BHEL RC Puram lands in clear lengths

S.No	Description	Ref. Code	Total Qty	unit	Unit Rate (Rs.)	Total Amount (Rs.)
31	Supply & installation of Boom Barrer 6 meter width. Boom built from highly stable Aluminium alloy to produce rectangular profile of 100 x 55 x 1.6 mm or 80 x 38 x 1.6 mm. If the boom length is more than 3 meters end support is required. Power supply: Power supply 230 V ± 10% 50/60 Hz single - phase Motor revolutions: 1400 rpm. Absorbed power: 250 W Capacitor : 15uF. Absorbed current : 1 A Manual manoeuvre : Personalized release key - knob No. of manoeuvres in 24 h : continuous service Thermal protection : 110 ° C Environmental conditions : 15 ° C to + 60 °C. Degree of protection : IP 53 Insulation class : F Reduction gear : Erg oil. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	BQ	4.00	Nos	88400.00	353600.00
32	Dry stone soling/ pitching 22.5 cm thick including supply of stones and prepare surface complete All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	16.11	4600.00	Sq.m	270.93	1246278.00
33	Supply and stacking of machine crushed graded stone aggregate at site of size 63 to 45mm hard granite stone metal including all incidental charges etc complete all as directed by Engineer-In-charge. (1/7 qty will be deducted for voids) All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	16.3.2	2000.00	Cu.m	1191.45	2382900.00
34	Supply and stacking of machine crushed graded stone aggregate at site of size 53 to 22.4 mm hard granite stone metal including all incidental charges etc complete all as directed by Engineer-In-charge. (1/7 qty will be deducted for voids) All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	16.3.3	2000.00	Cu.m	1196.50	2393000.00
35	Laying, spreading and compacting stone aggregate of size to WBM specifications including spreading in uniform thickness, hand picking, rolling with 3 wheeled road/vibratory roller 8-10 tonne in stages to proper grade and camber , applying and brooming requisite type of screening/binding material to fill up interstices of coarse aggregate, watering and compacting to the required density etc complete all as directed by Engineer-in-charge .All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	16.4	5300.00	Cu.m	425.05	2252765.00
36	Supply & fixing of various sizes of MS bolts,nuts and washers conforming to IS 1367-1961 including cost of all materials,labour etc, complete (MR)(32x4=128) All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	BHEL Approved rate	200.00	Kg	49.83	9966.00
37	Supply & fixing of 3 mm thick glass of plain/opaque /pin headed etc with MS glazing clips and putty at all floors of buildings ,all as directed by Engineer-in charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	BHEL Approved rate	280.00	Kg	341.00	95480.00
38	Drilling holes in RCC Columns for fixing 25 mm dia bolts and grouting with Fos Rock upto 350 mm depth. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	...L.S...	128.00	Cum	100.00	12800.00

Schedule - A - Price bid

Tender Notice NO: HY/TA/OT-03/2019-20

Date: 12.06.2019

Name of Work: Construction of Boundary wall along the periphery of BHEL RC Puram lands in clear lengths

S.No	Description	Ref. Code	Total Qty	unit	Unit Rate (Rs.)	Total Amount (Rs.)
39	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.5 mm (+0.50%) total coated thickness with zinc coating 120 gms per sqm as per IS:277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x55 mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	DSR-12.50/ p-212	240.00	Sqm	547.33	131359.20
40	Providing and fixing pre-coated galvanised steel sheet roofing Ridges plain (500-600mm) 0.50 mm (+0.05%) total coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling / self tapping screws complete. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	DSR-2012/ 12.51.1	24.00	Rmt	558.30	13399.20
41	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering. All work up to plinth level. 1:2:4 (1 cement 2 coarse sand 4 graded stone aggregate 20 mm nominal size) including curing, cost of all materials etc., complete. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	4.1.3/ P.85	284.65	Cu.m	4926.94	1402453.47
42	Supply, laying and compaction of moorum soil (excluding rock) - upto 3 kms lead, as directed by Engineer-in-Charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	code 1.1.1	4038.00	Cu.m	101.61	410301.18
43	Steel work welded in built up sections / framed work including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc as required In gratings frames guard bar ladder railing brackets gates and similar works cost of all materials. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	10.25.2	116816.50	Kgs	82.30	9613997.95
44	Supply of JCB including driver , diesel and all other misc. expenses including repairs, break downs expenses for removal / loading of earth etc complete all as directed by Engineer-in-charge.	Quotation	500.00	Hrs	800.00	400000.00
	Misc Items					
45	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material.					
	a) Beyond 30 cm girth upto and including 60 cm girth	code 2.33.1	10.00	Each	196.70	1967.00
	b) Beyond 60 cm girth upto and including 120 cm girth	code 2.33.2	10.00	Each	871.10	8711.00
46	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding grills with binding wire all complete by cold twisted bars . Complete as directed by engineer-in-charge. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	code 5.22.3	1000.00	Kgs	60.54	60540.00

Schedule - A - Price bid

Tender Notice NO: HY/TA/OT-03/2019-20

Date: 12.06.2019

Name of Work: Construction of Boundary wall along the periphery of BHEL RC Puram lands in clear lengths

S.No	Description	Ref. Code	Total Qty	unit	Unit Rate (Rs.)	Total Amount (Rs.)
47	Coursed rubble masonry with hard stone (first or second sort) in superstructure above plinth level and upto floor five level. Masonry work (second sort) , in cement mortar 1:6 (1 cement: 6 coarse sand) - Dismantled CRS stone shall be used for the construction (excluding cost of CRS Stone only). Dismantled CRS Stone shall be used for construction, remaining all other materials are in the contractor scope.	Rate An of code 7.8.2	50.00	Cu.m	3687.22	184361.00
48	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	code 15.7.4	100.00	Cu.m	754.10	75410.00
49	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge :	code 15.9.2	50.00	Cu.m	899.85	44992.50
50	Centering and shuttering including strutting propping etc. and removal of form work for walls (any thickness) including attached pilasters, buttersesses plinth and string courses etc. All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	code 4.3.3	100.00	Sq.m	385.09	38509.00
51	Erection RCC poles/M.S angles posts in position by coveying the same to the places as directed.	Rate contract	260.00	Nos	46.17	12004.20
52	Providing and laying in position specified grade, of Reinforced cement concrete excluding the cost of centering,shuttering, finishing and reinforcement - all work up to plinth level with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) - complete as directed by engineer-in-charge . All the materials are in contractor scope, BHEL Will not give any Material FREE Issue.	4.2.3	46.80	Cu.m	5910.64	276617.95
Total Amount Rs.						108,783,275.85
Agency to quote in below format only.						
Tender %	In words	Figures				
Excess						
Less						
Estimate						
Notes:						
1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the Contract Value. Please refer to the payment terms of technical bid.					
2	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department BHEL.					
3	The Contract period of the work is 18 months from the date of commencement . Maintenance period is of 12 Months from the date of completion . The security deposit will be released only after successful completion of maitenance period.					
4	All the terms & conditions of the contract with respect to Taxes & Duties are subject to the new taxation laws introduced from time to time (e.g., GST). The terms & conditions will be modified in accordance with the provisions of new laws (e.g., GST)					
5	All the materials including necessary fittings are in the agency scope only.					
6	If BHEL provided Electricity and Water Facility to Agency, corresponding Electricity charges and water charges shall be recovered from running bills.					