

**BHARAT HEAVY ELECTRICALS LIMITED
HPEP-HYDERABAD; RAMACHANDRAPURAM
CORPORATE SOCIAL RESPONSIBILITY Cell**

Tender Notice No: HY/CSR/2016-17/ULC Minutes, dated.09.12.2016, SI.No.2

PRICE BID - PART - B

**Name of work:- Construction of Community Hall - Chowdarpally (v) - Dubak (m),
Siddipet (d) - under CSR**

S No	Description of the item	Cumm. Qty	Unit	Rate (Rs)	Amount (Rs)
1	Earth work in excavation in all soils by mechanical means (Hydraulic Excavators) / manual means in foundations trenches or drains (not exceeding 1.5m or more / of any depth in width or 10 Sq.m on plan) including dressing of sides and ramming of bottoms, lift upto 1.5m, including getting out the excavated soil and disposal of surplus excavated soil as directed , within a lead of 50M.	151.98	Cu.m	130.80	19878.98
2	Earth work in excavation by mechanical means (Hydraulic Excavators) / manual measn over areas (exceeding 30 cm in depth , 1.5 m in width as well as 10 Sq.m on plan) including disposal of excavated earth , lead upto 50 m and lift upto 1.5 m, disposing earth to be levelled and neatly dressed for Hard Rock (Blasting prohibited).	25.00	Cu.M	212.00	5300.00
3	Providing and laying in position cement concrete of specified garde excluding the cost of centering and shuttering including consolidation by vibrations for all works up to plinth level with 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate of 20 mm nominal size).	10.71	Cu.M	3593.30	38484.24
4	Providing and laying in position specified grade, of Reinforced cement concrete excluding the cost of centering,shuttering, finishing and reinforcement - all work up to plinth level with 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) -	40.00	Cu.M	4703.90	188156.00
5	Centering and shuttering including strutting, propping etc; and removal of form work, for columns, pillars,peirs, abutments, machine foundations, posts and struts.	160.13	Sq.M	166.90	26725.70
6	Reinforcement for R.C.C. work including straightening , cutting , bending , placing in position and binding grills with binding wire all complete by cold twisted bars.	2.40	MT	62250.00	149400.00
7	Conveyance of excavated spoil up to a lead of 2 Kms, including loading , unloading and spreading etc. complete as directed by Engineer- in- charge.	20.00	Cu.M	93.94	1878.80
8	Filling with available excavated earth (excluding rock) in trenches , plinth , sides of foundations etc. in layers not exceeding 20 cm in depth , consolidation each deposited layer by ramming and watering , lead upto 50.00 m and lift upto 1.50 m.	45.00	Cu.M	83.80	3771.00
9	Coursed rubble masonry in second sort with hard stone in foundation & plinth with cement mortar 1:6 (1 cement :6 coarse sand)	32.91	Cu.M	3255.25	107130.28
10	Brick work with FPS bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in cement mortar 1:6.	27.00	Cu.M	3876.15	104656.05
11	Plastering in CM 1:6 , 20 mm thick to internal and external surfaces of walls including the cost of all materials , labour , curing etc, complete -Upto 10.00 M level.	324.80	Sq.M	156.15	50717.52
12	Cement Plaster to ceiling /walls with 12mm thick cement plaster finished with a floating coat of neat cement of mix 1:3 (1 cement : 3 fine sand) .	32.73	Sq.M	164.50	5384.09

S No	Description of the item	Cumm. Qty	Unit	Rate (Rs)	Amount (Rs)
13	Supply and fixing of top fixed, side hung of NCL Seccolor Ajantha windows & Ventilators fabricated from Roll formed section made of pre painted steel (Base steel as per IS 513 of 0.6 mm thick, 'D' quality, galvanized as per IS 277 with zinc 120 GSM / Sq. Mtr). Section for shutter should be of 46 x 46 mm, external frame should be of 46 x 52 mm, section for glass beading should be of 18 x 25 mm & center mullion should be 46 x 70 mm. The sections to be cut to length, meter joined with corner bracket. Centre mullions are to be fixed using mullion cap. Handle made of high grade aluminium powder coated & with nylon receiver & glazed with 5 mm thick, Modi/Saint Gobain float glass. Gasket made of E.P.D.M. Corner brackets made of C.R.C.A with zinc phosphating. Million caps made of glass filled nylon. The above frames should be fixed to the concrete / masonry walls by means of self expanding screws. Approximate size of windows 1.30mx0.9m and 3.00mx2.10m -Double shutter without guard bars(grills)... Excise duty the basis of measurement for finished work only.	4.50	Sq.M	3000.00	13500.00
14	Supply and fixing of aluminum window grills of size 1.50 Mx1.80M approx and 1.20 mx1.80M approx . along with aluminium frame consisting aluminium 'F' (solid) 0.80kg/12' supply and fixing of design of 4" aperture aluminium grill to the above frame work with necessary fixtures. It includes fixing of total frame to the existing brick work, finishing etc complete. (The material shall be aluminium alloy :6063, thick 7 mm, ultimate tensile strength more than 19 kgs/sq.mm)	4.50	Sq.M	1540.00	6930.00
15	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement :2 fine sand) including testing of joints etc. complete - 250mm dia R.C.C pipe.	8.00	RMT	342.45	2739.60
16	Providing and Laying Damp-Proof Course 40 mm thick with cement concrete 1:2:4 (1 cement : 2 coarse Sand : 4 Graded stone aggregate 12.5 mm nominal size).	28.00	Sq.M	207.55	5811.40
17	Providing and fixing 10mm thick acid and alkali resisitant tiles over a bed of 10 mm thick mortar 1:4 (1 acid proof cement :4 coarse sand) of approved make and colour using acid and or aikali reisiting mortar bedding and joints filled with acid and or alkali resisting cement as per Is:4457 complete as per the directions of Engineer-in-charge ,	3.48	Sq.M	207.55	722.27
18	Plastering over roof slab in CM 1:4, 20mm thick mixed with water proofing compound, Make: "Sika" @ 3% by weight of cement as per manufacturer's specification, curing as directed. Rate quoted shall include finishing, cost of all materials and labour etc., complete. (Cement =7.69 kgs/sq.m x3% WP@ Rs 20.00 per kg = Rs 4.61) upto 10 m height.	32.73	Sq.M	1075.60	35204.39
19	Supplying and laying of vitrified tiles of brighter shades and marble design of Premium Quality (1st quality) in required texture, design and colour, for flooring /skirting /cladding using vitrified tiles of size 600 x 600mmx8 mm thick of approved make. It includes cost of cutting, champering of tiles to required size, with base of Conmax C - 500 tile adhesive for fixing tiles on existing mosaic/cement flooring, jointing the tiles with colour tint etc. complete as directed by Engineer-in-charge. The rate quoted shall include cost of all materials, labour, adhesives, colour tint material, leads and lifts etc. complete. Amount will be paid on the basis of measurement of the area of finished work only. It also includes surface preparation of existing ceramic floor giving necessary slopes, cleaning joints and grouting joints with pigmented additives to match shade of the tile, making pockets for electrical, communication, network cables etc. complete as directed by Engineer-in-charge. Amount will be paid on the basis of measurement for finished work only.	36.21	Sq.M	1337.10	48416.39

S No	Description of the item	Cumm. Qty	Unit	Rate (Rs)	Amount (Rs)
20	Supply and fixing of new "Parry ware" make Indian Water Closet, Orissa pan of size 580mm x410mm - open rim (code No. c8109) with all accessories like Parryware flush kit suitable for the above flush tank with all required accessories etc., complete. colour: silky off-white.	2.00	Each	3000.00	6000.00
21	Interior Finishing: Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade, New Work two or more coats over and including water thinnable priming coat with cement primer.	32.73	Sq.M	66.70	2183.09
22	Exterior Finishing: Finishing walls with acrylic smooth exterior paint of required shade, New Work (two or more coat applied @ 1.67 ltr/10 sq.m) over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm	32.73	sq.m	67.50	2209.28
23	supply and fixing of 75mm dia single socket PVC/SWR pipe - 6 kg/sq.cm of make prince/sudhakar/kisan/supreme or any ISI brand including all bends	10.00	RMT	144.00	1440.00
24	Supplying ,laying ,jointing and testing 152.4 mm (6") SWG pipes of ISI make conforming to ISI 651 & 4127 with airtight cement joints in Cement mortar 1:5:1 prop. including excavation of trenches and socket pits in any soil(except rock requiring blasting) up to 1524 mm(5'0") depth and refilling with watering and tamping.	10.00	RMT	254.00	2540.00
25	Providing and placing on terrace (at all floor levels) of polyethylene water storage tank of 1000 ltrs capacity with double layer approved brand and manufacture as per ISI with cover and suitable locking arrangement and making necessary holes for inlet and outlet and overflow pipes with fittings (ballcock, inlet and outlet nipples) without base support for tank. (Brick work will be paid separately).Syntex/Aqua	2.00	Each	6000.00	12000.00
26	Dismantling brick masonry walls for all heights, removing and clearing the debris and carting away upto to lead of 2 KM including loading, unloading and spreading segregating useful materials as directed by Engineer-in-charge including the cost of all labour scaffolding etc., complete.	10.00	Cu.M	566.60	5666.00
27	Dismantling reinforced cement concrete / plain cement concrete and disposing of debris upto to a lead of 2 KM including loading, unloading and spreading as directed by Engineer-in-charge etc., complete.	10.00	Cu.m	1054.10	10541.00
28	Supply & fixing "Marc" make oyster series brass bib cocks. With all accessories / Cat: MOY 1030.	2.00	Each	506.00	1012.00
29	Supply & fixing "Marc" make oyster series brass pillar cocks. (Cat: MOY 1010) with all accessories etc.	1.00	Each	519.00	519.00
30	Supply & fixing "Marc" make oyster series brass stop cocks. (Cat: MOY 1040) with all accessories.	1.00	Each	698.00	698.00
31	Providing and fixing shutters along with frames for toilets that are 30 mm thick factory made PVC rigid foam paneled, door and shutters manufactured by M/s. Rajashri made from M.S. tube, 19 gauge thick, size 19x19mm for styles and 15x15mm for top and bottom rails, covered with heat moulded PVC "C" channel of 5mm thick sheet and 30x50mm wide for styles and 5mm thick and 75mm wide PVC sheets for top rail and bottom rail either side and 5 mm thick, 20mm wide cross PVC sheet as gap insert for top rail and bottom rail, paneling of 5mm thick PVC sheet fitted with M.S. frame welded / sealed to the styles and rails with 5x30mm PVC sheet beading on either side and joined together with solvent cement adhesive etc. complete in all respects as per direction of engineer in-charge fixed to frames. This includes providing brass hinges, brass aldrops, brass tower bolts, brass handles and brass door stoppers (For W.C. and bathroom doors)	3.30	sq.m	1830.00	6039.00
32	Supply and fixing in position medium teak wood door frame along with single leaf shutters solid core non - decorative type 30 mm thick of approved quality and brand including 3 No.s MS hinges 10 cm long and 1 no. mortise lock (Godrej make) , using scantling of size 100 mm X 75 mm (including with MS holdfasts of size 230 X 50 X 4 mm - 6 No.s and painting with coal tar to the faces coming in contact with masonry / concrete . including cost of all materials , labour etc. complete as directed by Engineer - in - charge	10.00	sq.m	3180.00	31800.00

S No	Description of the item	Cumm. Qty	Unit	Rate (Rs)	Amount (Rs)
33	Supplying and fixing CI Nahany traps 1st quality ISI marked conforming to IS: 1729 - 1979 with C.P Grating fixing with white cement as per site requirements with standard practice - 100mm inlet - 75 mm dia (3") outlet pipe - 4 Kgs.	1.00	Each	200.00	200.00
34	Construction of brick masonry chamber of size 23 x 30 Cm (9" x 12") in brick work in CM 1:6 and plastering in CM 1:4, 20 mm for gully trap 150 mmx100mm including cost of excavation, PCC 1:4:8, 75 mm thick, all materials, labour etc., complete.	4.00	Each	321.00	1284.00
35	Construction of brick masonry chamber of dimension 0.914 x 0.457 x 0.914 m (3' x 1'6" x 3') with brick in CM 1:6 including plastering over both sides with CM 1:4, 20 mm thick and fitted with light weight CI frame and cover of size 0.914 x 0.457 m in CM 1:4 including bed concrete of CC 1:4:8 as required, supplying and fixing one CI steps in brick masonry if necessary if necessary including earth work excavation in all soils, refilling around the chamber removing the surplus earth etc. complete as directed.CI frame and cover of 40 kgs.	1.00	Each	3226.00	3226.00
36	constructing brick masonry manhole in cement mortar 1:4 (1cement:4coarse sand) with R.C.C top slab with 1:2:4 mix (1cement:2coarse sand:4graded stone aggregate 20mm nominal size), foundation concrete 1:4:8mix (1cement:4coarse sand:8graded stone aggregate 40mm nominal size), inside plastering 12mm thick with cement mortar 1:3 (1cement:3coarse sand) finished with floating coat of neat cement and making channels in cement concrete 1:2:4 (1cement:2coarse sand:4graded tone aggregate 20mm nominal size)finished with a floating coat of neat cement complete as per standard design: Inside size 90x80cm and 45cm deep including C.I cover with frame (light duty) 455x610mm internal dimensions, total weight of cover and frame to be not less than 38kg (weight of cover 23kg and weight of frame 15kg) with common burnt clay F.P.S (non modular) bricks of class designation 7.5	1.00	nos	9845.00	9845.00
37	providing and fixing G.I pipes complete with GI fittings and clamps i/c cutting and making good the walls etc.	25.00	RMT	142.25	3556.25
38	providing and fixing G.I pipes complete with GI fittings and clamps i/c cutting and making good the walls etc.	25.00	RMT	161.60	4040.00
39	providing and fixing G.I pipes complete with G.I fittings including trenching and refilling etc. 25mm dia nominal bore	25.00	RMT	209.40	5235.00
40	providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. 20mm dia nominal bore	30.00	RMT	161.25	4837.50
41	providing and fixing wash basin with C.I. brackets, 15mm C.P. Brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever required: white vitreous china angle back wash basin size 400x400mm with single 15mm c.p. brass pillar tap	1.00	Each	1315.35	1315.35
42	Supplying and fixing plain PVC pipe of 90mm dia of 4 kg's/cm ² of approved quality with specials, accessories and approved sealing /jointing compound on the exterior of the inserted portion of the fitting and fixing in position and joing to MS gutters , including cost of all materials ,sealing compound ,labour etc., for all heights complete	12.00	RMT	104.00	1248.00
43	Supplying and fixing plain PVC pipe of 75mm dia of 4 kg's/cm ² of approved quality with specials, accessories and approved sealing /jointing compound on the exterior of the inserted portion of the fitting and fixing in position and joing to MS gutters , including cost of all materials ,sealing compound ,labour etc., for all heights complete	10.00	RMT	144.00	1440.00

S No	Description of the item	Cumm. Qty	Unit	Rate (Rs)	Amount (Rs)
44	supply and execute the concealed / surface PVC/MS pipe wiring with 1.5 sq.mm 660/1100 v. Grad PVC insulated copper wire multi strand of make finolex/ Rediant/fincab/Havells/L&T. In PVC pipe of suitable dia (As per IS for wiring points) with 14 G/1.5 sq.mm green colour copper wire for earth continuity. Each light/fan point should be connected to three plate ceiling rose code 30090 of Roma modular type of Anchor or North West make / connector suspended duly with couduit / pvc pipe etc. Each circuit should not have more than 7 points 700 watts	4.00	Pts	901.39	3605.56
45	Supply and fixing of 10 Amps 250 V. SP switches for control of light fitting and fans with Roma Type code: 21011 of Anchor or North West make. Fixed on a suitable modular type concealed box with suitable top cover. Testing & commissioning.	2.00	Nos	218.75	437.50
46	Supply and fixing of 3pin, 250v. 20/16 Amps power socket cum switch with indication Roma type code 21124 and 21077 of anchor make or north west. Fixed on suitable modular type concealed box top cover. Testing & commissioning.	2.00	nos	411.13	822.26
47	supply of ceiling fan with double ball bearing conforming to IS: 374/79 class 1 with the following specifications. 56" (1400mm) sweep, 230v ac 1-phase, white colour, 600mm down rod, ornamental design with gold finish shanks on blades and decorative canopy. Alongwith Electronic regulator of modular type. Anchor Roma, socket type. make: CG/orient/usha/khaitan/Bajaj/Havell's	2.00	nos	2191.53	4383.06
48	Fixing, connecting and testing of ceiling fan. The job includes supply of anchor roma ceiling rose & 1.5sq.mm copper wire for connection between ceiling rose and fan. Fixing of regulator on the roma switch board.	2.00	nos	388.00	776.00
49	Fixing, connecting and testing of 2x36W different types of Tube light/false ceiling fittings. The light fitting shall be fixed with suitable down rod, ball and socket etc and the supply of the material is in the contractors scope. The job includes supply of 1.5sq.mm copper wire for connection between ceiling rose and TL.	4.00	nos	457.67	1830.68
50	Any Miscellaneous expenses - lumpsum				25000.00
	Total Estimation Cost is = Rs.				970536.24
Tender %	In Words	Figures			
Excess					
Less					
Estimate					
Notes:					
1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of the gross value of work				
2	The Tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time				
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.				
4	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR				
5	The agency shall submit the I.R. clearance certificate for the above work and arrange to get the final bill sent to Finance within one month from the actual date of completion of work.				
6	The msintenance period of the work is 12 months. The security deposit will be released after satisfactory completion of the work and after getting I.R. clearance and payment of final bill.				