

BHARAT HEAVY ELECTRICALS LIMITEDHPEP-HYDERABAD; RAMACHANDRAPURAM
CORPORATE SOCIAL RESPONSIBILITY Cell**Schedule-A****Price Bid***Tender Notice No:HY/TN/CSR/OT-01/2017-18, dated. 12.02.2018, Item No.01.***Name of work:- Providing solar water heating system for the school childrens of "Telangana social welfare residential school / JC(G), vikarabad".**

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
1	Installation of ETC based, 500 LPD Solar Water Heating Systems at all floor levels, Solar Water Heater of 500 LPD - System Capacity 500LPD, System Temperature output 60-80 Dedree Celsius, solar vaccume tube - selectively coated (Tube-High Borosilicate Glass, Qty - 34 No's per 1 system, coating (tri-element) - copper-aluminium-ss, Dimensions - 58 dia / 2100 mm; application - bathing; Circulation - Thermosyphon; Hot Water Storage Tank (500 Litres, mild steel epoxy coating, puff insulation material, 50mm insulation thickness, tank thickness 1.6mm, GI powder coated cladding material); Mild steel powder coated supporting structure; Frame thickness of 2.0 mm thick, 3 KW Electrical Heater. etc. Rates are inclusive GST & all taxes, with transportation charges etc. complete in all respects as directed by engineer - in - charge.	2.00	Nos.	79,800.00	1,59,600.00
2	Installation of CPVC of minimum 1 inch or other relative diameter pipes of minimum length of 150 mtrs as specified by engineer-in-charge at all floor levels, with all bends and fittings and taps and other connection with including all civil works and transportation charges for Two 500 LPD solar water heating systems. Rates are inclusive GST & all taxes, with transportation charges etc. complete in all respects as directed by engineer - in - charge.	1.00	Nos.	15,400.00	15,400.00
3	Providing and placing on terrace (at all floor levels) of polyethylene water storage tank of 1000 ltrs capacity with double layer approved brand and manufacture as per ISI with cover and suitable locking arrangement and making necessary holes for inlet and outlet and overflow pipes with fittings (ballcock, inlet and outlet nipples) with out base support for tank.Rates are inclusive GST & all taxes, with transportation charges etc. complete in all respects as directed by engineer - in - charge.	1.00	Nos.	6,000.00	6,000.00

S No	Description of the item	Qty	Unit	Rate (Rs)	Amount (Rs)
4	PVC Overhead Tank Stand Structure, as directed by engineer - in - charge at all floor levels with including all related civil works and transportation charges complete in all respect. Rates are inclusive GST & all taxes, with transportation charges etc. complete in all respects as directed by engineer - in - charge.	1.00	Nos.	10,000.00	10,000.00
Total Estimation Cost is = Rs.					1,91,000.00

Note : The bidders are required to quote the tender value on percentage (%) basis at excess or less or on par with estimate value in figures and words.

Tender %	In figure	In words
Excess		
Less		
Estimated value		