

FOR OFFICIAL USE ONLY
NOT FOR PUBLICATION

TENDERER'S COPY
ORIGINAL COPY

TENDER SPECIFICATION

TENDER NO. BHEL/NR/SCT/PROJECTS/PORTA CABIN /1073

FOR

**“RECTIFICATION AND RENOVATION WORK OF PROJECTS DEPTT.
PORTA CABIN FLOORING AT BHEL PSNR & HRDI COMPLEX, PLOT
NO. 25, SECTOR- 16A, NOIDA- 201301, UTTAR PRADESH”**

PART II – PRICE BID



Bharat Heavy Electricals Limited
(A Govt. Of India Undertaking)
Power Sector – Northern Region,
Plot No. 25 , Sector - 16A ,
Distt. Gautam Budh Nagar, NOIDA – 201 301.INDIA



Maharatna Company
ISO 9001, ISO 14001,
OHSAS 18001 & SA 8000
 certified company
 SubContract and Purchase Deptt.

Bharat Heavy Electricals Limited
 (A Govt. Of India Undertaking)
Power Sector – Northern Region,
Plot No. 25 , Sector - 16A ,
Distt. Gautam Budh Nagar, NOIDA – 201 301(INDIA)
Phone: 0091-0120- 2416500/2416262
Fax 091-0120-2416528
Email: cs@bhel.in/susmitabasu@bhel.in

TENDER NO. BHEL/NR/SCT/PROJECTS/PORTA CABIN /1073

IMPORTANT NOTE

PURCHASER OF THIS TENDER DOCUMENT IS ADVISED TO CHECK AND ENSURE COMPLETION OF ALL PAGES OF TENDER DOCUMENT AND REPORT ANY DISCREPANCY TIMELY FOR CORRECTIVE ACTION, IF ANY, TO THE ISSUING AUTHORITY BEFORE THE BIDS ARE SUBMITTED. ORIGINAL COPY OF TENDER DOCUMENT COMPLETE IN ALL RESPECTS MUST BE SUBMITTED BACK AS PART OF THE BID WITHOUT WHICH THE SAME IS LIABLE TO BE REJECTED BY BHEL.

THIS TENDER SPECIFICATION ISSUED TO:

M/S-----

JOB	“RECTIFICATION AND RENOVATION WORK OF PROJECTS DEPTT. PORTA CABIN FLOORING AT BHEL PSNR & HRDI COMPLEX, PLOT NO. 25, SECTOR- 16A, NOIDA- 201301, UTTAR PRADESH”.
TENDER NO.	BHEL/NR/SCT/PROJECTS/PORTA CABIN /1073 Dtd. 25/08/2017

Sl. No.	Description of Item	Lump sum Price (“A”) in Rupees (in figures and words)
1.0	LUMP SUM PRICE FOR THE WORK OF “RECTIFICATION AND RENOVATION WORK OF PROJECTS DEPT. PORTA CABIN FLOORING AT BHEL PSNR & HRDI COMPLEX, PLOT NO. 25, SECTOR- 16A, NOIDA- 201301, UTTAR PRADESH.”	In Figures: _____ In Words: _____ _____

Notes:

- The rates of different items for the entire scope shall be worked out & awarded as per BOQ Cum Rate schedule (“Annexure-I”) of TCC.
- The price will remain firm for entire contract period.
- GST as applicable shall be paid extra.

TENDER ENQ. NO. BHEL/NR/SCT/PROJECTS/PORTA CABIN /1073

BOQ Cum Rate Schedule

Name of Work: Rectification and Renovation work of Projects Dept. Porta Cabin Flooring at BHEL PSNR & HRDI Complex, Plot No. 25, Sector- 16A, Noida- 201301, Uttar Pradesh.

Sl. No.	Description	UOM	Qty.	Factor (F)	Rate (Rs.) = Factor (F) * A / 1000 (Rounded off to two place after decimal)	Amount (Rs.) = Rate *Quantity
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to Plinth / Floor level :					
(i)	1:4:8 (1 Cement : 4 coarse sand : 8 graded stone aggregate 40 mm nominal size)	CUM	1.00	10.550		
(ii)	1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	CUM	3.40	12.910		
2	Form Work: Centering and shuttering including strutting, propping etc. and removal of form for : Foundations, footings, bases of columns, etc. for mass concrete.	SQM	35.30	0.460		
3	Lifting the Porta Cabin (Approx. Size: 12.2m X 21.3m) on the Jack supports for carrying out the base strengthening work (i.e. providing additional supports of concrete footings, painting on the base channels and wooden base etc.) including providing and fixing all the jacks, base supporting beams, all special tools and tackles till completion of the work and reinstating the porta cabin on the concrete pedestal supports (properly levelled surface) after removal of the jack system.	L.S.	1.00	140.685		
4	Structural steel work for providing bottom support beam (ISMB- 100) in single section, fixed with or without connecting plate, including cutting, hoisting, fixing /welding in position and applying a priming coat of approved steel primer all complete	Kg	818.80	0.140		
5	Providing and laying 2 mm thick antistatic PVC flooring / skirting of approved shade as per IS:3462 and laying as per IS:5316 all complete.	SQ.M.	235.00	1.800		
6	Replacing the existing damaged wooden ply base, including removing the existing ply base, providing and fixing 18 mm thick marine plywood (confirming to IS: 710), with necessary screws, bolts, accessories etc. and disposing the removed materials as directed by BHEL Engineer.	SQM	24.00	5.110		

TENDER ENQ. NO. BHEL/NR/SCT/PROJECTS/PORTA CABIN /1073**BOQ Cum Rate Schedule**

Name of Work: Rectification and Renovation work of Projects Dept. Porta Cabin Flooring at BHEL PSNR & HRDI Complex, Plot No. 25, Sector- 16A, Noida- 201301, Uttar Pradesh.

Sl. No.	Description	UOM	Qty.	Factor (F)	Rate (Rs.) = Factor (F) * A / 1000 (Rounded off to two place after decimal)	Amount (Rs.) = Rate *Quantity
7	Relacing the Existing damaged Floor Tiles, with the rectified Glazed Ceramic Floor tiles (matt finish) of size 300 X 300 mm (thickness to be specified by the manufacturer), of 1st quality confirming to IS : 15622, of approved make and approved color, to be fixed with cement based high polymer modified quick-set tile adhesive (water based) confirming to IS: 15477 in average 3 mm thickness, grouting the joints with white cement and matching pigments, including removing the existing damaged tiles and disposing off the same as directed by BHEL Engineer.	SQM	3.00	1.960		
8	Dismantling / Removing the existing PVC sheet flooring, including dismantling / opening the furniture items, shifting, placing and re-shifting the same for providing the open area for PVC Flooring work.	L.S.	1.00	100.160		
9	Painting with black anti-corrosive bitumastic paint of approved brand and manufacture to give an even shade : One or more coats on old work	SQM	235.00	0.095		
10	Total Lumpsum Price (A)					
NOTES:						
1	Bidder's quoted price above shall be complete in all respect for the full scope defined in specification and in accordance with all terms & conditions of tender.					
2	Contractor shall fully understand description and Specifications of items mentioned in BOQ.					
3	Conditional price bids with any deviation / clarification etc. are liable to be rejected. No cutting / erasing / over writing shall be done.					
4	Quantities mentioned in rate schedules are approximate only and liable for variation on either side depending upon site / design requirement. The tentative contract value (CV) of entire scope of work shall be calculated as per finally quoted / accepted rates & the Quantities indicated in BOQ cum Rate Schedule .					
5	Contractor's total quoted price as per rate schedule will be taken as tentative only. The contractor undertakes to execute actual quantities as per advice of BHEL Engineer and accordingly the final contract price shall be worked out on the basis of quantities actually executed at site and payments will also be regulated for the same.					
6	In case of any mis-match in rate and amount on price discrepancy, the same will be dealt as per clause no. 1.4 of GCC.					