

BHARAT HEAVY ELECTRICALS LIMITED
HPEP, RAMACHANDRAPURAM, HYDERABAD-32
(Township Administration Department)

HY/TA/OT-06/2019-20, Date: 09.08.2019

Schedule-A PRICE BID

Name of work: Fabrication and Fixing in Position of Sign Boards

Sl. no	Description	Total Qty	Unit	Rate (Rs.)	Amount (In Rs.)
1	Earth work in excavation by mechanical means (hydraulic excavator) manual means over areas (exceeding 30cm in depth. 1.5m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50m and lift upto 1.5m, disposal earth to be levelled and neatly dressed. All kinds of soil	27.5	Cum	81.65	2,245.38
2	Preparing the supplied boards of different sizes to receive the painting as per the drawing and painting the letters of different sizes in different shapes with synthetic enamel paint of approved make in different shades as per the instructions. The quoted rate shall include rubbing of the existing painted surface to receive the new painting and cost of all materials like brushes, paints etc as directed by Engineering - in charge. (all materials like brushes, paints etc in under contractor scope only)	325	Sqm	260.00	84,500.00
3	Structural steel work in single section fixed with or without connecting plate including cutting hoisting fixing in position and applying a priming coat of approved steel primer all complete (Only steel will be free issued other related material under contractor scope)	21600.00	kg	5.09	1,09,944.00
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work upto plinth level 1:4:8 (1cement 4:coares sand 8 grade stone aggregate 40mm nominal size) (Only cement will be free issued and other materials are under contractor scope only)	9.20	Cum	1600.84	14,727.73

Sl. no	Description	Total Qty	Unit	Rate (Rs.)	Amount (In Rs.)
5	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centering shuttering finishing and reinforcement All work up to plinth level 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size) (Only cement will be free issued and other materials are under contractor scope only)	27.50	Cum	1750.83	48,147.83
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture etc directed by Engineering - in charge. (Only Synthetic Enamel Paint will be supplied by BHEL, free of cost at their stores)	30.00	Cum	24.67	740.10
Amount Rs.					2,60,305.03

Note:-

Tender %	In words	Figures
Excess		
Less		
Estimate		

Notes-

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work. Please refer to the payment terms of technical bid. Penalty shall be applicable as per NIT terms.
2	All the bills of the contractors will be cleared subject to the production of clearance certificate by the contractors in respect of compliance of all statutory requirement, issued by IR section of HR department BHEL.
3	Contract Period of the work is 02 Months . The maintenance period of the work is 12 months . The security deposit will be released after satisfactory completion of the work and after getting I.R clearance and payment of final bill.
4	All the terms & conditions of the contract with respect to Taxes & Duties are subject to the new taxation laws introduced from time to time (e.g., GST). The terms & conditions will be modified in accordance with the provisions of new laws (e.g., GST)
5	Only cement , synthetic enamel paint & Structural steel will be free issued by BHEL store.
	All other materials related this work are under contractor scope only.

Sl. no	Description	Total Qty	Unit	Rate (Rs.)	Amount (In Rs.)
6	Electricity , water charges will be recovered as per rules.				