

Price Bid Format			Volume- II of NIT			
Tender Ref no.T0ATX00030, dated:07.07.2020						
Name of the work:“Horticulture works of tree plantation and development of lawns at various locations” in Railway Electrification Birlanagar-Etawah 386RKM/440TKM Project.						
I	II	III	IV	V	VI	VII
Sl. No.	Item Description	UOM	Qty	Rate	Amount	Weightage %
1	Digging holes in ordinary soil and refilling the same with the excavated earth mixed with manure or sludge in the ratio of 2:1 by volume (2 parts of stacked volume of earth after reduction by 20% : 1 part of stacked volume of manure after reduction by 8%) flooding with water, dressing including removal of rubbish and surplus earth, if any, with all leads and lifts (cost ofmanure, sludge or extra good earth if needed to be paid for separately) : a) Holes 60 cm dia, and 60 cm deep	Nos.	255	note here	note here	0.3249%
2	Supply and stacking of Azadirachta indica (Neem) plant of height 120-130cm in big polybag of size 25 cm as per direction of the officer-in-charge.	Nos.	60			0.1244%
3	Supply and stacking of Delonix regia (Gulmohar) plant of height 150-165 cm. in big poly bags of size 25 cm as per direction of the officer-in-charge	Nos.	65			0.1244%
4	Supply and stacking of Polyalthia longifolia (Ashok) plant of height 150-165 cm. in earthen pots of size 25 cm as per direction of the officer-incharge.	Nos.	65			0.1659%
5	Supply and stacking of Ficus religiosa (Peepal) plant of height 150-165 cm. in big poly bags of size 30 cm as per direction of the officer-in-charge.	Nos.	65			0.1348%
6	Supplying and stacking of good earth at site including royalty and carriage upto 5 km lead complete (earth measured in stacks will be reduced by 20% for payment).	cum	510			7.6370%
7	Complete maintenance of trees (Out side garden features), jobs like making of basin at regular interval i/c watering, weeding, pruning & application of fertilizer etc, (excluding the cost of material which shall be supplied by the department and other T & P material/articles shall be provided by the contractor) and as per direction of officer in charge. (Trees for 250 no/(up to 4 & up to 3 year Slow & Fast growing group))	Per Tree per month	765			1.6299%
8	Trenching in ordinary soil up to a depth of 60 cm including removal and stacking of serviceable materials and then disposing of surplus soil, by spreading and neatly levelling within a lead of 50 m and making up the trenched area to proper levels by filling with earth or earth mixed with sludge or / and manure before and after flooding trench with water (excluding cost of imported earth, sludge or manure).	cum	8400			18.4057%

Price Bid Format			Volume- II of NIT			
Tender Ref no.T0ATX00030, dated:07.07.2020						
Name of the work:“Horticulture works of tree plantation and development of lawns at various locations” in Railway Electrification Birlanagar-Etawah 386RKM/440TKM Project.						
I	II	III	IV	V	VI	VII
Sl. No.	Item Description	UOM	Qty	Rate	Amount	Weightage %
9	Supplying and stacking at site dump manure from approved source, including carriage upto 5 km lead complete (manure measured in stacks will be reduced by 8% for payment) : Screened through sieve of I.S. designation 20 mm	cum	2818.36	Do not q	Do not q	20.6703%
10	Mixing earth and sludge or manure in the required proportion specified or directed by the Officer-in-charge	cum	8455.08			8.6564%
11	Providing & laying Selection no. 1 grass turf with earth 50mm to 60mm thickness of existing ground prepared with proper level and ramming with required tools wooden and than rolling the surface with light roller make the surface smoothen and light watering the same maintenance for 30 days or more till the grass establish properly,as per direction of officer in charge	Per Sqm	14000			37.6643%
12	Complete maintenance of the entire garden features having as per yard stick in the garden area i.e. lawn trees, shrubs, herbs, edge, flower beds, foliages, creepers etc. including hoeing,weeding, pruning, replacement of plants, gap filling, watering, mowing of lawn, grass cutting by lawn mover and brush cutter, removal of garden waste, applying insecticide, pesticide & fertilizers(whenever required) top dressing of lawn with good earth and manure and maintenance of other garden related works as directed by office-in-charge (Cost of Good Earth, Manure, Fertilizer, Insecticide, Pesticide will be provided by the Department & lawn mover and brush cutter with fuel and other T & P material/articles shall be provided by the contractor.) and as per direction of officer in charge. Prestigious works / H.M. house & officers entitled to free accommodation.(1Mali for 1.00Acre)	Per Sqm/per month	14000			2.0094%

Price Bid Format			Volume- II of NIT			
Tender Ref no.T0ATX00030, dated:07.07.2020						
Name of the work:“Horticulture works of tree plantation and development of lawns at various locations” in Railway Electrification Birlanagar-Etawah 386RKM/440TKM Project.						
I	II	III	IV	V	VI	VII
Sl. No.	Item Description	UOM	Qty	Rate	Amount	Weightage %
13	Edging with bricks laid dry length wise, including required excavation, refilling, consolidating with hand packing and spreading surplus earth neatly within a lead of 50 m : Common burnt clay F.P.S (non modular) bricks of Class designation 7.5	Metre	2000			2.4527%
14	Total sum of Weightage					100%
	Total amount in figure (In Rupees)					
	Total amount in word (In Rupees)					
	Note					
1	Bidders should quote only the Total Amount both in figures & words in the specified place. They should not fill/quote/write anything in col. (V) & (VI) . These rates & amount will be derived from the Total amount quoted and weightage factor assigned against respective items indicated in col. (VII).					
2	Evaluation Shall be based on total amount quoted by bidder.					
3	The rate and amount are inclusive of all applicable taxes, except for the GST. For details of taxes, clause no. 13.0 of the SCC will be applicable.					
4	Details of BOQ items shall be read in conjunction with the corresponding specifications, drawings and other tender terms.					