PROJECT:-2 X 800 MW TANGEDCO UPPUR TPP-BTG

TENDER ENQUIRY NO.PE/PG/UPP/E-5771/2017 Dt: 06.11.2017

ANNEXURE-I BOQ CUM PRICE SCHEDULE FOR SUPPLY OF VIS (STEEL HELICAL SPRING AND VISCOUS DAMPER) FOR MILL (18 NOS.) FOUNDATION

NAME OF VENDOR- .....

SL NO (1)	ITEM DESCRIPTION AS PER TENDER BOQ (2)	Required Load carrying Capacity (kN) for each foundation (3)	No of machine foundation (4)	HSN CODE (TO BE FILLED BY THE BIDDER) FOR EACH ITEM (5)	FOR INDIAN BIDDER: UNIT EX-WORKS PRICE (DULY PACKED) (INR) (6)	TOTAL EX- WORKS PRICE (DULY PACKED) (INR) (7)	FREIGHT CHARGES (8): @ % OF TOTAL EX WORKS (8A)	FREIGHT CHARGES (8): AMOUNT IN (INR) (8B) =[7X8A]	TOTAL PRICES (ex works + freight) (INR) (9) [7+8B]	APPLICABLE GST RATE IN % ON(TOTAL EX WORKS + FREIGHT) BOTH (INR) (10): GST RATE IN % ON(TOTAL EX WORKS + FREIGHT) (10A)	TOTAL AMOUNT IN (INR) (10B) [9X10A]	TOTAL PRICE F.O.R Prices with taxes (INR) (11) [9+10B]	FOR FOREIGN BIDDERS: UNIT C&F Chennai Sea Port Price (Currency) (12)	Total C&F Chennai Sea Port Price (Currency) (13)	APPLICABLE GST RATE IN % ON Site Activities (Currency)(14)	GRAND TOTAL (Currency) (15) (12+13+14)	REMARKS
	SUPPLY OF VIS (STEEL HELICAL SPRING AND VISCOUS DAMPER) FOR MILL (18 NOS.) FOUNDATION																
A1*	COST OF VIS FOR MILL FOUNDATION	5732	18														
A2	PACKING & FORWARDING CHARGES																
A3	TOOLS FOR ACCESSORIES (Electric pump included)																
A	**TOTAL COST OF VIS, INCLUDING PACKING FORWARDING & TOOLS FOR ERECTION(A1+A2+A3)**																
	DESIGN ENGINEERING OF MILL FOUNDATION DECK SUPPORTED ON VIS (SPRING TYPE)																
B1	CIVIL DESIGN ENGINEERING DOCUMENT FOR MILL FOUNDATION RESTING ON VIS																
B	**TOTAL COST OF DESIGN ENGINEERING DOCUMENT OF MILL FOUNDATION RESTING ON VIS (B1)**																
C	**TOTAL COST OF VIS INCLUDING CIVIL DESIGN ENGINEERING DOCUMENT (A+B)**																
	SUPERVISION OF ERECTION AND COMISSIONING OF VIS (STEEL HELICAL SPRING AND VISCOUS DAMPER) FOR MILL (18 NOS.) FOUNDATION																
		NO OF VISITS															
D1	SUPERVISION OF ERECTION & COMMISSIONING OF VIS FOR MILL FOUNDATION RESTING ON VIS	10															One visit consisting of 5 days
D	TOTAL SUPERVISION PRICE (D1)																
	In case of an extra visit, the above charges would be applicable for the visit and if there is any extra/less stay during the visit at site, the charges shall be @ Rs. -----/ per day																
E	**TOTAL COST OF PACKAGE (C+D)**																

Note (as per NIT requirement/Technical Specification),If any :-

1. Load carrying capacity mentioned for the variable items (* marked) is tentative only and shall be used for bid evaluation and ordering purpose.
2. The actual load carrying capacity of the springs may undergo change after ordering , based on springs selected during detailed engineering.
3. In such a case, price bid evaluation shall be done again based on revised load carrying capacity of the springs keeping all the prices same as quoted originally. In case of change in L1 status, the quoted price per unit load carrying capacity (kN) of the varibale items (i.e A1) of the original L1 vendor shall be proportionately reduced to maintain L1 status.
4. Based on above, amendment to PO, if required, shall be issued.
5. Generally the damping shall be required in the range of 5% to 20% of critical damping of whole machine foundation system to meet the design requirement. In exceptional case it may vary upto 30 % depending upon the available/selected spring unit as well as layout constraints. The bidder shall accordingly include the cost of damping in their quoted price for Cost of VIS per Unit load carrying capacity(kN). No extra price shall be provided on account of required damping. Cost of dampers is deemed to be included in the quoted rate of VIS (per kN).
6. Price per Visit is lumsump which includes travel and accomodation charge.

Points for consideration before filling above price schedule-

1. PRICES SHALL BE FIRM UNLESS OTHERWISE SPECIFICALLY INDICATED IN NIT .
2. Vendor to mention HSN Code in specific Column for each item of BOQ.
3. In case of discrepancy in GST rate corresponding to HSN code and quoted GST, the evaluation shall be done on quoted price and correct GST rate shall be considered for ordering (limited to quoted FOR Site price)
4. Unless the context requires otherwise, in all tenders and tender related documents any reference to taxes such as ED, CST/VAT, Services. Tax etc. shall refer to GST as implemented by GOI w.e.f. 1.07.2017.
5. CGST/SGST/UGST/IGST shall be paid at actuals against documentary evidence but restricted to the amount and percentage in the order/contract.
6. In case, any GST credit is delayed/denied to BHEL due to non/delayed receipt of goods and/or tax invoice or expiry to timeline prescribed in the relevant Act for availing such ITC, or any other reasons not attributable to BHEL, tax amount shall be recoverable from the vendor/contractor along with interest levied/leviable on BHEL.
7. All taxes and duties other than CGST/SGST/UGST/IGST shall be deemed to be included in the Ex-Works prices unless specified otherwise by the bidder in the price bid. No variation in other taxes and duties shall be payable by Purchaser.

06/11/17