

BHARAT HEAVY ELECTRICALS LIMITED
RAMACHANDRAPURAM :: HYDERABAD-502032
(TOWNSHIP ADMINISTRATION)

Tender Notice No: HY/TA/OT-04/2016-17,
 Date: 16.07.2016

Schedule - A (Price Bid)

Name of work: Conducting DGPS Survey for demarcating lands of BHEL, Ramachandrapuram Unit.

SI.No	Description	Total Qty	Unit	Rate	Amount
DGPS Survey of Land					
1	Conducting DGPS Survey for demarcating the BHEL, RC Puram Land and The survey shall be based on Revenue Records provided by Township Administration dept., BHEL, RC Puram authenticated by Land and Survey dept. The scope of the agency includes: • Establishing the actual boundary line as per the Survey records available with Township Administration dept. in coordination with Land and Survey dept, Telangana State. • Permanent Marking of boundary on the ground with survey posts. • Authenticating the boundary marked on the ground by Asst. Director of Survey & Land Records • The survey map submitted by the agency shall show the position of existing BHEL boundary and boundary as per revenue records including marking the deviation of BHEL boundary wall from boundary as per Revenue Records. • To provide co-ordinates of the boundary at various locations w.r.t major milestones in the proximity so that the same can be referenced even in the absence/tampering of survey posts. • Submission of Survey Report along with Survey Maps in colour print outs-3 sets duly attested by Asst. Director of Survey & Land Records.	2000	acres	950.00	1900000.00
2	Supply and fixing of RCC Poles as per the drawing and as directed by Engineer-in charge with BHEL Letters engraved on one side of pole				
2a	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size)	2.88	CuM	5094.85	14673.17
2b	Steel reinforcement for R.C.C. work including carriage, straightening, cutting, bending, placing in position and binding all complete .Cold twisted bars/ Hot rolled deformed bars	554.4	Kg	62.25	34511.40
2c	Centering and shuttering including strutting propping etc. and removal of form work for walls (any thickness) including attached pilasters, butteresses plinth and string courses etc.	92.025	SqM	285.15	26240.93
2d	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means over areas (exceeding 30cm in depth. 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth, lead upto 50m and lift upto 1.5m, disposed earth to be levelled and neatly dressed.	3.6	CuM	129.35	465.66
2e	Erection RCC poles/M.S angles posts in position by conveying the same to the places as directed.	90	Each	46.17	4155.30
2f	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering- All work upto plinth level, 1:2:4 (1cement 2:coares sand 4 grade stone aggregate 20mm nominal size)	2.7	CuM	4514.05	12187.94
2g	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade ,Two or more coats on new work	45.9	SqM	53.85	2471.72
Grand Total					1994706.11

Tender %	In Words	In Figures
Excess		
Less		
Estimate		

Notes:

1	A penalty of 0.5% of the gross value of work will be levied for every week's delay of work subject to a maximum penalty of 10% of the gross value of work.
2	The tender % age quoted by the contractor shall be inclusive of all taxes and duties other than service tax as applicable from time to time.
3	Service tax if paid by the contractor with respect to this work will be reimbursed by BHEL on production of documentary evidence for having paid the service tax by the contractor.