

Annexure - I

SCOPE OF WORK

Indent No.: 20190244

- 1). Removal of existing old asbestos sheets without breaking / damage.
- 2). Contractor shall also remove debris (if any) resulting due to work and dispose-off the same within a distance of 150 mtrs. as per IS 11768.
- 3). Supply & installation of new color coated (blue color) Galvalume Sheets, FRP sheets, puffed sheets, Gutters, Ridges, down take pipe and Turbo ventilator etc. in following structures: (a) OPS, (b) REG / Quality office, (c) OAB, (d) Central stores & (e) Parking shed at BHEL-CFP, Rudrapur, as specified in Annexure - III. Quantity mentioned in Annexure-III is tentative and will be subject to actual quantity used as per the final measurement of work. (Note: All quantity of any item supplied should be of single make from the makes mentioned in annexure-III)
- 4). All hardware required for installation will be in contractor scope. All hardware should be of SS type.
- 5). Levelled area for storage of items within BHEL premises shall be provided by BHEL. Contractor should ensure proper storage & maintenance of supplied items with required props till execution/installation, as per the direction of BHEL.

