

	BHARAT HEAVY ELECTRICALS LIMITED TRANSMISSION PROJECTS ENGINEERING MANAGEMENT										
	DOCUMENT No.	TB-4-377-510-051A		Rev. No.	01		Prepared	Checked	Approved		
	TYPE OF DOC.	TECHNICAL SPECIFICATION				NAME	RD	VK	VK		
	TITLE 1.1kV POWER & CONTROL CABLES					SIGN	Sd/-	Sd/-	Sd/-		
						DATE	10/04/19	10/04/19	10/04/19		
						GROUP	TBEM	W.O. No			
	CUSTOMER	TELANGANA STATE POWER GENERATION CORPORATION LTD.									
	PROJECTS	1) 400kV SWITCHYARD AT 4X270 MW BHADRADRI TPS 2) 400kV SWITCHYARD AT 1X800MW KOTHAGUDEM TPS STAGE-VII, UNIT#12									
	CONTENTS										
	Section	Description								No. of Sheets	
1.	SCOPE, SPECIFIC TECHNICAL REQUIREMENTS & BILL OF QUANTITIES								4		
2.	DETAILED TECHNICAL REQUIREMENTS – EQUIPMENT SPECIFICATION								17		
3.	PROJECT DETAILS AND GENERAL SPECIFICATION								14		
4.	CHECK LIST (TO BE FILLED AT TENDER STAGE)								3		
	ANNEXURE-1 & 2 (TO BE FILLED AT TENDER STAGE)								8		
01	8/5/19	RD	VK	VK	FGD cable quantity added.						
Rev No.	Date	Altered	Checked	Approved	REVISION DETAILS						
					Distribution	TBMM	TBQM	TBCM	TBTS		
					Copies	2	-	-	-		

COPYRIGHT AND CONFIDENTIALITY
 The information on this document is the property of BHARAT HEAVY ELECTRICALS LTD.
 It must not be used directly or indirectly in anyway detrimental to the interest of the company

SECTION 1

SCOPE, SPECIFIC TECHNICAL REQUIREMENTS AND QUANTITIES

1.0 SCOPE

This technical specification covers the requirements of design, manufacture, testing at works, packing and dispatch of 1.1kV Control & Aux. Power Cables. This section covers the specific technical requirements of the cables.

In case of any conflict between the technical details mentioned in this section and the remaining sections of this document, then Section-1 shall prevail and is to be considered as binding requirement.

1.1 The equipment is required for the following Project.

Name of customer : TELANGANA STATE POWER GENERATION CORPORATION LIMITED (TSGENCO).

Name of the Project : 1) 400kV SWITCHYARD AT 4X270 MW BHADRADRI TPS
2) 400kV SWITCHYARD AT 1X 800 MW KOTHAGUDEM TPS
STAGE-VII, UNIT#12

Refer Section – 2: Equipment Specification.
Section – 3: Project Details and General Specifications.
Section – 4: Standard Technical Data Sheet.
Section – 5: Checklist

2.0 SPECIFIC TECHNICAL PARTICULARS

2.1 PVC Insulated 1.1kV Control cable:

The PVC (70°C) insulated 1100V grade Control shall be of FRLS type conforming to IS: 1554 (Part-I) and its amendments.

S.No	Parameters	Control Cable
1.	Voltage grade of cable	1100 Volts
2.	Material of conductor	Stranded, non-compacted & circular, high conductivity annealed plain copper, conforming to IS: 8130.
3.	Strands	Minimum no. of strands are 7
4.	Conductor insulation.	Extruded HRPVC type-C compound conforming to IS: 5831. The minimum volume resistivity of insulation shall be 3.5×10^{14} ohm-cm at 27°C and 3.5×10^{11} OHM-CM at 85 °C.
5.	Inner Sheath	Extruded HRPVC compound conforming to type ST2 FRLS of IS: 5831 for multicore cables. Single core cables shall have no inner sheath. Filler shall be of same material as of inner sheath i.e. ST2.
6.	Armour**	Galvanised single round steel wire for twin and multicore cables.
7.	Overall sheathing	Extruded FRLSH HRPVC compound conforming to type ST2 of IS: 5831.

(**) Strip armouring method (a) mentioned in Table 5, Page-6 of IS: 1554 (Part 1) - 1988 shall not be accepted for any of the cables

2.2 XLPE insulated Aux. Power cable:

The XLPE insulated cable shall be of FRLS type conforming to IS: 7098 (Part-I) and its amendments.

S.No	Parameters	Aux. Power cables
1.	Voltage grade of cable	1100 Volts
2.	Material of conductor	Stranded and compacted plain aluminium of grade H2 and class 2 stranded, high conductivity annealed plain copper for cable sizes up to 2.5 sq.mm conforming to IS: 8130.
3.	Conductor insulation.	Extruded cross-linked polyethylene (XLPE) conforming to IS: 7098 (Part-1)
4.	Inner Sheath	Extruded HRPVC FRLS compound conforming to type ST2 of IS: 5831 for multicore cable. Single core cables shall have no inner sheath. Filler shall be of same material as of inner sheath i.e. ST2
5.	Armour^^	Galvanized single round steel wire armour for twin and multicore cables. Non-magnetic hard drawn aluminum single round wire conforming to H4 of IS-8130 latest for single core cables
6.	Overall sheathing	Extruded FRLSH HRPVC compound conforming to type ST2 of IS: 5831.

(^^) Strip armouring method (a) mentioned in Table 6, Page-6 of IS: 7098 (Part 1) - 1988 shall not be accepted for any of the cables

3.0 BILL OF QUANTITY:

The cable type, size and length requirement shall be as per tables below. ***However, the length of each cable type procured may be subject to a change of +/- 30% before placement of order. Quantity variation on the total ordered quantity shall be +/- 20% at contract stage.***

The standard drum length for control cables shall not be less than 1000 metres & for power cables it shall not be less than 500m. Cut lengths for cable marked as (**) below shall be informed during detailed engineering stage. The length per drum shall be subjected to a maximum tolerance of +/- 5% of the standard drum length. ***Some of the cable type might not be ordered at all at contract stage.***

The Employer shall have the option of rejecting cable drums with shorter lengths. For each size, the variance of total quantity, adding all the supplied drum lengths, from the ordered quantity, shall not exceed +/- 2%.

Manufacturing clearance shall be divided into single / two Lots.

Second lot shall be cleared for manufacturing based on progress of engineering and site requirements.

3.1 XLPE insulated 1.1kV Aux Power Cables:

S. No.	Description	Unit	Bhadradri S/s	Kothagudem S/s
1.	2C x 16 sq mm XLPE/ Al. Aux Power Cable	m	0	0
2.	4C x 16 sq mm XLPE/ Al. Aux Power Cable	m	3000	0
3.	4C x 35 sq mm XLPE/ Al. Aux Power Cable	m	4000	0
4.	3.5C x 70 sq mm XLPE/ Al. Aux Power Cable	m	0	0
5.	3.5C x 95 sq mm XLPE/ Al. Aux Power Cable	m	0	0
6.	3.5 C X 185 Sq.mm XLPE/AL Aux Power Cable**	m	0	0
7.	3.5C x 300sq mm XLPE / Al Aux Power Cable**	m	0	0
8.	1C x 630sq mm XLPE / Al Aux Power Cable **	m	0	0

3.2 PVC insulated 1.1kV Control Cables:

S. No.	Description	Unit	Bhadradri S/s	Kothagudem S/s
1.	2C x 2.5 sq mm HRPVC / Cu. Control Cable	m	4500	0
2.	5C x 2.5 sq mm HRPVC / Cu. Control Cable	m	0	0
3.	7C x 2.5 sq mm HRPVC / Cu. Control Cable	m	0	0
4.	9C x 2.5 sq mm HRPVC / Cu. Control Cable	m	0	0
5.	12C x 2.5 sq mm HRPVC / Cu. Control Cable	m	0	0
6.	20C x 2.5 sq mm HRPVC / Cu. Control Cable	m	0	0

3.4 Fire survival Power Cables:

S. No.	Description	Unit	Bhadradri S/s	Kothagudem S/s
1.	2C x 35 sq.mm EPR / Cu. FS Power Cable	m	0	0

** Cut length shall be informed during detailed engineering.

4.0 DEVIATIONS:

The bidder shall list all the deviation from the specification separately. Offers without specific deviation will be deemed to be totally in compliance with the specification and NO DEVIATION on any account will be entertained at a later date.

5.0 TESTS:

Tests shall be carried out as per clause 5.00.00 of Section-II.

6.0 PROVEN-MAKE CRITERIA FOR LT POWER AND CONTROL CABLES

6.1 Sub-Qualifying Requirements for LT Control Cables:

Bidder should have manufactured and supplied as on date of LOA the following:

- a. At least 300 km of PVC insulated, PVC sheathed stranded copper conductor 1.1 kV grade cables in one single contract
- b. At least one (1) km of Flame retardant low smoke cables.

6.2 Sub-Qualifying Requirement for LT Power Cables

Bidder should have manufactured and supplied as on date of LOA the following:

- a. At least 100 Kms of aluminium conductor, XLPE insulated, PVC sheathed power cables of 1.1 kV or higher grade in one single contract.
- b. At least 100 km of aluminium conductor, PVC insulated, PVC sheathed power cables of 1.1 kV or higher grade in one single contract.
- c. At least one (1) km of flame retardant low smoke cables.
- d. 1.1 kV or higher grade power cable of minimum 630 sq.mm. Conductor size.

Bidder to submit the filled provenness data sheets (attached as Annexure to Section 5: CHECKLIST) along with offer.

7.0 QUALITY PLAN

The contractor shall carry out contract works in accordance with sound quality management principles which shall include such as controls which are necessary to ensure full compliance to all requirements of the specification & applicable international standards. These quality management requirement shall apply to all activities during design, procurement, manufacturing, inspection, testing, packaging, shipping, inland transportation, storage, site erection & commissioning. Contractor shall submit detailed Quality Plan for BHEL / customer's approval.

SECTION-II
CONTENT

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE OF SUPPLY
2.00.00	CODES & STANDARDS
3.00.00	DESIGN CRITERIA
4.00.00	SPECIFIC REQUIREMENTS
5.00.00	TESTS
6.00.00	DRAWINGS DATA & MANUALS

ATTACHMENTS

ANNEXURE-A	RATINGS AND REQUIREMENTS - H.V POWER CABLES (11KV & 3.3 KV)
ANNEXURE-B	RATINGS AND REQUIREMENTS - L.V POWER CABLES
ANNEXURE-C	RATINGS AND REQUIREMENTS - CONTROL CABLES
ANNEXURE-D	RATINGS AND REQUIREMENTS - 1.1KV FS POWER & CONTROL CABLE
ANNEXURE-E	RATINGS AND REQUIREMENTS - FLEXIBLE TRAILING CABLES
ANNEXURE-F	CABLE SIZES

**TECHNICAL SPECIFICATION
FOR
CABLES**

1.00.00 SCOPE OF SUPPLY

1.01.00 Power and Control Cables shall cover the requirement of entire Plant including the switchyard.

Other cables including special cables, if any, which may be necessary as per proven engineering practice for satisfactory and trouble free operation of the entire cable system of the plant shall also be within the scope of supply. These shall include all such cables for electrical integral with mechanical equipment systems and subsystems.

1.02.00 Cable shall be furnished in accordance with this specification and the following annexures :

- a) 11kV & 3.3 kV Power cables : Annexure - A
- b) 1100V Power Cables : Annexure – B
- c) Control Cables : Annexure – C
- d) Fire Survival Cables : Annexure – D
- e) Flexible Trailing cable : Annexure – E

1.03.00 All relevant drawings, data and instruction manuals

2.00.00 CODES & STANDARDS

2.01.00 All cable and materials shall be designed, manufactured and tested in accordance with the latest applicable Indian Standards (IS) and IEC except where modified and/or supplemented by this specification.

2.02.00 Cable and material conforming to any other standard which ensures equal or better quality, may be accepted. In such case, copies of the English version of the standard adopted shall be submitted along with the bid.

2.03.00 The electrical installation shall meet the requirements of Indian Electricity Rules as amended upto date and relevant IS Code of Practice. In addition, other rules and regulations applicable to the work shall be followed.

3.00.00 DESIGN CRITERIA

3.01.00 Cables will be generally laid on ladder type trays or drawn through rigid PVC/GI /HDPE pipe/conduits. Cable tunnels shall be avoided as far as possible, except at locations where overhead trays are not possible, with prior approval of the Owner.

- 3.02.00 For continuous operation at specified rating, maximum conductor temperature shall be limited to the permissible value as per relevant standard and/or this specification which one is more stringent.
- 3.03.00 The insulation and sheath materials shall be resistant to oil, acid and alkali and shall be tough enough to withstand mechanical stresses during handling.
- 3.04.00 Armouring shall be single round wire of galvanized steel for multicore cables and aluminum for single core cable for power and control cables. For fire survival control cable, the armouring over inner sheath shall consist of single layer of wire / round galvanised steel wire as per IS 3975 amended upto date. For Fire survival power cable, Single core cables to be used in A.C. system, the armouring over inner sheath shall consist of single layer of round copper wire, for multi-core cables to be used in A.C. system and single core cables in D.C. System, the armouring over inner sheath shall consist of single layer of round galvanised steel wire.
- 3.05.00 The outer sheath shall have flame retardant low smoke halogen evolution (FRLSH) characteristics or fire survival characteristics as applicable and shall meet the requirements of additional tests specified for the purpose.
- 3.06.00 Core identification for multicore cable shall be provided by colour coding.
- 3.07.00 HT cables shall be manufactured by triple extrusion dry cured (CCV) process using pressurized nitrogen.

4.00.00 **SPECIFIC REQUIREMENTS**

4.01.00 **General Description**

All Cables shall be furnished in strict compliance with ratings and requirements and sizes as given in Annexures to this Specification.

4.02.00 **Drum Length and Tolerance**

The cables shall be supplied in non-returnable packing steel drum for 11 kV & 3.3 kV power cables, wooden drums for 1100V power and control cables, each containing minimum 500 meters length of larger sizes of cable unless specifically asked for. For smaller sizes of cables, each drum shall contain 1000 meters length of cable. Allowable tolerance on individual drum length is $\pm 5\%$.

4.03.00 **Non-Standard Length**

Non-standard lengths upto 5% of the total ordered quantity may be accepted. However the Contractor will be required to obtain approval before packing the Cables on drums. Non-standard lengths shall not be less than 100 metres in any case.

4.04.00 **Cable identification**

Cable identification shall be provided by embossing on every meter on the outer sheath the following :

- a) TSGENCO
- b) Manufacturer's name or trade mark
- c) Voltage grade
- d) Year of manufacture
- e) Type of insulation, e.g. XLPE/PVC/HR85/IE2 etc.
- f) No. of core and size of cables.
- g) Type of improved fire performance, e.g. FR/FRLSH/FS
- h) IS number

4.05.00 Packing

4.05.01 Cables shall be supplied in non returnable drums. The drums shall be of heavy construction. All wooden parts shall be manufactured from seasoned wood. All ferrous parts used shall be treated with suitable rust preventive finish or coating to avoid rusting during transit or storage. Wooden cable drum shall be treated by immersing in copper-nitrate solution.

4.05.02 Cable shall be wound and packed on drums in such a manner that it will be properly sealed and firmly secured to the drum. The ends of each length shall be sealed before shipment.

4.05.03 The cable drums should carry the following details in printed form:

- a) TSGENCO
- b) Manufacturer's name or trade make
- c) Type of cable & voltage grade
- d) Year of manufacture
- e) Type of insulation e.g. XLPE/HRPVC/IE2
- f) No. of core and size of cables
- g) Cable code e.g. FRLSH/FS
- h) Length of cable on drum
- i) No. of length on drum, if more than one
- j) Direction of rotation, by arrow
- k) Approx. gross mass.

- l) IS/IEC number and ISI mark

4.06.00 **Joints and Terminations**

Materials of construction for a joint/termination shall perfectly match with the dielectric chemical and physical characteristics of the associated cables. The material and design concepts shall incorporate a high degree of operating compatibility between the cable and joints. The protective outer covering (jacket) used on the joints/terminations shall have the same qualities as that of the cable outer sheath in terms of ambient/operating temperature withstand capability and resistance to hazardous environments and corrosive elements. Straight through joints and terminations for HT cables shall be heat shrinkable type.

4.07.00 **Selection Criteria**

- 4.07.01 a) HT and LT power cables shall be selected on the basis of current carrying capacity, short circuit rating and permissible voltage drop.

- b) While sizing power cables, following aspects shall be reckoned:

- i) Ground/Ambient Air temperature
- ii) Depth of Laying.
- iii) Power Cables touching each other.

- c) Cables, for circuit breaker controlled feeders, shall withstand the short circuit current for the fault clearing time 0.16 Sec. for outgoing feeder, 0.5 Sec. for Tie feeder and 1.0 Sec. for Incomer.

- d) HT cables shall be sized based on the following considerations:

Rated current of the equipment and ground/ambient temperature.

Touching/spacing of cable.

Laying on multi-tier racks, trench

Depth of laying.

The voltage drop of the cable , during motor starting condition , shall be limited to 15% and during full load running condition shall be limited to 3 % rated voltage. For BFP motor, the voltage drop during motor starting condition shall be limited to 20% and for Mill motor shall be limited to 10%. Other outgoing feeder / transformer feeder shall be limited to 3% rated voltage.

Short circuits withstand capability

- e) For fuse/MCCB/Breaker protected circuits the conductor size shall depend upon full load current subject to voltage drop limited to 3% during running of all feeders and 15% during starting for motor feeders. In addition, transformer regulation shall also be considered for loads fed from 415V PMCC. Incase of other out going line feeder voltage drop shall be limited to 3%.

- f) For loads fed from local panels, the total running voltage drop in cable from 415V PMCC to local panel and from local panel to individual motor shall be limited to 3% at full load motor current while the same during starting shall be limited to 15%.
- g) As per national electric code (NEC) current rating capacity of motor feeder/cables should be 125% of full load current.
- h) For welding receptacle, 3% running drop shall only be considered.

The minimum sizes of L.T cable to be chosen are as below:

AL - 16 mm² (3 core) & 16mm² (2 core) Cu - 2.5 mm²

4.07.02 Apart from above, consideration shall also be given to limit the cable to some standard sizes instead of using too many types.

4.07.03 The standard cable sizes, amp capacities, derating factors. as given in IS/IEC will be generally followed.

4.07.04 a) For breaker protected circuits minimum size of the cable shall be as follows:

1100V Power Cable : 240 Sq mm XLPE AL

3300V Power Cable : 185 Sq mm XLPE AL

11000V Power Cable : 240 Sq mm XLPE AL

b) For motor circuits the selection of size will be made ensuring that the cable shall withstand a short circuit fault directly following a second hot start.

4.07.05 For fuse/MCCB protected circuit, the conductor size will depend on full load current subject to voltage drop not exceeding 3%. For practical purposes, the minimum size chosen is as below :

a) Aluminium : 6 Sq mm.

b) Copper : 2.5 Sq mm.

4.07.06 All control cables shall be 2.5 Sq mm copper cable.

4.07.07 Multicore control cables will generally have spare conductor (s) in accordance with the following chart :

Conductors required	Cables
1 or 2	1-3/C
3 or 4	1-5/C
5 or 6	1-7/C
7 or 8	1-9/C

9 or 10

1-12/C

Above 10

Two or more of above cables

4.07.08 Separate cables for each type of following services/functions as applicable shall be used for each feeder. Same multicore cable using different services shall not be acceptable.

- a) Power.
- b) Control, interlock and indication.
- c) Metering and measuring.
- d) Alarm and annunciation.
- e) C.T. Cables.
- f) V.T. Cables.

4.08.00 **Cable Identification**

Cable identification shall be provided by embossing on the outer sheath the following :

- a) Manufacturer's name or trade mark
- b) Manufacturer's name or trade mark
- c) Voltage grade
- d) Year of manufacture
- e) Type of insulation, e.g. XLPE, HRPVC & IE2 etc.
- f) No. of core & size of cables
- g) Type of outer sheath e.g. FRLSH, FS etc.

4.09.00 Selected sizes of power and control cables are given in Annexure-G.

4.10.00 Fire Survival Cables shall be used for important auxiliaries / area as recommended in Standard Technical Specification by CEA for the following services. The fire survival time of these cables shall not be less than 3 hours at 750 deg. C.

- i. DC emergency lube oil pump
- ii. DC hydrogen seal pump
- iii. Turbine lube oil pump/barring gear
- iv. DC emergency lighting for main building and service building
- v. DC cables for battery to charger & DC distribution boards

- vi. Jacking oil pump
- vii. Emergency turbine trip in control room
- viii. Boiler Turbine : Generator inter trip which include the interconnection between
 - Boiler master fuel trip and turbine trip relays
 - Generator trip relays & turbine trip relays
 - Generator trip relays & generator breaker
 - Generator trip relays & field breaker
 - Generator trip relays & unit auxiliary transformer breaker
 - Incomer cables for DG board, emergency board, DC lighting board etc.

5.00.00 **TESTS**

5.01.00 **Shop Tests**

The Cables shall be subject to shop tests in accordance relevant IS/IEC standards to prove the design and general qualities of the Cables as below:

5.01.01 Routine tests on each drum of cables.

5.01.02 Acceptance Tests on 1 drum out of every 10 drums chosen at random for acceptance of the lot for every size.

5.01.03 Type test on each type and size of cable, inclusive of measurement of armour DC resistance of power cables on one drum out of every 10 drums of cable.

5.02.00 **Additional Tests**

Following additional acceptance tests shall also be performed on each type of cables having outer sheath with improved fire performance (category C1, Type FR/ Category C2, Type FRLSH)

5.02.01 Oxygen index test (both C1 & C2)

The Oxygen index shall not be less than 29.

5.02.02 Temperature Index Test (both C1 & C2)

The measured value of temperature index shall be 21 at a temperature of 250°C for FRLS cables and 350°C for FS cables

5.02.03 Flame Retardance test on single cable and on bunched cables (both C1 & C2)

After the test, there should be no visible damages on the test specimen within 300mm from its upper end.

After burning has ceased, the cables should be wiped clean and the charred or affected portion should not have reached a height exceeding 2.5 meter above the bottom edge of the burner, measured at the front and rear of the cable assembly. 3 Hours fire rating test shall be carried out for FS cable as per IEC-331

5.02.04 Halogen acid gas evolution test (for Category C2)

The level of HCL evolved shall not exceed 20 per cent by weight. HCL evolved shall not be exceed 2% for FS cable.

5.02.05 Smoke density test (for Category C2)

The cables shall meet the requirements of light transmission of minimum 40% after the test. Minimum transmission shall be 80% for FS cable.

5.02.06 Test for specific optical density of smoke

The cables shall meet the requirements of IS/IEC.

5.02.07 Test for rodent & termite repulsion property

The test shall be carried out to note the presence of rodent and termite repelling chemical in PVC compound. Normal procedure is that a few chippings of the PVC compound are slowly ignited in a porcelain dish or crucible in a muffle furnace at about 600°C. The resulting ignited ash is boiled with a little ammonium acetate solution (10%). A drop of aqueous sodium sulphide solution is placed on a thick filter paper and it is allowed to soak. The spot is touched with a drop of above extract. A black spot indicates the presence of anti-termite & rodent compound.

Flammability test shall be carried on finished cables as per following standards-

- a) Swedish Chimney test – SS: 424-14-75
- b) IEEE std.383 – 1974 latest
- c) IEC std. 332-1, 332-3 and IEC 331

6.00.00 **DRAWINGS, DATA & MANUALS**

6.01.00 Drawings, Data and Manuals shall be submitted with the bid and for approval/ reference and subsequent distribution after the issue of Letter of Intent in quantities and procedures as specified in General condition of contract and/or

6.02.00 **To be submitted with the Bid**

- a) Manufacturer's catalogues giving cable construction details and characteristics.

- b) Cable current ratings for different types of installation, inclusive of derating factors for ambient temperature, grouping etc.
- c) Write-up on Manufacturer's recommended method of splicing, jointing, termination etc. of the cables.
- d) Type test reports on 11 KV & 3.3 KV Power, LT FRLSH Power & control, FS power and control cables.
- e) Filled-up proposal particulars.

6.03.00 To be submitted for Owner/Purchaser's Approval and Distribution

All relevant drawings and data pertaining to the equipment like GTP, QAP, etc. shall be submitted by the Bidder for the approval of Owner/Owner's consultant. Also refer clause no. 1.19.02(u) of Section-I of Volume – V-A: Technical Specifications for Electrical Equipment & Accessories.

ANNEXURE-A

**RATINGS AND REQUIREMENTS
HV POWER CABLES (11 KV & 3.3 KV)**

- 1.0 11000/11000V & 3300/3300V grade 90⁰C continuous rating under normal condition and 250⁰C rating under short circuit condition heavy duty XLPE power cable suitable for use in 11000V/3300V non-effectively earthed system conforming to following requirement and in line with IS-7098, IS-8130, IS-5831 & IS-3975, manufactured by Triple Extrusion Dry Cure (CCV) process using pressurized Nitrogen.
- 1.1 Conductor : Stranded and compacted aluminium conductor of grade H2 & class 2 for all sizes, generally conforming to IS: 8130.
- 1.2 Conductor Screen : Extruded semi-conducting compound.
- 1.3 Insulation : Extruded cross linked polyethylene (XLPE) conforming to IS: 7098 (Part-2)
- 1.4 Insulation Screen : Extruded semi-conducting compound with a layer of non-magnetic metallic tape. For single core armoured cables, the armouring shall constitute the metallic part of screening. The semi-conducting tape shall be easily strippable.
- 1.5 Core Identification : By coloured strips applied on (For three core cables) cores.
- 1.6 Inner Sheath : Extruded HRPVC/FRLS compound conforming to type ST2 of IS: 5831 for three core cables. Single core cables shall have inner sheath. Filler material shall also be of type ST2 PVC.
- 1.7 Armour : Galvanised single round steel wire armour for twin and multicore cables.

Non-magnetic hard drawn aluminum single round wire conforming to H4 of IS-8130 latest for single core cables
- 1.8 Overall Sheath : Extruded FRLSH HRPVC compound conforming to type ST2 of IS: 5831.
- 1.9 Drum : Steel Drum

ANNEXURE-B

**RATINGS AND REQUIREMENTS
LV POWER CABLES [1.1KV (XLPE TYPE)]**

- 1.0 1100 V grade, 90°C continuous rating under normal condition and 250°C under short circuit condition rating, XLPE heavy duty, power cable conforming to following requirement and in line with IS 7098 Part-I. IS 8130 & IS 5831 and IS 3975.
- 1.1 Conductor : Stranded and compacted plain aluminium of grade H2 and class 2 stranded, high conductivity annealed plain copper for cable sizes upto 2.5 mm² conforming to IS:8130.
- 1.2 Insulation : Extruded cross-linked polyethylene (XLPE) conforming to IS: 7098 (Part-1)
- 1.3 Core Identification : By color coding
- 1.4 Inner Sheath : Extruded HRPVC FRLS compound conforming to type ST2 of IS: 5831 for multicore cable. Single core cables shall have no inner sheath. Filler shall be of same material as of inner sheath i.e. ST2
- 1.5 Armour : Galvanized single round steel wire armour for twin and multicore cables.

Non-magnetic hard drawn aluminum single round wire conforming to H4 of IS-8130 latest for single core cables
- 1.6 Overall Sheath : Extruded FRLSH HRPVC compound conforming to type ST2 of IS: 5831.
- 1.7 Drum : Conforming to IS-10418 (Wooden drum)

ANNEXURE-C

**RATINGS AND REQUIREMENTS
CONTROL CABLES**

- 1.0 1100 V grade 85°C continuous rating under normal condition and 160°C under short circuit condition rating HRPVC Control cable (YWY) conforming to following requirement and in line with IS:1554, IS:8130, IS:5831 and IS:3975.
- 1.1 Conductor : Stranded, non-compacted & circular, high conductivity annealed plain copper, generally conforming to IS: 8130.
- 1.2 Insulation : Extruded HRPVC type-C compound conforming to IS: 5831. The minimum volume resistivity of insulation shall be 3.5×10^{14} ohm-cm at 27°C and 3.5×10^{11} OHM-CM at 85°C.
- 1.3 Core Identification : By color coding and numbering at interval of 100mm or less
- 1.4 Inner sheath : Extruded HRPVC compound conforming to type ST2 FRLS of IS: 5831 for multicore cables. Single core cables shall have no inner sheath. Filler shall be of same material as of inner sheath i.e. ST2.
- 1.5 Armour : Galvanised single round steel wire for twin and multicore cables.
- 1.6 Overall sheath : Extruded FRLSH HRPVC compound conforming to type ST2 of IS: 5831.
- 1.7 Drum : Conforming to IS: 10418 (Wooden drum)

ANNEXURE-D

RATINGS AND REQUIREMENTS

(1.1KV GRADE COPPER CONDUCTOR FS POWER CABLES)

1100 V, copper conductor, heat resisting insulation, extruded inner sheath of low smoke and very low halogen content fire resisting material, single layer of copper wire armour for single core/ single layer of round galvanised steel wire for multicore, outer sheath of low smoke and very low halogen content fire resistant material, suitable for minimum temperature of 750 deg.C for 3 hours. The cables shall be in compliance with IEC-60331, Part 11.

RATINGS AND REQUIREMENTS

(1.1KV GRADE COPPER CONDUCTOR FS CONTROL CABLES)

1100 V, copper conductor, heat resisting insulation, extruded inner sheath of low smoke and very low halogen content fire resisting material, single layer of copper wire armour for single core/ single layer of round galvanised steel wire for multicore, outer sheath of low smoke and very low halogen content fire resistant material, suitable for minimum temperature of 750 deg.C for 3 hours. The cables shall be in compliance with IEC-60331, Part 11.

ANNEXURE-E

**RATINGS AND REQUIREMENTS
FLEXIBLE TRAILING CABLES**

i) 3300 V Unearthed Grade

Flexible trailing cable, annealed plain copper conductor, Class-5 of IS-8130, insulated with EPR, conductor and insulation shielded with EPR, cores screened with ATC wire braiding, cores laid up, HD CSP inner sheathed, proof cotton taped and FRLS HD CSP sheathed overall, conforming to IS:9968. Alternatively PCP sheathing may be acceptable.

ii) 1100 V Grade

1100 V Grade trailing cable shall be plain copper of Class-5 of IS-8130, heat resistant elastomeric compound based on EPR insulation, inner sheath of heat resistant elastomeric compound PCP sheath, nylon cord reinforcement and heat resistant, oil resistant and flame retardant heavy duty elastomeric compound FRLS CSP outer sheath.

ANNEXURE-F

CABLE SIZES

Following sizes are given as a general guideline. Standard sizes as per IEC/IS shall be adopted.

Sl. No.	Cable Size	Conductor	Insulation
1.0	H. T. CABLES (11kV)		
1.1	1 core 1000 sq.mm	AL	XLPE (FRLS)
1.1	1 core 630 Sq.mm	AL	XLPE (FRLS)
1.2	3 core 400 Sq.mm	AL	XLPE (FRLS)
1.3	3 core 240 Sq.mm	AL	XLPE (FRLS)
1.4	1 core 70 Sq.mm	AL	XLPE (FRLS)
1.0	H. T. CABLES (3.3kV)		
1.1	1 core 630 Sq.mm	AL	XLPE (FRLS)
1.2	3 core 300 Sq.mm	AL	XLPE (FRLS)
1.3	3 core 240 Sq.mm	AL	XLPE (FRLS)
1.4	3 core 185 Sq.mm	AL	XLPE (FRLS)
1.5	1 core 70 Sq.mm	AL	XLPE (FRLS)
2.0	L. T. POWER CABLES		
2.1	3 core 2.5 Sq.mm	CU	XLPE (FRLS)
2.2	2 core 16 Sq.mm	AL	XLPE (FRLS)
2.3	3 core 16 Sq.mm	AL	XLPE (FRLS)
2.4	4 core 16 Sq.mm	AL	XLPE (FRLS)
2.5	2 core 35 Sq.mm	AL	XLPE (FRLS)
2.6	3 core 35 Sq.mm	AL	XLPE (FRLS)
2.7	4 core 35 Sq.mm	AL	XLPE (FRLS)
2.8	3 core 70 Sq.mm	AL	XLPE (FRLS)

Sl. No.	Cable Size	Conductor	Insulation
2.9	3.1/2 core 70 Sq.mm	AL	XLPE (FRLS)
2.10	3 core 95 Sq.mm	AL	XLPE (FRLS)
2.11	3.1/2 core 95 Sq.mm	AL	XLPE (FRLS)
2.12	3 core 185 Sq.mm	AL	XLPE (FRLS)
2.13	3.1/2 core 185 Sq.mm	AL	XLPE (FRLS)
2.14	3 core 240 Sq.mm	AL	XLPE (FRLS)
2.15	3.1/2 core 240 Sq.mm	AL	XLPE (FRLS)
2.16	3 core 300 Sq.mm	AL	XLPE (FRLS)
2.17	3.1/2 core 300 Sq.mm	AL	XLPE (FRLS)
2.18	1 core 630 Sq.mm	AL	XLPE (FRLS)
3.0	CONTROL CABLE		
3.1	2 core 2.5 Sq.mm	CU	HRPVC (FRLS)
3.2	3 core 2.5 Sq.mm	CU	HRPVC (FRLS)
3.3	5 core 2.5 Sq.mm	CU	HRPVC (FRLS)
3.4	7 core 2.5 Sq.mm	CU	HRPVC (FRLS)
3.5	9 core 2.5 Sq.mm	CU	HRPVC (FRLS)
3.6	12 core 2.5 Sq.mm	CU	HRPVC (FRLS)
3.7	20 core 2.5 Sq.mm	CU	HRPVC (FRLS)
4.0	FS POWER CABLES		
4.1	3 core 2.5 Sq.mm	CU	EPR
4.2	2 core 16 Sq.mm	CU	EPR
4.3	3 core 16 Sq.mm	CU	EPR
4.4	4 core 16 Sq.mm	CU	EPR
4.5	2 core 35 Sq.mm	CU	EPR

Sl. No.	Cable Size	Conductor	Insulation
4.6	3 core 35 Sq.mm	CU	EPR
4.7	4 core 35 Sq.mm	CU	EPR
4.8	3 core 95 Sq.mm	CU	EPR
4.9	3.1/2 core 95 Sq.mm	CU	EPR
5.0	FS CONTROL CABLE		
5.1	2 core 2.5 Sq.mm	CU	EPR
5.2	3 core 2.5 Sq.mm	CU	EPR
5.3	5 core 2.5 Sq.mm	CU	EPR
5.4	7 core 2.5 Sq.mm	CU	EPR
5.5	9 core 2.5 Sq.mm	CU	EPR
5.6	12 core 2.5 Sq.mm	CU	EPR



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

SECTION - 3

PROJECT DETAILS AND GENERAL SPECIFICATIONS

GENERAL TECHNICAL REQUIREMENTS

1.0 PROJECT DETAILS

A) Kothagudem TPS

A)

Customer : M/s Telangana State Power Generation Corporation Ltd.

Project Title : 1x800MW Kothagudem Thermal Power Station Stage VII, Unit 12

Project Location : Paloncha Village, Khammam District, Telangana

Nearest Railway station : Bhadrachalam Road railway station.

Nearest Road Head : Khammam 16 km approx., Nearest Highway NH221
(Vijaywada – Jagdalpur Highway).

Nearest Airport : Hyderabad (about 200 Km)
Chief Engineer (O&M), Kothagudem Thermal Power Station Stage

Postal Address : VII, Unit – 12, TSGENCO, Village - Paloncha, Dist. – Khammam,
Telangana -507115

B) Bhadradri TPS

Customer : M/s Telangana State Power Generation Corporation Ltd.

Project Title : 4x270MW Bhadradri Thermal Power Station

Project Location : Ramanujavaram Village, Khammam District, Telangana

Nearest Railway station : Manuguru railway station.

Nearest Road Head : Khammam

Nearest Airport : Hyderabad (about 345 Km)

Postal Address : Chief Engineer (O&M), Bhadradri Thermal Power Station Stage
TSGENCO, Village - Ramanujavaram, Dist. – Khammam, Telangana



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

1.1 SITE CONDITIONS (FOR DESIGN PURPOSES)

1.1.1 SITE CONDITIONS

- a). Average rainfall per year : 1124 mm
b). Maximum hourly rainfall intensity : 102 mm
c). Altitude : 1000 m

1.1.2 DESIGN AMBIENT

- a). Minimum Temperature : 13.5°C
b). Maximum Temperature : 45°C
c). Design Ambient Temperature : 50 °C

1.1.3 RELATIVE HUMIDITY

- a). Maximum :: 85%

1.1.4 WIND PRESSURE (AS PER IS:875-1987)

- a). Design wind speed : 44 m/sec.

1.1.5 SEISMIC FACTORS

- a). Horizontal Seismic Coefficient : As per latest IS : 1893
b). Vertical Seismic Coefficient : As per latest IS : 1893 } *Zone – III*

1.1.6 ELECTRICAL DATA

		400 kV System	415V AC System	240V AC System	220 V DC System	48 V DC System
1.	Nominal Voltage	400 kV	415 V	240 V	220 V	48 V
2.	Highest System Voltage	420 kV	457 V	264 V	242 V	55 V
3.	No. of phases	3	3	1	NA	NA
4.	Frequency	50 Hz	50 Hz	50 Hz	NA	NA
5.	Voltage variation	± 5%	± 10 %	± 10 %	+10 % to -15%	± 10 %



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

6.	Neutral Earthing	Effectively Earthed	Solidly Earthed	Solidly Earthed	-	-
7.	Fault Level	50 kA for 1 sec.	50 kA for 1 sec.	50 kA for 1 sec.	15 kA for 1 sec.	-

1.1.7 SYSTEM PARAMETERS

Dry and wet one minute power frequency withstand voltage	630 kVrms
Dry impulse withstand voltage positive and negative	1425 kVpeak
Minimum Total Creepage	25 mm/kV

1.1.8 MINIMUM CLEARENCE (AS PER IS: 10118)

Phase to phase (PP)	4200 mm
Phase to earth (PE)	3500 mm
Section clearance	6500 mm
Minimum ground clearance from plinth level (Plinth level : 300 mm)	8000 mm
Vertical ground clearance to nearest part not at earth potential of an insulator supporting live conductor/ equipment	2440 mm

1.2 INSTRUCTION TO BIDDERS

The bidders shall submit the technical requirements, data and information as per the technical data sheets, provided in Section-4.

The bidders shall furnish catalogues, engineering data, technical information, design documents, drawings etc fully in conformity with the technical specification. It is recognised that the Manufacturer may have standardised on the use of certain components, materials, processes or procedures different than those specified herein. Alternate proposals offering similar equipment based on the manufacturer's standard practice will also be considered provided such proposals meet the specified designs, standard and performance requirements and are acceptable to the Purchaser. Unless brought out clearly, the Bidder shall be deemed to conform to this specification scrupulously.

1.3 STANDARDS

The works covered by the specification shall be designed, engineered, manufactured, built, tested and commissioned in accordance with the Acts, Rules, Laws and Regulations of India.

The equipment to be furnished under this specification shall conform to latest issue (with all amendments) of specified standards.



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

In addition to meeting the specific requirement called for in Sections 1 and 2 of the Technical Specification, the equipment shall also conform to the general requirement of the applicable standards, which shall form an integral part of the specification. The Bidder shall note that standards mentioned in the specification are not mutually exclusive or complete in themselves, but intended to complement each other. When the specific requirements stipulated in the specifications exceed or differ from those required by the applicable standards, the stipulation of the specification shall take precedence.

Other internationally accepted standards, which ensure equivalent or better performance than that specified in the standards referred, shall also be accepted. The bidder shall submit copies of such standards.

In case governing standard for the equipment is different from IS or IEC, the salient points of difference shall be clearly brought out in the offer along with English language version of standard or relevant extract of the same. The equipment conforming to standards other than IS/IEC shall be subject to Purchaser's / owner's approval. The bidder shall clearly indicate in his bid the specific standards in accordance with which the works will be carried out.

1.4 TYPE TESTING, INSPECTION, TESTING & INSPECTION CERTIFICATE

All equipment being supplied shall conform to type tests and shall be subject to routine and acceptance tests in accordance with requirements stipulated under respective sections. Purchaser reserves the right to witness any or all the tests. The Manufacturer shall intimate the Purchaser the detailed programme about the tests at least three (3) weeks in advance in case of domestic supplies & six (6) weeks in advance in case of foreign supplies. Purchaser reserves the option for getting any or all the type tests repeated on the equipment. The Manufacturer shall also submit type test procedure for approval of the Purchaser.

In the event of any discrepancy in the test reports i.e. any test report not acceptable due to any design/manufacturing changes (including substitution of components) or due to non-compliance with the requirement stipulated in the technical specification or any/all additional type tests not carried out without any additional cost implication to the Purchaser.

The price of conducting all tests and additional type tests is deemed to be included in Bid price. In case any bidder indicates that he shall not carry out a particular test, his offer shall be considered incomplete and shall be liable to be rejected.

The purchaser intends to repeat the type tests and additional type tests on cables for which test charges shall be payable as per provision of contract.



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

The Purchaser, his duly authorised representative and/or outside inspection agency acting on behalf of the Purchaser shall have at all reasonable times free access to the Contractors premises or Works and shall have the power, at all reasonable times to inspect and examine the materials and workmanship of the Works during its manufacture or erection if part of the Works is being manufactured or assembled at other premises or works, the Manufacturer shall obtain for the Engineer and for his duly authorized representative permission to inspect as if the works were manufactured or assembled on the Manufacturer's own premises or works. Inspection may be made at any stage of manufacture, dispatch or at site at the option of the Purchaser and the equipment if found unsatisfactory due to bad workmanship or quality, material is liable to be rejected.

The Manufacturer shall give the Purchaser/inspector thirty (30) days written notice of any material being ready for testing. Such tests shall be to the Manufacturer's account except for the expenses of the inspector. Unless witnessing of the tests is virtually waived, the Purchaser/ inspector will attend such tests within thirty (30) days of the date of which the equipment is notified as being ready for test/ inspection, failing which the Manufacturer may proceed with the test which shall be deemed to have been made in the Inspector's presence and the Manufacturer shall forthwith forward duly certified copies of test reports in triplicate to the Inspector.

The Purchaser or Inspector shall, within fifteen (15) days from the date of inspection as defined herein, give notice in writing to the Manufacturer, of any objection to any drawings and all or any equipment and workmanship which in his opinion is not in accordance with the Contract. The Manufacturer shall give due consideration to such objections and shall either make the modifications that may be necessary to meet the said objections or shall confirm in writing to the Purchaser/ inspector giving reasons therein, that no modifications are necessary to comply with the Contract.

When the factory tests have been completed at the Manufacturer's works, the Purchaser/ inspector shall issue a certificate to this effect within fifteen (15) days after completion of tests but if the tests are not witnessed by the Purchaser/inspector, the certificate shall be issued within fifteen (15) days of receipt of the Manufacturer's Test certificate by the Engineer/ Inspector. Failure of the Purchaser/inspector to issue such a certificate shall not prevent the Manufacturer from proceeding with the Works. The completion of this test or the issue of the certificate shall not bind the Purchaser to accept the equipment should it, on further tests/ after erection, be found not to comply with the Contract. The equipment shall be dispatched to site only after approval of test reports and issuance of MICC by the Purchaser.

In all cases where the Contract provides for tests whether at the premises or at the works of the Manufacturer or of any Sub-Contractor, the Manufacturer except where otherwise specified shall provide free of charge such items as labour, materials, electricity, fuel, water, stores, apparatus and instruments as may be reasonably demanded by the Purchaser /Inspector or his authorised representative to carry out effectively such tests of the equipment in accordance with the Contract and shall give facilities to the Purchaser Inspector or to his authorised representative to accomplish testing.



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

The inspection by Purchaser and issue of Inspection Certificate thereon shall in no way limit the liabilities and responsibilities of the Manufacturer in respect of the agreed quality assurance programme forming a part of the Contract.

The Purchaser will have the right of having at his own expenses any other test(s) of reasonable nature carded out at Manufacturer's premises or at site or in any other place in addition of aforesaid type and routine tests, to satisfy that the material comply with the specification.

The Purchaser reserves the right for getting any field tests not specified in respective sections of the technical specification conducted on the completely assembled equipment at site. The testing equipment for these tests shall be provided by the Purchaser.

1.5 MATERIAL/WORKMANSHIP

1.5.1 GENERAL REQUIREMENT

Where the specification does not contain characteristics with reference to workmanship, equipment, materials and components of the covered Equipment it is understood that the same must be new, of highest grade of the best quality of their kind conforming to best engineering practice and suitable for the purposes for which they are intended.

The design of the Works shall be such that installation, future expansions, replacements and general maintenance may be undertaken with a minimum of time and expenses. Each component shall be designed to be consistent with its duty and suitable factors of safety, subject to mutual agreements and shall be used throughout the design. All joints and fastenings shall be devised, constructed and documented so that the component parts shall be accurately positioned and restrained to fulfil their required function. In general screw threads shall be standard metric threads. The use of other thread forms will only be permitted when prior approval has been obtained from purchaser.

Whenever possible, all similar part of the Works shall be made to gauge and shall also be made interchangeable with similar parts. All spare parts shall be interchangeable with, and shall be made of the same materials and workmanship as the corresponding parts of the Equipment supplied under the Specification. Where feasible, common component units shall be employed in different pieces of equipment in order to minimize spare parts stocking requirements. All equipment of the same type and rating shall be physically and electrically interchangeable.

All materials and equipment shall be installed in strict accordance with the manufacturer's recommendation(s). Only first-class work in accordance with the best modern practices will be accepted. Installation shall be construed as being the erection of equipment at its permanent location. This, unless otherwise specified, shall include unpacking, cleaning and lifting into position, grouting,



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

levelling, aligning, coupling of or bolting down to previously installed equipment bases/foundations, performing the alignment check and final adjustment prior to initial operation, testing and commissioning in accordance with the manufacturer's tolerances /instructions and the Specification. All factory assembled rotating machinery shall be checked for alignment and adjustments made as necessary to re-establish the manufacture's limits. Suitable guards shall be provided for the protection of personal on all exposed rotating and / or moving machine parts and shall be designed for easy installation and removal for maintenance purpose. The spare equipment(s) shall be installed at designated locations and tested for healthiness.

The Contractor shall apply oil and grease of the proper specification to suit the machinery, as is necessary for the installation of the equipment. Lubricants used for installation purposes shall be drained out and the system flushed through where necessary for applying the lubricant required for operation. The Contractor shall apply all operational lubricants to the equipment installed by him.

All oil, grease and other consumables used in the Works/ Equipment shall be purchased in India unless the Contractor has any special requirement for the specific application of a type of oil or grease not available in India. If such is the case, he shall declare in the proposal where such oil or grease is available. He shall help purchaser in establishing equivalent Indian make and Indian Contractor. The same shall be applicable to other consumables too.

1.5.2 PROVISIONS FOR EXPOSURE TO HOT AND HUMID CLIMATE

Outdoor equipment supplied under the specification shall be suitable for service and storage under tropical conditions of high temperature, high humidity, heavy rainfall and environment favourable to the growth of fungi and mildew. The indoor equipments located in non-air conditioned areas shall also be of same type.

1.6 COLOUR SCHEME AND CODES FOR PIPE SERVICE

The contractor shall propose a colour scheme for those equipment/Items for which the colour scheme has not been specified in the specification for the approval of purchaser. The decision of purchaser shall be final. The scheme shall include:

Finishing colour of Indoor equipment

Finishing colour of Outdoor equipment.

Finish colour of all cubicles.

Finishing colour of various auxiliary system equipment including piping

Finishing colour of various building items.

All steel structures, plates etc. shall be painted with non-corrosive paint on a suitable primer. It may be noted that normally all electrical equipment in switchyard are painted with shade 631 of IS-5. All The indoor cubicles shall be of same colour scheme and for other miscellaneous items, colour scheme will be approved by the purchaser.



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

1.7 PAINTING

- a) All sheet steel work shall be phosphated in accordance with the following procedure and in accordance with IS: 6005 "Code of practice for Phosphating Iron and Steel".
- b) Oil, grease, dirt and swerve shall be thoroughly removed from emulsion by cleaning.
- c) Rust and scale shall be removed by pickling with dilute acid followed by washing with running water, rinsing with slightly alkaline hot water and drying.
- d) After phosphating, thorough rinsing shall be carried out with clean water followed by final rinsing with dilute bichromate solution and over drying.
- e) The phosphate coating shall be sealed by the application of two coats of ready mixed, stoving type zinc chromate primer. The first coat may be "Flash dried" while the second coat shall be stoved.
- f) After application of the primer, two coats of finishing epoxy paint shall be applied, each coat followed by stoving. The panel shall have colour conforming to shade 631 of IS-5 for outside and inside of the panel with black colour for base frame.
- g) Each coat of primer and finishing paint shall be of a slightly different shade to enable inspection of the painting.
- h) Finished painted appearance of panel shall present an asthetically pleasing appearance free from dents and uneven surface.
- i) A small quantity of finishing paint shall be supplied for minor touching up required at site after the installation of the panels.

1.8 PROTECTION

- a) All coated surfaces shall be protected against abrasion, impact, discoloration and any other damages. All exposed threaded portions shall be suitably protected with either a metallic or a non-metallic protecting device. All ends of all valves, pipings and conduit equipment connections shall be properly sealed with suitable devices to protect them from damage.
- b) All equipment accessories and wiring shall have fungus protection, involving special treatment of insulation and metal against fungus, insects and corrosion.
- c) The parts which are likely to get rusted, due to exposure to weather should also be properly treated and protected in a suitable manner.
- d) Screens of corrosion resistant material shall be furnished on all ventilating louvers to prevent entry of insects.



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

1.9 FUNGISTATIC VARNISH

Besides the space heaters, special moisture and fungus resistant varnish shall be applied on the parts, which may be subjected or predisposed to the formation of fungi due to the presence or deposit of nutrient substances. The varnish shall not be applied to any surface of part where the treatment will interface with the operation or performance of the equipment. Such surfaces or parts shall be protected against the application to the varnish.

1.10 SURFACE FINISH

All interiors and exteriors of tanks, control cubicles and other metal parts shall be thoroughly cleaned to remove all rust, scales, corrosion, greases or other adhering foreign matter. All steel surfaces in contact with insulating oil as far as accessible shall be painted with not less than two coats of heat resistant, oil insoluble, insulating paints.

All metal surfaces exposed to atmosphere shall be given two primer coats of zinc chromate and two coats of epoxy paint with epoxy base thinner. All metal parts not accessible for painting shall be made of corrosion resisting material. All machine finished or bright surfaces shall be coated with a suitable preventive compound and suitably wrapped or otherwise protected. All paints shall be carefully selected to withstand tropical heat and extremes of weather within the limit specified. The paint shall not scale off or wrinkle or be removed by abrasion due to normal handling.

1.11 GALVANIZING

All ferrous parts including all sizes of nuts, bolts, Plain and spring washers, support channels, structures, shall be hot dip galvanised conforming to latest version of IS:2629 or any other equivalent authoritative standard. However, hardware less than M12 size shall be electro-galvanized. Minimum weight of zinc coating shall be 610 gm/sq.mm and minimum thickness of coating shall be 85 microns for all items thicker than 6mm. For items lower than 6 mm thickness, requirement of coating shall be as per relevant ASTM.

1.12 AUXILIARY POWER SUPPLY

1.12.1 A.C power supply for auxiliaries will be available at 240 V, 50 C/s 1-phase, 2 wire and 415V, 50 C/s, 3-phase, 4 wire, neutral solidly earthed with variation in frequency of +/-5% and variation in voltage +/-10%

1.12.2 D.C. power supply at 220 V, 2-wire ungrounded will be available 187 V to 242 V.

1.13 INSPECTION AND TESTING

All tests and inspection of the equipment specified shall be performed to the extent and in the manner as stipulated in the relevant standards and in this specification. All type tests/routine tests/acceptance tests as specified shall be conducted in the presence of purchaser. Wherever equipment similar to the one being offered has already been type tested within 5 years from the date



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

of opening the bid. Type tests done in an independent government laboratory or in the presence of representative of State Electricity Board or other reputed public undertakings, the type test reports of the same shall be submitted for scrutiny /approval. If these are found suitable and technically acceptable, conducting of type tests shall be waived off. Otherwise the subcontractor will have to carry out the type tests without any extra cost and without any delivery implications.

1.14 PACKAGING

Aluminium Tube shall be partially packed with Hessians cloths. Similar items shall be grouped and tied with steel wires/strip for convenient handling during transits.

MARKINGS

The following details are to be clearly indicated in the material forwarding documents:

- a) Name and address of the consignee.
- b) Purchase order number.
- c) Name of supplier/s.
- d) Description of equipment / material.
- e) Tare weight.
- f) Gross weight.

All the equipments shall be suitably protected, coated, covered or boxed and crated to prevent damage or deterioration during transit, handling and storage at Site till the time of erection. On request of the purchaser, the Contractor shall also submit packing details/associated drawing for any equipment material under his scope of supply, to facilitate the purchaser to repack any equipment/material at a later date, in case the need arises, while packing all the materials, the limitation from the point of view of availability of Railway wagon sizes in India should be taken account of. The Contractor shall be responsible for any loss or damage during transportation, handling and storage due to improper packing. Any demurrage wagons and other such charges claimed by the transporters, railways etc. shall be to the account of the Contractor. Purchaser takes no responsibility of the availability of the wagons.

1.15 HANDLING, STORING AND INSTALLATION

In accordance with the specific installation instructions as shown on manufacturer's drawings or as directed by the purchaser or his representative, the Contractor shall unload, store, erect, install, wire, test and place into commercial use all the equipment included in the contract. Equipment shall be installed in a neat, workmanlike manner so that it is level, plumb, square and properly aligned and



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

oriented. Commercial use of switchyard equipment means completion of all site tests specified and energisation at rated voltage.

Contractor may engage manufacturer's Engineers to supervise the unloading, transportation to site, storing, testing and commissioning of the various equipment being procured by them separately. Contractor shall unload, transport, store, erect, test and commission the equipment as per instructions of the manufacturer's supervisory Engineer(s) and shall extend full cooperation to them.

In case of any doubt/misunderstanding as to the correct interpretation of manufacturer's drawings or instructions, necessary clarifications shall be obtained from the purchaser.

Contractor shall be held responsible for any damage to the equipment consequent to not following manufacturer's drawings/instructions correctly.

Where assemblies are supplied in more than one section, contractor shall make all necessary mechanical and electrical connections between sections including the connection between buses. Contractor shall also do necessary adjustments/alignments necessary for proper operation of circuit breakers, isolators and their operating mechanisms. All components shall be protected against damage during unloading, transportation, storage, installation, testing and commissioning. Any equipment damaged due to negligence or carelessness or otherwise shall be replaced by the contractor at his own expenses.

Contractor shall be responsible for examining all the shipment immediately of any damage, shortage, discrepancy etc. for the purpose of Purchaser's information only. The Contractor shall submit to the purchaser every week a report detailing all the receipts during the weeks. However, the Contractor shall be solely responsible for any shortages or damages in transit, handling and/or in storage and erection of the equipment at Site. Any demurrage, pilferage and other such charges claimed by the transporters, railways etc. shall be to the Contractor's account.

The Contractor shall be fully responsible, for the equipment/material until the same is handed over to the purchaser in an operating condition after commissioning. Contractor shall be responsible for the maintenance to the equipment/material while in storage as well as after erection until taken over by Purchaser, as well as protection of the same against theft, element of such nature, corrosion, damages etc.

The Contractor shall be responsible for making suitable indoor storage facilities, to store all equipments which require indoor storage.

The words erection and installation used in the specification are synonymous. Exposed live parts shall be placed high enough above ground to meet the requirements of electrical and other statutory safety codes.



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

The minimum phase to earth, phase to phase and section clearance along-with other technical parameters for the various switchyard voltage levels to be maintained shall be strictly as per the approved drawings.

The design and workmanship shall be in accordance with the best engineering practices to ensure satisfactory performance throughout the service life. If at any stage during the execution of the Contract, it is observed that the erected equipment(s) do not meet the above minimum clearances, the Contractor shall immediately proceed to correct the discrepancy at his risks and costs.

1.16 TOOLS AND TACKLES

The Contractor shall supply with the equipment one complete set of all special tools and tackles for the erection, assembly, dis-assembly and maintenance of the equipment. However, these tools and tackles shall be separately, packed and brought on to Site.

1.14 EQUIPMENT BASES

A cast iron or welded steel base-plate shall be provided for all rotating equipment, which is to be installed on a concrete base unless otherwise agreed to by the Purchaser. Each base-plate shall support the unit and its drive assembly, shall be of a neat design with pads for anchoring the units shall have a raised lip all around, and shall have threaded drain connections.

1.15 QUALITY

BHEL quality plan to be followed subject to TBEM / customer's approval.

1.16 DOCUMENTATION

1.16.1 DRAWINGS

All drawings shall be prepared in AutoCAD and ultimate documentation would include drawings/documents on CDs. All dimensions and data shall be in SI metric units.

All items of the equipment should be clearly identified by proper part nos. in the contract drawings. Such parts, which are to be dispatched to site from works in dispatchable units and are reassembled at site, should be marked by proper identification marks at works and indicated in the drawings and quantified. The shipping list should be sent along with the general arrangement drawings for engineer's approval. All the items of the shipping list should be identified in the drawing.

The drawing submitted by the supplier shall be reviewed by the purchaser as far as practicable within two weeks of receipt of drawings and shall be modified by the sub-contractor if any modifications and/or corrections are required by the purchaser. The sub-contractor shall incorporate such modifications and / or corrections and submit the final drawings for approval. Any delay arising out of failure of the subcontractor to rectify the drawings shall not alter the contract completion date.



Project: 1x800 MW KOTHAGUEDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

Further work by the subcontractor shall be in strict accordance with these drawings and no deviation shall be allowed without the written approval of the purchaser.

All manufacturing and fabrication work in connection with the equipment prior to the approval of the drawings shall be at supplier's risk.

Approval of drawing or work by the purchaser/consultant shall not relieve the subcontractor of any of his responsibilities and liabilities under the contract.

In case of any modifications that may be necessary during erection or commissioning of the equipment, the subcontractor shall carry out modifications in the original drawing & submit 'As Built drawings' and required no. of prints thereof.

1.16.2 INSTRUCTION MANUALS

The supplier shall submit to the purchaser, draft instruction manuals for approval within 30 days of placement of order. The final instruction manuals complete in all respects shall be submitted 60 days before the first shipment of the equipment. The instruction manuals shall contain full details and drawings of all the equipment furnished, the erection procedures, testing, operation & maintenance procedures of the equipment.

If after the commissioning and initial operation of the plant, the instruction manuals require any modification/ addition / changes, the same shall be incorporated and the up- dated final instruction manuals shall be submitted as required.

1.16.3 TITLE BLOCK & DRAWING/ DOCUMENT NUMBERING SCHEME

Title block for drawing / document should be followed as per ANNEXURE-3

1.16.4 DOCUMENTATION SCHEDULE AT CONTRACT STAGE

A.	<u>For approval</u>	<u>No of Copies</u>
	Copies of all drawings with project details, dimension, shipping weights, No. of cases & dimensions, fixing details, tolerance etc.	10
	Copies of type test reports.	5
	Copies of works quality plan & field quality plan.	5



Project: 1x800 MW KOTHAGUDEM THERMAL POWER STATION STAGE VII, UNIT 12 &
4x270 MW BHADRADRI THERMAL POWER STATION.

Customer: TELANGANA STATE POWER GENERATION CORPORATION LTD

Section-3: Project Details & General Specifications

Rev. No. 00

Copies of installation, operation & maintenance manual.	5
Copies of drawings on floppies/CDs	1 set

B. After approval and for information / distribution

Copies of all drawings	15
Copies of installation, operation & maintenance manual including Routine test reports	15
Sets of RTF of drawings	2
CDs of Drgs.	3

C. As Built Drawings

Hard copies of Drawings	15
CDs	3

NOTE:

1. Any revision of drawings / documents shall be submitted in the same no. of copies submitted first time for approval
2. Final drawings / documents shall be submitted in bound volume with customer and project details etc. written on the top.

SECTION 4
CHECK LIST FOR INFORMATION TO BE FURNISHED WITH OFFER RETURN
THIS CHECKLIST AS PART OF THE OFFER DULY SIGNED

The offer may not be considered if the following information and this Checklist are not enclosed with the Offer.

BHEL ENQUIRY. NO:

BIDDER: OFFER REFERENCE:

A) TECHNICAL PARAMETERS-

S. No.	Parameters	Data	Confirmation	Remarks
1.	Applicable Standards	Latest IS -1554, 5831, 8130, 3975, 613, ASTM-D2843, ASTM-D2863, IEC60754, IEC60332, IS3961, IS 10418, SS4241475, NEMA WC-70, IEEE-383	Yes	
2.	Rated Voltage	1100V Grade	Yes	
3.	Construction feature for PVC Control cable			
3.1	Material of Conductor for Control cables	Stranded, non-compacted & circular, high conductivity annealed plain copper Conductor (with Min. 7 strands)	Yes	
3.2	Conductor Insulation	Extruded HRPVC, Type-C	Yes	
3.3	Inner sheath	Extruded HRPVC, Type ST-2	Yes	
3.4	Armouring for Control Cables	Galvanised single round steel wire for twin and multicore cables.	Yes	
3.5	Outer sheath	Extruded FRLSH HRPVC compound Type ST-2 For Control cables: Grey colour.	Yes	
4.	Construction feature for XLPE Aux Power cable			
4.1	Material of Conductor for Power cables	Stranded and compacted plain aluminium of grade H2 (electrolytic Grade) with min 7 strands; Circular/ Sector shaped	Yes	
4.2	Conductor Insulation	Extruded cross-linked polyethylene (XLPE)	Yes	
4.3	Inner sheath	Extruded HRPVC FRLS compound conforming to type ST2	Yes	
4.4	Armouring for XLPE Aux Power Cables	Galvanized single round steel wire Armour for twin and multicore cables. Non-magnetic hard drawn aluminum single round wire conforming to H4 of IS-8130 latest for single core cables	Yes	

S. No	Parameters	Data	Confirmation	Remarks
4.5	Outer sheath	Extruded FRLSH HRPVC compound conforming to type ST2 For Power cables: Black colour.	Yes	
5.	Construction feature for FS Power cable			
5.1	Material of Conductor for FS Power cables	Copper conductor	Yes	
5.2	Conductor Insulation	Heat resisting insulation	Yes	
5.3	Inner sheath	Extruded inner sheath of low smoke and very low halogen content fire resisting material	Yes	
5.4	Armouring	Single layer of copper wire armour for single core/ single layer of round galvanised steel wire for multicore	Yes	
5.5	Outer sheath	Low smoke and very low halogen content fire resistant material, suitable for minimum temperature of 750 deg.C for 3hours.	Yes	
6.	FRLS properties of Outer sheath			
6.1	Minimum Oxygen index	29 as per IS 10810 part-58	Yes	
6.2	Minimum Temperature index	250°C	Yes	
6.3	Acid gas emission	Max 20% as per IEC-754-I	Yes	
6.4	Smoke density rating	Max 60% as per ASTM-2843	Yes	
7.	Allowable Tolerance on overall diameter	± 2mm	Yes	
8.	Chemicals added to outer sheath to protect from rodent, vermin and termite attack	Yes	Yes	
9.	Standard lengths of each Power & Control Cable	500m / 1000m	Yes	
10.	Tolerance on Cable Length per Drum.	+/-5% of the standard drum length.	Yes	
11.	Overall Tolerance on ordered quantity	+/-2% of total ordered quantity	Yes	
12	Layer of water proof paper shall be applied to surface of the drums and over the outermost cable layer.	Yes	Yes	
13	Minimum bending radius for multicore cables	12 x D	Yes	
14	Core Identification / markings		Yes	
14.a	For control cables	By color coding and numbering at interval of 100mm or less	Yes	
14.b	For Power cables	By color coding	Yes	
15	Filler shall be of same material as of inner sheath i.e. ST2	Yes	Yes	
16	Provenness criteria for LT power & Control cables	Filled provenness data sheets (refer Annexure attached with this checklist) and required doc attached .	Yes	

B) TYPE TESTS

- i) Test Shall be carried out as per clause 5.00.00 of section-II **(YES)**

Date:

Signature of the authorized representative of Bidder
Company Seal

Sub-vendor's Name and Address : To
[Employer's Name & Address]

Dear Sirs,

Sub : Sub-Qualifying Requirement for LT Control Cables

We declare that we have manufactured and supplied the following cables, as on date of
LOA | :

- (a) Atleast 300 Kms of PVC insulated, PVC sheathed stranded copper conductor 1.1 kV grade control cables in one single contract.
- (b) Atleast one (1) km of flame retardant low smoke cables.
- (i) The details of above (a) are given as under :

Sl.No. Particulars

- 1. Client name and its address,
fax no. & telephone no.
- 2. Name & Designation of the responsible
person in client's organisation
- 3. Name, Address, telephone no. &
fax no. of the user of the cables
- 4. Name & designation of the responsible
person in user's organisation
- 5. Contract No. and date

Sl.No.	Particulars	
6.	Details of copper conductor, PVC insulated, PVC sheathed stranded control cables of 1.1 KV grade	
(i)	Manufactured	Yes/No
(ii)	Supplied	Yes/No
(iii)	Rated voltage of cable	 KV
(iv)	Type of Cable	
(v)	Total Quantity supplied as on date of bid opening in one single contract	 Km
7.	User's Certificate of Cable enclosed	

(ii) The details of above (b) are given as under :

Sl.No.	Particulars
1.	Client name and its address, fax no. & telephone no.
2.	Name & Designation of the responsible person in client's organisation
3.	Name, Address, telephone no. & fax no. of the user of the cables
4.	Name & designation of the responsible person in user's organisation
5.	Contract No. and date

Sl.No.	Particulars	
6.	Details of Flame Retardant Low Smoke cables	
(i)	Manufactured	Yes/No
(ii)	Supplied	Yes/No
(iii)	Type of Cable	
(iv)	Total Quantity supplied as on date of bid opening	 Km
7.	User's Certificate of Cable enclosed	

Date : (Signature).....
 Place : (Printed Name).....
 (Designation).....
 (Common seal).....

Note :

- Continuation sheets of like size and format may be used as per the Sub-vendor's requirement and shall be annexed to this Attachment-~~3A17~~.
- Sub-vendor is required to attach necessary documents like copies of work order, completion certificates, agreements, drawings etc. in support of the details furnished above.

Sub-vendor's Name and Address : To
[Employer's Name & Address]

Dear Sirs,

Sub : Sub-Qualifying Requirement for LT Power Cables

We declare that we have manufactured and supplied the following cables, as on date of
LOA :

- (a) Atleast 100 Kms of aluminium conductor, XLPE insulated, PVC sheathed power cables of 1.1 kV or higher grade in one single contract.
- (b) Atleast 100 km of aluminium conductor, PVC insulated, PVC sheathed power cables of 1.1 kV or higher grade in one single contract.
- (c) Atleast one (1) km of flame retardant low smoke cables.
- (d) 1.1 kV or higher grade power cable of minimum 630 sq.mm. conductor size.
- (i) The details of above (a) are given as under :

Sl.No. Particulars

- 1. Client name and its address,
fax no. & telephone no.
- 2. Name & Designation of the responsible
person in client's organisation
- 3. Name, Address, telephone no. &
fax no. of the user of the cables

Sl.No.	Particulars	
4.	Name & designation of the responsible person in user's organisation	
5.	Contract No. and date	
6.	Details of aluminium conductor, XLPE insulated, PVC sheathed Power cables of 1.1 KV or higher grade	
(i)	Manufactured	Yes/No
(ii)	Supplied	Yes/No
(iii)	Rated voltage of cable	 KV
(iv)	Type of Cable	
(v)	Total Quantity supplied as on date of bid opening	 Km
7.	User's Certificate of Cable enclosed	Yes/No

(ii) The details of above (b) are given as under :

Sl.No.	Particulars
1.	Client name and its address, fax no. & telephone no.
2.	Name & Designation of the responsible person in client's organisation
3.	Name, Address, telephone no. & fax no. of the user of the cables

Sl.No.	Particulars	
4.	Name & designation of the responsible person in user's organisation	
5.	Contract No. and date	
6.	Details of aluminium conductor, PVC insulated, PVC sheathed Power cables of 1.1 KV or higher grade	
(i)	Manufactured	Yes/No
(ii)	Supplied	Yes/No
(iii)	Rated Voltage of Cable	KV
(iv)	Type of Cable	
(v)	Total Quantity supplied as on date of bid opening in one single contract	 Km
7.	User's Certificate of Cable enclosed	Yes/No

(iii) The details of above (c) are given as under :

Sl.No.	Particulars
1.	Client name and its address, fax no. & telephone no.
2.	Name & Designation of the responsible person in client's organisation
3.	Name, Address, telephone no. & fax no. of the user of the cables

Sl.No.	Particulars	
4.	Name & designation of the responsible person in user's organisation	
5.	Contract No. and date	
6.	Details of Flame Retardant Low Smoke cables	
(i)	Manufactured	Yes/No
(ii)	Supplied	Yes/No
(iii)	Type of Cable	
(iv)	Total Quantity supplied as on date of bid opening	 Km
7.	User's Certificate of Cable enclosed	Yes/No

(iv) The details of above (d) are given as under :

Sl.No.	Particulars
1.	Client name and its address, fax no. & telephone no.
2.	Name & Designation of the responsible person in client's organisation
3.	Name, Address, telephone no. & fax no. of the user of the cables
4.	Name & designation of the responsible person in user's organisation
5.	Contract No. and date

Sl.No.	Particulars	
6.	Details of 1.1 kV or higher grade power cable of aluminium 630 sq.mm conductor size	
(i)	Manufactured	Yes/No
(ii)	Supplied	Yes/No
(iii)	Rated Voltage of Cable	 kV
(iv)	Size of Cable	 sq.mm.
7.	User's Certificate of Cable enclosed	Yes/No

Date : (Signature).....

Place : (Printed Name).....

(Designation).....

(Common seal).....

Note :

- Continuation sheets of like size and format may be used as per the Sub-vendor's requirement and shall be annexed to this Attachment-~~3A18~~.
- Sub-vendor is required to attach necessary documents like copies of work order, completion certificates, agreements, drawings etc. in support of the details furnished above.