

		QUALITY PLAN SHEET 1 OF 2	CUSTOMER :			PROJECT			SPECIFICATION :				
			BIDDER/ :			TITLE			NUMBER :				
			VENDOR			QUALITY PLAN			SPECIFICATION				
SYSTEM			NUMBER PED-506-00-Q-006, REV-01			TITLE				SECTION		VOLUME III	
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/ METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS	
									P	W	V		
1	2	3	4	5	6	7	8	9	10			11	
1.0	ASSEMBLY	1.WORKMANSHIP	MA	VISUAL	100%	MANUF'S SPEC	MANUF'S SPEC	-DO-	2	-	-		
		2.DIMENSIONS	MA	-DO-	-DO-	MFG. DRG./ MFG. SPEC.	MFG. DRG./ MFG. SPEC.	-DO-	2	-	-		
		3.CORRECTNESS COMPLETENESS TERMINATIONS/ MARKING/COLOUR CODE	MA	VISUAL	100%	MFG.SPEC./ RELEVANT IS	MFG.SPEC. RELEVANT IS	-DO-	2	-	-		
2.0	PAINTING	1.SHADE	MA	VISUAL	SAMPLE	MANUFR'S SPEC/BHEL SPEC./RELEVANT STANDARD	BHEL SPEC. SAME AS COL.7	LOG BOOK	2	-	-		
3.0	TESTS	1.ROUTINE TEST INCLUDING SPECIAL TEST AS PER BHEL SPEC.	MA	-DO-	100%	IS-325/ BHEL SPEC./ DATA SHEET	SAME AS COL.7	TEST REPORT	2	1			NOTE -1 & NOTE-3
		2.OVERALL DIMENSIONS & ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/DATA SHEET	APPROVED DRG/DATA SHEET & RELEVANT IS	INSPN. REPORT	2	1	-	NOTE -1 & NOTE-3	
BHEL			PARTICULARS		BIDDER/VENDOR								
			NAME										
			SIGNATURE										

		QUALITY PLAN		CUSTOMER :			PROJECT			SPECIFICATION :		
				BIDDER/ :			TITLE			NUMBER :		
		SHEET 2 OF 2		VENDOR			QUALITY PLAN			SPECIFICATION :		
		SYSTEM			NUMBER PED-506-00-Q-006, REV-01			TITLE :				
		ITEM AC ELECT. MOTORS BELOW 55KW (LV)			SECTION			VOLUME III				
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
									P	W	V	
1	2	3	4	5	6	7	8	9	10			11
		3.NAMEPLATE DETAILS	MA	VISUAL	100%	IS-325 & DATA SHEET	IS-325 & DATA SHEET	INSPN. REPORT	2	1	-	
NOTES:												
1 ROUTINE TESTS ON 100% MOTORS SHALL BE DONE BY THE VENDOR. HOWEVER, BHEL SHALL WITNESS ROUTINE TESTS ON RANDOM SAMPLES. THE SAMPLING PLAN SHALL BE MUTUALLY AGREED UPON												
2 WHERE EVER CUSTOMER IS INVOLVED IN INSPECTION, (1) SHALL MEAN BHEL AND CUSTOMERS BOTH TOGETHER.												
3 FOR EXHAUST/VENTILATION FAN MOTORS OF RATING UPTO 1.5KW , ONLY ROUTINE TEST CERTIFICATES SHALL BE FURNISHED FOR SCRUTINY.												
<u>Legends for Inspection agency</u>												
1. BHEL/CUSTOMER												
2. VENDOR (MOTOR MANUFACTURER)												
3. SUB-VENDOR (RAW MATERIAL/COMPONENTS SUPPLIER)												
P. PERFORM												
W. WITNESS												
V. VERIFY												
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			

[illegible]

Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.

1. For the purpose of clarity, it may please be noted that the information given in regard to the cables to be routed through WinPath as per the system elaborated below is called "Cable List", while the term "Cable Schedule" applies to the cable list with routing information added after routing has been carried out.
2. The cable list shall be entered as an MS Excel file in the format as per enclosed template EXT_CAB_SCH_FORMAT.XLS. No blank lines, special characters, header, footer, lines, etc. shall be introduced in the file. No changes shall be made in the title line (first line) of the template.
3. The field properties shall be as under:
 - a. UNITCABLENO: A/N, up to sixteen (16) characters; each cable shall have its own unique, unduplicated cable number. In case this rule is violated, the cable cannot be taken up for routing.
 - b. FROM: A/N, up to sixty (60) characters; the "From" end equipment/ device description and location to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
 - c. TO: A/N, up to sixty (60) characters; the "To" end equipment/ device description and location to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
 - d. PURPOSE: A/N, up to sixty (60) characters; the purpose (i.e. power cable/ indication/ measurement, etc.) to be specified here. Information in excess of 60 characters will be truncated after 60 characters.
 - e. REMARKS: A/N, up to forty (40) characters; Any information pertinent to routing to be specified here (e.g., cable number of the cable redundant to the cable number being entered). Information in excess of 40 characters will be truncated after 40 characters.
 - f. CABLESIZE: A/N, 7 characters exactly as per the codes indicated below shall be specified here. The program cannot route cables described in any other way/ format.
 - g. PATHCABLENO: Field reserved for utilization by the program. User shall not enter any information here.
4. One list shall be prepared for each system/ equipment (i.e., separate and unique cable lists shall be prepared for each system).
5. The cables shall be described as per the scheme listed below:

Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.

A	NN	NNN
Cable	No. of cores	Cable size
Voltage	(e.g. 01,03,3H, 07)	(e.g. 035,185,2.5, 0.5)
Code (see B below)		

please refer below examples:

- i) 3C x 120 sq. mm. (1.1kV) PVC FRLS, Unarmoured Aluminium cable, the voltage code shall be D03G120
- ii) 3C x 2.5 sq. mm. (1.1kV) PVC FRLS, Unarmoured Copper cable, the voltage code shall be D03C2.5
- iii) 3.5C x 120 sq. mm. (1.1kV) PVC non-FRLS, Armoured Aluminium cable, the voltage code shall be D3HF120

(A) SYSTEM VOLTAGE CODES:

- (ac) A = 11KV, B = 6.6KV, C = 3.3KV, D = 415V, E = 240V, F = 110V
- (dc) G = 220V, H = 110V, J = 48V, K = +24V, L = -24V

(B) CABLE VOLTAGE CODES:

- A = 11KV (Power cables)
- B = 6.6KV (Power cables)
- C = 3.3KV (Power cables)
- D = 1.1KV (LV & DC system power & control cables)
- E = 0.6KV (0.5 sq. mm. Control cables)

(C) CABLE CODES

PVC Copper

- A = Armoured FRLS
- C = unarmoured FRLS
- B = Armoured Non-FRLS
- D = Unarmoured Non-FRLS

Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.

<u>PVC Aluminium</u>	
E = Armoured FRLS	F = Armoured Non-FRLS
G = unarmoured FRLS	H = Unarmoured Non-FRLS
<u>XLPE Copper</u>	
J = Armoured FRLS	K = Armoured Non-FRLS
L = unarmoured FRLS	M = Unarmoured Non-FRLS
<u>XLPE Aluminium</u>	
N = Armoured FRLS	P = Armoured Non-FRLS
Q = unarmoured FRLS	R = Unarmoured Non-FRLS
S = FIRE SURVIVAL CABLES	
T = TOUGH RUBBER SHEATH	
U = OVERALL SCREENED	
V = PAIRED OVERALL SCREENED	
W = PAIRED INDIVIDUAL SCREENED	
Y = COMPENSATING CABLES	
I = PRE-FABRICATED CABLES	
Z = JELLY FILLED CABLES	

6. Once a cable list has been given to PEM for routing, any subsequent changes required in the cable list (which may be in the form of addition of cables, deletion of cables, change of type or size of cable, etc.) must be informed as specific changes (as a separate file MS Excel of the same format as the original file) to the cable list given earlier if the cable list has been routed and cable schedule generated. The routing status of the cable list shall be got confirmed from PEM by the agency that has prepared the cable list before the changes are intimated. In case PEM confirms that the cable list in question has not been taken up for routing, and the revised cable list is acceptable,

Explanatory notes for filling up cable list for routing through WinPath, the cable routing program (developed by Corporate R&D) being used in PEM.

the same may be sent. Since cable routing through the program involves adding each cable list to the project cable schedule database, the original cable schedule shall not be furnished to PEM with revisions incorporated within.

7. For any assistance or clarifications, please contact <mailto:praveendutta@bhelpem.co.in>



TITLE:
3 X 800 MW PATRATU STPP STAGE - I

SPECIFICATION NO. PE-TS-434-164-A001

**TECHNICAL SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

REV. NO. 00

DATE : 29/05/2019

SUB-SECTION IC

SPECIFIC & GENERAL TECHNICAL REQUIREMENTS (CONTROL & INSTRUMENTATION)

	3 x 800 MW PVUNL PATRATU TPP PHASE-I	SECTION: C
	TECHNICAL REQUIREMENTS (C&I) EFFLUENT TREATMENT PLANT	

CONTROL AND INSTRUMENTATION FOR EFFLUENT TREATMENT PLANT

	3 x 800 MW PVUNL PATRATU TPP PHASE-I		DESG	AR <i>Atul</i> 05/01/18
	JOB NO: 434		CHKD	MK <i>18</i> 05/01/18
	REV. NO. 00	DATE: 05.01.2018	APPD	BS <i>12</i> 05/01/18



**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

|



C&I SPECIFICATION FOR EFFLUENT TREATMENT PLANT

SECTION: C
SUB SECTION: C&I

INDEX

S. No.	DESCRIPTION
1	TITLE SHEET
2	INDEX SHEET
3	C&I SPECIFIC TECHNICAL REQUIREMENTS
4	GENERAL TECHNICAL SPECIFICATION
5	LIST OF DOCUMENTS/DELIVERABLES
6	MEASURING INSTRUMENTS (PRIMARY & SECONDARY)
7	DATA SHEETS FOR MOTORISED VALVE ACTUATOR
8	SIGNL EXCHANGE BETWEEN DRIVES & DCS
9	DRIVE AND INSTRUMENT INTERFACE DIAGRAM
10	INSTRUMENT CABLE INTERCONNECTION AND TERMINATION PHILOSOPHY
11	QUALITY ASSURANCE
12	TYPE TEST REQUIREMENT
13	INSTRUMENT STUB DETAILS
14	INSTRUMENT INSTALLATION DRAWING
15	SUB VENDOR LIST
16	KKS TAGGING PHILOSOPHY
17	FORMAT FOR PROVENNESS CERTIFICATE
18	ANNUAL MAINTENANCE CONTRACT (AMC)



**C&I SPECIFIC TECHNICAL REQUIREMENT
FOR DCS BASED
EFFLUENT TREATMENT PLANT**

|



C&I SPECIFICATION FOR EFFLUENT TREATMENT PLANT

SECTION: C
SUB SECTION: C&I

Specific Technical Requirements (C&I):

1. Effluent treatment plant (ETP) shall be operated from DCS (BHEL's scope).
2. The Contractor shall provide complete Instrumentation for control, monitoring and operation of entire ETP. The requirements given are to be read in conjunction with detailed Technical specification enclosed in the specification. Further in case of any discrepancy in the requirement within the same section noted by the bidder in the specification, the same will be brought to the notice of BHEL in the form of pre- bid clarification. In absence of any pre-bid clarification, the more stringent requirement as per interpretation of customer shall prevail without any commercial implication.
3. The make/model of various instruments/items/systems shall be as per NTPC approved vendor list. No commercial and delivery implication in this regard shall be acceptable. In case of any conflict and repetition of clauses in the specification, the more stringent requirements among them are to be complied with.
4. All instruments and control elements shall be terminated on JB/LCP in field and both instrument and JB/LCP are in bidder scope. Number of Junction Boxes shall be sufficient and positioned in the field to minimize local cabling (max 12-15 mtrs) and trunk cable.
5. For cable scope refer to electrical scope between BHEL and vendor defined in electrical specification.
6. Bidder to provide mandatory spares as per mandatory spares list.
7. Electrical Actuators with integral starter shall be provided for all on/off and inching type valves along with necessary interface units for linking to corresponding Control System as applicable, typical Hook-up diagram of drives is included for reference.
8. The specifications for instruments mentioned in the specification are minimum requirements. The detail specifications shall be finalized during detail engineering.
9. The bidders shall specifically mention any deviation they would like to take on the C&I specification. In absence of only deviation, a No deviation certificate is to be furnished.
10. The quantity of instruments for the system shall be as per tender P & ID wherever provided of the respective system as a minimum, for bidding purpose. However, Bidder shall also include in his proposal all the instruments and devices that are needed for the completeness of the plant auxiliary system/ equipment supplied by the bidder, even if the same is not specifically appearing in the P & ID. During detail engineering if any additional instruments are required for safe & reliable operation of plant, bidder shall supply the same without any price implication.
11. Bidder to terminate all instrumentation and control elements in junction boxes. Bidder to provide input/output list, drives list, junction box schedule and termination details, recommended control logics / write-up etc. the list of documents to be submitted after award of contract is to be referred by bidder.
12. All the transmitters supplied by Bidder shall be rack mounted. The transmitter racks shall be in Bidder's scope of supply. All transmitters shall be HART compatible.



C&I SPECIFICATION FOR EFFLUENT TREATMENT PLANT

SECTION: C
SUB SECTION: C&I

13. Bidder to perform tests of C&I items/instruments/systems as per Quality plans/type test attached in the specification. However, if any test not specified in the quality plan but specified in specification Tests for I&C equipment included elsewhere in specification will have to perform by Bidder without any cost implication. The make/model of various instruments/items/systems shall be as per customer/BHEL approved vendor list. No commercial and delivery implication in this regard shall be acceptable. In case of any conflict and repetition of clauses in the specification, the more stringent requirements among them are to be complied with.
14. Instrument installation and accessories required for the same shall be in Bidder's scope and shall be submitted after award of contract. However, any instrument/ analyser installation not covered in the same shall be subject to customer and BHEL approval during detailed engineering.
15. temperature transmitter shall be provided for all temperature measurement applications.
16. Bidder to provide temperature transmitter, JB/Rack & other erection hardware.
17. Bidder to furnish electrical load/UPS load data during detailed engineering.
18. UPS Power supply shall be provided by BHEL at a single point, further distribution to various instruments/equipment of the system shall be in bidder scope. Bidder to include necessary power distribution board in his scope. Any power supply other than the above, if required by any instrument/equipment has to be derived by the bidder from the above supply & all necessary hardware for the same shall be in bidder scope. Bidder to submit the power requirement along with the bid.
19. Bidder's presence is required for 3 Man days (Excluding travel time) at EDN Bangalore during FAT of DDCMIS for certifying correctness & completeness of implementation of Control logic. Intimation to attained FAT shall be informed in 2 days advance. All the expenses like boarding, lodging and travel, Air fare etc. shall be in bidder's scope.
20. Contractor's C&I representative shall be present at BHEL-PEM for 3 man-days, for preparation of Control scheme of ETP. All the expenses like boarding, lodging and travel, Air fare etc. shall be in bidder's scope.
21. Bidder's presence is required for 15 Man days (in three visit) at site during commissioning of DDCMIS for assistance related to process correctness. Three visit with total 15 Man days (Excluding travel time) in which one visit shall be of 5 Man days each. All the expenses like boarding, lodging and travel, Air fare etc. shall be in bidder's scope.
22. Contractor shall furnish Instrument Schedule, I/O list, Drive list, Cable Schedule, Cable interconnection (DCS end terminal details shall be provided to vendor during detail engineering to incorporate in cable interconnection), JB grouping, Annunciation list, SOE list, List of Instruments/devices for HART in BHEL approved format. Also reusable database format like MS Excel, MS Access etc. of these documents shall also be provided by Contractor in BHEL approved format. Soft copy of the formats shall be provided to the successful bidder.



C&I SPECIFICATION FOR EFFLUENT TREATMENT PLANT

SECTION: C
SUB SECTION: C&I

23. Interface of MCC, Solenoid valves, field instruments, Actuators etc. with DDCMIS based control system shall be as per Drive Control Philosophy enclosed in specification.
24. Local control panel if any required for operation shall be in bidder scope.
25. The solenoid operated valves/Dampers/Gate shall have a limit switch for open/close feedback. Solenoid Valve shall be rated for 24V Dc only.
26. All field instruments enclosure shall be IP65 local panel/cabinet enclosure shall be IP 55, unless otherwise specified.
27. Diaphragm seal shall be provided with Instruments having contact with corrosive media.
28. Redundancy of sensors shall be provided by bidder
 - (i) Triple redundancy for all analog and binary inputs required for protection of system/drives.
 - (ii) For all other control functions dual redundancy of the sensors shall be provided by the bidder.
29. Use of process actuated shall be avoided unless unavoidable.
30. Number of pairs to be selected for Screen /Control cable
 - a) F-Type: 2P/4P/8P/12P (Size: 0.5sqmm2)
 - b) G-Type: 2P/4P/8P/12P (Size: 0.5sqmm2)
 - c) Core Cable: 3CX2.5sqmm2/ 5CX2.5sqmm2/ 12CX1.5sqmm2
31. Sodium Analyser and Silica Analyser, if applicable, shall be of Multi stream with sequencer /stream selector (min. 4 streams)
32. Instrument installation shall be as per the attached "Standard Hook-up diagram of instrument."
33. In addition to requirements specified here, all C&I systems/ sub-systems/ equipment/ devices shall also meet other requirements stipulated under other Sub-sections/ parts/ sections of specification.
34. In case of any conflict and repetition of clauses in the specification, BHEL discretion will prevail.
35. Measuring instruments (primary & secondary), SWAS equipment/analysers offered for this package shall have at least one year's satisfactory operation in one power station having unit rating of 200 MW or above. Provenness certificate shall be provided as per the attached format (Annexure - 1).
36. All the outdoor field instruments such as analysers/transmitters/meters etc. shall be provided with suitable Free standing cabinet(s)/panel/rack so that the equipment are protected against rain/ sunlight etc.



**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

37. Comprehensive Annual Maintenance Contract (AMC) for three (03) years after warranty period shall be provided by the contractor for EQMS and analyzer instruments. For more details, please refer Annual Maintenance Contract (AMC) chapter.

|



**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

LIST OF DOCUMENTS/DELIVERABLES

|



C&I SPECIFICATION FOR EFFLUENT TREATMENT PLANT

SECTION: C
SUB SECTION: C&I

LIST OF DELIVERABLES OF PEM - C&I DEPARTMENT

Sl. No.	DRAWING NO.	DRAWING/DOCUMENT TITLE	CATEGORY
1	PE-V1-434-145-I901	CONTROL & OPERATIONAL WRITE-UP FOR THE SYSTEM WITH SET POINTS	A
2	PE-V1-434-145-I902	CONTROL SCHEME/LOGIC DIAGRAM (TO BE IMPLEMENTED IN DDCMIS)	A
3	PE-V1-434-145-I903	HMI PICTURES/PLANT SCHEMATICS	A
4	PE-V1-434-145-I904	INSTRUMENT SCHEDULE WITH SET POINTS	A
5	PE-V1-434-145-I905	I/O LIST (ANALOG & BINARY)	A
6	PE-V1-434-145-I906	DRIVE LIST/SOLENOID/ACTUATOR VALVE LIST WITH LOCATION DATA	A
7	PE-V1-434-145-I907	FIELD JB/LIE/LIR,DRIVES TERMINATIONS	A
8	PE-V1-434-145-I908	DATASHEETS FOR INSTRUMENTS, JBs, etc.	A
9	PE-V1-434-145-I909	QUALITY PLANS (INSTRUMENTS, VMS, etc.)	A
10	PE-V1-434-145-I910	INSTRUMENT HOOK-UP DRAWING	A
11	PE-V1-434-145-I911	THERMOWELL SIZING CALCULATION	A
12	PE-V1-434-145-I913	CABLE SCHEDULE & INTERCONNECTION	A
13	PE-V1-434-145-I914	ANNUNCIATION & SOE LIST	A

NOTES:

ANY OTHER DOCUMENT DECIDED DURING DETAILED ENGINEERING SHALL BE PROVIDED BY BIDDER WITHOUT ANY COMMERCIAL/TECHNICAL IMPLICATION.

CONTRACTOR TO SUBMIT REUSABLE DATABASE FORMATS IN BHEL/CUSTOMER APPROVED FORMATS LIKE MS EXCEL, MS ACCESS OF DOCUMENTS LIKE INSTRUMENT SCHEDULE, I/O LIST, DRIVE LIST, FIELD JB TERMINATIONS, CABLE SCHEDULE & INTERCONNECTION, etc. SOFT COPY OF FORMATS SHALL BE PROVIDED TO SUCCESSFUL BIDDERS.

	SPECIFICATION FOR CONTROL & INSTRUMENTATION FOR AUX PACKAGES	SPECIFICATION NO.:	
		VOLUME	
		SUB SECTION	
		REV. NO.	DATE :
		SHEET	OF

GENERAL REQUIREMENT

1.0 Bidder shall provide complete and independent control & instrumentation system with all accessories, auxiliaries and associated equipments for the safe, efficient and reliable operation of auxiliary systems.

2.0 The quantity of instruments for auxiliary system shall be as per tender P & ID wherever provided of the respective system as a minimum, for bidding purpose. However, Bidder shall also include in his proposal all the instruments and devices that are needed for the completeness of the plant auxiliary system/ equipment supplied by the bidder, even if the same is not specifically appearing in the P & ID. During detail engineering if any additional instruments are required for safe & reliable operation of plant, bidder shall supply the same without any price implication.

3.0 Measuring instruments/equipment and subsystems offered by the bidder shall be from reputed experienced manufacturers of specified type and range of equipment, whose guaranteed and trouble free operation has been proven. Further all the instruments shall be of proven reliability, accuracy, and acceptable international standards and shall be subject to employer's approval. All instrumentation equipment and accessories under this specification shall be furnished as per technical specification, ranges, makes/ numbers as approved by the employer' during detail engineering.

4.0 The necessary root valves, impulse piping, drain cocks, gauge-zeroing cocks, valve manifold and all the other accessories required for mounting/ erection of these local instruments shall be furnished, even if not specifically asked for, on as required basis. The contacts of equipment mounted instruments; sensors, switches etc for external connection including spare contacts shall be wired out to suitably located junction boxes.

5.0 The customer specification attached as Specific Technical Requirement will supercede the Data sheets, if there is any mismatch.



**MEASURING INSTRUMENTS
(PRIMARY & SECONDARY)
&
SPECIFICATION FOR ELECTRONIC
TRANSMITTERS**

CLAUSE NO.	TECHNICAL REQUIREMENTS			
1.00.00	MEASURING INSTRUMENTS (PRIMARY AND SECONDARY)			
1.01.00	Measuring instruments/equipment and subsystems offered by the Bidder shall be from reputed experienced manufacturers of specified type and range of equipment, whose guaranteed and trouble free operation has been proven. Refer Sub-section Basic Design Criteria. Further, all instruments shall be of proven reliability, accuracy, and repeatability requiring a minimum of maintenance and shall comply with the acceptable international standards and shall be subject to Employer's approval.			
1.02.00	Every panel-mounted instrument requiring power supply shall be provided with easily replaceable glass cartridge fuses of suitable rating. Every instrument shall be provided with a grounding terminal and shall be suitably connected to the panel grounding bus.			
1.03.00	All transmitters, sensors, switches and gauges for parameters like pressure, temperature, level, flow etc. as required for the safe and efficient operation and maintenance as well as for operator and management information (including all computation) of equipment in the system under the scope of specification shall be provided on as required basis with in quoted lump sum price. The Contractor shall furnish all Instrumentation / Control equipment & accessories under this specification as per technical specification, ranges, makes & model as approved by the Employer during detailed engineering.			
1.04.00	The necessary root valves, impulse piping, drain cocks, gauge-zeroing cocks, valve manifolds and all the other accessories required for mounting/erection of these local instruments shall be furnished, even if not specifically asked for, on as required basis. The contacts of equipment mounted instruments, sensors, switches etc. for external connection including spare contacts shall be wired out in flexible/rigid conduits, independently to suitably located common junction boxes. The proposal shall include the necessary cables, flexible conduits, junction boxes and accessories for the above purpose. Double root valves shall be provided for all pressure tapping where the pressure exceeds 40 Kg./sq.cm.			
1.05.00	All instruments envisaged for sea water applications, shall be provided with wetted parts made of Monel/ Hastelloy C or any other material (if provenness experience of the proposed material for such applications is established by contractor). For Chlorine application: Instruments shall be provided with wetted parts (e.g. diaphragm seal, etc.) made of Hastelloy C. Also, filled liquid shall be Fluorolube oil/ Inert Hydrocarbon / CTFE etc., for these applications. For applications of FECL3 solution: Instruments shall be provided with wetted parts (e.g. diaphragm seal, etc.) made of Tantalum.			
1.06.00	For coastal areas, all instruments shall be provided with durable epoxy coating for housings and all exposed surfaces of the instruments.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 1 OF 46

Page 464 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS		
2.00.00	SPECIFICATION FOR ELECTRONIC TRANSMITTERS		
2.01.00	SPECIFICATION FOR ELECTRONIC TRANSMITTER FOR PRESSURE, DIFF PRESS AND DP BASED FLOW / LEVEL MEASUREMENTS		
	Sl.No.	Features	Essential/Minimum Requirements
	1.	Type of Transmitter	Microprocessor based 2 wire type (loop powered), Hart protocol compatible.
	2.	Accuracy	± 0.1% of calibrated span (minimum)
	3.	Output signal range	4-20 mA DC (Analog) along with superimposed digital signal (based on HART protocol)
	4.	Turn down ratio (minimum)	10:1 for vacuum/very low pressure applications (i.e. pressure <= 200 mmWC) 5:1 for very high pressure application (i.e. pressure >= 200 Kg/cm2) 30:1 for other applications
	5.	Stability	± 0.1% of calibrated span for six months for Ranges up to and including 70 Kg/cm² ± 0.25% of calibrated span for six months for Ranges more than 70 Kg/cm²
	6.	Zero and span drift	+/- 0.015% per deg.C at max span +/-0.11% per deg.C at min. Span
	7.	Load impedance	500 ohm (minimum)
	8.	Housing	Weather proof as per IP-65, metallic housing with durable corrosion resistant coating
	9.	Over Pressure	150% of max. Operating pressure
	10.	Connection (Electrical)	Plug and socket type
	11.	Process connection	1/2 inch NPT (F)
	12.	Span and Zero	Continuous, tamper proof, Remote as well as manual adjustability from instrument with zero suppression and elevation facility.
	13.	Accessories	-Diaphragm seal, pulsation dampeners, syphon etc. as required by service and operating condition. -2 valve manifold for absolute & Gauge pressure transmitters, 3-valve and 5 valve manifold for DP/Level/Flow applications. The valve manifold shall be non integral type (except Fuel Oil area).
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)
			PAGE 2 OF 46

CLAUSE NO.	TECHNICAL REQUIREMENTS															
2.02.00	-For hazardous area, explosions proof enclosure as described in NEC article 500 Mounting: 2 inch pipe mounting. 14. Diagnostics & displaySelf-Indicating feature and digital display on transmitter 15. Power supply24V DC ± 10%. 16. Adjustment/calibration/maintenanceFrom hand held HART calibrator/ centralized PC based system (as applicable). Notes - For primary air/ secondary air/flue gas applications, DP type transmitters shall be provided for pressure measurement. - LVDT type is not acceptable. - Where the process fluids are corrosive, viscous, solid bearing or slurry type, diaphragm seals shall be provided. Parts below the diaphragm shall be removable for cleaning. The entire volume above the diaphragm shall be completely filled with an inert liquid suitable for the application.															
	GUIDED WAVE RADAR TYPE LEVEL TRANSMITTER <table><tr><td>Type</td><td>Microprocessor based 2 wire type (loop powered), HART protocol compatible Guided wave radar transmitter.</td></tr><tr><td>Principle</td><td>TDR (Time domain reflectometry)</td></tr><tr><td>Probe Type & Material</td><td>(i) Coaxial probe of SS316/316L. If required, probe shall be suitable for overfill prevention. (ii) Rod probe, cable probe of SS316/SS316L can be used for applications wherever coaxial probe is not suitable.</td></tr><tr><td>Output signal</td><td>4-20 mA DC along with superimposed digital signal (based on HART protocol), suitable for over fill prevention.</td></tr><tr><td>Accuracy</td><td>+/- 0.5% of calibrated span or minimum 5mm.</td></tr><tr><td>Power supply</td><td>24 VDC +/- 10%.</td></tr><tr><td>Housing</td><td>Weather proof as per IP-65, metallic housing with durable corrosion resistance coating.</td></tr></table>			Type	Microprocessor based 2 wire type (loop powered), HART protocol compatible Guided wave radar transmitter.	Principle	TDR (Time domain reflectometry)	Probe Type & Material	(i) Coaxial probe of SS316/316L. If required, probe shall be suitable for overfill prevention. (ii) Rod probe, cable probe of SS316/SS316L can be used for applications wherever coaxial probe is not suitable.	Output signal	4-20 mA DC along with superimposed digital signal (based on HART protocol), suitable for over fill prevention.	Accuracy	+/- 0.5% of calibrated span or minimum 5mm.	Power supply	24 VDC +/- 10%.	Housing
Type	Microprocessor based 2 wire type (loop powered), HART protocol compatible Guided wave radar transmitter.															
Principle	TDR (Time domain reflectometry)															
Probe Type & Material	(i) Coaxial probe of SS316/316L. If required, probe shall be suitable for overfill prevention. (ii) Rod probe, cable probe of SS316/SS316L can be used for applications wherever coaxial probe is not suitable.															
Output signal	4-20 mA DC along with superimposed digital signal (based on HART protocol), suitable for over fill prevention.															
Accuracy	+/- 0.5% of calibrated span or minimum 5mm.															
Power supply	24 VDC +/- 10%.															
Housing	Weather proof as per IP-65, metallic housing with durable corrosion resistance coating.															
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 3 OF 46												

Page 466 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS		एनटीपीसी NTPC														
2.03.00	<table><tr><td>Adjustment/ calibration</td><td>Using hand held HART calibrator/ centralized PC based system (as applicable).</td></tr><tr><td>Zero & span adjustment</td><td>Continuous, temper proof, remote as well as manual adjustability from instrument. It should be possible to calibrate the instrument without any level in the tank/sump etc.</td></tr><tr><td>Display</td><td>Integral digital display.</td></tr><tr><td>Load Impedance</td><td>500 ohms (minimum).</td></tr><tr><td>Electromagnetic compatibility</td><td>Shall meet EN 61326-1 (1997) and AmdtA1, class A equipment/EN 50081-2 & EN 5008 1-2 & EN 50082-2</td></tr><tr><td>Mounting</td><td>(i) External cage shall be provided where ever side mounting is required. External cage and other mounting accessories to be provided by the contractor. (ii) Where ever top mounting is required, all mounting accessories, stilling well (as required) etc., shall be provided by the contractor. (iii) All weather canopy shall be provided for protection from direct sunlight and direct rain for open locations.</td></tr></table>		Adjustment/ calibration	Using hand held HART calibrator/ centralized PC based system (as applicable).	Zero & span adjustment	Continuous, temper proof, remote as well as manual adjustability from instrument. It should be possible to calibrate the instrument without any level in the tank/sump etc.	Display	Integral digital display.	Load Impedance	500 ohms (minimum).	Electromagnetic compatibility	Shall meet EN 61326-1 (1997) and AmdtA1, class A equipment/EN 50081-2 & EN 5008 1-2 & EN 50082-2	Mounting	(i) External cage shall be provided where ever side mounting is required. External cage and other mounting accessories to be provided by the contractor. (ii) Where ever top mounting is required, all mounting accessories, stilling well (as required) etc., shall be provided by the contractor. (iii) All weather canopy shall be provided for protection from direct sunlight and direct rain for open locations.	Note: Four wire type transmitters can also be provided for applications where 2- wire transmitter has some technical limitations, subject to employer's approval during detailed engineering stage. However, in such cases isolated 4-20 mA DC (analog) output shall be provided. Power supply required for such transmitters shall be 240V AC / 24V DC.		
	Adjustment/ calibration	Using hand held HART calibrator/ centralized PC based system (as applicable).															
	Zero & span adjustment	Continuous, temper proof, remote as well as manual adjustability from instrument. It should be possible to calibrate the instrument without any level in the tank/sump etc.															
	Display	Integral digital display.															
	Load Impedance	500 ohms (minimum).															
	Electromagnetic compatibility	Shall meet EN 61326-1 (1997) and AmdtA1, class A equipment/EN 50081-2 & EN 5008 1-2 & EN 50082-2															
	Mounting	(i) External cage shall be provided where ever side mounting is required. External cage and other mounting accessories to be provided by the contractor. (ii) Where ever top mounting is required, all mounting accessories, stilling well (as required) etc., shall be provided by the contractor. (iii) All weather canopy shall be provided for protection from direct sunlight and direct rain for open locations.															
	Ultrasonic Type level Transmitter																
	<table><tr><th>S.No.</th><th>Features</th><th>Essential/Minimum requirement</th></tr><tr><td>1.</td><td>Type of Transmitter</td><td>Non-contact Microprocessor based 2 wire type (loop powered), HART protocol compatible Ultrasonic transmitter.</td></tr><tr><td>2.</td><td>Output signal</td><td>4-20 mA DC (Analog) along with superimposed digital signal (based on HART protocol).</td></tr></table>		S.No.	Features	Essential/Minimum requirement	1.	Type of Transmitter	Non-contact Microprocessor based 2 wire type (loop powered), HART protocol compatible Ultrasonic transmitter.	2.	Output signal	4-20 mA DC (Analog) along with superimposed digital signal (based on HART protocol).						
	S.No.	Features	Essential/Minimum requirement														
1.	Type of Transmitter	Non-contact Microprocessor based 2 wire type (loop powered), HART protocol compatible Ultrasonic transmitter.															
2.	Output signal	4-20 mA DC (Analog) along with superimposed digital signal (based on HART protocol).															

EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 4 OF 46
---	---	---	-----------------

Page 467 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	3.	Accuracy	+/- 0.5% of calibrated span or minimum 5mm.	
	4.	Power supply	24 V DC +/- 10%.	
	5.	Temperature compensation	To be provided within transducer.	
	6.	Housing	Weather proof as per IP-65, metallic housing with durable corrosion resistance coating.	
	7.	Adjustment/calibration/ maintenance	Using hand held HART calibrator/ centralized PC based system (as applicable).	
	8.	Zero and Span adjustment	Continuous, tamper proof, remote as well as manual adjustability from instrument. It should be possible to calibrate the instrument without any level in the tank/sump etc.	
	9.	Sensor Material	Corrosion resistant material to suit individual application requirement.	
	10.	False signal tolerance	Transmitter shall be capable of ignoring false echoes from internal tank/sumps obstructions such as pipes, heating coils or agitator blades. Also transmitter shall have adjustable damping circuitry.	
	11.	Range	Range of transmitter shall be capable of covering the complete level span of tank taking care of blocking distance, frequency attenuation due to surface, obstructions, vapors etc.	
	12.	Display	Integral digital display	
	13.	Diagnostics	Loss of echo alarm etc.	
	14.	Load Impedance	500 ohms (minimum).	
15.	Electrical Connection	Plug and socket		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 5 OF 46

Page 468 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
2.04.00	16.	Accessories	- All weather canopy shall be provided for protection from direct sunlight and direct rain for open locations. - All mounting accessories required for erection and commissioning shall be provided. - For hazardous area, explosion proof enclosure as described in NEC article 500	
	Note: - Contractor can also provide Radar type transmitter as per above specification in place of ultrasonic transmitter subject to approval by Employer during detailed Engineering. Sonic frequency based transmitters can also be provided under "ultrasonic transmitters" category for fly ash silo level. - Four wire type transmitters can also be provided for applications where 2- wire transmitter has some technical limitations, subject to employer's approval during detailed engineering stage. However, in such cases isolated 4-20 mA DC (analog) output shall be provided. Power supply required for such transmitters shall be 240V AC / 24V DC. - For applications where transmitter location is not accessible, the transmitter shall have separate sensor unit and electronic unit for such applications. It shall be possible to mount the electronic unit at accessible location. HART Hand Held calibrator Hand held calibrator shall be provided for adjustment/calibration/maintenance of the HART compatible transmitters. The hand held calibrator shall be suitable for all types of transmitters supplied in the package. If one type of hand held type calibrator is not suitable for communicating with all types of transmitters then separate hand held calibrator will be provided for that specific type of transmitter.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)
PAGE 6 OF 46		Page 469 of 1005		

CLAUSE NO.	TECHNICAL REQUIREMENTS																																					
3.00.00 3.01.00 3.02.00	Temperature Elements and accessories Thermocouple <table border="1"> <thead> <tr> <th>Sr. No.</th><th>Features</th><th>Essential/Minimum Requirements</th></tr> </thead> <tbody> <tr> <td>1</td><td>Type of Thermocouple.</td><td>: 16 AWG wire of Chromel-Alumel (Type K) or 24 AWG wire Pt-Rhodium Pt (Type R) depending on operating temperature Range (ungrounded separate junction type).</td></tr> <tr> <td>2</td><td>No. of element</td><td>: Duplex</td></tr> <tr> <td>3</td><td>Housing/Head</td><td>: IP-65/Diecast Aluminium. Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable). Plug in connectors are to be provided for external signal cable connection. TE terminal head shall be spring loaded for positive contacts with the thermo well.</td></tr> <tr> <td>4</td><td>Insulation and Sheathing of Thermocouple</td><td>: Swaged type mineral (magnesium oxide) insulation and SS316 sheath.</td></tr> <tr> <td>5</td><td>Calibration and accuracy</td><td>: As per IEC-584/ ANSI-MC-96.1 (special limits of errors/ class1) for T/C.</td></tr> <tr> <td>6</td><td>Accessories</td><td>: Thermo well and associated fittings</td></tr> <tr> <td>7</td><td>Standard</td><td>: IEC-584/ ANSI MC 96.1 for Thermocouple and ASME PTC-19.3 for Thermo-well</td></tr> </tbody> </table> Resistance Temperature Detector (RTD) <table border="1"> <thead> <tr> <th>Sr. No.</th><th>Features</th><th>Essential/Minimum Requirements</th></tr> </thead> <tbody> <tr> <td>1</td><td>Type of RTD.</td><td>: Four wire, Pt-100 (100 Ohms resistance at zero degree Centigrade).</td></tr> <tr> <td>2</td><td>No. of element</td><td>: Duplex</td></tr> <tr> <td>3</td><td>Housing/Head</td><td>: IP-65/Diecast Aluminium. Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable). Plug in connectors are to be</td></tr> </tbody> </table>	Sr. No.	Features	Essential/Minimum Requirements	1	Type of Thermocouple.	: 16 AWG wire of Chromel-Alumel (Type K) or 24 AWG wire Pt-Rhodium Pt (Type R) depending on operating temperature Range (ungrounded separate junction type).	2	No. of element	: Duplex	3	Housing/Head	: IP-65/Diecast Aluminium. Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable). Plug in connectors are to be provided for external signal cable connection. TE terminal head shall be spring loaded for positive contacts with the thermo well.	4	Insulation and Sheathing of Thermocouple	: Swaged type mineral (magnesium oxide) insulation and SS316 sheath.	5	Calibration and accuracy	: As per IEC-584/ ANSI-MC-96.1 (special limits of errors/ class1) for T/C.	6	Accessories	: Thermo well and associated fittings	7	Standard	: IEC-584/ ANSI MC 96.1 for Thermocouple and ASME PTC-19.3 for Thermo-well	Sr. No.	Features	Essential/Minimum Requirements	1	Type of RTD.	: Four wire, Pt-100 (100 Ohms resistance at zero degree Centigrade).	2	No. of element	: Duplex	3	Housing/Head	: IP-65/Diecast Aluminium. Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable). Plug in connectors are to be	
Sr. No.	Features	Essential/Minimum Requirements																																				
1	Type of Thermocouple.	: 16 AWG wire of Chromel-Alumel (Type K) or 24 AWG wire Pt-Rhodium Pt (Type R) depending on operating temperature Range (ungrounded separate junction type).																																				
2	No. of element	: Duplex																																				
3	Housing/Head	: IP-65/Diecast Aluminium. Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable). Plug in connectors are to be provided for external signal cable connection. TE terminal head shall be spring loaded for positive contacts with the thermo well.																																				
4	Insulation and Sheathing of Thermocouple	: Swaged type mineral (magnesium oxide) insulation and SS316 sheath.																																				
5	Calibration and accuracy	: As per IEC-584/ ANSI-MC-96.1 (special limits of errors/ class1) for T/C.																																				
6	Accessories	: Thermo well and associated fittings																																				
7	Standard	: IEC-584/ ANSI MC 96.1 for Thermocouple and ASME PTC-19.3 for Thermo-well																																				
Sr. No.	Features	Essential/Minimum Requirements																																				
1	Type of RTD.	: Four wire, Pt-100 (100 Ohms resistance at zero degree Centigrade).																																				
2	No. of element	: Duplex																																				
3	Housing/Head	: IP-65/Diecast Aluminium. Head of TE to be provided with sufficient space and arrangement to mount head mounted temperature transmitter (as applicable). Plug in connectors are to be																																				
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY) PAGE 7 OF 46																																				

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC
	provided for external signal cable connection. TE terminal head shall be spring loaded for positive contacts with the thermo well 4 Insulation and sheathing of RTD : Mineral (magnesium oxide) insulation and SS316 sheath, 5 Calibration and accuracy : As per IEC-751/ DIN-43760 Class-A for RTD 6 Accessories : Thermo well and associated fittings 7 Standard : IEC-751/ DIN-43760 for RTD and ASME PTC-19.3 for Thermo-well. NOTES : 1) The specifications for RTDs of winding/ bearings of motor/pump, can be as per their manufacturer standards. The manufacturer shall submit the adequate supporting documents for establishing their standard practice. However the type of RTD shall be Pt100. 2) The specifications of temp elements for air conditioning & ventilation system / process can be as per system manufacturer's standards. The manufacturer shall submit the adequate supporting documents for establishing their standard practice.	
3.03.00	Metal Temperature Thermocouples Measuring Medium Metal Temperature Material of Thermocouple. Chromel Alumel Type K Type of Thermocouple Duplex with ungrounded separate hot junctions Insulation Mineral Insulation (Magnesium Oxide). Thermocouple wire gauge 16 AWG Protective sheath SS 321 Protective sheath dia 8 mm OD Calibration & accuracy As per IEC-584/ ANSI-MC-96.1 (special limits of error) for T/C Mounting accessories 1/2" BSP SS sliding end connector, weld pad, clamps of heat resistant steel SS310. Adjustable gland fitting for connection at the junction box end as per manufacturer's standard. Cold end sealing SS pot seal with colour coded PTFE Insulated flexible tails. Sealing compound- Epoxy resin. Length of PTFE insulated flying leads shall be minimum 750 mm.	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)
		PAGE 8 OF 46

CLAUSE NO.	TECHNICAL REQUIREMENTS	
3.04.00 3.05.00 3.06.0	Minimum bending radius 30 mm Length of T/C On as required basis considering location of measurement point and the JB/TTJB location. Notes : 1) The specification for thermocouples of bearings metal temp measurements can be as per their manufacturer standards. The manufacturer shall submit the adequate supporting documents for establishing their standard practice. However type of thermocouples shall be K-type. 2) For boiler metal temperature applications, considering the location of installations and response time, manufacturer's standard and proven specification for metal temperature measurement can also be accepted subject to employer's approval. The manufacturer shall submit adequate supporting documents for establishing their standard and proven practice. Thermo well (for all process temp. elements) (a) Shall be one piece solid bored type of 316 SS of step-less tapered design. (As per ASME PTC 19.3, 1974) (b) For Mill classifier outlet long life solid sintered tungsten carbide material of high abrasion resistance shall be provided. (c) For Air & Flue gas 316 SS protecting tube with welded cap. (However contractor shall provide better material for Flue gas service if required based on the specified boiler design parameters). (d) For furnace zone, impervious ceramic protecting tube of suitable material along with Incoloy supporting tubes and adjustable flanges. Not Used TEMPERATURE TRANSMITTER (TT) Following types of 2-wire (loop powered) temperature transmitter (directly powered from 4-20mA input cards of DDCMIS/PLC) shall be provided. The temperature transmitter shall be fully compatible with thermocouples and RTDs being provided by the contractor. Temperature compensation of the thermocouples shall be performed in the temperature transmitter itself. a. Single Input Head mounted Temperature Transmitter These shall be suitable for mounting in the head of temperature element itself. Temperature transmitter and associated temperature element shall be factory fitted. b. Single Input DIN-rail mounted Temperature Transmitter These shall be suitable for mounting on DIN-rails in JB's. The specifications of the JB's shall be same as indicated in Subsection INST CABLE with additional DIN-rails and IP 65 Protection class. This temperature transmitter shall be the ones which are	
	EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW) TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2 SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY) PAGE 9 OF 46	Page 472 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS			एनटीपीसी NTPC																																				
	especially designed for DIN-rail mounting with IP 20 protection class. These shall have terminals for input/output provided on front side when mounted on DIN-rail. Head mounted temperature transmitter with clamps to make it suitable for DIN-rail mounting shall not be acceptable under this category. c. Dual-input Temperature Transmitter With integral Indicator: These shall be suitable for mounting on pipes/ support. Both elements of the duplex thermocouple/ RTD shall be wired to a single transmitter. Integral indicator shall be provided with these transmitters. These transmitters shall have bump less change over facility to second sensor in case first sensor fails .This change-over is to be alarmed. Protection class shall be IP65 minimum. d. Common requirements for each of the above type of temperature transmitters. <table><tr><td>Output</td><td>:</td><td colspan="2">2-wire (power supply from input card of Control System) with 4-20mA output with superimposed HART protocol signal.</td></tr><tr><td>Input</td><td>:</td><td colspan="2">Same transmitter shall be capable to handle Pt-100 RTD, Thermocouples –K & R types (input type to be selectable at site through HART terminal).</td></tr><tr><td>Isolation</td><td>:</td><td colspan="2">Min. 500 V AC.</td></tr><tr><td>EMC compatibility</td><td>:</td><td colspan="2">As per EN 61326.</td></tr><tr><td>Operating ambient temperature</td><td>:</td><td colspan="2">0 to 85 deg C (without indicator). 0 to 70 deg C (with indicator).</td></tr><tr><td>Power supply</td><td>:</td><td colspan="2">24V DC +/- 10%.</td></tr><tr><td>Accessories</td><td>:</td><td colspan="2">Mounting arrangements including clamps etc.</td></tr><tr><td>Composite Accuracy (Refer note 2)</td><td>(i)</td><td colspan="2">For head mounted and DIN-rail mounted types: RTD = <0.4% of 0-250 deg C span T/C-K type = <0.4% of 0-600 deg C span T/C-R type = <0.4% of 0-1000 deg C span CJC accuracy (for thermocouples) shall be =< 1 deg C</td></tr><tr><td></td><td>(ii)</td><td colspan="2">For dual-input type: RTD = <0.25% of 0-250 deg C span T/C-K type = <0.2% of 0-600 deg C span CJC accuracy (for thermocouples) shall be =< 1 deg C</td></tr></table> e. Field bus compatible temperature transmitters Temperature transmitters of this category shall be field mounting type & shall be capable of withstanding operating ambient temperature upto 85 deg C. These modules shall be connected to DDCMIS through field bus such as Profibus, Foundation Field bus etc directly from the transmitter. Maximum Number of inputs per such temperature transmitter shall be eight. These shall be mounted in cabinets/enclosures/JBs in non-AC areas.				Output	:	2-wire (power supply from input card of Control System) with 4-20mA output with superimposed HART protocol signal.		Input	:	Same transmitter shall be capable to handle Pt-100 RTD, Thermocouples –K & R types (input type to be selectable at site through HART terminal).		Isolation	:	Min. 500 V AC.		EMC compatibility	:	As per EN 61326.		Operating ambient temperature	:	0 to 85 deg C (without indicator). 0 to 70 deg C (with indicator).		Power supply	:	24V DC +/- 10%.		Accessories	:	Mounting arrangements including clamps etc.		Composite Accuracy (Refer note 2)	(i)	For head mounted and DIN-rail mounted types: RTD = <0.4% of 0-250 deg C span T/C-K type = <0.4% of 0-600 deg C span T/C-R type = <0.4% of 0-1000 deg C span CJC accuracy (for thermocouples) shall be =< 1 deg C			(ii)	For dual-input type: RTD = <0.25% of 0-250 deg C span T/C-K type = <0.2% of 0-600 deg C span CJC accuracy (for thermocouples) shall be =< 1 deg C	
Output	:	2-wire (power supply from input card of Control System) with 4-20mA output with superimposed HART protocol signal.																																						
Input	:	Same transmitter shall be capable to handle Pt-100 RTD, Thermocouples –K & R types (input type to be selectable at site through HART terminal).																																						
Isolation	:	Min. 500 V AC.																																						
EMC compatibility	:	As per EN 61326.																																						
Operating ambient temperature	:	0 to 85 deg C (without indicator). 0 to 70 deg C (with indicator).																																						
Power supply	:	24V DC +/- 10%.																																						
Accessories	:	Mounting arrangements including clamps etc.																																						
Composite Accuracy (Refer note 2)	(i)	For head mounted and DIN-rail mounted types: RTD = <0.4% of 0-250 deg C span T/C-K type = <0.4% of 0-600 deg C span T/C-R type = <0.4% of 0-1000 deg C span CJC accuracy (for thermocouples) shall be =< 1 deg C																																						
	(ii)	For dual-input type: RTD = <0.25% of 0-250 deg C span T/C-K type = <0.2% of 0-600 deg C span CJC accuracy (for thermocouples) shall be =< 1 deg C																																						
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 10 OF 46																																				

Page 473 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
	As an alternate, these signals from temperature transmitters can be connected to DDCMIS through standard remote I/O modules of the DCS, in which case, the temperature transmitter signals will be acquired through 4-20mA input modules in the remote I/O cabinet for connecting to DDCMIS through remote I/O bus. Air conditioned panel shall be provided for remote I/O. Notes (Common for a) to d) above):- 1. In case of failure (open or burn-out) of RTD/thermocouple, temp. Transmitter shall provide low temperature output. 2. Composite Accuracy is to be calculated as summation of all applicable accuracies of temp transmitter, for converting sensor input to output in 4-20 mA (e.g., basic accuracy, digital accuracy, D/A accuracy, etc.) and temperature effect on these accuracies at ambient temperature of 50 deg C, based on the figure/ formula given in the standard product catalogue for span as specified above for various types of Temperature Elements specified. All such accuracy/ temp effect figures in catalogue shall be first converted to deg C, and then percentage of this converted accuracy in specified span shall be calculated to compare with the specified composite accuracy figures. All temperature transmitters are to be interchangeable (i.e. can be used for either RTD or thermocouple) and composite accuracy shall be met for each type of input specified in (i) & (ii).			
4.00.00	ELECTRICAL METERING INSTRUMENTS			
	Electrical metering instruments shall be furnished in accordance with the following general specifications. However, the scope shall be governed by the Contract quantity given in appendix-1 to part-A. Application standard for electrical metering instruments shall be as per IS: 1248- 2003 (Revised). The size of each instrument shall be as approved by Employer during detailed engg. All metering instruments shall be flush panel mounting type.			
4.01.00	(a) Frequency meters for Synchronization purposes: Accuracy: $\pm 1.5\%$ of full scale. (b) Synchroscope: Accuracy class: 0.5 or better. (c) Voltmeters: Accuracy: $\pm 2.0\%$ of full scale or better.			
4.02.00	Synchronizing Relays Synchronizing check relay with necessary ancillary equipment shall be provided which shall permit breakers to close after checking the requirements of synchronizing of incoming and running supply. The phase angle setting shall not exceed 10 Degree and this angle shall be adjustable and shall take the account the circuit breaker closing period. This relay shall have a response time of less than 200 milliseconds when the two system conditions are met within preset limits and with the timer disconnected. The relay shall have a frequency difference setting not exceeding 0.45% at rated value and at the minimum time setting. The relay shall have a continuously adjustable time setting range of 0.5-3 secs. Additionally, a guard relay shall be provided to prevent the closing attempt by means of synchronizing check relay when control switch is kept in closed position long before the two systems are in synchronism. The Control Voltage shall be 220V DC and PT input Voltage shall be 110 V AC.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 11 OF 46

8.00.00

E-P Converter

E-P converters and associated accessories shall be furnished in accordance with the specifications given below :

A. Fail Freeze Type E/P convertes

1	Air supply Pressure	:	2 kg/sq. cm.
2	Input signal	:	4-20mA DC
3	Output signal	:	0.2 to 1.0 kg/sq. cm
4	Linearity	:	0.5% of span or better.
5	Span/Zero Adjustment	:	To be provided
6	Hysteresis	:	0.5% of span or better.
7	Fail Freeze Feature	:	Stay put at last position on failure of 4 –20mA signal.
8	Allowable drift rate	:	Maximum 2% set point/ hour.
9	Ambient Temperature Effect	:	less than 0.02% of span per deg C between -
10	Mounting	:	Surface/Pipe/Bracket Mounting.
11	Protection class	:	IP 65.
12	Connection Port Sizes	:	¼ inch NPT (F)
13	Electrical Cable Entry	:	½ inch NPT
14	Output Pressure Gauge	:	1/4 inch NPT connection, 2 inch dial.
15	Accessories	:	All accessories like mounting brackets, fittings etc. required for installation is to be supplied.

CLAUSE NO.	TECHNICAL REQUIREMENTS			
9.00.00 10.00.00 10.01.00 10.01.01 10.01.02 10.01.03 10.01.04	B. FailL Safe type E/P converters			
	1	Air supply Pressure	:	2 kg/sq. cm.
	2	Input signal	:	4-20mA DC
	3	Output signal	:	0.2 to 1.0 kg/sq. cm
	4	Linearity	:	0.5% of span or better.
	5	Span/Zero Adjustment	:	To be provided.
	6	Hysteresis	:	0.5% of span or better.
	7	Fail Safe Feature	:	Output shall drive to minimum on failure of either 4-20mA signal or air supply.
	8	Mounting	:	Surface/Pipe/Bracket Mounting.
	9	Ambient Temperature Effect	:	less than 0.02% of span per deg C between -20 to +60 deg C.
	10	Protection class	:	IP 65.
	11	Connection Port Sizes	:	¼ inch NPT (F)
	12	Electrical Cable Entry	:	½ inch NPT
	13	Output Pressure Gauge	:	1/4 inch NPT connection, 2 inch dial.
	14	Accessories	:	All accessories like mounting brackets, fittings etc. required for installation is to be supplied.
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)
				PAGE 24 OF 46
Page 476 of 1005				

CLAUSE NO.	TECHNICAL REQUIREMENTS		एनटीपीसी NTPC																												
13.04.00	ROTAMETERS <table><thead><tr><th>Sr. No.</th><th>Features</th><th>Essential / minimum requirements</th></tr></thead><tbody><tr><td>1.</td><td>Type</td><td>Variable Area Metal Tube</td></tr><tr><td>2.</td><td>Fluid media</td><td>Water/oil</td></tr><tr><td>3.</td><td>Tube body</td><td>SS316</td></tr><tr><td>4.</td><td>Material of float</td><td>316 SS</td></tr><tr><td>5.</td><td>Indicator</td><td>Linear scale</td></tr><tr><td>6.</td><td>Accessories</td><td>Flange, orifice in case of bypass Rota meter (for line size above 100 mm)</td></tr><tr><td>7.</td><td>Housing protection class</td><td>IP-55</td></tr><tr><td>8.</td><td>Accuracy</td><td>± 2% of measured value.</td></tr></tbody></table>				Sr. No.	Features	Essential / minimum requirements	1.	Type	Variable Area Metal Tube	2.	Fluid media	Water/oil	3.	Tube body	SS316	4.	Material of float	316 SS	5.	Indicator	Linear scale	6.	Accessories	Flange, orifice in case of bypass Rota meter (for line size above 100 mm)	7.	Housing protection class	IP-55	8.	Accuracy	± 2% of measured value.
Sr. No.	Features	Essential / minimum requirements																													
1.	Type	Variable Area Metal Tube																													
2.	Fluid media	Water/oil																													
3.	Tube body	SS316																													
4.	Material of float	316 SS																													
5.	Indicator	Linear scale																													
6.	Accessories	Flange, orifice in case of bypass Rota meter (for line size above 100 mm)																													
7.	Housing protection class	IP-55																													
8.	Accuracy	± 2% of measured value.																													
14.00.00	POSITIVE DISPLACEMENT TYPE FLOW TRANSMITTERS The Bidder shall provide positive displacement type flow transmitters for fuel oil flow measurement, suitable for the fuel oil being used for the project, i.e., keeping in view the pressure, temperature and viscosity of the fuel oil. The meter shall be a volumetric meter type consisting of two meshing oval wheels driven by the fluid. Each revolution of the oval wheels shall displace a precisely known volume of the fluid from inlet to outlet. The housing/measuring chamber and oval wheels shall be of 316 SS.																														
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 37 OF 46																											

Page 477 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS			
16.00.00	NOT USED			
17.00.00	SOLENOID VALVES Solenoid valves shall fulfil the following requirements: a. Type 2/3/4 way SS 316/Forged Brass (depending on the application subject to Employer's approval during detailed Engg.) b. Power supply : 24 V DC $\pm$ 10%. c. Plug and socket electrical connection. d. Insulation : Class 'H'			
18.00.00	REVERSE ROTATION INDICATOR (RRI) Reverse rotation indicator comprising of proximity sensors, processing electronics with output of 4-20mA (corresponding to speed) interconnecting cables, speed display in rpm,			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 39 OF 46

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
	normal, reverse indication and required channel alarm contact shall be provided. The contact rating shall be 60VDC, 6VA (or more if required by Control system). The exact details of the RRI shall be strictly as approved by Employer during detailed engineering. The power supply of RRI is to be arranged by the Bidder			
19.00.00	WATER SYSTEM RELATED SPECIAL INSTRUMENTS (DM PLANT, CPU PLANT, PT PLANT, ETC)			
19.01.00	ANALYSER INSTRUMENTS: For Technical specification of Cation/Specific Conductivity, pH, Sodium, Silica, Turbidity, Total Dissolved Solids (TDS) and Concentration analysers, please refer Specification of Analysers, Part-B, Sub-section IIIC-13, SWAS chapter of this specification.			
19.02.00	Residual Chlorine Analyser a An automatic chlorine residual analyser of amperometric type shall be provided alongwith the chlorinating plant for monitoring the residual chlorine content of cooling water. The analyser shall be suitable for accurate residual measurement in open/closed systems. The measurement accuracy shall not be affected by presence of treatment chemicals as chromates, phosphates, de-former highly polluted water, change in temperature etc. b The analyser shall comply with the following specification requirements, as a minimum (i) Indicator : Provision of LC display in the panel of analyser. (ii) Range : 0 to 20.0 mg/L (ppm) (iii) Accuracy : 2% or better (iv) Sensitivity : 0.01 mg/l (v) Output signal : 4-20mA DC isolated output, (vi) Alarm annunciation : High and low alarms to be provided on panel and shall be field adjustable. (vii) Calibration : Zero and span adjustment facility to be provided. Final calibration adjustments of the analyser to be done at site and duly verified by titration. Temperature compensation range 0 to 50degC. (x) Mounting : The analyser shall be suitable for field mounting conform to protection class IP-55. (xii) Electrodes : Platinum/Gold and copper electrodes shall be provided with cell cleaning system. (c) Circulating water as sample to residual chlorine analyser shall be taken from hot circulating water pipe work before entry to cooling towers. Exact location and layout of sampling arrangement shall be finalised during detailed engg. stage. Bidder shall provide necessary pumping system (with 100% standby) for meeting the analyser requirements, if needed. All the drains shall be terminated up to the nearest plant drainage system.			
19.03.00	All the outdoor field instruments such as analysers/transmitters/meters etc. shall be provided with suitable Free standing cabinet(s)/panel/rack so that the equipments are protected against rain/ sunlight etc.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE – I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 40 OF 46 Page 479 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC																					
19.04.00	Parshall Flume The Bidder shall provide all the control and Instrument devices including primary sensors, transmitters, flow indicator cum integrator / totaliser and shall include all required accessories for the flow measurement of raw water through the clarifier. The system shall be of reputed make and acceptable to the owner. Level measurement shall be based on ultrasonic/radon technology. The flow compensation is to be implemented in the transmitter itself. The transmitter shall provide 4-20 mA DC in direct proportion to flow and shall be able to drive a load impedance of 500 ohms minimum Accuracy shall be +/- 1 % or better. All the mounting hardware and accessories required for erection and commissioning of the same are to be provided by the contractor. Mounting fittings material shall be SS316. All weather canopy is to be provided for electronics/sensor to protect the same from rain/sunlight etc. The Type makes and models no. shall be subject to Owner's approval.																						
19.05.00	Electronic Flow-Meter The electronic flow meter shall include flow sensor and flow indicator cum integrator / totaliser and shall include all required accessories for satisfactory operation. The flow meter shall be based on full bore electromagnetic principle and shall be electronic type of proven design, make and model acceptable to the owner. The Bidder shall submit all necessary technical literature and details of selection criteria of the instrument offered to substantiate the model selected. The Bidder shall also furnish list of similar installation along with feed back on satisfactory performance of the instruments. The flow meter shall meet or exceed the following requirement : <table border="0"> <tr> <td>(a) Output</td><td>:</td><td>4-20 mA DC Isolated output</td></tr> <tr> <td>(b) Accuracy</td><td>:</td><td>± 0.5% of calibrated span or better *</td></tr> <tr> <td>(c) Repeatability</td><td>:</td><td>± 0.2% of calibrated span or better</td></tr> <tr> <td>(d) Power Supply</td><td>:</td><td>240V AC ± 10%, 50 HZ ± 5%/ 24 V DC, to be arranged by the contractor.</td></tr> <tr> <td>(f) Protection class</td><td>:</td><td>IP-55</td></tr> <tr> <td>(e) Flow tube</td><td>:</td><td>SS304</td></tr> <tr> <td>(f) liner</td><td>:</td><td>Hard Rubber</td></tr> </table> The flow meter shall provide local indication for instantaneous flow. It should also be possible to get local display for daily and monthly discharge. The flow meter shall indicate totaliser/ integrator to get the daily and monthly discharge as stated above.	(a) Output	:	4-20 mA DC Isolated output	(b) Accuracy	:	± 0.5% of calibrated span or better *	(c) Repeatability	:	± 0.2% of calibrated span or better	(d) Power Supply	:	240V AC ± 10%, 50 HZ ± 5%/ 24 V DC, to be arranged by the contractor.	(f) Protection class	:	IP-55	(e) Flow tube	:	SS304	(f) liner	:	Hard Rubber	
(a) Output	:	4-20 mA DC Isolated output																					
(b) Accuracy	:	± 0.5% of calibrated span or better *																					
(c) Repeatability	:	± 0.2% of calibrated span or better																					
(d) Power Supply	:	240V AC ± 10%, 50 HZ ± 5%/ 24 V DC, to be arranged by the contractor.																					
(f) Protection class	:	IP-55																					
(e) Flow tube	:	SS304																					
(f) liner	:	Hard Rubber																					
20.00.00	AC PLANT RELATED SPECIAL INSTRUMENTS																						
20.01.00	HUMIDITY SENSOR <table border="0"> <tr> <td>Sensor</td><td>:</td><td>Capacitance type</td></tr> <tr> <td>Accuracy</td><td>:</td><td>+/- 3% R.H</td></tr> <tr> <td>Range</td><td>:</td><td>0-100% R.H</td></tr> <tr> <td>Output</td><td>:</td><td>4-20 ma</td></tr> </table>	Sensor	:	Capacitance type	Accuracy	:	+/- 3% R.H	Range	:	0-100% R.H	Output	:	4-20 ma										
Sensor	:	Capacitance type																					
Accuracy	:	+/- 3% R.H																					
Range	:	0-100% R.H																					
Output	:	4-20 ma																					
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE – I (3X 800MW)		<table border="1"> <tr> <td data-bbox="630 1892 1015 2018"> TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2 </td><td data-bbox="1015 1892 1320 2018"> SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY) </td><td data-bbox="1320 1892 1471 2018"> PAGE 41 OF 46 </td></tr> </table> Page 480 of 1005	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 41 OF 46																		
TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 41 OF 46																					

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC																			
20.02.00	Time constant : 2 mins. Output from the sensor is to be connected to respective control system. Contractor can also provide combined instrument for measurement of humidity and temperature subject to Employer's approval during detailed engineering. In all such cases, 4-20 ma outputs, each for temperature and humidity measurements are to be provided. TEMPERATURE/ HUMIDITY INDICATOR Sensor : RTD for(Pt 100) for temperature : Capacitance Type for Humidity (specs for humidity and temperature shall be as mentioned above) Display : Combined enclosure with two three digit seven segments LED display with decimal point after two digits. LED height shall be 4 inches, clearly legible from a distance of at least 10 meters. Range : 0-60 Deg C for temperature. : 0-95.0 % for Relative Humidity. Accuracy : Better than +/- 0.5 % for Temperature : Better than +/- 2.5 % for Relative Humidity Mounting : Table Top/ wall mounting. Power supply : 240 V AC, 50 Hz. Output : 4-20 mA signal each for temperature. Qty. : 15 nos. each of temperature & Humidity indicators (combined indicators for Humidity and temperature is also applicable). One Set of output signal is to be connected to respective control system. Apart from displaying the temperature/humidity values on indicator.																				
	21.00.00	Limit switches For offsite plant application Limit switches shall be gold plated with high conductivity and non corrosive type. Contact rating shall be sufficient to meet the requirement of DDCMIS subject to a minimum of 60 V, 6 VA rating. Protection class shall be IP 55. For main plant application limit switches are to be provided as per contractor standard and proven practice.																			
22.00.00	SPECIFICATIONS OF EFFLUENT QUALITY MONITORING SYSTEM (EQMS)																				
22.01.00	COMMON REQUIREMENTS FOR ALL ANALYSERS <table><tr><th>Sno</th><th>Features</th><th>Minimum Requirement</th></tr><tr><td>1.</td><td>Output signals</td><td>Analog 4-20 mA DC galvanically isolated.</td></tr><tr><td>2.</td><td>Zero & span Adjustment</td><td>To be provided with range selection facility</td></tr><tr><td>3.</td><td>Ambient temp</td><td>50 degC</td></tr><tr><td>4.</td><td>Sample Temperature</td><td>40 degC</td></tr><tr><td>5.</td><td>Indication</td><td>Digital Alphanumeric Display of reading in engineering units shall be provided.</td></tr></table>	Sno	Features	Minimum Requirement	1.	Output signals	Analog 4-20 mA DC galvanically isolated.	2.	Zero & span Adjustment	To be provided with range selection facility	3.	Ambient temp	50 degC	4.	Sample Temperature	40 degC	5.	Indication	Digital Alphanumeric Display of reading in engineering units shall be provided.		
Sno	Features	Minimum Requirement																			
1.	Output signals	Analog 4-20 mA DC galvanically isolated.																			
2.	Zero & span Adjustment	To be provided with range selection facility																			
3.	Ambient temp	50 degC																			
4.	Sample Temperature	40 degC																			
5.	Indication	Digital Alphanumeric Display of reading in engineering units shall be provided.																			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 42 OF 46																	

CLAUSE NO.	TECHNICAL REQUIREMENTS		एनटीपीसी NTPC	
	6.	Type of Electronics	Microprocessor based with self-diagnostic	
	7.	Calibration	Manual	
	8.	Others	All interconnection tubing and cabling between sensor and analyzer / analyzer panel etc to be provided. All chemical reagents required for EQMS analyzers for entire AMC period is to be supplied in phased manner depending on shelf life.	
	9.	Location of the Temp & flow measurement	Effluent Treatment plant outlet (Exact location to be decided by contractor in consultation with site)	
	10.	Location of the Analyser cabinet/enclosure		
	11.	Accessories	All the accessories required for mounting the sensor/analyser are to be provided	
	12.	Digital Signal Transmission	Each analyser shall have a provision for bidirectional soft connectivity over Modbus/RS232/RS485 with employer's central cloud server in addition to 4-20 ma connectivity to DDCMIS.	
	13.	Compliance to standards	CPCB's (Central Pollution control Board) latest regulatory requirement prevailing at the time of execution of the contract.	
22.02.00	CONDUCTIVITY ANALYSER			
	Type		Continuous flow through type	
	Measuring Range		0 – 60000 µS/cm for sea water application 0-5000 µS/cm for other application	
	Response Time		<= 5 sec (90% of full scale)	
	Temperature Compensation		Automatic	
	Power		To be arranged by the contractor	
	Accuracy		<= +/- 1 %	
	pH ANALYSER			
	Type		Cell flow through sample	
	Measuring Range		0-14 units of pH	
	Temperature Compensation		Automatic	
	Power		To be arranged by the contractor.	
Accuracy		<= +/- 1 %		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 43 OF 46

CLAUSE NO.	TECHNICAL REQUIREMENTS			एनटीपीसी NTPC		
22.04.00	BOD BIOLOGICAL OXYGEN DEMAND / COD CHEMICAL OXYGEN DEMAND ANALYSER					
	Principle		COD/BOD measurement by: Option A. Total Organic Carbon (TOC) measurement complying to US EPA 415.1 / 415.2 or equivalent standard for effluent/sewage/waste water. Option B. UV-VIS spectrometer measuring absorption in UV-VIS spectrum.			
	Measuring Range		0-50 mg/L for BOD, 0-500 mg/L for COD			
	Response Time		<= 15 min			
	Power		To be arranged by contractor			
	Cleaning		Self-cleaning (Automatic)			
	Accuracy		+/- 3%			
	22.05.00	OIL IN WATER ANALYSER				
		Principle		UV Fluorescence		
		Measuring Range		0 to 30 mg/l		
		Response Time		<= 60 sec		
		Power		To be arranged by the contractor.		
		Cleaning		Self-cleaning (Automatic)		
		Accuracy		+/- 5 % of full scale		
		22.06.00	TOTAL SUSPENDED SOLIDS – TSS ANALYSER			
			Principle		Light reflection principle	
Measuring Range			0-500 mg/l			
Response Time			<= 5 min			
Power			To be arranged by bidder (Refer terminal point)			
Cleaning			Self-cleaning (Automatic)			
Accuracy			+/- 5%			
</						

CLAUSE NO.	TECHNICAL REQUIREMENTS			एनटीपीसी NTPC
22.07.00	ENCLOSURE/CABINETS / PANELS The enclosure shall accommodate all EQMS Analyser. The enclosure shall provide protection from dust, humidity, precipitations, sunlight and environmental pollution. The material for the enclosure shall be of steel plate with minimum 2 mm thick frame and 1.6 mm thick CRCA steel sheet of protection IP 55 or better with safety lock of good quality. The lighting provision in the cabinet and the canopy for the cabinet is to be provided. The cabinets shall be designed such that the wet section and dry section are separate, the exact details shall be finalized during detailed engineering. In order to ensure the healthy operation of the installed electronic modules, cards, analyzers, etc inside the enclosure during continuous operation, the EQMS enclosure shall be provided with Air conditioner unit .			
23.00.00	Monitoring System for Coal Bunker, Fly Ash Silo and ESP Hopper (First Field) Complete Level Monitoring System comprising of Acoustic Frequency Based 3D Level Scanners, PC, electronic modules, splitters, modems, junction boxes, mounting kit, enclosures, interconnecting cables, software and all other accessories required to make the system complete and fully functional, shall be provided on as required basis for continuous level measurement and monitoring of level of each coal bunker, each Fly Ash Silo and each ESP Hopper (First Field of ESP Only) complying with following requirements:			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE –I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-04 MEASURING INSTRUMENTS (PRIMARY & SECONDARY)	PAGE 45 OF 46

Page 484 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS		एनटीपीसी NTPC

SUB-SECTION – IIIC - 13

STEAM AND WATER ANALYSIS SYSTEM (SWAS)

Grab Samples

Sample Sink

A continuous sink, located at the place of grab sample analysis, shall be provided. The sink shall be of 316 stainless steel, 14 gage minimum. The sample sink shall be connected to waste drain header. Sample sink shall contain an integral stainless steel ledge to accommodate sample container. DM water connection shall be provided for cleaning of sample containers.

SPECIFICATION OF ANALYSERS

Field proven reputed international make microprocessor based monitors/analyzers with LCD display and with necessary fault diagnostic features shall be employed. All analysers shall provide 4-20mA output signal capable of driving a load impedance of 500Ohms minimum. The type, size, capacity, material, make, model and other specification details of the rest of the SWAS system like coolers, gauges/switches, sample pipes, filter, pressure reducing elements, grab sampling arrangement, valves & fittings, panels etc. shall be as decided during detailed engineering stage and shall be subject to Employer's approval. The power supply to all the analysers/ monitors shall be supplied by Contractor from his UPS system with all necessary switches, fuses, wiring/cabling and other required accessories etc. for distribution to individual requirements.

Minimum specifications of analysers					
Requirements	Conductivity	PH	Phosphate	Chloride	Turbidity
Type	For Hotwell, Two removable Type of Cells, For Others, Continuous Flow Through Type	Cell Flow Through sample	Colorimetric	Continuous Flow Through Type with Chloride & Sulphate Responsive Electrodes	Light reflection principle
Accuracy	$\leq \pm 1\%$	$\leq \pm 1\%$	$\leq \pm 5\%$ of reading	$\leq \pm 5\%$	$\leq 2\%$ for range 0-50 NTU, $\leq 5\%$ for range 50 – 200 NTU

Response Time (90 % of Full Scale)	≤ 5 sec.		≤ 16 min.		≤ 5 min.
Range	0-1, 0-10, 0-100 micro-mho/cm (freely programmable) for Specific Conductivity. 0-1 micro-mho/cm log scale for Cation conductivity	6-11 pH freely programmable	0-10 ppm freely programmable	0-1000 ppb freely programmable	0 – 100, 0-200 MTU, programmable
Temperature Compensation	Automatic/	Automatic	Automatic	Automatic	
Sample Flow			50-150 ml/min		
No. of Streams	Single	Single	Single	Single	
Minimum specifications of analyserscontinued					
Requirements	Hydrazine	Silica	Sodium	Dissolved O2	Total Iron (Fe)
Type	Automatic Continuous Electrochemical Type	Continuous Colorimetric Type	Continuous Flow Through sample	Continuous Flow Through sample	Continuous Flow Through sample
Accuracy	≤ ± 5%	≤ ± 5% of reading	≤ ± 10% of reading	≤ ± 5% of reading	<±5 % of reading or ±0.005 ppm
Response Time (90 % of Full Scale)	≤ 3 min.	≤ 15 min. (including sample switching)	≤ 4 min.	≤ 30 sec.	≤ 15 min. (including sample switching)
Stability	Calibration Once in a Month		Calibration Once in a Month		

CLAUSE NO.	TECHNICAL REQUIREMENTS						एनटीपीसी NTPC
4.00.00	Range	0-50, 0-100 ppb freely programmable	0-50, 0-100 ,0-500 ppb freely programmable	0-1,0-10, 0-200 ppb freely programmable	0-20,0-200 ppb freely programmable	0-50ppb, 0-150ppb, 0-300ppb, 0-1ppm, 0-5ppm freely programmable or as per the process requirement.	
	No. of Streams	Single	Multi stream with sequencer/ stream selector (min. 4 streams)	Multi stream with sequencer/ stream selector (min. 4 streams)	Single	Multi stream with sequencer/ stream selector (min. 4streams)	
	Temperature Compensation	Automatic	Automatic	Automatic	Automatic	Automatic	
	Sample Flow	170 ml/min (max)	50-150 ml/min	125 ml/min (max)	170 ml/min (max)	200ml/min (max)	
	REMARKS	All the analysers/cells shall have open Corrosion resistant drain to waste header.					
		Analysers/ monitors/ cells shall be suitable for operating under the conditions specified.					
		Dual cation exchange column shall be provided for cation conductivity.					
		For Hot well conductivity measurement, the Contractor shall provide direct insertion / withdrawal type conductivity cell whereas for all other samples it shall be flow-through type. Monitors for hot well conductivity shall be suitable for field mounting.					
	4.00.00	SAMPLE PIPING SYSTEM					
	4.01.00	This shall include piping, fittings, valves and accessories from tapping point upto SWAS conditioning panel located in SWAS room on as required basis. All sample piping shall be 3/4" NB seamless type of material ASTM A213 TP 316 H, conforming to ANSI B36.19. The schedule number shall be suitable for the particular application.					
	4.02.00	All fittings shall be socket welding type and of material ASTMA182 F316H conforming to ANSI B 16.11.					
	4.03.00	Single and multi tubes shall run with the minimum number of changes in direction. Suitable identification tags shall be provided for easy check up and for proper connections.					
4.04.00	The valves to be used in sample piping shall be of stainless steel conforming to ASTM A182. The pressure temperature ratings shall be as per ANSI B16.34. The valve design shall be such that the seats can be reconditioned and stem and disc can be replaced without						
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)			TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION - IIIC-13 SWAS		PAGE 489 of 1095

4.05.00

The piping to be furnished and installed for water and steam analysis system shall be as indicated below:

	Piping System	Material
1.	Piping from the sample inlet bulk head fittings to the shut off valves	Stainless steel, ASTM A 213, Type 316H, 16 BWG tubing
2.	Piping for the high pressure samples and sample blow down piping	Stainless steel, ASTM A 213, Type 316 H. 14 BWG tubing
3.	Blow down header	Stainless steel, ASTM A 312, Type 304 Schedule 160
4.	Miscellaneous drains receiver holder	Stainless steel, ASTM A 312, Type 304 Schedule 40
5.	Piping from the shut-off valves to the terminal points including branch piping and the closed cooling water grab sample piping	Stainless steel, ASTM A 213, Type 316 H, 16 BWG tubing
6.	Closed cooling water piping except grab sample and water purge line	Carbon steel, ASTM A 53 Gr. A, Schedule 40.
7.	Sample through drain piping and waste header piping	Carbon steel, ASTM A 53 Gr. A, Schedule 40.
8.	Purge air piping/tubing and filling valves	Brass/Copper

4.06.00

S. No.	Service / Location	End Size	Pr. Class	Type	End Preparation	Body	Make (as specified or equivalent)
1	Sample Shut off valve	0.38	6000	Globe	SW	316SS	Thiedig
2	Sample blow down valve	0.38	6000	Ball valve	SW	316SS	Thiedig
3	Solenoid valve	--	--	2 way	--	316SS	ASCO
4	Pr. reducing Valve	0.38	--	Needle	Tube	316SS	Thiedig
5	Safety relief Valve	0.25	3000	Relief	Tube	316SS	Nupro
6	PI and FI isolation valve	0.25	3000	Needle	Tube	316SS	Whiety
7	Back pr. regulating valve	0.25	300	C.W.	SCR	316SS	Cono. flow H30XT-

5.00.00

							HAXXXG
8	Grab	0.25	300	3-way	Tube	316SS	Whiety
9	Quick	--	--	ball	--	316SS	Hancock Walther
10	Individual P.C. and S.C. inlet & outlet valve					316SS	Hancock/ ACKER MANN
11	P.C. I/L & O/L header & chilled water I/L & O/L isolation valve	--	--	Gate	--	316SS	Hancock
12	Safety relief valve at each PC & SC and cooling water header	--	--	Relief	--	316SS	Baldota
13	High Pressure reducing valve	--	--	--	--	316SS	--
14	Isolation valve before primary cooler	--	--	Needle	Tube	316SS	Whiety

SPECIFICATIONS FOR PR. GAUGE, D.P. GAUGE, TEMP. GAUGE AND LEVEL GAUGE.

SI. No	FEATURES	ESSENTIAL/MINIMUM REQUIREMENTS		
		Pr. Gauge/ DP Gauge/ Draught gauges	Temperature Gauge	Level Gauge
1	Sensing Element and material	Bourdon for high pressure, Diaphragm/Bellow for low pr. Of 316 SS	Mercury in steel for below 450°C and inert gas actuated for above 450°C of SS bulb and capillary.	Tempered * toughened Borosilicate gauge glass steel armoured reflex or transparent type.
2	Body material	Die-cast aluminium	Die-cast aluminium	Forged carbon steel/304 SS
3	Dial size	150mm	150 mm	Tubular covering entire range
4	End connection	1/2 inch NPT (M)	3/4" NPT (M)	Process connection as per ASME PTC and drain/vent 15 NB
5	Accuracy	±1% of span	± 1% of span	± 2%
6	Scale	Linear, 270° arc graduated in metric units	Linear, 270° arc graduated in °C	Linear vertical
7	Range selection	Cover 125% of max. of scale	Cover 125% of max. of scale	Cover 125% of max. of scale
8	Over range test	Test pr. for the assembly shall be 1.5 to the max. Design pr. at 38°C.		
9	Housing	Weather and dust proof as per IP-55	Weather and dust proof as per IP-55	CS/304 SS leak proof
10	Zero/span adjustment	Provided	Provided	--
11	Identification	Engraved with service legend or laminated phenolic name plate		

12	Accessories	Blow out disc, SS Thermowell siphon, snubber, pulsation dampener, chemical seal (if required by process) gauge isolation valve	Gasket for all KEL-F shield for transparent type vent and drain valves of Steel/SS as per CS/Alloy process Requirement.
13	Material of Bourdon/ movement	316 SS / 304 SS	316 SS / 304 SS

Notes:-

*Bicolour type level gauges will be provided for applications involving steam and water except for condensate and feed water services.

Length of gauge glass shall not be more than 1400 mm. If the vessel is higher, multiple gauge glasses with 50 mm overlapping shall be provided.

Where the process fluids are corrosive, viscous, solid bearing or slurry type, diaphragm seals shall be provided. Parts below the diaphragm shall be removable for cleaning. The entire volume above the diaphragm shall be completely filled with an inert liquid suitable for the application.



**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

**DATA SHEETS FOR MOTORISED VALVE
ACTUATOR**

|

	SPECIFICATION FOR MOTORISED VALVE ACTUATOR			
	REV. NO.	01	DATE: 11.05.2018	
SHEET	1 OF	4		
Data Sheet A & B				
DATA SHEET-A (TO BE FILLED BY PURCHASER)			DATA SHEET-B (TO BE FILLED-UP BY BIDDER)	
GENERAL *	* PROJECT	3 x 800 MW PATRATU TPP		
	OFFER REFERENCE			
	* TAG NO. SERVICE			
	* DUTY	☐ ON / OFF	☐ INCHING	
	* LINE SIZE (inlet/outlet): MATERIAL			
	* VALVE TYPE	☐ GLOBE ☐ GATE ☐ REG. GLOBE ☐ BUTTERFLY		
	* OPENING / CLOSING TIME			
	* WORKING PRESSURE			
	AMBIENT CONDITION	SHALL BE SUITABLE FOR CONTINUOUS OPERATION UNDER AN AMBIENT TEMP. OF 0-55 DEG C AND RELATIVE HUMIDITY OF 0-95%		
	VALVE SEAT TEST PRESS	BIDDER TO SPECIFY		
	REQUIRED VALVE TORQUE	BIDDER TO SPECIFY		
	ACTUATOR RATED TORQUE	BIDDER TO SPECIFY		
CONSTRUCTION AND SIZING	CONSTRUCTION	TOTALLY ENCLOSED, WEATHER PROOF, IP:55		
	MECHANICAL POSITION INDICATOR	TO BE PROVIDED FOR 0-100% TRAVEL		
	BEARINGS	DOUBLE SHIELDED, GREASE LUBRICATED ANTI-FRICTION.		
	GEAR TRAIN FOR LIMIT SWITCH/TORQUE SWITCH OPERATION	METAL (NOT FIBRE GEARS). SELF-LOCKING TO PREVENT DRIFT UNDER TORQUE SWITCH SPRING PRESSURE WHEN MOTOR IS DE-ENERGIZED.		
	SIZING	OPEN/CLOSE AT RATED SPEED AGAINST DESIGNED DIFFERENTIAL PRESSURE AT 90% OF RATED VOLTAGE. FOR ISOLATING SERVICE THREE SUCCESSIVE OPEN-CLOSE OPERATIONS OR 15 MINS. WHICHEVER IS HIGHER. FOR INCHING /REGULATING SERVICE - 150 STARTS/HR MINIMUM.		
HANDWHEEL	* REQUIRED	☒ YES ☐ NO		
	* ORIENTATION	☐ TOP MOUNTED ☐ SIDE MOUNTED		
	*TO DISENGAGE AUTOMATICALLY DURING MOTOR OPERATION.			
ELECTRIC ACTUATOR	ACTUATOR MAKE/MODEL	BIDDER TO SPECIFY		
	MOTOR MAKE / MODEL / TYPE / RATING (KW)	BIDDER TO SPECIFY		
	@ MOTOR TYPE	SQUIRREL CAGE INDUCTION MOTOR, STARTING CURRENT LIMITED TO SIX TIMES THE RATED CURRENT- INCLUSIVE OF I.S. TOLERANCE		
	ACTUATOR APPLICABLE WIRING DIAGRAM	☒ ENCLOSED (BIDDER TO CONFIRM) A: ☐ DRG. NO. 3-V-MISC-24227 R00 B: ☐ DRG. NO. 3-V-MISC-24550 R00 C: ☐ DRG. NO. 3-V-MISC-24283 R00 D: ☐ DRG. NO. 4-V-MISC-90271 R11 E: ☐ For Thyristor based Integral starter, Bidder/Vendor to furnish wiring diagram		
	COLOUR SHADE	☒ BLUE (RAL 5012) ENAMEL ☐		
	PAINT TYPE (## Refer Notes)	☐ ENAMEL ☐ EPOXY ☐		
	SHAFT RPM	BIDDER TO SPECIFY		
	OLR SET VALUE	BIDDER TO SPECIFY		
	@ STARTING / FULL LOAD CURRENT	BIDDER TO SPECIFY		
	NO. OF REV FOR FULL TRAVEL	BIDDER TO SPECIFY		
	@ PWR SUPP TO MTR / STARTER	415V +/- 10 % , 3PH,3 W, AC 50 HZ +/- 5 %		
	@ CONTROL VOLTAGE REQUIREMENT	TO BE DERIVED FROM THE POWER SUPPLY TO THE STARTER ☐ 230 V ☒ 110 V AC/24V DC		

	SPECIFICATION FOR MOTORISED VALVE ACTUATOR				
	REV. NO. 01		DATE: 11.05.2018		
SHEET 2 OF		4			
Data Sheet A & B					
DATA SHEET-A (TO BE FILLED BY PURCHASER)			DATA SHEET-B (TO BE FILLED-UP BY BIDDER)		
	MOTOR BEARING WITH 2 EARTH TERMINALS	DOUBLE SHIELDED, GREASE LUBRICATED ANTI FRICTION			
	@ ENCLOSURE CLASS OF MOTOR	IP 67 FOR OUTDOOR & IP 55 FOR INDOOR (TOTALLY ENCLOSED SELF VENTILATED)			
	@ INSULATION CLASS	CLASS-F TEMP. RISE LIMITED TO CLASS-B			
	@ WINDING TEMP PROTECTION	☒ THERMOSTAT (3 Nos., 1 IN EACH PHASE) ☐ _____			
	SINGLE PHASE / WRONG PHASE SEQUENCE PROTECTION	REQUIRED			
INTEGRAL STARTER	INTEGRAL STARTER	☒ REQUIRED ☐ NOT REQUIRED			
	TYPE OF SWITCHING DEVICE	☒ CONTACTORS ☐ THYRISTORS			
	TYPE	☒ CONVENTIONAL ☐ SMART (NON-INTRUSIVE)			
	IF SMART	(NOT APPLICABLE)			
	a) SERIAL LINK INTERFACE	☐ INTEGRAL ☐ FIELD MOUNTED			
	b) SERIAL LINK PROTOCOL	☐ FOUNDATION FIELD-BUS ☐ PROFI-BUS ☐ DEVICE NET ☐			
	c) SERIAL LINK MEDIA	☐ TWISTED PAIR Cu-CBL ☐ CO-AXIAL Cu-CBL ☐ OFC			
	d) HAND HELD PROGRAMMER	☐ REQUIRED ☐ NOT REQUIRED			
	e) TYPE OF HAND HELD PROGRAMMER	☐ BLUETOOTH ☐ INFRARED ☐			
	f) MASTER STATION	☐ REQUIRED ☐ NOT REQUIRED			
	g) MASTER STN INTRFACE WITH DCS	☐ MODBUS ☐ TCP/IP			
	h) DETAILS OF SPECIAL CABLE	☐ ENCLOSED ☐ NOT REQUIRED			
	STEP DOWN CONT. TRANSFORMER	☒ REQUIRED			
	OPEN / CLOSE PB	☒ REQUIRED ☐ NOT REQUIRED			
	STOP PB	☒ REQUIRED ☐ NOT REQUIRED			
	INDICATING LAMPS	☒ REQUIRED ☐ NOT REQUIRED			
	LOCAL REMOTE S/S	☒ REQUIRED ☐ NOT REQUIRED			
	STATUS CONTACTS FOR MONITORING	☒ REQUIRED ☐ NOT REQUIRED			
		INTEGRAL STARTER DISTURBED SIGNAL	REQUIRED (O/L RELAY OPERATED, CONT./POWER SUPPLY FAILED, S/S IN LOCAL, TORQUE SWITCH OPTD. MID WAY)		
	INTERPOSING RELAY/OPTO COUPLER (Applicable for integral Starter)	TYPE OF ISOLATING DEVICE	☒ INTERPOSING RELAY ☐ OPTO COUPLER ☐ EITHER		
QUANTITY		☒ 2 NOs. ☐ 3 NOs.			
DRIVING VOLTAGE		☒ 20.5 – 24V DC ☐ _____ V DC			
DRIVING CURRENT		☒ 125mA MAX ☐ _____ mA MAX			
LOAD RESISTANCE		☒ > 192 ohms - < 25 k ohms ☐ > _____ ohms - < _____ ohms			
TORQUE SWITCH (Not Applicable for Smart Actuator) (\$\$ Refer Notes)	MFR & MODEL NO.	BIDDER TO SPECIFY			
	OPEN / CLOSE	☒ 1 No. ☐ 2Nos. / ☒ 1 No. ☐ 2Nos			
	CONTACT TYPE	2 NO + 2 NC			
	RATING	5A 240V AC AND 0.5A 220V DC			
	CALIBRATED KNOBS(OPEN&CLOSE TS)	REQUIRED FOR SETTING DESIRED TORQUE			
	ACCURACY	+3% OF SET VALUE			
LIMIT SWITCH (Not Applicable for Smart Actuator) (\$\$	MFR & MODEL NO.	BIDDER TO SPECIFY			
	OPEN : INT : CLOSE	☐ 1 No ☒ 2 Nos.	☐ 1 No. ☒ 2Nos.		
	CONTACT TYPE	2 NO + 2 NC			


	SPECIFICATION FOR MOTORISED VALVE ACTUATOR			
	REV. NO.	01	DATE: 11.05.2018	
SHEET		3 OF	4	
Data Sheet A & B				
DATA SHEET-A (TO BE FILLED BY PURCHASER)			DATA SHEET-B (TO BE FILLED-UP BY BIDDER)	
Refer Notes)	RATING (AC / DC)	5A 240V AC AND 0.5A 220V DC		
Limit switches shall be silver plated with high conductivity and non-corrosive type. Contact rating shall be sufficient to meet the requirement of control system subject to a minimum of 60 V, 6 VA rating. Protection class shall be IP 55.				

POSITION TRANSMITTER	POSITION TRANSMITTER (For inching duty applications)	☒ REQUIRED ☐ NOT REQUIRED	
	MFR & MODEL NO.	BIDDER TO SPECIFY	
	TYPE	☐ ELECTRONIC (2 WIRE) R/I CONVERTER ☒ ELECTRONIC (2 WIRE) CONTACTLESS INDUCTIVE TYPE ,EXTERNAL 24 V DC OPERATED ,SUITABLE FOR STABILISED 4-20 mA SIGNAL	
	SUPPLY	☒ 24V DC ☐	
	OUTPUT	☒ 4-20mA	
	ACCURACY	$\pm$ 1% FS	
SPACE HEATER	@SPACE HEATER	REQUIRED	
	@ POWER SUPPLY (NON INTEGRAL)	230V AC,1 PH.,50 Hz	
	@ POWER SUPPLY (INTEGRAL)	POWER SUPPLY DERIVED FROM MAIN POWER SUPPLY AVAILABLE AT ACTUATOR END.	
	@ RATING		
TERMINAL BOX	ACTUATOR/MOTOR TERMINAL BOX	REQUIRED	
	ENCL CLASS ACTUATOR/MOTOR T.B.	☒ IP 68 @ ☐	
	@ EARTHING TERMINAL	REQUIRED	
	PLUG & SOCKET(9 PIN) (FOR COMMD, LS/TS FEED BACK, PoT)	☒ REQUIRED ☐ NOT REQUIRED ☐ ☒ 2 NOS. PRE WIRED ☐	
CABLE GLANDS	@ POWER CABLE GLAND	SIZE:-----	
	@ SPACE HEATER CABLE GLAND	SIZE:-----	
	OTHER CONTROL CABLE GLANDS-1	2 NOS SUITABLE FOR 4P,0.5SQ MM	
	OTHER CONTROL CABLE GLAND	1 No. for BFV of CW PUMP(Cable size 2Px1.5mm2)	

	SPECIFICATION FOR MOTORISED VALVE ACTUATOR			
	REV. NO. 01		DATE: 11.05.2018	
SHEET 4 OF		4		
Data Sheet A & B				
DATA SHEET-A (TO BE FILLED BY PURCHASER)			DATA SHEET-B (TO BE FILLED-UP BY BIDDER)	
WEIGHT	TOTAL WEIGHT (ACTUATOR + ACCESSORIES)	BIDDER TO SPECIFY		_____ Kg.
NOTES: 1. SCOPE: DESIGN, MANUFACTURE, INSPECTION, TESTING AND DELIVERY TO SITE OF ELECTRIC ACTUATOR FOR INCHING OR OPEN / CLOSE DUTY. 2. CODES & STANDARDS: DESIGN AND MATERIALS USED SHALL COMPLY WITH THE RELEVANT LATEST NATIONAL AND INTERNATIONAL STANDARD. AS A MINIMUM, THE FOLLOWING STANDARDS SHALL BE COMPLIED WITH: IS-9334, IS-2147, IS-2148, IS-325, IS-2959, IS-4691 AND IS-4722 3. TEMPERATURE RISE SHALL BE RESTRICTED TO 70 DEG. C FOR AMBIENT TEMPERATURE OF 50 DEG C. 4. CABLE GLANDS OF DOUBLE COMPRESSION TYPE, BRASS MATERIAL SHALL BE PROVIDED. 5. THE TORQUE SWITCHES SHALL BE PROVIDED WITH MECHANICAL LATCHING DEVICE TO PREVENT OPERATION WHEN UNSEATING FROM THE END POSITIONS. THE LATCHING DEVICE SHALL UNLATCH AS SOON AS THE VALVE LEAVES THE END POSITION. IF SUCH PROVISION IS NOT POSSIBLE, THE TORQUE SWITCHES SHALL BE BYPASSED BY END-POSITION LIMIT SWITCHES WHICH OPENS ON VALVE LEAVING END POSITION. THESE LIMIT SWITCHES ARE ADDITIONAL TO THE NUMBER OF LIMIT SWITCHES SPECIFIED ELSEWHERE. 6. THE MOTOR SHALL OPERATE SATISFACTORILY UNDER THE +/- 10% SUPPLY VOLTAGE VARIATION AT RATED FREQUENCY, -5% TO +3% VARIATION IN FREQUENCY AT RATED SUPPLY VOLTAGE, SIMULTANEOUS VARIATION IN VOLTAGE & FREQUENCY THE SUM OF ABSOLUTE PERCENTAGE NOT EXCEEDING 10%. 7. THE MOTOR SHALL BE SUITABLE FOR DIRECT ON LINE STARTING. \$\$ TORQUE SWITCH & LIMIT SWITCH SHALL ACT INDEPENDENT OF EACH OTHER. TANDEM OPERATION IS NOT ACCEPTABLE. ## EPOXY PAINT IS RECOMMENDED FOR COASTAL AREAS. 8. IT SHALL BE POSSIBLE TO OPERATE THE ACTUATOR LOCALLY. LOCKABLE LOCAL/REMOTE SELECTION SHALL BE PROVIDED ON THE ACTUATOR. 9. POSITION INDICATOR SHALL BE PROVIDED FOR 0 TO 100 % TRAVEL 10. WIRING SHALL BE SUITABLE VOLTAGE GRADE COPPER WIRE.				
NAME SIGNATURE DATE	PREPARED BY	CHECKED BY	APPROVED BY	VENDOR COMPANY SEAL NAME SIGNATURE DATE
	Madhav gupta	Mayank kesharwani	Bharat Singh	
	01.03.2018 01.	03.2018	01.03.2018	
NOTES* = TO BE FILLED BY MPL (LEAD AGENCY). @ = TO BE FILLED BY ES				

ALL DIMENSIONS ARE IN MILLIMETRES. FOR TOLERANCES OF UNTOLERANCED DIMENSIONS DURING MANUFACTURE REFER RELEVANT QCP / QP.

24283-JSIN-A-3
ON DRAWING



CONTACT DEVELOPMENT DIAGRAM

OTS	1-2	OPEN AT OVER TORQUE DURING OPENING TRAVEL
CTS	3-4	CLOSE AT OVER TORQUE DURING OPENING TRAVEL
CLS-1	5-6	OPEN AT OVER TORQUE DURING CLOSING TRAVEL
CLS-2	7-8	CLOSE AT OVER TORQUE DURING CLOSING TRAVEL
CLS-1	9-10	
CLS-2	11-12	
CLS-1	13-14	
CLS-2	15-16	
CLS-1	17-18	
CLS-2	19-20	
CLS-1	21-22	
CLS-2	23-24	
SWITCH	TERMINAL NO.	VALVE POSITION
	o	INTERMEDIATE
	b	FULL CLOSE
		INDICATES CONTACT CLOSED
		INDICATES CONTACT OPEN

CONTACT RATING: 5A AT 250V AC & 0.5A AT 220V DC

VALVES	OPEN	CLOSE
MAIN	BACK UP	MAIN
CLS	OTS	CLS
CLS	OTS	CLS
CLS	OTS	CLS

SETTING PROCEDURE OF POSITION LIMIT AND TORQUE SWITCH

GATE VALVE OF 100 mm AND ABOVE
IN 1500 CL AND ABOVE RATINGS

ALL OTHER GATE & GLOBE VALVES

CLS NOT TO BE CONNECTED IN TRIP CIRCUIT

OTS - BYPASS OTS FOR INITIAL 5% OF TRAVEL (FOR GATE VALVES ONLY)

TYPE OF PRODUCT OR NAME OF CUSTOMER/PROJECT		ELECTRICAL VALVE ACTUATORS (AC) WITH INTEGRAL STARTERS FOR NTPC PROJECTS (DRAWN FOR INTERMEDIATE POSITION OF VALVES)	
BHARAT HEAVY ELECTRICALS LTD., UNIT: HIGH PRESSURE BOILER PLANT, THERUCHIRAPALLY-620014.		NAME N.P.ESWAR D.DINAKARAN K.ARUNACHALAM	SIGN N.P. D.D. K.A.
DEPT 385-121	SCALE NTS	DATE 17.03.05	NO. OF VAR.
CODE VL	WEIGHT (KG)	DATE 17.03.05	NO. OF VAR.
REV CHD & APD	WIRING DIAGRAM (TERMINAL PLAN)	DRAWING NO. 3-V-MISC-24283	REV 0
TITLE FOR ACTUATOR WITH INTEGRAL STARTER WITH PLUG & SOCKET FOR NTPC PROJECTS		Page 6 of 6	

- NOTE:-
1. ALL TORQUE AND LIMIT SWITCHES (OTS, CTS, OLS1 & 2, CLS1 & 2) ARE WITH 2NO+2NC CONTACTS. '1NO+1NC' IS TERMINATED IN TBS 1-24. REMAINING CONTACTS ARE FOR INTERNAL USE. ANY SPARE CONTACTS WHICH ARE NOT USED INTERNALLY ARE TO BE TERMINATED IN TBS 25-32.
 2. CTS - TORQUE SWITCHES FOR CW ROTATION (CLOSE)
 3. OTS - TORQUE SWITCHES FOR CCW ROTATION (OPEN)
 4. OLS-1, OLS-2 - LIMIT SWITCHES FOR POSITION OPEN
 5. CLS-1, CLS-2 - LIMIT SWITCHES FOR POSITION CLOSE
 6. EPT - ELECTRONIC POSITION TRANSMITTER (CONTACTLESS TYPE, FOR INCHING DUTY)
 7. R1-R2 - POTENTIOMETER 2 x 100 OHMS (FOR ON-OFF DUTY)
 8. FOR COMMANDS & EPT EITHER INTERNALLY GENERATED 24 VDC OR EXTERNAL SUPPLY OF 24VDC CAN BE USED
 9. M - MOTOR 3φ 415V 50 Hz AC SUPPLY
 10. TORQUE SWITCH BYPASS WITH LIMIT SWITCH BOTH ON OPEN & CLOSE DIRECTION TO BE DONE INTERNALLY.




**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

**SIGNL EXCHANGE BETWEEN DRIVES &
DCS**

|

DDCMIS INTERFACE WITH LT MCC (LT)



NOTE:-1 \$\$\$ REDUNDANT OUTPUTS WHEREVER APPLICABLE

NOTE:-2 # 8 LEVEL TERMINAL BLOCK

NOTE:-3 @@ INEACH DDCMIS POST,UNUSED TB'S ARE USED FOR SPARE CORE TERMINATION SEQUENTIALLY.

NOTE:-4 * MCC DISTURBED= THERMAL O/L OPT/CONT SUPP FAIL/EPB OPTD /DRIVE POWER SUPPLY OFF




3X800 MW NTPC PATRATU STPP
PHASE-1

DDCMIS INTERFACE WITH LT MCC (LT)

DRG.NO. 9585-001-406-PVI-B-152B

SHT 05 OF 34

DDCMIS INTERFACE WITH BID/MOV/MOD



NOTE:-1 \$\$\$ REDUNDANT OUTPUTS WHEREVER APPLICABLE

NOTE:-2 # 8 LEVEL TERMINAL BLOCK

NOTE:-3 @@ INEACH DDCMIS POST,UNUSED TB'S ARE USED FOR SPARE CORE

TERMINATION.

NOTE:-4 * DISTURBANCE=LOSS OF POWER SUPPLY(1PHASE/3PHASE)/LOSS OF

CONTROL SUPPLY/MOTOR THERMOSTAT TRIP/THERMAL OVER LOAD/

TORQUE SWITCH OPERATED, LOCAL/OFF/REMOTE SWITCH IN LOCAL/OFF POSITION



3XB00 MW NTPC PATRATU STPP PHASE-I

DRG.NO. 9686-001-406-PVI-B-162B



DDCMIS INTERFACE WITH BID

SHT

06 OF 26




DDCMIS INTERFACE WITH BIDI/MODI/MOVI




04

MARSHALLING PANEL



ACTUATOR (WITH INTEGRAL STARTER)



NOTE:-1 \$\$ REDUNDANT OUTPUTS WHEREVER APPLICABLE
NOTE:-2 # 8 LEVEL TERMINAL BLOCK
NOTE:-3 @@ INEACH DDCMIS POST,UNUSED TB'S ARE USED FOR SPARE CORE TERMINATION.
NOTE:-4 F-TYPE: INDIVIDUAL & OVERALL SHIELD CABLE.
NOTE:-5 *DISTURBANCE=LOSS OF POWER SUPPLY/LOSS OF CONTROL SUPPLY/ MOTOR THERMOSTAT TRIP/THERMAL OVERLOAD/TORQUE SWITCH OPTD/ LOCAL/OFF/REMOTE SWITCH IN LOCAL/OFF POSITION




3X800 MW NTPC PATRATU STPP
PHASE-1

DDCMIS INTERFACE WITH BIDI

DRG.NO. 9585-001-405-PVI-B-162B

SHT 07 OF 34

DDCMIS INTERFACE WITH SOV/O/L(WITH FEED BACKS)



NOTE:-1 \$\$ REDUNDANT OUTPUTS WHEREVER APPLICABLE.

NOTE:-2 # 8 LEVEL TERMINAL BLOCK.

NOTE:-3 @ @ INEACH DDCMIS POST,UNUSED TB'S ARE USED FOR SPARE CORE TERMINATION.

NOTE:-4 * FEEDBACKS/COMMANDS OF DSOV/SOV CAN BE GROUPED IN FIELD JB/RELAY PANEL AND MULTIPAIR/MULTICORE CABLE IS TO BE USED FOR GROUPED SIGNALS FROM FIELD JB/RELAYPANEL TO MARSHALLING PANEL.

NOTE:-5 FOR ON/OFF TYPE,SOLENOID ACTUATED CONTROL VALVE.



3XB00 MW NTPC PATRATU STPP
PHASE-1

DRG.NO.

9686-001-405-PV-B-162B

DDCMIS INTERFACE WITH SOV/O/L(WITH FEEDBACKS)

SHT

12



OF

34


DDCMIS INTERFACE WITH DIGITAL INPUT SIGNAL

G-TYPE 4PAIR 0.5sqmm

INST.CABLE FIELD JB



Det 'A'




NOTE:-1 #8 LEVEL TERMINAL BLOCK.

NOTE:-2 @ @ IN EACH DDCMIS POST, UNUSED TB'S ARE USED FOR SPARE CORE TERMINATION.

PROJECT: 3XB00 MW PATRATU STPP		DRG. NO.	9585-001-405-PVI-B-152B
STAGE-I		DATE	19.09.2018
DDCMIS INTERFACE WITH DIGITAL INPUT SIGNAL		REV. NO.	03
		SHT	23 OF 34

DDCMIS INTERFACE WITH DIGITAL OUTPUT SIGNAL




NOTE:-1 #8 LEVEL TERMINAL BLOCK.

NOTE:-2 @ @ IN EACH DDCMIS POST, UNUSED TB's ARE USED FOR SPARE CORE TERMINATION.


		PROJECT: 3XB00 MW PATRATU STPP		DRG. NO.	9585-001-405-PVI-B-152B
DDCMIS INTERFACE WITH DIGITAL OUTPUT SIGNAL		STAGE-I		DATE	19.09.2018
				REV. NO.	03
				SHT	24 OF 34

DDCMIS INTERFACE WITH ANALOG INPUT SIGNAL

AI INTERFACE(4-20mA POWERED BY SYSTEM)



AI INTERFACE(4-20mA POWERED EXTERNALLY)



NOTE:-1 #8 LEVEL TERMINAL BLOCK.


NOTE:-2 @ @ IN EACH DDCMIS POST, UNUSED TB'S ARE USED FOR SPARE CORE TERMINATION.

NOTE:-3 F-TYPE: INDIVIDUAL & OVERALL SHIELD CABLE.

		PROJECT: 2X800 MW PATRATU STPP		DRG.NO:	0686-001-405-PVT-B-152B
DDCMIS INTERFACE WITH ANALOG INPUT SIGNAL		STAGE-1		DATE	19.09.2018
				REV.NO.	03
				SHT	25 OF 34

DDCMIS INTERFACE WITH ANALOG OUTPUT SIGNAL

AO INTERFACE



- NOTE:-1 #8 LEVEL TERMINAL BLOCK.
- NOTE:-2 @ @ IN EACH DDCMIS POST, UNUSED TB's ARE USED FOR SPARE CORE TERMINATION.
- NOTE:-3 F-TYPE: INDIVIDUAL & OVERALL SHIELD CABLE.

			
PROJECT: 3XB00 MW PATRATU STPP		DRG.NO:	0686-001-405-PVT-B-152B
STAGE-1		DATE	19.09.2018
DDCMIS INTERFACE WITH ANALOG OUTPUT SIGNAL		REV.NO.	03
		SHT	26 OF 34



DRIVE & INSTRUMENT INTERFACE DIAGRAM






|

LIST OF MATERIALS

ITEM NO.	DESCRIPTION
1.	ISOLATION VALVE(gate/globe). SS.
2.	SEAMLESS SS PIPE.
3.	AIR FILTER REGULATOR.
4.	INST. AIR HEADER SS.
10.	COMP. NEEDLE VALVE SS.
11.	AIR PURGE SET.
12.	COMP VALVE SS.
13.	PLUG SS.
15.	TUBE SS CONNECTOR.
16.	TUBE COMP. EQUAL TEE UNION.
24.	BULKHEAD-SS SUITABLE FOR G PIPE CONNECTION
25.	SEAMLESS TUBE SS.
27.	BRANCH TEE SS.
28.	PR. GAUGE.
30.	NYLON FLEX. HOSE BRAIDED WITH SS WIRE.
31.	HOSE BARBED CONN. SS.
33.	QUICK DISCONNECT SS (PURGE AIR CONNECTION TO INSTRUMENT SOURCE END).

LIST OF MATERIALS

ITEM NO.	DESCRIPTION
14.	SW GLOBE VALVE.
17.	SW EQUAL TEE
18.	S.S. NIPPLE
19.	5 VALVE MANIFOLD
20.	SW HALF COUPLER CS
21.	PIPE x TUBE UNION
22.	SUITABLE ADAPTER
23.	SS TUBE



TYPICAL PURGE AIR CONNECTION INSIDE THE INST. ENCLOSURE (APPLICABLE FOR MILL, AIR & FLUE GAS SERVICE INSTRUMENTS REQUIRING PURGE AIR)
(Drain Header of each LE/LIR shall be connected to nearest plant drain)

TYPICAL ARRANGEMENT OF DP TRANSMITTER (DRUG LE/LIR) MOUNTED BELOW INSTRUMENT SOURCE POINT


FOR TENDER PURPOSE ONLY

NTPC LIMITED (A CENTRAL GOVERNMENT ENTERPRISE) NEW DELHI-110001	
PROJECT	TYPICAL THERMAL POWER PROJECT (TURNKEY EPC PACKAGE)
TITLE	TYPICAL GA OF LOCAL INSTRUMENT ENCLOSURE, PURGING SCHEME, DP TRANSMITTER
SIZE	A3
SCALE	N.T.S.
DATE	0000-9999-POI-A-036
REV. NO.	A

REV. NO.	DESCRIPTION	DATE	BY	CHECKED BY	APPROVED BY
A	FIRST ISSUE				

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.
No part of this document will be reproduced by any means without the written permission.


TERMINATION AT
CONTROL SYSTEM END



FOR TENDER PURPOSE ONLY

 एन टी पी सी लिमिटेड NTPC LIMITED (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION		PROJECT TYPICAL THERMAL POWER PROJECT	
TITLE INTERFACING OF ACTUATORS		SIZE A3	SCALE N.T.S.
REV. NO. A	DRG. NO. 0000-999-POI-A-063	DATE 28.04.06	APPD ARCH.
DESCRIPTION		M E C O I E R C L E A R E D B Y	CHKD. DRAWN

MARSHALLING/TERMINATION
CUBICLE




FOR TENDER PURPOSE ONLY



एन टी सी लिमिटेड
NTPC LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION

PROJECT		TYPICAL THERMAL POWER PROJECT	
TITLE		INTERFACING OF FIELD INSTRUMENTS/ SWGR SWITCH (COC) TERMINATION DETAILS	
REV. NO.	SIZE	SCALE	DRG. NO.
A	A3	NTS	0000-999-POI-A-065
DESCRIPTION		SH 01 OF 14	
FIRST ISSUE		DATE	REV. NO.
		20.04.08	A
DRAWN DESIGN		APPD	
CHKD.		ARCH.	
C&I		C	
E		M	
CLEARED BY			

No part of this document is the property of NATIONAL THERMAL POWER CORPORATION LTD.
This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.
No part of this document will be reproduced by any means without the written permission.




* BI/Ge/Gr/Wt CORE SHALL BE TERMINATED IN TERMINAL 1 OR 3, 11 OR 13, 21 OR 23 AND 31 OR 33 RESPECTIVELY DEPENDING ON THE PARTICULAR TYPE OF CONTACT (NO OR NC) IS TO BE WIRED TO DDCMIS.

FOR TENDER PURPOSE ONLY

एन टी पी सी लिमिटेड NTPC LIMITED (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION		एन टी पी सी लिमिटेड NTPC		PROJECT TYPICAL THERMAL POWER PROJECT	
TITLE INTERFACING OF FIELD INSTRUMENTS SWITCH TERMINATION DETAILS NO/NC		DATE 29.04.08		REV. NO. A	
SIZE A3		SCALE NTS		DRG. NO. 0000-999-POI-A-065	
SH 02 OF 14		Cleared By: M E C C&I ARCH.		DRAWN DESIGN CHKD.	
DESCRIPTION		FIRST ISSUE		REV. NO.	

MARSHALLING/TERMINATION
CUBICLE

4 PAIR, 0.5 mmSq.



FOR TENDER PURPOSE ONLY


एन टी पी लिमिटेड
NTPC LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION

एन टी पी लिमिटेड
NTPC

PROJECT
TYPICAL THERMAL POWER PROJECT

TITLE
INTERFACING OF FIELD INSTRUMENTS
CONTROL VALVE

REV. NO.	SH	OF	REV. NO.
A	0000-999-POI-A-065	SH 03 OF 14	A
SCALE	SIZE	DATE	DATE
NTS	A3	29.04.06	
APPD	ARCH.	C&I	C
DESIGN	CHKD	CHKD	CHKD
DESCRIPTION	DESCRIPTION	DESCRIPTION	DESCRIPTION
A FIRST ISSUE			



FOR TENDER PURPOSE ONLY

ena Ti pl sal ilaimaToD
NTPC LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION


TYPICAL THERMAL POWER PROJECT

INTERFACING OF FIELD INSTRUMENTS
4-20mA

REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	CD	ARCH.	APPD	DATE	SIZE	SCALE	DRG. NO.	REV. NO.
C	NOTE REGARDING CABLE IS ADDED.										10.12.13				
B	INTERNAL WIRING FOR I.E./U/R MOUNTED SHOWN WIRING OF STAND ALONE TXTR SHOWN										10.12.06				
A	FIRST ISSUE										12.1.05				
														0000-999-POI-A-065	C
														SH 04 OF 14	

MARSHALLING/ TERMINATION CUBICLES


4 PAIR,
0.5 Sq. mm
MCC/SWGR



NOTE


1. FOR CHP DRIVES, THE SCHEME SHALL BE FINALISED DURING DETAILED ENGS.

FOR TENDER PURPOSE ONLY



एन टी पी सी लिमिटेड
NTPC LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION

ENGINEERING 21/11/2006																			
PROJECT		TYPICAL THERMAL POWER PROJECT																	
TITLE		INTERFACING OF FIELD INSTRUMENTS INTERFACE OF DDCMIS WITH MCC/SWGR/ACTUATOR (LT MOTORS)																	
REV. NO. A	A	FIRST ISSUE	DESCRIPTION	DRAWN 	DESIGN 	CHKD. 	M	E	C	C&D	ARCH.	APPD 	DATE 29.04.06	SIZE A3	SCALE NTS	DRG. NO. 0000-999-POI-A-065	REV. NO. A	SH 05 OF 14	
CLEARED BY																			





NOTE : 1) ABOVE IS THE TYP. ORG. FOR DIN RAIL MOUNTED TEMP TRANSMITTERS
FOR RTD APPLICATION. EXACT TYPE OF TEMP TRANSMITTER SHALL BE
AS PER PART-A OF SPECIFICATION.
2) THE EXACT GROUPING OF TEMP TXs SHALL BE FINALISED DURING
DETAILED ENGG. STAGE.

FOR TENDER PURPOSE ONLY



NTPC LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION

		TYPICAL THERMAL POWER PROJECT									
		INTERFACING OF FIELD INSTRUMENTS TYPICAL RTD CONNECTION WITH TEMP TRANSMITTERS IN JBS									
TITLE											
		29.04.06									
		DATE									
		APPD									
		ARCH.									
		C&I									
		C									
		E									
		M									
		CHKD.									
		DESIGN									
		DRAWN									
		A									
		FIRST ISSUE									
A											
REV.NO.		DESCRIPTION									
		SIZE									
		A3									
		SCALE									
		NTS									
		DRG. NO.									
		0000-999-POI-A-065									
		REV. NO.									
		C									
		SH. 06 OF 14									



NOTE:-


1. SPARE CORES AT MCC/SWGR END ARE TO BE TERMINATED AT SPARE TERMINALS.
2. OVERLOAD ALARM & RELAY FAULT ALONG WITH OTHER INFORMATION SHALL FLOW THROUGH SOFT LINK.

FOR TENDER PURPOSE ONLY

एन टी पी सी लिमिटेड
NTPC LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION

एन टी पी सी
NTPC


PROJECT		TYPICAL THERMAL POWER PROJECT	
TITLE		INTERFACING OF FIELD INSTRUMENTS INTERFACE OF DDCMIS WITH MCC/SWGR/ACTUATOR (HT MOTORS)	
REV. NO.	SCALE	DRG. NO.	REV. NO.
B	A3	0000-999-POI-A-065	B
DATE		SH 07 OF 14	
DRAWN		CHECKED BY	
DESIGN		C&I ARCH.	
DESCRIPTION		CLEARED BY	
Revised for Numerical relay based SWGR		14.02.00	



- 1) * FEEDBACKS OF SOVs CAN BE GROUPED IN FIELD JB AND MULTI PAIR CABLE IS TO BE USED FROM FIELD JB TO MARSHALLING/TERMINATION CUBICLE FOR FEEDBACKS OF GROUP OF SOVs. TYP ARRANGEMENT IS SHOWN FOR A GROUP OF TWO SOVs WITH OPEN AND CLOSE LIMIT SWITCHES.
- 2) NO. OF LIMIT SWITCHES/NO. OF CONTACT IN LIMIT SWITCHES SHALL BE PROVIDED FOR EACH VALVE AS PER SPEC. REQUIREMENT/ PHILOSOPHY FOR RESPECTIVE SYSTEM.
- 3) ** MULTIPAIR CABLE IS TO BE USED FOR CONNECTION OF COMMAND OUTPUTS FROM MARSHALLING/TERMINATION CUBICLE TO RELAY PANEL FOR A GROUP OF SOVs.

National Thermal Power Corporation Ltd. (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION	
PROJECT TYPICAL THERMAL POWER PROJECT	
TITLE INTERFACING OF FIELD INSTRUMENTS INTERFACE OF DDCMIS WITH MCC/SWGR/ACTUATOR (SINGLE COIL SOLENOID)	
REV. NO. B	DATE 30.10.02
REV. NO. C	DATE
SIZE A3	SCALE NTS
DRG. NO. 0000-999-POI-A-065	SH 08 OF 14
CLEARED BY	
DRAWN DESIGN CHKO.	
DESCRIPTION	

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.
No part of this document will be reproduced by any means without the written permission.




- NOTE: 1) ABOVE IS THE TYP DRG. FOR DIN RAIL MOUNTED TEMP TRANSMITTER FOR T/C APPLICATION. EXACT TYPE OF TEMP TRANSMITTERS SHALL BE AS PER PART-A OF SPECIFICATION.
- 2) THE EXACT GROUPING OF TEMP TxS SHALL BE FINALISED DURING DETAILED ENGG. STAGE.
- 3) AFTER GLANDING OF T/C CABLES ON JB, THE CABLE PAIR OF FIRST ELEMENT WILL BE DIRECTLY CONNECTED TO TT AND FOR CABLE PAIR OF SECOND ELEMENT LOOP SHALL BE KEPT, BEFORE TERMINATION AT INPUT TBs FOR FUTURE USE.

FOR TENDER PURPOSE ONLY

NTPC LIMITED (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION		PROJECT		TYPICAL THERMAL POWER PROJECT	
TITLE		INTERFACING OF FIELD INSTRUMENTS		TYPICAL T/C CONNECTION WITH TEMP TxS IN JBS	
REV. NO.	0000-999-POI-A-065	DRG. NO.	SH 11 OF 14	SCALE	NTS
SIZE	A3	DATE	29.04.06	APPD	ARCH.
DESCRIPTION		DRAWN DESIGN CHKD.		CLEARED BY	
A	FIRST ISSUE	M		E C C&I	

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD.
No part of this document will be reproduced by any means without the written permission.



SECTION A-A

WALL TYPE
HANDSET STATION

NOTES

1. LOCATIONS SHALL BE FINALISED DURING DETAILED ENGINEERING.

FOR TENDER PURPOSE ONLY



एन टी पी सी लिमिटेड
NTPC LIMITED
(A GOVERNMENT OF INDIA ENTERPRISE)
ENGINEERING DIVISION

PROJECT		TYPICAL THERMAL POWER PROJECT									
TITLE		ACOUSTIC HOOD OUT LINE									
REV. NO.	DESCRIPTION	DRAWN	DESIGN	CHKD.	M	E	C	C&I	ARCH.	APPD	DATE
A	FIRST ISSUE										20.04.08
SCALE		SIZE		DRG. NO.		SCALE		N.T.S.		REV. NO.	
		A3		0000-999-POI-A-070						A	



INSTRUMENTATION CABLE INTERCONNECTION AND TERMINATION PHILOSOPHY

CLAUSE NO.	TECHNICAL REQUIREMENTS																																																				
3.07.00																																																					
4.00.00																																																					
5.00.00																																																					
	INSTRUMENTATION CABLE INTERCONNECTION AND TERMINATION PHILOSOPHY																																																				
	The cable interconnection philosophy to be adopted shall be such that extensive grouping of signals by large scale use of field mounted Group Junction Boxes (JBs) at strategic locations (where large concentration of signals are available, e.g. valves limit & torque switches, switchgear) is done and consequently cable with higher number of pairs are extensively used. The details of termination to be followed are mentioned in the given Table A.																																																				
	TABLE A: CABLE TERMINATION TO BE FOLLOWED																																																				
	<table><tr><th colspan="2">Application</th><th colspan="2">Type Of Termination</th><th rowspan="2">Type Of Cable</th></tr><tr><th>FROM (A)</th><th>TO (B)</th><th>END A</th><th>END B</th></tr><tr><td>Valves/dampers drives (Integral Junction box)</td><td>Marshalling / Marshalling – cum Termination Cubicle / local group JB</td><td>Plug in connector</td><td>Post mount cage clamp type.</td><td>G</td></tr><tr><td>Transmitters, Process Actuated switches mounted in LIE/LIR</td><td>Integral Junction box of LIE/LIR</td><td>Plug in connector</td><td>Cage clamp (Rail mount) type.</td><td>F,G</td></tr><tr><td>RTD heads</td><td>Local junction box</td><td>Plug in connector</td><td>Cage clamp (Rail mount) type.</td><td>F</td></tr><tr><td>Thermocouple</td><td>Local junction box / CJC box (if applicable)</td><td>Plug in connector</td><td>Cage clamp (Rail mount) type.</td><td>A, B, C*</td></tr><tr><td>Other Field mounted Instrument</td><td>Local JB / Group JB</td><td>Plug in connector</td><td>Cage clamp (Rail mount) type.</td><td>F,G</td></tr><tr><td>RTD</td><td>Temperature transmitter</td><td>Plug in connector</td><td>Screwed, Cage clamp type</td><td>F</td></tr><tr><td>Thermocouple</td><td>Temperature transmitter</td><td>Plug in connector</td><td>Screwed, Cage clamp type</td><td>A, B, C*</td></tr><tr><td>Local Junction box, Temperature Transmitter, Int. Junction box of LIE/ LIR/ MCC/SWGR</td><td>Group JB</td><td>Cage clamp (Rail mount) type.</td><td>Cage clamp (Rail mount) type.</td><td>F,G</td></tr></table>				Application		Type Of Termination		Type Of Cable	FROM (A)	TO (B)	END A	END B	Valves/dampers drives (Integral Junction box)	Marshalling / Marshalling – cum Termination Cubicle / local group JB	Plug in connector	Post mount cage clamp type.	G	Transmitters, Process Actuated switches mounted in LIE/LIR	Integral Junction box of LIE/LIR	Plug in connector	Cage clamp (Rail mount) type.	F,G	RTD heads	Local junction box	Plug in connector	Cage clamp (Rail mount) type.	F	Thermocouple	Local junction box / CJC box (if applicable)	Plug in connector	Cage clamp (Rail mount) type.	A, B, C*	Other Field mounted Instrument	Local JB / Group JB	Plug in connector	Cage clamp (Rail mount) type.	F,G	RTD	Temperature transmitter	Plug in connector	Screwed, Cage clamp type	F	Thermocouple	Temperature transmitter	Plug in connector	Screwed, Cage clamp type	A, B, C*	Local Junction box, Temperature Transmitter, Int. Junction box of LIE/ LIR/ MCC/SWGR	Group JB	Cage clamp (Rail mount) type.	Cage clamp (Rail mount) type.	F,G
Application		Type Of Termination		Type Of Cable																																																	
FROM (A)	TO (B)	END A	END B																																																		
Valves/dampers drives (Integral Junction box)	Marshalling / Marshalling – cum Termination Cubicle / local group JB	Plug in connector	Post mount cage clamp type.	G																																																	
Transmitters, Process Actuated switches mounted in LIE/LIR	Integral Junction box of LIE/LIR	Plug in connector	Cage clamp (Rail mount) type.	F,G																																																	
RTD heads	Local junction box	Plug in connector	Cage clamp (Rail mount) type.	F																																																	
Thermocouple	Local junction box / CJC box (if applicable)	Plug in connector	Cage clamp (Rail mount) type.	A, B, C*																																																	
Other Field mounted Instrument	Local JB / Group JB	Plug in connector	Cage clamp (Rail mount) type.	F,G																																																	
RTD	Temperature transmitter	Plug in connector	Screwed, Cage clamp type	F																																																	
Thermocouple	Temperature transmitter	Plug in connector	Screwed, Cage clamp type	A, B, C*																																																	
Local Junction box, Temperature Transmitter, Int. Junction box of LIE/ LIR/ MCC/SWGR	Group JB	Cage clamp (Rail mount) type.	Cage clamp (Rail mount) type.	F,G																																																	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION-IIIC-07 INSTRUMENTATION CABLES	PAGE 7 OF 13																																																

Page 523 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS				एनटीपीसी NTPC
	Application		Type Of Termination		Type Of Cable
	FROM (A)	TO (B)	END A	END B	
	Local Junction box, Temperature Transmitter, Int. Junction box of LIE/ LIR/ Group JB / MCC/SWGR	Marshalling / Marshalling – cum Termination Cubicle	Cage clamp (Rail mount) type.	Cage clamp (Post mounted) type.	F,G
	Marshalling cubicle/ Termination Cabinet	Electronic system cabinet	Cage clamp (Post mounted) type.	Plug-in connector / other system as per Mfr.'s Standard	Internal wiring
	Marshalling/ Termination System Cabinets	UCD mounted equipments	Cage clamp (Post mounted) type.	Plug in connector / Cage clamp type (rail mounted).	F,G (with plug-in connect or at one end)
	DDCMIS/PLC cabinets	PC, Printers etc.	Plug in connector	Plug in connector	Mfr.'s Standard
	Notes 1 Normally 10% spare cores shall be provided when the numbers of pairs of cables are more than four pairs, except for pre-fabricated cables which shall be as per manufacturer's standard. 2 For analog signals, individual pair shielding & overall shielding & for Binary signals, only overall shielding of instrumentation cables shall be provided. 3 * For high temperature applications only. 4 . For connection between field/JB and DDCMIS marshalling cabinet minimum 4 pair instrumentation cable shall be used. 5 All the spare cores of instrumentation cable have to be terminated in Marshalling cabinets/ DCS panel end. 6 For Cable type and cable termination scheme for the instruments/ equipment that are connected to Steam Turbine and Generator (STG) control system defined at Part A, sub section IIC, clause no. 2.03.01 (a) (ii) above and hydrogen generation plant auxiliaries system, Contractor's standard and proven practice is also acceptable. However, for termination of instrumentation cable at marshalling cabinets/DCS panel end, cage-clamp termination shall be offered. For power and control cable termination, Contractor's standard and proven practice would be acceptable				
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION-IIC-07 INSTRUMENTATION CABLES	PAGE 8 OF 13

CLAUSE NO.	TECHNICAL REQUIREMENTS		एनटीपीसी NTPC	
6.00.00	TERMINAL BLOCKS			
6.01.00	All terminal blocks shall be rail mounted/post mounted, cage clamp type with high quality non-flammable insulating material of melamine suitable for working temperature of 105 deg. C. The terminal blocks in field mounted junction boxes, temperature transmitters, instrument enclosures/racks, etc., shall be suitable for cage clamp connections. The terminal blocks in Control Equipment Room logic/termination/marshalling cubicles shall be suitable for post mounted cage clamp connection at the field input end. The exact type of terminal blocks to be provided by the Bidder and the technical details of the same including width etc. shall be subject to Employer's approval.			
6.02.00	All the terminal blocks shall be provided complete with all required accessories including assembly rail, locking pin and section, end brackets, partitions, small partitions, transparent covers, support brackets, distance sleeves, warning label, marking, etc.			
6.03.00	The marking on terminal strips shall correspond to the terminal numbering on wiring diagrams. At least 20% spare unused terminals shall be provided everywhere including local junction boxes, instrument racks/enclosures, termination/marshalling cabinets, etc. All terminal blocks shall be numbered for identification and grouped according to the function. Engraved labels shall be provided on the terminal blocks.			
6.04.00	For terminating each process actuated switches, drive actuators, control valves, Thermocouple, RTD, etc. in Local Junction Boxes, etc, refer Drg no. 0000-999-POI-A-065.			
6.05.00	The terminal blocks shall be arranged with at least 100 mm clearance between two sets of terminal blocks and between terminal blocks and junction box walls.			
7.00.00	INTERNAL PANELS/ SYSTEM CABINETS WIRING			
7.01.00	Internal panel/cabinet wiring shall be of multi-stranded copper conductor with FRLS PVC insulation without shield and outer sheath meeting the requirements of VDE 0815.			
7.02.00	All internal wires shall be provided with tag and identification nos. etched on tightly fitted ferules at both ends. All wires directly connected to trip devices shall be distinguished by one additional red colour ferrule.			
7.03.00	All external connection shall be made with one wire per termination point. Wires shall not be tapped or spliced between terminal points.			
7.04.00	All floor slots of desk/panels/cabinets used for cable entrance shall be provided with removable gasketed gland plates and sealing material. Split type grommets shall be used for prefabricated cables.			
7.05.00	All the special tools as may be required for solder less connections shall be provided by Bidder.			
7.06.00	Wire sizes to be utilised for internal wiring.			
	(i)	Current (4-20 mA), low voltage signals (48V); Ammeter/Voltmeter circuit, control switches etc. for electrical system.	0.5 Sq.mm.	
	(ii)	Power supply and internal illumination.	2.5Sq.mm. minimum (shall be as per load requirement.)	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-07 INSTRUMENTATION CABLES	PAGE 9 OF 13

Page 525 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
8.00.00 8.01.00 8.02.00 8.03.00 8.04.00 8.05.00	INSTRUMENTATION CABLE INSTALLATION AND ROUTING All cables assigned to a particular duct/conduit shall be grouped and pulled in simultaneously using cable grips and suitable lubricants. Cables removed from one duct/conduit shall not be reused without approval of Employer. Cables shall be segregated as per IEEE Std.-422. In vertically stacked trays, the higher voltage cable shall be in higher position and instrumentation cable shall be in bottom tier of the tray stack. The distance between instrumentation cables and those of other system shall be as follows: From 11 kV/6.6 kV/3.3 kV tray system - 914 mm From 415V tray system - 610 mm From control cable tray system - 305 mm Cables shall terminate in the enclosure through cable glands. All cable glands shall be properly gasketed. Sealing (to prevent ingress of dust entry and propagation of fire) shall be provided for all floor slots used for cable entrance. Compression cable glands (double for armoured and single for other cables) shall be provided. Not in use The cables emanating from redundant equipment/devices shall be routed through different paths. The above segregation of cables & wiring for redundant equipments/devices shall be in accordance with IEEE-Std-422.			
9.00.00 9.01.00	CABLE LAYING AND ACCESSORIES CABLE LAYING 1 Cables shall be laid strictly in line with cable schedule. 2 Identification tags for cables. Indelible tags to be provided at all terminations, on both sides of wall or floor crossing, on each conduit/duct/pipe entry/exit, and at every 20 m in cable trench/tray. 3 Cable tray numbering and marking. To be provided at every 10m and at each end of cable way & branch connection. 4 No jointing is permissible for Instrumentation cables. For other cables Jointing for more than 250 Meters run of cable shall be permitted. 5 Buried cable protection With concrete slabs; Route markers at every 20 Meters along the route & at every bend. 6 Road Crossings Cables to pass through buried high density PE pipes encased in PCC. At least 300			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-07 INSTRUMENTATION CABLES	PAGE 10 OF 13 Page 526 of 1005	

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	mm clearance shall be provided between - HT power & LT power cables, - LT power & LT control/instrumentation cables, Spacing between cables of same voltage grade shall be in accordance with the derating criteria adopted for cable sizing. 7 Segregation (physical isolation to prevent fire jumping) - a All cable associated with the unit shall be segregated from cables of other Units. - b Interplant cables of station auxiliaries and unit critical drives shall be segregated in such a way that not more than half of the drives are lost in case of single incident of fire. 8 Cable clamping All cables laid on trays shall be neatly dressed up & suitably clamped/tied to the tray. For cables in trefoil formation, trefoil clamps shall be provided. 9 Optical fiber cables (OFCs) : Outside Building Area - to be laid necessarily inside GI conduit with support from cable tray/Trestle structure Inside Building Area – to be laid on separate cable sub-trays While buried- in separate buried trench approx.1.0 meter depth, to be laid in 2" rodent proof HDPE conduits covered with sand, brick, laid breadth-wise and soil along the pipe line route by contractor; While crossing roads - to be laid in GI/ rodent proof HDPE conduits with sand filling at bottom and sand, soil filling at top with cement concrete; While crossing canals/river- to be laid in rodent proof HDPE conduits within hume pipe. 10 Laying of Network Cable (UTP/STP) : Out side Building Area- to be laid necessarily inside GI conduits with support from cable tray / Trestle structure. Inside Building Area- to be laid necessarily inside GI conduits on separate cable sub-trays. 9.02.00 Bidder shall supply and install all cable accessories and fittings like Light Interface Units, Surge suppressors, Opto isolators, Interface Converters, Fibre Optic Card Cage, Fibre Optic Line Driver, Repeater / Modem (for Optical Fibre Cables), cable glands, grommets, lugs, termination kits etc. on as required basis. 9.03.00 Cables, which terminate in cabinets of draw out sections shall have sufficient cable coiled in the bottom of the cabinet to permit full withdrawal of draw out sections without disconnecting the cables. When prefabricated cables with factory connectors on both ends are longer than required, the excess cable shall be coiled in the bottom of one or both termination cabinets.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-07 INSTRUMENTATION CABLES	PAGE 11 OF 13 Page 527 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
9.04.00	The Bidder shall be responsible for proper grounding of all equipment under this package. Further, proper termination of cable shields shall be verified and the grounding of the same shall be coordinated so as to achieve grounding of all instrumentation cable shields at same potential. This shall be completed prior to system tests.			
9.05.00	The Contractor shall take full care while laying / installing cables as recommended by cable manufacturers regarding pulling tensions and cable bends. Cables damaged in any way during installation shall be replaced at the expense of the Contractor.			
10.00.00	FIELD MOUNTED LOCAL JUNCTION BOXES (i) No. of ways 12/24/36/48/64/72/96/128 with 20% spares terminals. (ii) Material and Thickness 4mm thick Fiberglass Reinforced Polyester (FRP). (iii) Type Screwed at all four corners for door. Door gasket shall be of synthetic rubber. (iv) Mounting clamps and accessories Suitable for mounting on walls, columns, structures etc. The brackets, bolts, nuts, screws, glands required for erection shall be of SS, included in Bidders scope of supply. (v) Type of terminal blocks Rail mounted cage-clamp type suitable for conductor size upto 2.5 mm ² . A M6 earthing stud shall be provided. (vi) Protection Class IP: 55 minimum for indoor & IP-65 minimum for outdoor applications. (vii) Grounding To be provided. (viii) Color RAL 7035			
11.00.00	CONDUITS			
11.01.00	Conduits shall be generally used for interconnecting cables from field instruments to Local JB's. All rigid conduits, couplings and elbows shall be hot dipped galvanised rigid mild steel in accordance with IS: 9537 Part-I (1980) and Part-II (1981). The conduit interior and exterior surfaces shall have continuous zinc coating with an overcoat of transparent enamel lacker or zinc chromate. Flexible conduit shall be heat resistant lead coated galvanized steel with , water leak, fire and rust proof protected <i>for the areas of Mills,Drum, Main Steam, RH steam Air Heaters and Furnace, BFPDT's</i> . <i>And for remaining applications, water leak, fire and rust proof flexible GI conduits shall be provided.</i> The temperature rating of flexible conduit shall be suitable for actual application.			
11.02.00	All rigid conduit fittings shall conform to the requirements of IS: 2667, 1976. Galvanized steel fitting shall be used with steel conduit. All flexible conduit fittings shall be liquid tight, galvanized steel. The end fittings shall be compatible with the flexible conduit supplied.			
11.03.00	Conduit sealing, explosion proof, dust proof and other types of special fittings shall be provided as required by these specifications and shall be consistent with the area and equipment with which they are installed. Fittings installed outdoors and in damp locations shall be sealed and gasketed. Hazardous area fittings and conduits sealing shall conform			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-07 INSTRUMENTATION CABLES	PAGE 12 OF 13 Page 528 of 1005



**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

QUALITY ASSURANCE-INSTRUMENTS

|

SUB-SECTION–E-61

MEASURING INSTRUMENTS (PRIMARY & SECONDARY)

MEASURING INSTRUMENTS (PRIMARY AND SECONDARY)

TESTS ITEMS									
	Dimensions (R)	Make, Model, Type, Rating (R)	Process / Electrical connection (R)	Calibration (R)	Test as per standard(R)	Insulation Resistance (R)	IBR Certification (if applicable)(R)	Hydro Test(R)	Material Test certificate ®
1. PR Gauge (IS-3624)	Y	Y	Y	Y	Y				
2. Temp. Gauge (BS-5235)	Y	Y	Y	Y	Y				
3. Pr./D.P.Switch(BS-6134)	Y	Y	Y	Y	Y	Y			
4. Electronic Transmitter(IEC-770)	Y	Y	Y	Y	Y	Y			
5. Temp. Switch	Y	Y	Y	Y	Y	Y			
6. Recorder(IS-9319/ANSI C-39.4)	Y	Y	Y	Y	Y	Y			
7. Vertical indicators	Y	Y	Y	Y		Y			
8. Digital Indicators	Y	Y	Y	Y		Y			
9. Integrators	Y	Y	Y	Y					
10. Electrical Metering Instrument (IS-1248)	Y	Y	Y	Y	Y	Y			
11. Transducer (IEC-688)	Y	Y	Y	Y	Y	Y			
12. Thermocouples (IEC – 754 / ANSI-MC-96.1)	Y	Y	Y	Y	Y	Y			
13. RTD(IEC-751)	Y	Y	Y	Y	Y	Y			
14. Thermowell	Y		Y				Y	Y	Y
R-Routine Test A- Acceptance Test Y – Test applicable									
: Note: 1) Detailed procedure of Environmental Stress Screening shall be as per Quality Assurance Programme in General Technical Conditions. Requirement of test and procedure (if required) finalized during QP finalization									
2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted alongwith relevant supporting documents.									

SUB-SECTION–E-61A

MEASURING INSTRUMENTS (PRIMARY & SECONDARY)

MEASURING INSTRUMENTS (PRIMARY AND SECONDARY)

TESTS ITEMS									
	Dimensions (R)	Make, Model, Type, Rating (R)	Process / Electrical connection (R)	Calibration (R)	Test as per standard(R)	Insulation Resistance (R)	IBR Certification (if applicable)(R)	Hydro Test(R)	Material Test certificate ®
1. PR Gauge (IS-3624)	Y	Y	Y	Y	Y				
2. Temp. Gauge (BS-5235)	Y	Y	Y	Y	Y				
3. Pr./D.P.Switch(BS-6134)	Y	Y	Y	Y	Y	Y			
4. Electronic Transmitter(IEC-770)	Y	Y	Y	Y	Y	Y			
5. Temp. Switch	Y	Y	Y	Y	Y	Y			
6. Recorder(IS-9319/ANSI C-39.4)	Y	Y	Y	Y	Y	Y			
7. Vertical indicators	Y	Y	Y	Y		Y			
8. Digital Indicators	Y	Y	Y	Y		Y			
9. Integrators	Y	Y	Y	Y					
10. Electrical Metering Instrument (IS-1248)	Y	Y	Y	Y	Y	Y			
11. Transducer (IEC-688)	Y	Y	Y	Y	Y	Y			
12. Thermocouples (ANSI-MC-96.1)	Y	Y	Y	Y	Y	Y			
13. RTD(IEC-751)	Y	Y	Y	Y	Y	Y			
14. Thermowell	Y		Y				Y	Y	Y
R-Routine Test A- Acceptance Test Y – Test applicable									
:									

ITEMS	TESTS											
	Dimensions (R)	Make, Model, Type, Rating (R)	Process / Electrical connection (R)	Calibration (R)	Requirement as per standard (R)	WPS approval (A)	Non-destructive testing (R)	Calculation for accuracy (R)	Insulation Resistance (R)	IBR Certification as applicable (R)	Hydro test (R)	Material test certificate (A)
15. Cold junction compensation box	Y	Y	Y	Y					Y			
16. Orifice plate(BS-1042)	Y	Y	Y	Y *	Y	Y **	Y **			Y	Y **	Y
17. Flow nozzle(BS-1042)	Y	Y	Y	Y *	Y	Y	Y			Y	Y	Y
18. Impact head type element	Y	Y	Y					Y				Y
19. Level transmitter/float type switch	Y	Y	Y	Y					Y	Y	Y	Y
20. Flue Gas analyser	Y	Y	Y	Y								
21. Dust emission monitors	Y	Y	Y	Y								
*Calibration to be carried out on one flow element of each type and size if calibration carried out as type test same shall not be repeated.												
** If applicable												
R-Routine Test A- Acceptance Test Y – Test applicable												
Note: 1) Detailed procedure of Environmental Stress screening test shall be as per Quality Assurance. Programme in General Technical Conditions 2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the Practices and Procedure adopted alongwith relevant supporting documents.												

ELECTRICAL ACTUATOR WITH INTEGRAL STARTER

Test/Attributes Characteristics													
ITEM/ COPONENT/ SUB SYSTEM ASSEMBLY/ TESTING	RPM ®	No Load Current ®	IR & HV Test®	Mounting Dimension®	All routine Test as per Standard & Specification®	Correct Phase Sequence®	Operation & Setting of limit Switch/Torque Switch®	Stall Torque/Current (A)	Hand Wheel operation/ Auto de clutch function (A)	Function of Aux. like Potentiometer, space heater, position indicator ®	EPT output ®	Grease leakage ®	Local/ Remote (Open-Stop-Close) Operation® Safety check (Single phasing, Phase correction, Tripping etc.) (A)
ELECTRICAL ACTUATOR WITH INTEGRAL STARTER(IS_9334)													
Motor	Y	Y	Y	Y	Y								
Final Testing	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y	Y
Note: 1) Detailed procedure of Environmental Stress Screening test shall be as per Quality Assurance Programme in General Technical Conditions. Requirement of test and procedure finalized during QP finalization 2) This is an indicative list of tests/checks. The manufacturer is to furnish a detailed quality plan indicating the practices and procedure adopted along with relevant supporting documents. ® - Routine Test (A) - Acceptance Test Y - Test applicable													

SUB-SECTION – IIC-10

TYPE TEST REQUIREMENTS

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC		
1.00.00 1.01.00 1.01.01 1.01.02 1.01.03 1.01.04 1.01.05	TYPE TEST REQUIREMENTS General Requirements The Contractor shall furnish the type test reports of all type tests as per relevant standards and codes as well as other specific tests indicated in this specification. If the bidder proposes a different standard/code from that indicated at table 3.00.00, same is acceptable provided the equivalence of the proposed standard is established by the bidder. A list of such tests are given for various equipment in table titled 'TYPE TEST REQUIREMENT FOR C&I SYSTEMS' at the end of this chapter and under the item Special Requirement for Solid State Equipments/Systems. For the balance equipment instrument, type tests may be conducted as per manufactures standard or if required by relevant standard. (a) Out of the tests listed, the Bidder/ sub-vendor/ manufacturer is required to conduct certain type tests specifically for this contract (and witnessed by Employer or his authorized representative) even if the same had been conducted earlier, as clearly indicated subsequently against such tests. (b) For the rest, submission of type test results and certificate shall be acceptable provided. i. The same has been carried out by the Bidder/ sub-vendor on exactly the same model /rating of equipment. ii. There has been no change in the components from the offered equipment & tested equipment. iii. The test has been carried out as per the latest standards alongwith amendments as on the date of Bid opening. (c) In case the approved equipment is different from the one on which the type test had been conducted earlier or any of the above grounds, then the tests have to be repeated and the cost of such tests shall be borne by the Bidder/ sub-vendor within the quoted price and no extra cost will be payable by the Employer on this account. As mentioned against certain items, the test certificates for some of the items shall be reviewed and approved by the main Bidder or his authorized representative and the balance have to be approved by the Employer. The schedule of conduction of type tests/ submission of reports shall be submitted and finalized during pre-award discussion. For the type tests to be conducted, Contractor shall submit detailed test procedure for approval by Employer. This shall clearly specify test setup, instruments to be used, procedure, acceptance norms (wherever applicable), recording of different parameters, interval of recording precautions to be taken etc. for the tests to be carried out. The Bidder shall indicate in the relevant BPS schedule, the cost of the type test for each item only for which type tests are to be conducted specifically for this project. The cost shall only be payable after conduction of the respective type test in presence of authorize representative of Employer. If a test is waived off, then the cost shall not be payable.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-10 TYPE TEST REQUIREMENTS	PAGE 1 OF 9	

CLAUSE NO.	TECHNICAL REQUIREMENTS			
2.00.00 2.01.00	SPECIAL REQUIREMENT FOR SOLID STATE EQUIPMENTS/ SYSTEMS The minimum type test reports, over and above the requirements of above clause, which are to be submitted for each of the major C&I systems shall be as indicated below: i) Surge Withstand Capability (SWC) for Solid State Equipments/ Systems All solid state systems/ equipments shall be able to withstand the electrical noise and surges as encountered in actual service conditions and inherent in a power plant. All the solid state systems/ equipments shall be provided with all required protections that needs the surge withstand capability as defined in ANSI 37.90.1/ IEEE-472. Hence, all front end cards which receive external signals like Analog input & output modules, Binary input & output modules etc. including power supply, data highway, data links shall be provided with protections that meets the surge withstand capability as defined in ANSI 37.90.1/ IEEE-472. Complete details of the features incorporated in electronics systems to meet this requirement, the relevant tests carried out, the test certificates etc. shall be submitted along with the proposal. As an alternative to above, suitable class of EN 61000-4-12 which is equivalent to ANSI 37.90.1/ IEEE-472 may also be adopted for SWC test. ii) Dry Heat test as per IEC-68-2-2 or equivalent. iii) Damp Heat test as per IEC-68-2-3 or equivalent. iv) Vibration test as per IEC-68-2-6 or equivalent. v) Electrostatic discharge tests as per EN 61000-4-2 or equivalent. vi) Radio frequency immunity test as per EN 61000-4-6 or equivalent. vii) Electromagnetic Field immunity as per EN 61000-4-3 or equivalent. Test listed at item no. v, vi, vii, above are applicable for electronic cards only as defined under item (i) above.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-10 TYPE TEST REQUIREMENTS	PAGE 2 OF 9	

CLAUSE NO.	TECHNICAL REQUIREMENTS						एनटीपीसी NTPC
3.00.00	TYPE TEST REQUIREMENT FOR C&I SYSTEMS						
	Sl. No	Item	Test Requirement	Standard	Test To Be Specifically Conducted	NTPC's Approval Req. On Test Certificate	
	Col 1	Col 2	Col 3	Col 4	Col 5	Col 6	
	1	Elect. Metering instruments	As per standard (col 4)	IS-1248	No	Yes	
	2	Transducers	As per standard (col 4)	IEC-60688,IS12784	No	Yes	
	3	Thermocouple	Degree of protection test	IS-13947	No	No	
	4	RTD	As per standard (col 4)	IEC-60751	No	No	
	5	Electronic transmitter	As per standard (col 4)	BS-6447 / IEC-60770	No	Yes	
	6	E/P converter	As per standard (col 4)	Mfr. standard	No	No	
	7	Dust emission monitor	Degree of protection test	IS-13947	No	Yes	
	8	Instrumentation Cables Twisted & Shielded*					
		-Conductor	Resistance test	VDE-0815	No	Yes	
			Diameter test	IS-10810	No	Yes	
			Tin Coating test (Persulphate test)	IS-8130	No	Yes	
		-Insulation	Loss of mass	VDE 0472	No	Yes	
		Ageing in air ovens**	VDE 0472	No	Yes		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)			TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION-IIIC-10 TYPE TEST REQUIREMENTS		PAGE 3 OF 9

Page 540 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS				एनटीपीसी NTPC																								
	* 1.0 All cables to be supplied shall be of type tested quality. The Contractor shall submit for Owner's approval the reports of all the type tests as listed in this specification and carried out within last Ten years from the date of bid opening. These reports should be for the tests conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. 2.0 In case the Contractor is not able to submit report of the type test(s) conducted within last Ten years from the date of bid opening, or in case the type test report(s) are not found to be meeting the specification requirements, the Contractor shall conduct all such tests either in an independent laboratory or at manufacturer's works in presence of Owner's representative under this contract free of cost to the Owner and submit the reports for approval. **These tests shall be carried out as per VDE0207 Part 6 & ASTM-D-2116 for TEFLON insulated & outer sheathed cables ***Applicable for armoured cables only 9 DC Power Supply System (Applicable for each model and rating) 1)The Type Test reports for offered rectifier module and the controller module irrespective of the rectifier bank shall be acceptable <table><tr><td>Surge Withstand Capability(SWC)</td><td>ANSI 37.90.1, No IEEE-472,EN 61000-4-12</td><td>Yes</td></tr><tr><td>Dry Heat Test</td><td>IEC-68-2-2 or No equivalent</td><td>Yes</td></tr><tr><td>Damp Heat test</td><td>IEC-68-2-3 or No equivalent</td><td>Yes</td></tr><tr><td>Vibration test</td><td>IEC68-2-6 or No equivalent</td><td>Yes</td></tr><tr><td>Electrostatic discharge test</td><td>EN 61000-4-2 No orr equivalent</td><td>Yes</td></tr><tr><td>Radio frequency immunity test</td><td>EN-61000-4-3 No orr equivalent</td><td>Yes</td></tr><tr><td>Electromagnetic field immunity</td><td>EN 61000-4-3 No orr equivalent</td><td>Yes</td></tr><tr><td>Degree of Protection</td><td>IS-13947 or No equivalent</td><td>Yes</td></tr></table>					Surge Withstand Capability(SWC)	ANSI 37.90.1, No IEEE-472,EN 61000-4-12	Yes	Dry Heat Test	IEC-68-2-2 or No equivalent	Yes	Damp Heat test	IEC-68-2-3 or No equivalent	Yes	Vibration test	IEC68-2-6 or No equivalent	Yes	Electrostatic discharge test	EN 61000-4-2 No orr equivalent	Yes	Radio frequency immunity test	EN-61000-4-3 No orr equivalent	Yes	Electromagnetic field immunity	EN 61000-4-3 No orr equivalent	Yes	Degree of Protection	IS-13947 or No equivalent	Yes
Surge Withstand Capability(SWC)	ANSI 37.90.1, No IEEE-472,EN 61000-4-12	Yes																											
Dry Heat Test	IEC-68-2-2 or No equivalent	Yes																											
Damp Heat test	IEC-68-2-3 or No equivalent	Yes																											
Vibration test	IEC68-2-6 or No equivalent	Yes																											
Electrostatic discharge test	EN 61000-4-2 No orr equivalent	Yes																											
Radio frequency immunity test	EN-61000-4-3 No orr equivalent	Yes																											
Electromagnetic field immunity	EN 61000-4-3 No orr equivalent	Yes																											
Degree of Protection	IS-13947 or No equivalent	Yes																											
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2	SUB-SECTION-IIIC-10 TYPE TEST REQUIREMENTS	PAGE 6 OF 9																										

Page 541 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS						
	13	Voltage Stabilisers	Over Load Test	Approved procedure	No	Yes	
			Temp rise test without redundant fans	Approved procedure	No	Yes	
	14	Public Address System					
		- Amplifiers	As per standard (col 4)	IS 9302, Part-II	No	Yes	
		Microphones	As per standard (col 4)	IS 9302, Part-III IS 15482:2004/ IEC 61842(2002)	No	Yes	
		Loudspeaker	As per standard (col 4)	IS 9302, Part-IV	No	Yes	
	15	LIE / LIR	Degree of protection test	IS-13947	No	Yes	
	16	Flue gas analyzers	Degree of protection test	IS-13947	No	Yes	
	17	Master Clock	Functional test	As per approved procedure	No	Yes	
	18	CJC Box	Degree Of protection test	IS-13947	No	Yes	
19	Junction Box	Degree Of protection Test	IS-13947	No	Yes		
20	OPC Access Server, Data Exchange & Server	OPC Compliance Testing		No	Yes (Self certification is also		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)			TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION-IIIC-10 TYPE TEST REQUIREMENTS		PAGE 8 OF 9

Page 542 of 1005

CLAUSE NO.	TECHNICAL REQUIREMENTS							एनटीपीसी NTPC
	Historical Data Access Server acceptable) 21 Conductivity Type Level Switch Degree protection test of IS-2147 No No 22 Local Gauges Degree protection test of IS-2147 No No 23 Process actuated Switches Degree protection test of IS-2147 No No 24 Control Valves CV test ISA 75.02& 75.11 No Yes 25 PLCs As per standard (Col 4) IEC 1131 No No 26 Flow Nozzle Orifice plates Calibration ASME PTC BS 1042 No Yes ## The contractor shall submit for Employers approval the reports of all the type test as per latest IS-10918 carried out within last ten years from the date of Bid opening and the test(s) should have been either conducted at an independent laboratory or in presence / owners representative. The complete type test reports shall be for any rating of Battery in a particular group based on plate dimensions being manufactured by supplier. Note: Type Tests are to be conducted only for the items, which are being supplied as a part of this Package.							
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)			TECHNICAL SPECIFICATIONS SECTION – VI, PART-B BID DOC. NO.: CS:9585-001-2		SUB-SECTION-IIIC-10 TYPE TEST REQUIREMENTS		PAGE 9 OF 9	

Page 543 of 1005




**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

INSTRUMENT STUB DETAILS

|



NOTE :

1. MATERIAL OF THE BOSS AND NIPPLE SHALL BE THE SAME AS THE PIPE INTO WHICH IT IS WELDED AND CONFORM TO ANSI B16.11.
2. THE LENGTH OF NIPPLE SHALL BE 250 MM.
3. ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE INDICATED
4. EDGE HOLE MUST BE CLEAN AND SQUARE OR ROUNDED SLIGHTLY (1/64" RADIUS) FREE FROM BURRS, WIRE EDGES OR OTHER IRREGULARITIES
5. STUB LENGTH SHALL BE 64mm UPTO 250Nb PIPE, 45mm ABOVE 200Nb PIPE SIZE.




TITLE :
**INSTRUMENT STUB DETAILS
 FOR PRESSURE MEASUREMENT**
 (APPLICABLE FOR TEMP < 500 DegC, CLASS 6000#)

DRG. NO.
PE-DG-434-145-I101

REV. 00
 SH. 03

Page 545 of 1005
 On 08/08/2015



NOTE :

1. MATERIAL OF THE BOSS AND NIPPLE SHALL BE THE SAME AS THE PIPE INTO WHICH IT IS WELDED AND CONFORM TO ANSI B16.11.
2. THE LENGTH OF NIPPLE SHALL BE 250 MM.
3. ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE INDICATED
4. EDGE HOLE MUST BE CLEAN AND SQUARE OR ROUNDED SLIGHTLY ($1/64$ " RADIUS) FREE FROM BURRS, WIRE EDGES OR OTHER IRREGULARITIES
5. STUB LENGTH SHALL BE 64mm UPTO 250Nb PIPE, 45mm ABOVE 200Nb PIPE SIZE.



TITLE :

INSTRUMENT STUB DETAILS FOR PRESSURE MEASUREMENT

DRG. NO.


PE-DG-434-145-I101

REV. 00

(SYSTEM PRESS UPTO 40Kg/Cm², TEMP < 400 Deg C) SH. 04 OF 08 SPS.

Page 546 of 1005

TEMP. MEASUREMENT



NOTES :-

1. THIS TYPE OF TEMPERATURE BOSS SHALL BE USED FOR THE PROCESS PRESS EQUAL/ ABOVE 40 KG/CM²(g) AND FOR PROCESS TEMP.>400 DEG C EVEN IF THE PROCESS PRESSURE IS LESS THAN 40 KG/CM²(g).
2. THE MATERIAL OF THE BOSS SHALL BE SIMILAR TO PIPING MATERIAL.
3. MATERIAL OF THE THERMOWELL SHALL BE OF 316SS.
4. THERMOWELL SHALL BE DRILLED BAR STOCK TYPE.
5. INTERNAL BORE OF THE THERMOWELL SHOULD BE SELECTED BASED ON THE NORMAL SIZE OF THE SENSING ELEMENT AS PER ASME PTC-19.3.
6. THE BOTTOM DIAMETER OF THE THERMOWELL TYPICALLY SHOWN HERE SHALL BE SUBJECT TO VARIATION BASED ON THE INTERNAL BORE OF THERMOWELL AND THICKNESS OF THERMOWELL MATERIAL TO WITHSTAND THE PROCESS PRESS AND TEMP AS PER ASME PTC-19.3.
7. THERMOWELL SHALL BE SUITABLE TO MATCH THE STUB DIMENSIONS AS PER Rc 1½.
8. THE 'U' & 'L' DIMENSIONS SHALL BE SELECTED BASED ON PARTICULAR APPLICATION.
9. ORIENTATION OF STUB ON VERTICAL/ HORIZONTAL PIPES SHALL BE 90° TO THE CENTRE LINE OF THE PIPES, FOR PIPE SIZE LARGER THAN 4". HEIGHT OF STUB SHALL BE 64mm FOR PIPE OD < 200Nb AND 45mm FOR PIPE OD ≤ 200Nb.
10. ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE INDICATED.



TITLE :

DRG. NO.

INSTRUMENT STUB DETAILS (TEMP)
(APPLICABLE FOR PIPE SIZE ABOVE 4")

PE-DG-434-145-1101


REV. 00

[PROCESS PRESS EQUAL/> 40 Kg/Cm2 (g)

SH. 05 OF 08 Page 547 of 1005.

PROCESS PRESS < 40 Kg/Cm2 (g), TEMP.EQUAL/>400 DEG C]

TEMP. MEASUREMENT



NOTES :-

1. THIS TYPE OF TEMPERATURE BOSS IS APPLICABLE FOR THE PROCESS PRESS/ TEMP. BELOW 40 KG/CM²(g)/400°C.
2. SEE NOTES-2 TO 9 IN SHT. 5 OF 8 OF THIS DRG.
3. ALL DIMENSIONS ARE IN MM UNLESS OTHERWISE INDICATED.



TITLE :

INST. STUB DETAILS (TEMP)

(APPLICABLE FOR PIPE SIZE ABOVE 4")

[PROCESS PRESS < 40 Kg/Cm² (g), TEMP < 400 °C]

DRG. NO.


PE-DG-434-145-I101

REV. 00

SH. 06 OF 08 SHTS.

Page 548 of 1005

THERMOWELL SUITABLE FOR THE BOSS
AS PER DRG. NO.
PE-DG-434-145-I101 SHT 5 & 6



NOTES :-

1. INCLINED INSTALLATION OF THERMOWELL SHALL BE APPLICABLE FOR 4" AND SMALLER LINE SIZE BUT LIMITED TO MIN. 3" LINE SIZE.
2. FOR 2" AND SMALLER LINE SIZE NECESSARY EXPANDER OF 3" SIZE OF MAIN PIPING SPECIFICATION SHALL BE USED.
3. THIS TYPE OF INSTALLATION IS APPLICABLE FOR HORIZONTAL AND VERTICAL PIPE SECTION.
4. FOR STEAM SERVICES EXPANDER SECTION MAY BE USED ONLY IN VERTICAL RUN.
5. THE EXPANDER SECTION SHALL BE OF ADEQUATE LENGTH (ATLEAST 3-4 TIMES DIA OF THE MAIN PROCESS PIPE AT BOTH SIDE OF INSTALLED THERMOWELL).



TITLE :

THERMOWELL INSTALLATION


DRG. NO.

PE-DG-434-145-I101

REV. 00

SH. 07 OF 08 SHS.

Page 549 of 1005



NOTES :-

1. FLOW INSTALLATION OF THERMOWELL SHALL BE APPLICABLE FOR 4" AND SMALLER LINE SIZE BUT LIMITED TO MINIMUM 3" LINE SIZE. THIS DETAIL IS APPLICABLE FOR THERMOWELL INSTALLATION IN BEND PIPES.
2. FOR 2" AND SMALLER LINE SIZE NECESSARY EXPANDER OF ELBOW FORM (AS SHOWN) OF 3" SIZE SHALL BE USED.
3. ELBOW EXPANDER SECTION IN HORIZONTAL PLANE TO BE USED FOR LIQUID SERVICE. FOR STEAM SERVICES EXPANDER SECTION TO BE USED IN VERTICAL PLANE.



TITLE :

**THERMOWELL INSTALLATION
(IN BEND PIPES)**

DRG. NO.

PE-DG-434-145-I101

REV. 00

SH. 08

Page 55 of 100
08 SHS.




**C&I SPECIFICATION FOR
EFFLUENT TREATMENT PLANT**

SECTION: C
SUB SECTION: C&I

INSTRUMENT INSTALLATION DRAWING

|


GROUNDING FOR EACH ROW OF PANELS (TYPICAL)



NOTES:-

1. SUPPLY, ERECTION, TERMINATION OF CABLES, FLATS ETC. REQUIRED FOR PROPER GROUNDING OF CONTRACTOR'S CONTROL SYSTEM, SYSTEM CABINETS, POWER SUPPLY CABINETS ETC. ARE IN THE SCOPE OF CONTRACTOR.
2. CABLE IN CONTRACTOR'S SCOPE.
3. TO BE LOCATED IN DCDB.
4. EXACT LOCATION, ARRANGEMENTS OF FLATS ETC. SHALL BE AS FINALISED WITH CONTRACTOR DURING DETAILED ENGINEERING.
5. CABINET BODY, CABINET BOTTOM PLATE, CABINET DOORS ARE TO BE CONNECTED TO PANEL EARTH FLAT COPPER CABLE BY CONTRACTOR.

FOR TENDER PURPOSE ONLY

 NTPC LIMITED (A GOVERNMENT OF INDIA ENTERPRISE) ENGINEERING DIVISION		PROJECT TYPICAL THERMAL POWER PROJECT	
TITLE INSTRUMENTATION CABLING DIAGRAM GROUNDING SCHEME FOR CABINETS / PANELS / POWER SUPPLY		REV. NO. A	
DATE 21.08.12		SCALE N.T.S.	
DATE 21.08.12		DRG. NO. 0000-999-POI-A-019A	
DATE 21.08.12		SH-2 OF 2	
DESCRIPTION		CHECKED BY	
REVISED		CLEAR BY	

This document is the property of NATIONAL THERMAL POWER CORPORATION LTD. No part of this document will be reproduced by any means without the written permission.