

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

Sl. No.	Technical Parameters	Unit	Particulars
1	Location	Panipat, Haryana, India	
1.1	Maximum ambient temperature	°C	50
1.2	Minimum ambient temperature	°C	-5
1.3	Average ambient temperature	°C	35
1.4	Design ambient temperature	°C	45
2	Average no. of thunder storm days	Days	45
3.1	Maximum Relative humidity	%	95
3.2	Maximum Relative humidity	%	26
4	Average Annual Rain Fall	Mm	900
5	Maximum Wind Pressure	Kg/ sqm	195
6	Maximum Altitude above Mean Sea Level	M	1000
7	Isoceraunic Level	Days/ Year	45
8	Seismic Level (Horizontal Acceleration)	Zone	4
9	Average no. of rainy day per Year	Days/ Year	120

NOTE: Moderately hot and humid tropical climate conducive to rust and fungus growth. The climate conditions are also prone to wide variations in ambient condition. Smoke is also present in the atmosphere. Heavy lightening also occurs during June to October. Switchyard is inside the refinery premise which is also prone to other corrosive gases like sulphur, H₂S, Chlorine etc.

4. Instruction to Bidders

1. The bidders shall submit the technical requirements, data and information as per the technical specifications provided in the bid documents.
2. The bidders shall furnish catalogues, engineering data, technical information, design document, drawings etc fully in conformity with the technical specification.
3. It is recognised that the contractor may have standardised on the use of certain components, materials, processes or procedures different than those specified herein. Alternate proposals offering similar equipment based on the manufacturer's standard practice will also be considered provided such proposals meet the specified designs, standard and performance requirements and are acceptable to the owner. Unless brought out clearly, the Bidder shall be deemed to conform to this specification scrupulously; All deviations from the specification shall be clearly brought out in the respective schedule of deviations. Any discrepancy between the specification and the catalogues or the bid, if not clearly brought out in the schedule, will not be considered as valid deviation.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

-
4. Equipment furnished shall be complete in every respect with all mountings, fittings, fixtures and standard accessories normally provided with such equipment and/or needed for erection, completion and safe operation of the equipment as required by applicable codes though they may not have been specifically detailed in the technical specifications unless include in the list of exclusions. Materials and components not specifically stated in the specification but which are necessary for commissioning and satisfactory operation of the switchyard shall be deemed to be included in the scope of the specification. All similar standard components/parts of similar standard equipment provided, shall be interchangeable with one another.
 5. Unless brought out clearly in the respective schedule of deviations, it will be considered that, the bid proposal scrupulously confirms compliance to the specification. The bidder must bring out all the deviations in the bid proposal.
 6. In case there is a discrepancy between the data offered equipment and catalogue furnished, and unless the deviations are brought out clearly in the Technical Deviation Schedule, the equipment will be deemed to conform compliance to the specification scrupulously.

5. Standards

1. The works covered by the specification shall be designed, engineered, manufactured, built tested and commissioned in accordance with the Acts, Rules, Laws and Regulations of India.
2. The equipment to be furnished under this specification shall conform to latest issue with all amendments of standard specified of this section as well as under respective Sections/Chapters of the specification.
3. In addition to meeting the specific requirement called for in the respective sections of the Technical Specification, the equipment shall also conform to the general requirement of the relevant standards and shall form an internal part of the specification.
4. The Bidder shall note that standards mentioned in the specification are not mutually exclusive or complete in themselves, but intend to complement each other.
5. The Contractor shall also note that list of standards presented in this specification is not complete. Wherever necessary the list of standards shall of the specification shall take precedence.
6. When the specific requirements stipulated in the specification exceed or differ than those required by the applicable standards, the stipulation of the specification shall take precedence.
7. Other internationally accepted standards which ensure equivalent or better performance than that specified in the standards referred shall also be accepted.
8. In case governing standards for the equipment is different from IS or IEC, the salient points of difference shall be clearly brought out in deviation sheets along with English language version of standard or relevant shall be subject to Owner's approval.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

9. Indicative List of Standards and Specifications General Standards Indian Electricity Rules shall be as per Annexure- A.

6. Services to be Performed by the Equipment being furnished

1. The 220/33 kV system is being designed to limit the switching surge over voltage and the power frequency over voltage within limits of IEC. The equipment furnished under this specification shall perform all its functions and operate satisfactorily without showing undue strain, re-strike etc. under such over voltage conditions and in system where line lengths would extend up to 200 km.
2. All equipment shall also perform satisfactorily under various Electro-mechanical and meteorological conditions of the site of installation.
3. All the Equipment shall be able to withstand all external and internal mechanical, thermal and electromechanical forces due to various factors like wind load, temperature variation, short circuit etc for the equipment.
4. The bidder shall design the various forces for terminal connectors of the equipment are required to withstand.
5. The equipment shall also comply to the following:
 - All outdoor EHV equipment shall be suitable for hot line washing.
 - To facilitate erection of equipment, all items to be assembled as site shall be "match marked". All piping, if any between equipment control cabinet operating mechanism to marshalling box of the equipment shall bear proper identification to facilitate the connection at site.

7. Engineering Data

1. The furnishing of engineering data by the Contractor shall be in accordance with the schedule for each set of equipment as specified in the technical specifications.
2. The review of these data by the owner will cover only general conformance of the data to the specifications and documents, interfaces with the equipment provided under the specifications, external connections and of the dimensions which might affect substation layout. This review by the owner may not indicate a thorough review of all dimensions, quantities and accuracy of the information submitted. This review and/or approval by the owner shall not be considered by the Contractor, as limiting any of his responsibilities and liabilities for mistakes and deviation from the requirements, specified under these specifications and documents.
3. All engineering data submitted by the Contractor after final process including review and approval by the owner shall form part of the Contract Document and the entire works performed under these specifications shall be performed in strict conformity, unless otherwise expressly requested by the owner in Writing.
4. LIST OF DOCUMENTS
 - 4.1 The bidder must furnish a detailed list of drawings/documents along with the bid proposal which he intends to submit to the owner after awarded of the contract.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

- 4.2 The supplier shall necessarily submit all the drawings/ documents unless anything is waived. The supplier shall submit required sets of drawings/design documents/test reports as may be required for the approval of the owner.
- 4.3 All engineering data submitted by the Contractor after final process including review and approval by the Owner shall form part of the Contract Document and the entire works performed under these specifications shall be performed in strict conformity, unless otherwise expressly requested by the owner in Writing.
5. DRAWINGS
- 5.1 All drawing submitted by the Contractor including those submitted at the time of bid shall be in sufficient detail to indicate the type, size, arrangement, material description, Bill of Materials, weight of each component, break-up for packing and shipment, the external connections, fixing arrangement required, the dimensions required for installation and interconnections with other equipment and materials, clearances and spaces required for installation and interconnection between various portions of equipment and any other information specifically requested in the specifications.
- 5.2 Each drawing submitted by the Contractor shall be clearly marked with the name of the Owner, the unit designation, the specifications title, the specification number and the name of the Project. If standard catalogue pages are submitted, the applicable items shall be indicated therein. All titles, noting, markings and writings on the drawing shall be in English. All the dimensions should be in metric units.
- 5.3 Further work by the Contractor shall be in strict accordance with these drawing and no deviation shall be permitted without the written approval of the Owner if so required.
- 5.4 All manufacturing and fabrication work in connection with the equipment prior to the approval of the drawing shall be at the Contractor's risk. The Contractor may make any changes in the design which are necessary to make the equipment conform to the provisions and intent of the Contract and such changes will again be subject to approval by the Owner. Approval of Contractor's drawing or work by the Owner shall not relieve the contractor of any of his responsibilities and liabilities under the Contract.
- 5.5 APPROVAL PROCEDURE
- The scheduled dates for the submission of these as well as for, any data/information to be furnished by the Owner would be discussed and finalised at the time of award. The supplier shall also submit six (6) copies of all drawings/design documents/test report for approval of the Owner. The following tentative schedule shall be followed in general for approval. However final schedule shall be prepared with approval of Engineer in-charge post award of approval.

1	Submission, comments, by resubmission and approval recommended agency	Within 4 weeks of receipt
2	Approval/ comments/ by Owner on initial submission	Within 4 weeks of receipt.
3	Resubmission	Within 3 (three) weeks (whenever from

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

		date of comments required) including both ways postal time.
4	Approval or comments	Within 3 weeks of receipt of commented drawing/ documents.
5	Furnishing of distribution copies	1 weeks from the date of last approval.

NOTE: The contractor may please note that all resubmission must incorporate all comments given in the submission by the Owner failing which the submission of documents is likely to be returned.

5.6 The drawing which are required to be referred frequently during execution should be submitted on cloth lined paper.

5.7 OTHER REQUIREMENTS OF DOCUMENTATION

5.7.1 One set of soft copy of all drawings, manual, catalogues to be submitted along with 6 sets of hardcopies during submission of as built documents.

5.7.2 6 copies of instruction/operation manuals for complete project shall also be furnished. The instruction Manuals shall contain full details of drawing of all equipment being supplied under this contract, their exploded diagrams with complete instruction for storage, handing, erection, commissioning, testing, operation, trouble shooting, servicing and overhauling procedures.

5.7.3 If after the commissioning and initial operation of the substation, the instruction manuals require any modifications/additions/changes, the same shall be incorporated and the updated final instruction manual in the form of one (1) reproducible original and twelve (12) copies shall be submitted by the Contractor to the Owner.

The Contractor shall furnish to the Owners, twelve (12) sets of spare part catalogue.

5.8 TITLE BLOCK

Title block for project shall be as follows,

Customer:	Indian Oil Corporation Ltd.
Consultant:	TATA Consulting Ltd.
LSTK Contractor:	Bharat Heavy Electricals Ltd.
Project:	LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

8. Colour Scheme and Codes

1. The contractor shall propose parts a colour scheme for those equipment/ Items for which the colour scheme has not been specified in the specification, for the approval of Owner. The decision of Owner shall be final. The scheme shall include,

- Finishing colour of Indoor equipment.
- Finishing colour of Outdoor equipment.
- Finishing colour of all cubicals.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

- Finishing colour of various auxiliary system equipment including piping.
- Finishing colour of various building items.

2. All steel structures, plates etc shall be hot dip galvanised or painted with noncorrosive paint on a suitable primer as per the provisions of the respective Section. It may be noted that normally all Owner's electrical equipment in Owner's switchyard are painted with shade 631 of IS-5 and Owner will prefer to follow the same for this project also. All the indoor cubicles shall be of same colour scheme and for other miscellaneous items colour scheme will be approved by the Owner.

9. Material/ Workmanship

1. GENERAL REQUIREMENTS

- 1.1 Where the specification does not contain characteristics with reference to workmanship, equipment, materials and component of the covered Equipment, it is understood that the same must be new, of highest, grade of the best quality of their kind, conforming to the best engineering practice and suitable for the purpose for which they are intended.
- 1.2 The equipment must be new, of highest grade, the best quality of their kind, to best engineering practice and latest state of art in accordance with purpose for which they are intended and to ensure satisfactory performance throughout the service life.
- 1.3 In case where the equipment, material or components are indicated in the specification as "similar" to any special standard, the Owner shall decide upon the question of similarity. When required by the specification or required by the Owner the supplier shall submit, for approval, all the information concerning the material or components supplied, installed or used without such approval shall run the risk of subsequent rejection, it being understood that the cost as well as the time delay associated with the rejection shall be borne by the Supplier.
- 1.4 The design of the work shall be such that installation, future expansions, replacement and general maintenance may be undertaken with a minimum of time and expenses. Each component shall be designed to be consistent with its duty and suitable factors of safety, subject to mutual agreements and shall be used throughout the design. All joints and fastenings shall be devised; constructed and documented so that the component part shall be accurately positioned and retained to fulfil their required function. In general, screw threads shall be standard metric threads. The use of other thread forms will only be permitted when prior approval has been obtained from the Owner.
- 1.5 Whenever possible, all similar part of the works shall be made to gauge and shall also be made interchangeable with similar parts. All spare parts shall be interchangeable with, and shall be made of the same material and workmanship as the corresponding parts of the equipment supplied under specification. Where feasible, common component units shall be Employed in different pieces of the equipment in order to

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

minimize spare parts stocking requirements. All equipment of the same type and rating shall be physically and electrically interchangeable.

- 1.6 All material and equipment shall be installed in strict accordance with the manufacturer's recommendation(s). The erection procedure must be approved by the OEM and erection completion shall be certified by OEM for satisfactory completion. The commissioning of all major equipment as recommended by Engineer in-charge.
 - 1.7 Only first-class work in accordance with the best modern practice will be accepted. Installation shall be constructed as being the erection of equipment at its permanent location. This, unless otherwise specified, shall include unpacking, cleaning and lifting into position, grouping, levelling, aligning, coupling of or bolting down to previously installed equipment bases/ foundation, performing the alignment check and final adjusting prior to initial operation, testing and commissioning in accordance with the manufacturer's tolerances and instruction and the specification. All factory assembled rotating machinery shall be checked for alignment and adjustments made as necessary to re-establish the manufacturer's limits suitable guards shall be provided for the protection of personnel on all exposed rotating and/or moving machine parts and shall be designed for easy installation and removal for maintenance purpose. The spare equipment(s) shall be installed at designated location and tested for healthiness.
 - 1.8 The Supplier shall apply oil and grease of the proper specification to suit the machinery, as is necessary for the installation of the equipment. Lubricants used for installation purpose shall be drained out and the system flushed through where necessary for applying the lubricant required for operation. The Supplier shall apply all operational lubricants to the equipment installed by him.
 - 1.9 All oil, grease and other consumable used in the Works/Equipment shall be purchased in India unless the Supplier has any special requirement for the specific application of a type of oil or grease not available in India. In such is the case he shall declare in the proposal, where such oil or grease is available. He shall help Owner in establishing equivalent India make and Indian supplier. The same shall be applicable to other consumable too.
 - 1.10 A cast iron or welded steel base plate shall be provided for all rotating equipment which are to be installed on a concrete base unless otherwise agreed to by the Owner. Each base plate shall support the units and its drive assembly, shall be of design with pads for anchoring the units and shall have a raised up all around and shall have threaded in air connections, if so required.
2. PROVISION FOR EXPOSURE TO HOT HUMID CLIMATE
- Outdoor equipment supplied under the specification shall be suitable for service and storage under tropical conditions of high temperature, high humidity, heavy rainfall and environment favourable to the growth of fungi and mildew. The indoor equipment located in non- air conditioned areas shall also be same type.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

2.1 SPACE HEATERS

2.1.1 The heater shall be suitable for continuous operation at 240 V as supply voltage. On-off switch and fuse shall be provided.

2.1.2 One or more adequately rated permanently or thermostatically connected heater shall be supplied to prevent condensation in any compartment. The heaters shall be installed in the lower portion of the compartment and electrical connection shall be made from below the heaters to minimize deterioration of supply wire insulation. The heaters shall be suitable to maintain the compartment temperature to prevent condensation. This shall be demonstrated by tests.

2.1.3 The heaters shall be suitably designed to prevent any contact between the heater wire and the air and shall consist of coiled resistance wire centred in a metal sheath and completely encased in a highly compacted powder of magnesium oxide or other material having equal heat conducting and electrical insulation properties, or they shall consist of resistance wire wound on a ceramic and completely covered with a ceramic material to prevent any contact between the wire and the air. Alternately, they shall consist of a resistance wire mounted into a tubular ceramic body and embedded in vitreous gale. The surface temperature of the heater shall be restricted wire is wound on a tubular ceramic body and embedded in vitreous glaze. The surface temperature of the heaters shall be restricted to a value which will not shorten the life of the heater sheaths or that of insulated wire or other component in the compartments.

2.2 FUNGISTATIC VARNISH

Besides the space heaters, special moisture and fungus resistant varnish shall be applied to parts which may be subjected or predisposed to the formation of fungi due to the presence or deposit of nutrient substances. The varnish shall not be applied to any surface of part where the treatment will interfere with the operation or performance of the equipment. Such surfaces or parts shall be protected against the application of the varnish.

2.3 VENTILATION OPENING

In order to ensure adequate ventilation, compartments shall have ventilation openings provided with fine wire mesh of brass or galvanized steel to prevent the entry of insects and to reduce to a minimum the entry of dirt and dust. Outdoor compartment openings shall be provided with shutter type blinds.

2.4 DEGREE OF PROTECTION

The enclosures of the control cabinets, junction boxes and marshalling boxes to be installed shall provide degree of protection as detailed here under:

- a) Installed outdoor: IP 55
- b) Installed indoor in air conditioned area: IP31

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

c) Installed in covered area: IP 52

d) Installed indoor in non-air-conditioned area where possibility of entry of water is limited: IP 41

The degree of protection shall be in accordance with IS: 13947(Part-I) or IEC-947 (Part-I). Type test report for degree of protection test, on each type of the box shall be submitted for approval.

The above requirement is indicative only. Requirements as provided in respective technical specification shall prevail.

10. Rating Plates, Name Plates and Labels

1. Each main and auxiliary item of substation is to be permanently attached to it in a conspicuous position a rating plate of non-corrosive material upon which is to be engraved manufacturer's name, year of manufacture, equipment name, type or serial number together with details of the loading condition under which the item of substation in question has been designed to operate, and such diagram plates as may be required by the Owner. The rating plates of each equipment shall be according to IEC requirement.
2. All such nameplates instruction plates, rating plates shall be bilingual with Hindi inscription first followed by English. Alternatively, two separate plates one with Hindi and the other English Instruction may be provided.

11. First Fill of Consumable, Oil and Lubricant

All the first fill consumable such as SF6, AC refrigerant, oil, lubricant, filling compounds, touch up paints, soldering/brazing material for all copper piping of circuit breakers and essential chemicals etc. which will be required to put the equipment covered under the scope of the specifications, into successful operation, shall be supplied by the Contractor unless specification excluded under the exclusions in these specifications and documents.

12. Design Improvements

1. The bidder may note that the equipment offered by him in the bid only shall be acceptable, however, the Purchaser or the Supplier may propose changes in the specification of the equipment or quality thereof and if the parties agreed upon any such changes, the specification shall be modified accordingly.
2. If any such agreed upon change is such that it affects the price and schedule of completion, the parties shall agree in writing as to the extent of any change in the price and/or schedule of the completion before the contractor proceeds with the change. Following such agreement, the provision thereof, shall be deemed to have been amended accordingly.

13. Quality Assurance Programme

1. To ensure that the equipment and services under the scope of this contract whether manufactured or performed within the contractor's Work or at his Subcontractor's premises or at the Owner's site or at any other place of work are in accordance with the

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

specification, the Contractor shall adopt suitable quality assurance programme to control such activities at all points necessary.

Such programme shall be outlined by the contractor and shall be finally accepted by the Owner after discussions before award of contract. A quality assurance programme of the contractor shall be generally covered the following,

- a) His Organization structure for the management and implementation of the proposed quality assurance programme.
- b) Qualification data for bidder's key personnel.
- c) Documentation control System.
- d) The procedure for purchases of material, parts components and selection of subcontractor's services including vendor analysis, source, inspection, incoming raw material inspection, verification of material purchases etc.
- e) System for shop manufacturing and, site erection control including process controls and fabrication and assembly control.
- f) Control and non-conforming items and system for corrective actions.
- g) Inspection and test procedure both for manufacture and field activities.
- h) Control of calibration and testing of measuring instruments and field activities.
- i) System for indication and appraisal of inspection status.
- j) System for quality audits.
- k) System for authorising release of manufactured product to the Purchaser.
- l) System for maintenance of records.
- m) System for handling storage and delivery. and
- n) A quality plan detailing out the specific quality control measures and procedures adopted for controlling the quality characteristics relevant to each item of equipment furnished and/or services ordered.

The Owner or his duly authorised representative reserves the right to carry out quality audit and quality surveillance of the system and procedure of the Contractor/his vendor's quality management and control activities.

2. QUALITY ASSURANCE DOCUMENTS

The contractor shall be required to submit the following quality Assurance Documents within three weeks after despatch of the equipment.

All Non-destructive Examination procedures, stress relief and weld repair procedure actually used during fabrication and report including radiography interpretation reports.

Welder identification list, listing welder's and welding operator qualification procedure and welding identification symbols.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

Welder and Welding operator qualification certificate.

Raw material test reports on components as specified by the specification and for agreed to in the quality plan.

Stress relief time temperature chart/oil impregnation tile temperature chart.

Factory test results for testing required as per applicable codes/ mutually agreed quality plan/standards referred in the technical specification.

The quality plan with verification of various customer inspection points(CAP) as mutually agreed and methods used to verify the inspection and testing points in the quality plan were performed satisfactory.

14. Inspection, Testing and Inspection Certificate

1. The Owner his duly authorised representative and/or outside inspection agency acting on behalf of the Owner shall have at all reasonable times free access to the Contractor's premises or Works and shall have the power at all reasonable times to inspect and examine the material and the Workmanship of the Works during its manufacture or erection and if part of the works during its manufacturing or erection and if the part of works being manufactured or assembled at other premises or works, the contractor shall obtain for the Engineer and for his duly authorised representative permission to inspect as if the work were manufactured or assembled on the Contractor own premises or works, Inspection may be made at any stage of manufacture, despatch or at site at the option of the Owner and equipment if found unsatisfactory due to bad workmanship or quality, material is liable to be rejected.
2. All equipment being supplied shall conform to type tests and shall be subject to routine tests in accordance with relevant standards.
3. The Contractor shall give the Owner/Inspector thirty (30) days written notice of any material being ready for testing along with work test certificate. Such tests shall be to the Contractor's account. The Owner unless witnessing of the tests is virtually waived, will attend such tests with thirty (30) days of the date of which the equipment is notified as being ready for tests/inspection, the contractor must ensure TPI for all inspections in line with tender documents.
4. The Owner or Inspector shall, within fifteen (15) days from the date of inspection as defined here in give notice in writing to the contractor, of any objection to any drawings and all any equipment and workmanship which in his opinion is not in accordance with the contract. The Contractor shall give due consideration to such objections and shall either made the modifications that may be necessary to meet the said objections or shall confirm in writing to the Engineer/Inspector giving reasons therein, that no modifications are necessary to comply with the Contract.
5. When the, factory tests have been completed at the Contractor's or Subcontractor's Works

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

the Owner/Inspector shall issue a certificate to this effect within fifteen (15) days after completion of tests. The completion of these tests or the issue of the certificate shall not bind the Owner to accept the equipment should, it, on further tests after erection be found not to comply with the Contract. The equipment shall be dispatched to site only after approval of test reports and issuance of dispatch clearances in approved by the Owner.

6. In all cases where the Contract provides for tests whether at the premises or at the works of the contractor or of any Sub-Contractor. The Contractor except where otherwise specified shall provide free of charge such items as labour, material electrically, field water, stores, apparatus and instruments as may be reasonably demanded by the Owner/Inspector or his authorized representative to carry out effectively such tests of the equipment in accordance with the contract and shall give facilities to the Owner/inspector or to his authorised representative to accomplish testing.
7. The inspection by Owner and issue of Inspection Certificate thereon shall in no way limit the liabilities and responsibilities of the Contractor in respect of the agreed quality assurance programme forming a part of the contractors.
8. The Owner will have the right of having at his own expenses any other test(s) of Reasonable nature carried out at Contractor premises or at site of in any other place in addition of aforesaid type and routine tests, to satisfy that the materials comply with the specification.
9. The Owner reserves the right for getting any field tests conducted on the completely assembled equipment at site.

15. Tests

1. CHARGING

On completion of erection of the equipment and before charging, each item of the equipment shall be thoroughly cleaned and then inspected jointly by the Owner and the Contractor for correctness and completeness of installation and acceptability for charging, leading to initial pre-commissioning tests at site. The list of pre-commissioning tests to be performed are given in section-7 and shall be included in the Contractor's quality assurance programme.

2. COMMISSIONING TESTS

2.1 The available instrumentation and control equipment will be used during such tests shall calibrated. However un-measurable parameters shall be taken into account in a reasonable manner by the Owner for the requirement of these tests. The tests will be conducted at the specified load points and as near the specified cycle condition as practicable. The Owner will apply proper corrections in calculation, to take into account conditions which do not correspond to the specified condition.

2.2 Any special equipment, tools and tackles required for the successful completion of the Commissioning Tests shall be provided by the Contractor, free of cost.

2.3 The specified tests to be conducted on equipment have been brought out in the respective chapters of the technical specification.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

2.4 The Contractor shall be responsible for obtaining statutory clearances from the concerned authorities for commissioning the equipment and the switchyard. However, necessary fee shall be paid by Owner.

16. Packing and Shipping

All the equipment shall be suitably protected, coated, covered or boxed and crated to prevent damage or deterioration during transit, handling and storage at site till the time of erection. While packing all the materials, the limitation from the point of view of availability of Railway wagon sizes in India should be taken account. The Contractor shall be responsible for any loss or damage during transportation, handling and storage due to improper packing. Owner takes no responsibility of the wagons.

17. Protection

All coated surfaces shall be protected against abrasion, impact, discoloration and any other damages. All exposed threaded portions shall be suitably protected with either a metallic or a non-metallic protecting device. All ends of all valves and pilings and conduit equipment connections shall be properly sealed with suitable devices to protect them from damage. The parts which are likely to get rusted, due to exposure to weather should also be properly treated and protected in a suitable manner.

18. Painting and Finishing of Metal Surfaces

1. GENERAL

All metal surfaces shall be subjected to treatment for anti-corrosion protection. All ferrous surfaces for external use shall be hot-dip galvanized after fabrication. High tensile steel nuts and bolts and spring washers shall be electro-galvanized to service condition. All steel conductors including those used for earthing/grounding (above ground level) shall also be galvanized according to IS: 2629.

2. HOT DIP GALVANIZING

2.1 The minimum weight of the zinc coating shall be 610g/sq.m and minimum thickness of coating shall be 85 microns for all items thicker than 6mm. For items lower than 6mm thickness requirement of coating thickness shall be as per relevant ASTM.

2.2 The galvanized surfaces shall consist of a continuous and uniform thick coating of zinc, firmly adhering to the surface of steel; The finished surfaces shall be clean and smooth and shall be free from defects like colour patches, are spots, unevenness of coating, plate which is loosely attached to the steel globules, spiky deposits, blistered surface, flaking or peeling off, etc. The presence of any of these defects noticed on visual or microscopic inspection shall render the material liable to rejection.

2.3 After galvanizing, no drilling or welding shall be performed on the galvanized parts of the equipment excepting that nuts may be threaded after galvanizing. Sodium

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

dichromate treatment shall be provided to avoid formation of white rust after hot dip galvanization.

2.4 The galvanized steel shall be subjected to six one minute dips in copper sulphate solution as per IS-2633.

2.5 Sharp edges with radii less than 2.5mm shall be able to withstand four immersions of the standard price test. All other coating shall withstand six immersions. The following galvanizing tests should essentially be performed as per relevant Indian Standards.

- Coating
- Uniformity of zinc
- Adhesion test
- Mass of Zinc

2.6 Galvanized material must be transported properly to ensure that galvanized surfaces are not damaged during transit. Application of zinc rich paint at site shall not be allowed.

3. PAINTING

3.1 All sheet steel work shall be degreased, pickled, phosphated in accordance with the IS-6005 "code of practice for phosphating iron and sheet". All surfaces which will not be easily accessible after shop assembly shall beforehand to be treated and protected for the life of the equipment. The surface which are to be finished painted after installation, shall be shop painted with at least two coats of primer. Oil, grease, dirt and swart shall be thoroughly removed by emulsion cleaning. Rust and scale shall be removed by pickling with dilute acid followed by washing with running water, rinsing with slightly alkaline hot water and drying.

3.2 After phosphating, thorough rinsing shall be carried out with clean water followed by final rinsing with dilute dichromate solution and over drying. The phosphate coating shall be sealed with application of two coats may be "flash dried" while the second coat shall be stoved.

3.3 After application of the primer, two coats of finishing synthetic enamel paint shall be applied, each coat followed by stoving. The second finishing coat shall be applied after inspection of first coat of painting.

3.4 The exterior colour of the paint shall be as per shade No.:631 of IS-5 and inside shall be glossy white. Each coat of primer and finishing paint shall be of slightly different shade to enable inspection of the painting. A small quantity of finishing paint shall be supplied for minor touching up required at site after installation of the equipment.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

3.5 In case the bidder proposes to follow his own standard surface finish and protection procedures or any other established painting procedures, like electrostatic painting etc. the procedure shall be submitted along with the bids for Owner's review & approval.

19. Handling, Storing and Installation

1. In accordance with the specific installation instructions as shown on manufacturer's drawings or as directed by the Owner or his representative, the contractor shall unload, store, erect, install, wire test and place into commercial use all the electrical equipment included in the contract. Equipment shall be installed in a neat, workmanlike manner so that it is level, plumb, square and properly aligned and oriented. Commercial use of switchyard equipment means completion of all site tests specified and energisation at rated voltage.
2. Contractor may engage manufacturer's engineer to supervise the unloading, transportation to site, storing and erection. The contractor shall engage the manufacturer's Engineer's for testing and commissioning of the various equipment being procured by them separately. Contractor shall unload, transport, store, erect, test and commission the equipment as per instructions of the manufacturer's supervisory Engineer(s)/ as per Manufacturer's approved process and shall extend full cooperation to them.
3. In case of any doubt or misunderstanding as to the correct interpretation of manufacture's drawing or instruction, necessary clarifications shall be obtained from the Owner/ Manufacturer. Contractor shall be held responsible for any damage to the equipment consequent to not following manufacturer's drawing/instructions correctly.
4. Where assemblies are supplied in more than one section, Contractor shall make all necessary mechanical and electrical connections between section including the connection between buses. Contractor shall also do necessary adjustments/alignments necessary for proper operation of circuit breakers, isolators and their operating mechanisms. All components shall be protected during testing and commissioning. Any equipment damaged due to negligence or carelessness or otherwise shall be replaced by the Contractor at his own expense.
5. Supplier shall be responsible for examining all the shipment and notify the Owner immediately of any damage, shortage, discrepancy etc. for the purpose of Owner's information only. The supplier shall submit to the Owner every week a report detailing all the receipts for any shortages or damages in transit, handling and/or in storage and erection of the equipment at Site. Any demurrage, wharf age and other such charges claimed by the transporters, railways etc. shall be to the account of the Supplier.
6. The Contractor shall be fully responsible for the equipment material unit the same is handed over to the Owner in an operating condition after commissioning. Contractor shall be responsible for the maintenance of the equipment material while in storage as well as after erection unit taken over by Owner, as well as protection of the same against theft,

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

element of nature, corrosion, damages etc.

7. Where material/equipment is unloaded by Owner before the Contractor arrives at site or even when he is at site. Owner by right can hand over the same to Contractor and there upon it will be the responsibility of Contractor to store the material in an orderly and proper manner.
8. The Supplier shall be responsible for making suitable indoor storage facilities, to store all equipment which require indoor storage.
9. The words 'erection' and 'installation' used in the specification are synonymous.
10. Exposed live parts shall be placed high enough above ground to meet the requirements of electrical and other statutory safety codes.
11. The minimum phase to earth, phase to phase and section clearance for the various 132 kV, 66 kV and 33 kV sections of the switchyard are given below,

Voltage Grade	220kV	132kV	33kV
Phase to earth (mm)	2100	1300	320
Phase to Phase (mm)	2100	1600	350
Section clearance (mm)	5000	4000	2800

The design and workmanship shall be in accordance with the best engineering practices to ensure satisfactory performance throughout the service life.

20. Protective Guard

Suitable guards shall be provided for protection of personnel on all exposed rotating and/or moving machine parts. All such guards with necessary spares and accessories shall be designed for easy installation and removal for maintenance purpose.

21. Design Co-ordination

1. The Contractor shall be responsible for the selection and design of appropriate equipment to provide the best co-ordinate performance of the entire system. The basic design requirements are detailed out in this Specification. The design of various components, sub-assemblies and assemblies shall be so done so that it facilitates easy field assembly and maintenance.
2. The Contractor has to coordinate designs and termination with the agencies (If any) who are LSTK vendors/ contractor for the Owner if applicable. The names of agencies shall be intimated to the successful bidders.

22. Design Co-Ordination Meeting

The Contractor will be called upon to attend design co-ordination meeting with the Engineer, other Contractor's and the LSTK vendors of Owner (If any) during the period of Contract. The Contractor shall attend such meeting at his own cost as and when required and fully cooperate with such person and agencies involved during those discussions.

23. Tools and Tackles

The Contractor shall supply with the equipment one complete set of all special tools and tackles for the erection, assembly, dis-assembly and maintenance of the equipment.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

However, these tools and tackles shall be separately, packed and brought on to Site.

24. Equipment Bases

A cast iron or welded steel base plate shall be provided for all rotating equipment which is to be installed on a concrete base unless otherwise agreed to by the Owner. Each base plate shall support the unit and its drive assembly, shall be of a neat design with pads for anchoring the units, shall have a raised lip all around, and shall have threaded drain connections.

25. Support Structure

1. The support structures should be hot dip galvanised with minimum 610 gram/m² net of Zinc.
2. In case of any deviation in this regard the bid is liable to be rejected.
3. Support structure shall meet the following mandatory requirements.
4. The minimum vertical distance from the bottom of the lowest porcelain part of the bushing, porcelain enclosures or supporting insulators to the bottom of the equipment base, where it rests on the foundation pad shall be 2.55 meters or as per applicable standard.
5. The design calculations taking into account the environmental conditions of the substations shall be furnished for sizing of the structures.

26. Clamps and Connectors including Terminal Connectors

1. All power clamps and connectors shall conform to IS:5561 & NEMA CC1 and shall be made of materials listed below,

a)	For connecting ACSR Conductors	Aluminium alloy casting conforming to designation A6 of IS:617 and shall be tested for all test as per IS:617
b)	For connecting equipment terminals made of copper with ACSR conductors	Bimetallic connectors made from aluminium alloy casting, conforming to designation A6 of IS 617 with 2mm thick bimetallic liner and shall tested as per IS:617
c)	For connecting GI shield wire	Galvanised mild steel
d)	Bolts, nuts & plain washer galvanised Spring washers for items 'a' to 'c'	Electro galvanisation for sizes Plain, washers below M12, for others hot dip galvanised. Electro-galvanised mild steel suitable for at least service condition-3 as per IS:1573

2. Each equipment shall be supplied with the necessary terminals and connectors, as required by the ultimate design for the particular installation. The conductor termination of equipment shall be suitable for Moose ACSR Conductor. The requirement regarding external RIV as specified for any equipment shall include its terminal fittings and the equipment shall be factory tested with the connectors in position.
3. Where copper to aluminium connections are required, bi-metallic clamps shall be used, which shall be properly designed to ensure that any deterioration of the connection is kept

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

to a minimum and restricted to parts which are not current carrying or subjected to stress. The design details of the joint shall be furnished to the Owner by the supplier.

4. Low voltage connectors, grounding connectors and accessories for grounding all equipment as specified in each particular case, are also included in the scope of work.
5. No current carrying part of any of any clamp shall be less than 12 mm thick. All ferrous parts shall be hot dip galvanised. Copper alloy liner of minimum 2 mm thickness shall be cast integral with aluminium body for Bi-metallic clamps.
6. Lateral load deflection test shall be carried out as an acceptance test. The test procedure and accepted norms shall be mutually discussed and agreed to.
7. All casting shall be free blow holes, surface blisters, cracks and cavities. All sharp edges and corners shall be blurred and rounded off.
8. Clamp shall be designed to carry the same current as the conductor and the temperature rise shall be equal or less than that of the conductor at the specified with respect to the specified reference ambient temperature, shall also be indelibly marked on each component of the clamp/connector, except on the hardware.
9. All current carrying parts shall be designed and manufactured to have minimum contact resistance.
10. Clamps and connectors shall be designed to be corona controlled. RIV level for 220 kV system shall not be more than 1000/ micro volts respectively at the specified test voltage as per IS/NEMA.

11. TESTS

Clamps and connectors shall conform to type tests and shall be subjected to routine tests as per IS:5561.

27. Control Cabinets, Junction Boxes, Terminal Boxes & Marshalling Boxes for Outdoor Equipment

1. All type of boxes, cabinets etc. shall generally conform to & be tested in accordance with IS5039/IS-8623, IEC-439, as applicable, and the clauses given below.
2. Control cabinet, junction boxes, marshalling boxes & terminal boxes shall be made of sheet steel or aluminium and shall be dust, water and vermin proof. Sheet used shall be least 2.0 mm cold rolled or 2.5 mm hot rolled. The box shall be properly braced to prevent wobbling. There shall be sufficient reinforcement to provide level surfaces, resistance to vibrations and rigidity during transportation and installation. In case of aluminium enclosed box the thickness of aluminium shall be such that it provides adequate rigidity and long life as comparable with sheet of specified thickness.
3. The enclosures of the control cabinets, junction boxes, terminal boxes & marshalling boxes shall provide a degree of protection of not less than IP 55 as per IS: 2147. The bidder shall offer type tested (IP:55) Marshalling kiosk and type test report for degree of protection test each type of box shall be furnished for arrival. After protection degree test of marshalling kiosk, 2.0 kVrms for 1 (one) minute, insulation resistance and functional test

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

should have been conducted. In case these tests have not been carried out during IP55 test, then the contractor shall carry out the IP-55 test along with these tests, at his cost.

4. Cabinet/boxes shall be free standing floor mounting type, wall mounting type or pedestal mounting type as per requirements.
5. All door, removable covers and plates shall be gasketed all around with suitably profiled EPDM gaskets. The gasket shall be tested in the presence of Owners representative. The quality of gasket shall be such that it does not get damaged/ cracked during the years of the equipment or its major overhaul whichever is earlier. All gasketed surfaces shall be smooth straight and reinforced of necessary to minimize distortion and to make a tight seal. Ventilating Louvers, if provided, shall have screen and filters. The screen shall be fine wire mesh made of brass or GI wires.
6. All boxes/cabinets shall be designed for the entry of cables from bottom by means of weather proof and dust-proof connection. Boxes and cabinet shall be designed with generous clearances to avoid interference between the wiring entering from below and any terminal blocks or accessories mounted within the base of the marshalling kiosk/box shall be provided for this purpose along with the proper blanking plates. Necessary number of cable glands shall be supplied and fitted on this gland plate. The gland shall project at least 25mm above gland plate to prevent entry of moisture in cable crutch. Gland plate shall have provision for some future glands to be provided later, if required. The Nickel plated glands shall be dust proof, screw on & double compression type and made of brass. The gland shall have provision for securing armour of the cable separately and shall be provided with earthing tag. The glands shall conform to BS:6121.
7. A 240V, single phase, 50Hz, 15amp AC plug and socket shall be provided the cabinet with ON-OFF switch for connection of hand lamps. Plug and socket shall be of industrial grade.
8. For illumination of control cabinet, a 7 Watt LED shall be provided.
9. All control switches shall be of rotary switch type and Toggle/piano switches shall not be provided.
10. EARTHING
Positive earthing of the cabinet shall be ensured by providing two separate earthing pads. The earth wire shall be terminated on to the earthing pad and secured by the use of star of self-etching washer. Earthing of hinged door shall be done by using a separate earth wire.
11. TESTS

The marshalling kiosks shall be subject to routine tests as per 18:5039. The following routine tests shall also be conducted:

- Check for wiring
- Visual and dimension check

Marshalling kiosks shall be provided with danger plate and a diagram showing the numbering/connection/ferruling by pasting the same on the inside of the door.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

28. Auxiliary Switches

The auxiliary switch shall confirm to the following type tests:

- a) Electrical endurance test -A minimum of 2000 operation for 2A DC with a time constant examination of mV drop/visual defects/temperature rise test.
- b) Mechanical endurance test. A minimum of operations as specified in the relevant IS with a subsequent checking of contact pressure test visual examination. Heat run test on contacts.

29. Terminal Blocks and Wiring

1. Control and instrument leads from the switchboards or from other equipment will be brought to terminal boxes or control cabinets in conduits. All inter-phase and external connections to equipment or to control cubicles will be made through terminal blocks.
2. Terminal blocks shall be 1100 v grade and have continuous rating to carry the maximum expected current on the terminals. Those shall be of moulded piece complete with insulated barriers stud type terminals, washers, nuts and lock nuts. Screw clamp, overall insulated, insertion type, rail mounted terminals can be used in place of stud type terminals. But preferably the terminal blocks shall be non-disconnecting stud type equivalent to Elmex type CATM4, Phoenix cage clamp type of Wedge or equivalent. The insulating material of terminal block shall be nylon 6.6 which shall be free of halogens, fluorocarbons etc.
3. Terminal block for current transformer and voltage transformer secondary leads shall be provided with test links and isolating facilities. The current transformer secondary leads shall also be provided with short circuiting and earthing facilities.
4. The terminal shall be that maximum contact area is achieved when a cable is terminated. The terminal shall have a locking characteristic to prevent cable from escaping from the terminal clamp unless it is done intentionally.
5. The conducting part in contact with cable shall preferably be tinned or silver plated however Nickel plated copper or zinc plated steel shall also be acceptable.
6. The terminal blocks shall be of extensible design.
7. The terminal blocks shall have locking arrangement to prevent its escape from the mounting rails.
8. The terminal blocks shall be fully enclosed with removable covers of transparent, non-deteriorating type plastic material. Insulating barriers shall be provided between the terminal blocks. These barriers shall not hinder the operator from carrying out the wiring without removing the barriers.
9. Unless otherwise specified terminal blocks shall be suitable for connecting the following conductors on each side.

a)	All circuits except CT circuits	Minimum of 2.5 sq.mm copper flexible
b)	All CT circuits copper flexible.	Minimum of 4 sq.mm.
10. The arrangements shall be in such a manner so that it is possible to safely connect or

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

disconnect terminals on live circuits and replace fuse links when the cabinet is live.

11. At least 20 % spare terminals shall be provided on each panel/cubicle/box and these spare terminals shall be uniformly distributed on all terminals rows.
12. There shall be a minimum clearance of 250 mm between the First bottom row of terminal block and the associated cable gland plate. Also the clearance between two rows of terminal blocks shall be a minimum of 150 mm.

The Supplier shall furnish all wire, conduits and terminals for the necessary interphase electrical connection (where applicable) as well as between phases and common terminal boxes or control cabinets. The wiring required in these items shall be run in metallic ducts or shielded cables in order to avoid surge overvoltage either transferred through the equipment or due to transients induced from the EHV circuits.

13. All input and output terminals of each control cubicle shall be tested for surge withstand capability and transverse modes. The supplier shall also provide all necessary to achieve an impulse withstand level at the cable interfaces of equipment.

30. Lamps and Sockets

1. LAMPS

All indication lamps shall also be LED based. Socket base shall be as per IS-1258, except in the case of signal lamps.

2. SOCKETS

All sockets (convenience outlets) shall be suitable to accept both 5 A & 15 A pin round Standard Indian plugs. They shall be switched sockets with shutters.

3. HAND LAMP

A 240 Volts, single phase, 50 Hz AC plug point shall be provided in the interior of each cubicle with ON-OFF Switch for connection of hand lamps.

4. INTERIOR LIGHTING

Each panel shall be provided with a LED lighting fixture of Standard Indian type rates for 240 Volts, single phase, 50 Hz supply for the interior illumination of the panel during maintenance. The Fitting shall be controlled by the respective panel door switch.

5. SWITCHES AND FUSES

5.1 Each control panel shall be provided with necessary arrangements for receiving, distributing, isolating and fusing of DC and AC supplies for various control, signaling, lighting and space heater circuits. The incoming and sub-circuits shall be separately provided with switch fuse units. Selection of the main and Sub-circuit fuse rating shall be such as to ensure selective clearance of sub-circuit faults. Potential circuits for relaying and metering shall be protected by fuses.

5.2 All fuses be of HRC cartridge type conforming to IS:9228 mounted on plug-in type fuse bases.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

5.3 Miniature circuit breakers with thermal protection and alarm contacts will also be accepted. All accessible live connection to fuse bases shall be adequately shrouded. Fuses shall have operation indicators for indicating blown fuse condition. Fuses carrier base shall have imprints of the fuse rating and voltage.

31. Bushings, Hollow Column Insulators, Support Insulators

1. The bidder shall offer composite silicon rubber polymer insulator for all insulation purpose as per project requirement, conforming to IEC-61109. In case if non-compliance of composite insulators with respect to State/National electricity authorities' guidelines/requirements, the anti-fog type porcelain insulators may be used wherever mandatory. The required deviations with respect to above requirements shall be clearly mentioned in the deviation sheet along with the supporting documents. In absence of such deviations statements, the compliance of this point is mandatory and binding on the vendor.
2. Bushing shall be manufactured and tested in accordance with IS:2099 & IEC: 137 while hollow column insulators shall be manufactured and tested in accordance with IEC 233/18 5621. The support insulators shall be manufactured and tested as per IS 2544/IEC 168 and IEC 273. The Insulators shall also conform to IEC 815 as applicable.
3. Following requirements to be fulfilled if anti-fog porcelain insulators are provided as instructed in point 29.1 of this chapter.
 - 3.1 Support insulators, bushings and hollow column insulators shall be manufactured from high quality porcelain. Porcelain used shall be homogeneous, free from lamination, cavities and other flaws or imperfections that might affect the mechanical or dielectric quality and shall be thoroughly vitrified tough and impervious to moisture.
 - 3.2 Glazing of the porcelain shall be uniform brown in colour, free from blisters, burrs and similar other defects.
 - 3.3 Support insulators/ bushings/ hollow column insulators shall be designed to have ample insulation, mechanical and rigidity for the conditions under which they will be used.
 - 3.4 When operating at rated voltage there shall be no electric discharge between the conductors and busbar which would cause corrosion or injury to conductors, insulators or supports by the formation of substances produced by chemical action. No radio interference shall be caused by the insulators/bushings when operating at the normal rated voltage.
 - 3.5 Bushing porcelain shall be robust and capable of withstanding the internal pressures likely to occur in service. The design and location of clamps and the shape and the strength of the porcelain flange securing the bushing to the tank shall be such that there is no risk of fracture. All portions of the assembled porcelain enclosures and support other than gaskets, which may in any way be exposed to the atmosphere shall be composed of completely non hygroscopic material such as metal or glazed

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

porcelain.

3.6 All iron parts shall be hot dip galvanised and all joints shall be air tight. Surface of joints shall be trued up porcelain parts by grinding and metal parts by machining. Insulator/bushing design shall be such as to ensure a uniform compressive pressure on the joints.

4. TESTS

Bushing hollow column insulators and support insulators shall conform to type tests and shall be subjected to routine tests in accordance with IS:2099 & IS: 2544.

4.1 Technical parameters of bushing/ Hollow column insulators/ support insulators,

3.1 Technical parameters of bushing/ Hollow column insulators/ support insulators;					
Sl. No.	Voltage Class	220kV System	132kV System	66kV System	33kV System
a)	Rated Voltage (kV)	245	145	72.5	36
b)	Impulse withstand voltage (dry and wet) (kVp)	1050	650	325	170
c)	Power frequency with stand voltage (dry and wet (kVrms))	460	275	140	75
d)	Total creepage distance (mm)	25mm/kV			
e)	Pollution	Class – III heavy (as per IEC 71) and as specified in section 2 for all class of equipment.			
f)	Insulator shall also meet requirement of and IEC-815 as applicable having alternate long and short sheds.				

32. Motors

Motors shall be "Squirrel Cage" three phase induction motors of sufficient size capable of satisfactory operation for the application and duty as required for the driven equipment and conform to type tests and shall be subjected to routine tests as per applicable standards. The motors shall be of approved make.

1. ENCLOSURES

- Motor to be installed shall have enclosure equivalent to IP 55 as per IS:4691.
- Two independent earthing points shall be provided on opposite sides of the motor for bolted connection of earthing conductor.
- Motors shall have drain plugs so located that they will drain water resulting from condensation or other causes from all pockets in the motor casing.
- Motor weighing more than 25 kg shall be provided with eyebolts, lugs or other means to facilitate lifting.

33. Rating Plates, Name Plates and Labels

Each main and auxiliary item of equipment is to have permanently attached to it in a conspicuous position a rating plate of non-corrosive material upon which is to be engraved manufacturer's name, year of manufacture, equipment, type or serial number together

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

with details of loading conditions under which the item of equipment in question has been designed to operate and such diagram plates as may be required by the Owner. The rating plate shall conform to IEC requirement.

All such name plates, instruction plates rating plates etc. shall be in bilingual with Hindi inscription first followed by English. Alternatively, two separate plates one with Hindi & the other with English inscription may be provided.

34. Radio Interference Voltage (RIV) Test

1. GENERAL

Unless otherwise stipulated, all equipment together with its associated connectors, where applicable, shall be tested for measurement of radio interference voltage (RIV).

2. TEST LEVELS

The test voltage levels for measurement of external RIV are listed under the relevant clauses of the specification.

3. TEST METHOD FOR RIV

3.1 RIV tests shall levels for according to measuring as per International Special-Committee on ratio Interference (CISPR) Publication 16-1 (1993) Part-1. The measuring circuit shall preferably be tuned to frequency with 10 % of 0.5 MHz but other frequency being recorded. The results shall be in microvolts.

3.2 Alternatively, RIV tests shall be in accordance with NEMA standard Publication No.107-1964, except otherwise noted herein.

3.3 In measurement, RIV, temporary additional external shielding may be provided. In measurements of RIV only standard fitting of identical type supplied with the equipment and a simulation of the connections as used in the actual installation will be permitted in the vicinity within 3.5 meters of terminals.

3.4 Ambient noise shall be measured before and after each series of tests to ensure that there is no ambient noise level. If variation is present, the lowest ambient noise level will form basis for the measurements. RIV levels shall be measured at increasing voltages 85%, 100%, 115% and 130% of the specified RIV test voltage for all equipment unless otherwise specified.

3.5 The metering instruments shall be as per CISPR recommendation or equivalent device so long as it has been used by other testing authorities.

3.6 The metering instruments shall be as per CISPR recommendation or equivalent device so long as it has been used by other testing authorities.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

Annexure-A:

List of Standards and Specifications/ General Standards/ Indian Electricity Rules

- IS-5: Colours for Ready Mixed Paints and Enamels IS-335 Insulating Oil for Transformers and switchgear
- IS-375: Marketing and Arrangement for Bus-bars, Main Connection & Auxiliary Winding
- IS-617: Aluminium and Aluminium alloy & Ingots and Castings for General Engineering Purposes
- IS-1448: Methods of Test for Petroleum and its Products.
- IS-2071: Measuring Devices
- IS-2147: Degree of Protection Provided by Enclosures of for Low voltage switch gear and control Gear
- IS-2165: Phase-to-Phase Insulation Co-ordination, Principles and Rules
- IS-2362: Determination of Water by the Karl fisher Method
- IS-3043: Codes of practice for earthing
- IS-3202: Code of Practice for climate proofing of electrical equipment
- IS-3637: Gas Operated Relays
- IS-6103: Methods of Test for specific resistance (Resistivity) of Electrical Insulating Liquids
- IS-6104: Method of Test for Interfacial Tension of Oil against Water by the Ring Method.
- IS-6262: Method for Determination of Electric strength of insulating liquids.
- IS-6792: Method for Radio Interference Tests on High Voltage Insulators
- IEC-214: On-Load Tap-Changers
- IEC-289: Reactors
- IEC-354: Loading Guide for Oil Immersed power transformers.
- IEC-551: Determination of Transformer and reactor Sound levels
- ANSI-C57, 12, 80: General requirements for Distribution, Power and Regulating Transformers.
- ANSI-C57, 12, 90: Test Code for Distribution, Power and Regulation Transformers.
- ANSI-C57, 16: Terminology & Test Code for current limiting Reactors.
- ANSI-C57, 21: Requirements Terminology and Test Code for Shunt Reactors Rates over 500 KVA.
- ANSI-C57, 92: Guide for loading Oil-Immersed Power Transformer up to and including 100 MVA with 55oC or 65oC Winding Rise
- ANSI-CG, IEEE-4: Standard Techniques for high Voltage Testing
- NEMA-TR-1: Transformers, Regulators and Reactors
- IS-4379: Identification of the Contents of Industrial Gas Cylinders

1. Circuit Breakers

- IEC-56: High Voltage Alternating Current Circuit Breakers
- IS 13118/ IEC-427: Synthetic Testing of high voltage alternating current circuit breakers

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

2. Current Transformers, Voltage Transformers and Coupling Capacitor Voltage Transformers

- IS-2705: Current Transformers
- IS-3156: Voltage Transformers
- IS-7311: Coupling capacitor and capacitor divider
- IEC-185: Current transformers
- EC-186A: Voltage Transformers
- IEC-186B: Coupling capacitors and capacitor dividers
- IEC-44: Instrument Transformers measurement of Partial discharges
- IEC-481: Requirements for instrument transformers
- ANSI-C93.1: Requirements for power line carrier coupling capacitor

3. Bushing Insulators

- IS-2099: Bushing for alternating Voltages above 1000V
- IEC-137: Insulated Bushings for Alternating voltages above 1000 V
- IEC-61109: Composite Silicon Rubber polymer insulators.
- IEC-60437: Radio Interference Test on High voltage Insulators
- IEC-60507: Artificial pollution test on high voltage insulators to be used on AC systems
- IEC-60815: Guide for the selection of insulators in respect of polluted conditions.
- IEC-61952: Insulators for overhead lines, composite line, post insulators for alternative current within nominal voltage greater than 1000 volts upto 245 KV- Definitions, test methods and acceptance criteria.
- IEC-61466/1: Composite strings, insulator units for overhead lines for nominal voltage greater than 1 KV-part-1 Standard strength classes and end fittings.
- IEC-61466/2: Composite strings, insulator units for overhead lines for nominal voltage greater than 1 KV-part-2 Dimensional and electrical characteristics.

4. Surge Arresters

- IS-3070: Lightning arrestors for alternating current systems: Metal (part-3) oxide lightning arrestors without gaps.
- IEC 99-4: Metal oxide surge arresters without gaps

5. Cubicles and Panels & Other related Equipment

- IS:722: AC Electricity Meters (P1 to P9)
- IS 1248 Direct acting indicating analogue electrical measuring instruments their accessories.
- IS722, IS-1248: (PO-3) Electrical relays for power system protection.
- IS-3231, 3231, IEC-68.2.2: Basic environmental testing procedures Part 2: Test B: Dry heat
- IEC-529: Degree of Protection provided by enclosures
- IEC-158: Low Voltage control gear, contractors
- IEC-439: Low voltage switchgear and control gear assemblies
- ANSI-C37.20: Switchgear assemblies, including metal enclosed bus.
- ANSI-C37.50: Test Procedures for low voltage alternating current power circuit breakers
- ANSI-C39: Electric Measuring instrument.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

-
- ANSI-C83: Components for electric equipment
IS:8623: Specification for sugar NEMA-AB-Moulded Case circuit and systems

6. Lt Switchgear

- IS:8623: Specification for factory built assemblies of Switchgear & Control gear for voltages upto and including 1000 V AC/ 1200V DC
IS:4237: General requirements for switchgear and control gear for voltage not exceeding 1000 V.
IS2147: Degree of protection provided by enclosures for low voltage switchgear and control gear.
IS:3202: Code of practice for climate proofing of electrical equipment.
IS:3072: Code of practice for installation and maintenance of switchgear
IS:8544: AC motor starters of voltage not exceeding 1000 Volts
IS:4064: Air-break switches, air break dis-connectors air break dis-connectors and fuse combination unit for voltages not exceeding 1000V AC or 1200V DC.
IS:3231: Electrical relays for power system protection.
IS:1248: Electricity indicating instruments
IS:722: AC Electricity meters.
IS:375: Marking and arrangements of bus bars.
IS:9224: HRC Cartridge fuses (Part II)
IS:6875: Switches and push-buttons
IS:6005: Code of practice of phosphating iron and steel
IS:5082: Wrought Aluminium and Aluminium alloys for electrical purposes.

7. Disconnecting Switches

- IEC-129: Alternating Current Dis-connectors (Isolators) and Earthing switches
IS-9921: Isolators
IEC-265: High voltage switches
ANSI-C37.32: Schedule of preferred Ratings, manufacturing specification and application guide of high voltage air switches, bus supports and switch accessories.
ANSI-C37.34: Test code for high voltage air switches
NEMA-SG6: Power switching equipment.

8. Protection and Control Equipment

- IEC-51: Recommendations for Direct acting indicating analogue electrical measuring instruments and their accessories.
IEC-255: Electrical relays
IEC-297: Dimensions of mechanical structures of the 482.6mm (19 inches) series.
IEC-359: Expression of the performance of electrical & electronic measuring equipment. IEC-387 Symbols for Alternating-Current Electricity meters
IEC-447: Man machine interface/ MM-Alternating principles
IEC-521: Class 0.5, 1 and 2 alternating current wall hour meters
IEC-547: Modular plug-in unit and standard 19-inch rack mounting unit based on NIM standard (for electronic nuclear instruments)
ANSI-81: Screw threads.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

-
- ANSI-B18: Bolts and Nuts
 - ANSI-C37.1: Relays, Station controls etc.
 - ANSI-C37.2: Manual and automatic station control, supervisory and associated telemetering equipment.
 - ANSI-C37.2: Relays and relay system associated with electric power apparatus.
 - ANSI-C39.1: Requirements for electrical analogue indicating instruments.

9. Motors

- IS-325: Three phase induction motors
- IS-4691: Degree of protection provided by enclosure for rotating electrical machinery
- IEC-34: Rotating electrical machines
- IEC-68 (P1 to P5): Environmental testing
- IEC-326 (P1 to P2): Printed boards.

10. Material and Workmanship Standards

- IS-1363: Hexagon head bolts, screws and nuts of product grade C.
- IS-1364: Hexagon head bolts, screws and nuts of products grades A and B
- IS-3138: Hexagonal Bolts and nuts (M42 to M150)
- IS-898: Fasteners: Bolts, screws and studs

11. Clamps and Connectors

- IS:2121: Fitting for aluminium and steel cored aluminium conductors for overhead power lines.
- IS:731: Porcelain insulators for overhead power line with a nominal voltage than 1000 V
- IS:2486: Insulator fitting for overhead power lines with a nominal voltage greater than 1000 V
- IEC-120: Dimensions of Ball and socket couplings of string insulator units.
- IEC-137: Insulated turning for alternating voltages above 1000 V.
- IEC-168: Tests on indoor and outdoor post insulators of glass for system with nominal voltages greater than 1000 V.
- IEC-233: Tests on Hollow insulators for use in electrical equipment.
- IEC-273: Characteristics of indoor and outdoor post insulators for systems with nominal voltage greater than 1000 V.
- IEC-305: Insulators for overhead lines with nominal volt above 1000 V-ceramic or glass mull units for AC system characteristics of string insulator units of the cap and pin type.
- IEC-372: Locking devices for ball and socket couplings of string insulator units dimensions and tests
- IEC-383: Insulators for overhead lines with a nominal voltage above 1000 V.
- IEC-433: Characteristics of string insulator units of the long rod type.
- IEC-471: Dimensions of Clevis and tongue coupling of string insulator units
- ANSI-C29: Wet Process porcelain insulators
- ANSI-C29.1: Test Methods for electrical power insulators
- ANSI-C29.2: For insulators, wet-process porcelain and toughened glass suspension type. ANSI-C29.8 For wet-process porcelain insulators apparatus, post-type.
- ANSI-G.8: Iron and steel hardware
- ASTM A-153: Zinc Coating (Hot-Dip) on iron and steel hardware

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

12. Strain and Rigid Bus-Conductor

- IS-2678: Dimensions & tolerances for wrought aluminium and aluminium alloys.
- IS-5082: Wrought aluminium and aluminium alloy bars, Rods, tubes and sections for electrical purposes.
- ASTM-B 230-82: Aluminium 1350 H19 Wire for electrical purposes
- ASTM-B 221-81: Concentric – lay – stranded, aluminium 1350 conductors
- ASTM-B 221: Aluminium – Alloy extruded bar, rod, wire shape.
- ASTM-B 236-83: Aluminium bars for electrical purpose (Bus-bars)
- ASTM-B 317-83: Aluminium – Alloy extruded bar, rod, pipe and structural shapes for electrical purposes (Bus Conductors)

13. Battery Chargers

- IS:3895: Mono-Crystalline Semiconductor Rectifier Cells and stacks
- IS:4540: Mono-crystalline semiconductor rectifier assemblies and equipment
- IS:6619: Safety code for semiconductor rectifier equipment.
- IS:2026: Power Transformer
- IS:2959: AC Contractors for voltage not exceeding 1000 Volts
- IS:1248: Indicating Instruments
- IS:2208: HRC Fuses
- IS:4064: Air break switches, air break Disconnecter & fuse combination units for voltage not exceeding 1000V Ac or 1200V DC.
- IS:2147: Degree of protection provided by enclosures for low voltage switchgear and control gear.
- IS: 600:5: Code of practice for phosphating of Iron and steel.
- IS:3231: Electrical relays for power system protection
- IS:3842: Electrical relay for AC systems.
- IS:5: Colours for ready mix paints.

14. Battery

- IS:1651: Stationary Cells and Batteries, Lead-Acid Type (with Tubular Positive Plates).
- IS:1652: Stationary Cells and Batteries, Lead-Acid Type (with Plant Positive Plates).
- IS:1146: Rubber and plastic containers for Lead-Acid Batteries
- IS:6071: Synthetic separators for Lead-Acid batteries.
- IS:266: Specification for Sulphuric Acid.
- IS:1069: Specification of water for storage batteries
- IS:3116: Specification for sealing compound for lead-acid batteries
- IS:1248: Indicating Instruments

15. Wire and Cables

- IS-694: PVC insulated cables for working voltages upto and including 1100Volts.
- IS-1255: Code of practice for installation and maintenance of power cables upto and including 33 kV rating.
- IS-1554: PVC insulated (heavy duty) electric cables (part 1) for working voltage upto and including 1100 V Part (2) for working voltage from 3.3 upto including 11 kV.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

IS-1753:	Aluminium conductors for insulated cables
IS-2982:	Copper conductors in insulated cables and cords.
IS-3961:	Recommended current rating for cables.
IS-3975:	Mild steel wires, formed wires and tapes for armouring of cables
IS-5831:	PVC insulated and sheath of electric cables
IS-6380:	Elastomeric insulating and sheath of electric cables.
IS-7098:	Cross linked polyethylene insulated PVC sheathed cables for working voltage up to and including 1100 volts. Part (2) Cross-linked polyethylene insulated PVC sheathed cables for working voltage from 3.3 kV up to and including 33 kV.
IS-8130:	Conductors for insulated electrical cables and flexible cords.
IS-10418:	Specification for drums for electrical cables. IEC-96 Radio Frequency cables
IEC-183:	Guide to the selection of High Voltage Cables.
IEC-189:	Low frequency cables and wires with PVC insulation and PVC Sheath
IEC-227:	Polyvinyl Chloride insulated cables of rated voltages up to and including 450/750 V.
IEC228L	Conductors of insulated cables.
IEC-230:	Impulse tests on cables and their accessories.
IEC-287:	Calculation of the continuous current rating of cables (100% load factor).
IEC-304:	Standard colours for insulation for low frequency cables and wires.
IEC-331:	Fire resisting characteristics of Electric cables.
IEC-332:	Tests on electric cables under fire conditions
IEC-502:	Extruded solid dielectric insulated power cable for rated voltages from 1 kV up to 30 kV.
IEC-754:	Tests on gases evolved during combustion of electric cables.
NEMA-WC1:	Asbestos and asbestos-varnished cloth and asbestos thermoplastic insulated wire and cable
NEMA-WC2:	Steel armour and associated covering for impregnated paper insulated cables
NEMA-WC3:	Rubber insulated wire and cable for transmission and distribution of electrical energy.
NEMA-WC5:	Thermoplastic insulated wire and cable for the transmission and distribution of electric energy.
NEMA-WC7:	Cross linked thermo setting polyethylene insulated wire and cable for the transmission and distribution of electrical energy.
NEMA-WC8:	Ethylene-propylene-rubber insulated wire and cable for the transmission and distribution of electrical energy.
NEMA-W67:	Cross linked thermo setting polyethylene
IS-659:	Safety code for air conditioning
IS-1391:	Room air conditioners.
IS-6272:	Industrial cooling fans.

16. Galvanizing

IS-209:	Zinc Ingot.
IS-2629:	Recommended practice for Hot-Dip galvanizing on iron and steel.
IS-2629:	Methods for testing uniformity of coating of zinc coating articles.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

ASTM-a-123: Specification for zinc (Hot galvanizing) coatings on products fabricated from rolled, pressed and forged steel shapes, plates, bars and strips.

ASTM-A-153: Specification for Zinc coating (Hot Dip) on iron and steel hardware

ASTM-A-239: Test method for locating the thinnest. Spot in a Zinc (galvanised) coating on iron and steel articles by the preece test (Copper sulfated dip).

17. Fire Protection

IS-554: Dimensions for pipe threads where pressure tight joints are required on the threads.

IS638: Sheet rubber jointing and rubber insertion jointing.

IS-778: Copper alloy gate, globe and check valves for water works purposes.

IS-780: Sluice valves for water-works purposes (50 to 300 mm size)

IS-1536: Centrifugally cast (spun) iron pressure pipes for water gas and sewage.

IS-1538(1993): Cast iron fitting for pressure pipes for water gas and sewage.

IS-1703(1989): Copper alloy bar valves (horizontal plunger type) for water supply fittings.

IS2379(1990): Colour code for identification of pipe lines.

IS-2643 (P1 to P3: 1990): Dimensions for pipe threads for fastening purposes.

IS-2685(1992): Code of practice for selection, installation and maintenance of sluice valves.

IS-2906(1990): Specification for sluice valves for water works purposes (350 to 1200 mm size)

IS-3589(1991): Seamers or eclectically welded steel pipes for water, gas and sewage (168.3 to 2032 mm outside diameter).

IS-4038(1990): Foot valves for water works purposes

IS-4927(1991): Unlined flax canvas hose for firefighting.

IS-5321-(P1 and P2 1991): Swing check type reflux (non-return) valves

IS-13095 (1991): Butterfly valves for general purposes

18. Steel Structures

IS-228: Method of chemical analysis of pig iron, cast iron and plain carbon and low alloy steels.

IS-802: Code of practice for use of structural steel in overhead transmission line towers.

IS-806: Code of practice for use of steel tubes in general building construction.

IS-808: Dimensions for hot rolled steel beam column channel and angle sections.

IS-814: Covered electrodes for manual arc welding of carbon manganese steel

IS-816: Code of practice for use of metal arc welding for general construction in mild steel.

IS817: Code of practice for training and testing of metal arc welders. Part 1: Manual metal arc welding

IS-875: Code of practice for design loads (other than earthquake) for buildings and structures.

IS-1161: Steel tube for structural purposes.

IS-1182: Recommended practice for radiographic examination of fusion welded but joints in steel plates.

IS-1363: Hexagonal head bolts, screws and nuts of products grade C.

IS-1364: Hexagon head bolts, screw & nuts of products grade A and B.

IS-1367: Technical supply condition for threaded steel fasteners

IS-1599: Method for bend test.

IS-1608: Method for tensile testing of steel products.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

IS-1893:	Criteria for earthquake resistant design of structures
IS-1978:	Line pipe
IS-2062:	Steel for general structural purposes
IS-2595:	Code of practice for Radiographic testing
IS-3063:	Single built rectangular section spring washers for bolts, nuts and screws.
IS-3664:	Code of practice for ultra-sonic pulse echo testing by contact and immersion methods.
IS-7205:	Safety code for erection of structural steel work.
IS-9595:	Recommendations for metal arc welding of iron and carbon manganese steels.
ANSI B18.2.1:	Inch series square and Hexagonal bolts and screws.
ANSI-B18.2.2:	Square and hexagonal nuts
ANSI-G8.14:	Round head bolts

19. Other Civil Works Standards

IS-269 33:	Grade ordinary portland cement
IS-2721:	Galvanized steel chain link fence fabric.
IS-278:	Galvanized steel barbed wire for fencing
IS-383:	Coarse and fine aggregates from natural sources for concrete.
IS-432:	Mild steel and medium tensile steel bars and hard-drawn steel wire for concrete reinforcement
IS-456:	Code of practice for plain and reinforced concrete.
IS-516:	Method of test for strength of concrete
IS-800:	Code of practice for general construction in steel
IS-806:	Steel tubes for structural purposes
IS-1172:	Basic requirements for water supply, drainage and sanitation
IS-1199:	Method of sampling and analysis of concrete
IS-1566:	Hard-drawn steel wire fabricated concrete reinforcement
IS-1742:	Building drainage
IS-1785:	Plain hard-drawn steel wire for pre stressed concrete
IS-1786:	High strength deformed and wires for concrete reinforcement
IS-1811:	Method of sampling Foundry sands.
IS-1893:	Criteria for earthquake resistant design of structures. IS-2062 Steel for general structural purposes
IS-2065:	Code of practice for water supply in buildings
IS-2090:	High tension steel bars used in pre-stressed concrete
IS-2140:	Standard galvanised steel wire for fencing
IS-2470:	Code of practice for installation of septic tanks
IS-2514:	Concrete vibrating tables
IS-2645:	Integral cement waterproofing compounds
IS-3025:	Method of sampling and test physical chemical for water waste water.
IS-4091:	Code of practice for design and construction of foundations for transmission line tower and poles
IS-4111:	Code of practice for ancillary structure in sewerage system

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

IS-4990: Plywood for concrete shuttering work

IS-5600: Sewage and drainage pumps

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

Contents

SECTION 4:.....	2
Annexure-A: Compliance Certificate of Technical Specification.....	2
SECTION 4:.....	3
Annexure-B: Deviation/ Change Request of Technical Specification.....	3
SECTION 4:.....	4
Annexure-C: Guaranteed Technical Particulars.....	4
SECTION 4:.....	7
Annexure-D: Technical Checklist	7

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

SECTION 4:

Annexure-A: Compliance Certificate of Technical Specification

The bidder shall confirm compliance to the following by signing and stamping this compliance certificate and furnishing same with the offer.

1. The scope of supply, technical details, construction features, design parameters etc. shall be as per technical specification & there are no exclusion/ deviation with regard to same.
2. There are no deviation(s) with respect to specification other than those furnished in the schedule of deviations.
3. Only those technical submittals which are specifically asked for in Notice Inviting Tender (NIT) to be submitted at tender stage shall be considered as part of offer. Any other submission, even if made, shall not be considered as part of technical offer.
4. Any comments/ clarifications on technical/ inspection requirements furnished as part of bidder's covering letter shall not be considered by BHEL, and bidder's offer shall be construed to be in conformance with the specification.
5. Any changes made by the bidder in the price schedule with respect to the description/ quantities from those given in 'BOQ' of the specification shall not be considered (i.e., technical description & quantities as per the specification shall prevail).

Date:

Bidder's Stamp & Signature

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

SECTION 4:

Annexure-B: Deviation/ Change Request of Technical Specification

Bidder shall list out all technical potential deviation/ change request (s) along with clause with respect to technical specifications.

Sl. No.	Page No.	Clause No.	Deviation	Reason/ Justification(s)
---------	----------	------------	-----------	--------------------------

Any deviation not specifically brought out in this section shall not be admissible for any commercial implication at later stage. Except to the technical deviations listed in this schedule, bidder's offer shall be considered in full compliance to the tender specifications irrespective of any such deviation indicated / taken elsewhere in the submitted offer.

Date:

Bidder's Stamp & Signature

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

SECTION 4:

Annexure-C: Guaranteed Technical Particulars

Sl. No.	Description	Unit	Particulars to be filled by Bidder
A.	33 KV Fault Current Limiter Panel with its accessories		
1.	General		
i)	Name of manufacturer (OEM)		
2.	Type & Designation		
i)	Type tested at Name of Laboratory		
ii)	Address of laboratory		
3.	Installation		
i)	Standards applicable		
ii)	Type		
iii)	No. of Phases		
iv)	Nominal system voltage	kV	
v)	Maximum operating voltage	kV	
vi)	Continuous Current	A	
vii)	Limiting fault level of system	kArms	
viii)	Basic Insulation Level	kV	
ix	Frequency	Hz	
x)	Creepage	mm/kV	
xi)	Earthing		
xii)	Ingress Protection	IP	
xiii)	Cable entry		
xiv)	Dimensions of vertical section (LxDxH)	mmxmmxmm	
xv)	Equipment working height limits from floor level	mm	
4.	Support Structure		
i)	Material		
ii)	Foundation channels /Anchor bolts		
5.	Earthing		
i)	Earthing Material		
ii)	Earthing of complete Panel		
6.	Maintenance		
i)	Maximum down time for replacement or removal of any part		
ii)	Recommended period for overhauling		

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

iii)	Operation and Maintenance manual attached		
iv)	List of recommended spares attached?		
v)	List of recommended special tools, etc. attached?		
vi)	List of commission spares attached?		
vii)	List of maintenance spares attached?		
B.	Off-load isolator Panel associated with 33 kV Fault Current Limiter Panel		
1.	General		
i)	Name of manufacturer (OEM)		
2.	Type & Designation		
i)	Type tested at Name of Laboratory		
ii)	Address of laboratory		
3.	Installation		
i)	Standards applicable		
ii)	Type		
iii)	No. of Phases		
iv)	Nominal system voltage	kV	
v)	Maximum operating voltage	kV	
vi)	Continuous Current	A	
vii)	Limiting fault level of system	kArms	
viii)	Basic Insulation Level	kV	
ix	Frequency	Hz	
x)	Creepage	mm/kV	
xi)	Earthing		
xii)	Ingress Protection	IP	
xiii)	Cable entry		
xiv)	Dimensions of vertical section (LxDxH)	mmxmmxmm	
xv)	Equipment working height limits from floor level	mm	
4.	Support Structure		
i)	Material		
ii)	Foundation channels /Anchor bolts		
5.	Earthing		
i)	Earthing Material		

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

ii)	Earthing of complete Panel		
6.	Maintenance		
i)	Maximum down time for replacement or removal of any part		
ii)	Recommended period for overhauling		
iii)	Operation and Maintenance manual attached		
iv)	List of recommended spares attached?		
v)	List of recommended special tools, etc. attached?		
vi)	List of commission spares attached?		
vii)	List of maintenance spares attached?		

Date:

Bidder's Stamp & Signature

Not to be submitted during TE.

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

SECTION 4: Annexure-D: Technical Checklist

Sl. No.	Particulars	Confirmation by Bidder	
1	Technical Qualifying Requirement		
1.1	The bidder to furnish relevant documents for meeting the qualifying requirement. Performance certificates shall be submitted in English. Translated pages should be attested by the ultimate customer, if attested only by the bidder it shall be notarized.	Confirmed	Yes/ No
1.2	The technical bid shall be submitted by the Manufacturer of 33kV Fault Current Limiter Panel with its Accessories in case of Indian Manufacturer; however, agent may submit the technical offer in case of foreign manufacturer. The bidder's scope includes supply and services such as -Supervision of installation, testing and commissioning.	Confirmed	Yes/ No
1.3	All the documents shall be submitted in English. Translated pages should be attested by the ultimate customer, if attested only by the bidder it shall be notarized.	Confirmed	Yes/ No
2	Un-priced BOQ		
2.1	Confirm that all items have been quoted separately. (If any item has not been quoted, the same shall be specifically brought out with technical reasons thereof, else offer shall be liable for rejection).	Confirmed	Yes/ No
2.2	Any other supply/ service required for the execution for the complete work of 33kV Fault Current Limiter Panel with its Accessories is deemed to be included in the offer, whether specifically mentioned in the specification or not. Bidder to submit list of items along with their respective quantities required for completeness of GIS & its accessories.	Confirmed (List is attached)	Yes/ No
2.3	Bidder to submit list of consumables with shelf life of less than one year. It shall be supplied before erection after clearance from BHEL/ Customer/ Consultant.	Confirmed (List is attached)	Yes/ No
2.4	Commissioning spares for testing & commissioning of 33kV Fault Current Limiter Panel with its Accessories till handing over shall be under bidder's scope.	Confirmed	Yes/ No
2.5	Detailed list of Tools & tackle & Testing Equipment to be supplied at site on returnable basis.	Confirmed (List is	Yes/ No

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

		attached)	
2.6	Detailed list of Tools & tackle & Testing Equipment to be supplied at site on non-returnable basis.	Confirmed (List attached)	Yes/ No
2.7	The scope of supply shall also include all erection and mounting hardware and interconnecting cables of panels under scope.	Confirmed	Yes/ No
3	Technical		
3.1	Internal components maintenance free for at least 10 years/as mentioned in technical specification.	Confirmed	Yes/ No
3.2	Bidder shall provide AC and DC auxiliary loads for panels.	Confirmed (Enclosed with bid)	Yes/ No
3.3	Catalogues of panels	Confirmed (Enclosed with bid)	Yes/ No
3.4	Catalogues of all test equipment. Bidder to confirm that offered equipment meets the requirements of specification.	Confirmed (Enclosed with bid)	Yes/ No
4	Calculations		
4.1	Carrying out the electrical system studies required for generation of information which is essential for design of fault limiting systems. The proposed fault limiting system shall have suitable short time rating and system trigger settings to ensure proper actuation of system while maintaining the system fault level limits.	Confirmed	Yes/ No
4.2	Collection of all existing system data as required for fault limiting system design shall be in the scope of bidder.	Confirmed	Yes/ No
5	Technical Deviations		
5.1	Confirm that the Complete systems have been offered as per the requirements of Technical Specification and Technical Deviation sheet has been submitted. Deviations mentioned elsewhere in the bid will not be considered.	Confirmed	Yes/ No
6	Bar-chart		
6.1	Bidder shall submit detailed bar chart indicating all the milestones from engineering till manufacturing/ testing, dispatch to site, supervision for installation, testing and commissioning.	Confirmed	Yes/ No

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

7	Office and Staff		
7.1	Bidder shall also provide their standard recommendations for precautions to be taken during unloading and storage etc. for approval of BHEL/ Customer/ Consultant. Requirement of closed store, if any shall be taken care by bidder.	Confirmed	Yes/ No
7.2	Office facilities & accommodation for bidder's staff along with conveyance, transportation of all special tools & plants, testing kits etc. shall be in bidder's scope.	Confirmed	Yes/ No
8	Site Test		
8.1	Any special tools and tackles required to complete the cable installation, testing and commissioning etc. shall be included in the offer. However, general tools and tackles for installation of 33kV Fault Current Limiter Panel with its Accessories shall be provided by BHEL.	Confirmed	Yes/ No
8.2	All field tests including tests during installation, pre-commissioning, commissioning, field acceptance tests shall be conducted by the bidder, in presence of representative of the BHEL/ Customer. No separate site test will be conducted by BHEL/ Customer	Confirmed	Yes/ No
8.3	Bidder shall depute its qualified supervisor for installation, testing & commissioning of 33kV Fault Current Limiter Panel with its Accessories.	Confirmed	Yes/ No
8.4	Bidder shall submit complete methodology for installation, testing & commissioning of 33kV Fault Current Limiter Panel with its Accessories for further approval of BHEL/ Customer/ Consultant.	Confirmed	Yes/ No
8.5	Bidder to note that 33kV Fault Current Limiter Panel with its Accessories may be commissioned at different point of time, and hence bidder shall be required to deploy the resources multiple times at site in line with site requirement.	Confirmed	Yes/ No
9	Type Test Requirements		
9.1	Bidder shall ensure that 33kV Fault Current Limiter Panel with its Accessories, being procured should have valid type test certificates as per specified in IS/ IEC standards (amended up to date) at any ISO/IEC accredited laboratories.	Confirmed	Yes/ No
9.2	Type test certificates shall not be more than five (5) years old as on original scheduled date of technical bid opening. In those cases, where type test certificates are more than five (5) years old from original scheduled date of technical bid opening, OEM/ bidder shall carry out the type tests at any ISO/ IEC accredited laboratories prior to dispatch of equipment with no	Confirmed	Yes/ No

Bharat Heavy Electricals Limited

Project: LSTK job for ISBL work of 220KV Grid Power Import at IOCL, Panipat Refinery

Technical Specification: 33kV AIS Local Isolation Breaker Panel with its Accessories

Doc No. TB-411-316-004 Rev 00

	commercial implication to BHEL/Customer.		
9.3	In case any of Type tests have not been conducted on the offered design or there has been a change in the design after the type tests. The requisite tests shall be conducted by bidder on the offered design without any extra cost and delivery impact to BHEL/ Customer.	Confirmed	Yes/ No

Date:

Bidder's Stamp & Signature

