

CLAUSE NO.	MANDATORY SPARES			
	enclosed. All cases, containers and other packages must be suitably marked and numbered for the purposes of identification.			
7.00.00	All cases, containers or other packages are to be opened for such examination as may be considered necessary by the Employer.			
8.00.00	The contractor will provide the Employer with all the addresses and particulars of his sub suppliers while placing the order on vendors for items/components/equipments covered under the contract and will further ensure with his vendors that the Employer, if so desires, will have the right to place order for spares directly on them on mutually agreed terms based on offers of such vendors.			
9.00.00	The Contractor shall warrant that all spares supplied will be new and in accordance with the contract Documents and will be free from defects in design, material and workmanship.			
10.00.00	In addition to the recommended spares listed by the contractor, if the employer further identifies certain particular items of spares, the contractor shall submit the prices and delivery quotation for such spares within 30 days of receipt of such request with a validity period of 6 months for consideration by the Employer and placement of order for additional spares if the Employer so desires.			
11.00.00	The Contractor shall guarantee the long term availability of spares to the Employer for the full life of the equipment covered under the contract. The Contractor shall guarantee that before going out of production of spares parts of the equipment covered under the Contract, he shall give the Employer at least 2 years advance notice so that the latter may order his bulk requirement of spares, if he so desires. The same provision will also be applicable to sub-contractors. Further, in case of discontinuance of manufacture of any spares by the Contractor and/or his sub contractors, Contractor will provide the Employers, two years in advance, with full manufacturing drawings, material specifications and technical information including information on alternative equivalent makes required by the Employer for the purpose of manufacture/procurement of such items.			
12.00.00	The bidder to provide datasheets/assembly drawings of the manufacturer/ any other relevant document showing Bill of Material(s), Make, Model Number, Part Number etc. through which the mandatory spares to be supplied can be uniquely identified. This would facilitate the Employer to assign a unique code to each of the mandatory spare as brought out in GCC. The bidder shall extend all necessary assistance in this regard.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-1 (3X800 MW)		TECHNICAL SPECIFICATION SECTION-VI, PART-A BID DOC. NO. CS-9585-001-2	SUB-SECTION-VI MANDATORY SPARES	PAGE 3 OF 3

CLAUSE NO.	LIST OF MANDATORY SPARES FOR FUEL OIL		एनटीपीसी NTPC
	----- ITEM -----	----- QUANTITY -----	
1.00.00	MECHANICAL ITEMS		
1.01.00	Strainer elements		
	a. F.O. Drain pumps	1 no.	
	b. HFO/ LSHS/HPS/ LDO unloading & transfer pumps	1 no.	
1.02.00	Floor Coil Heater		
	a. Oil water separator pit	15% of total length of coil	
1.03.00	Relief valve complete assembly		
	a. HFO/ LSHS/HPS/ LDO unloading pumps	1 no.	
	b. Pressure reducing station	1 no.	
1.04.00	Bearings of		
	a. HFO/ LSHS/HPS/ LDO unloading pumps	1 set	
	b. F. O. Drain pumps	1 set	
	c. Sump pumps	1 set	
	d. Dirty Oil pumps	1 set	
1.05.00	Rotor Assembly (Complete cartridge assembly)		
	a. HFO/ LSHS/HPS/ LDO unloading pumps	1 no.	
	b. F. O. Drain pumps	1 no.	
	c. Sump pumps	1 no.	
	d. Dirty Oil pumps	1 no.	
1.06.00	Coupling Bolts with nuts, washer and bushes for HFO/ LSHS/HPS/ LDO LDO unloading pumps	1 set for each size of coupling	
1.07.00	Wearing Rings	1 set for each type of pump	
1.08.00	Gland Packing (if applicable)	1 set for each type of pump	
1.09.00	Mechanical seal Assembly (if applicable)	2 sets each for Fuel Oil unloading cum transfer pump	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X800MW)		TECHNICAL SPECIFICATION SECTION-VI, PART-F BID DOC. NO. CS-9585-001-2	MANDATORY SPARES CHAPTER-11 FUEL OIL
			PAGE 1 OF 4

CLAUSE NO.	LIST OF MANDATORY SPARES FOR FUEL OIL		एनटीपीसी NTPC
1.10.00	Shaft Sleeve	1 set for each type of pump	
	----- ITEM -----	----- QUANTITY -----	
1.11.00	Valves (Each type and size)	a) 1 number, where the total quantity of a particular type and size of valve is less than or equal to 10. b) 2 numbers, where the total quantity of a particular type and size of valve is less than 40 but more than 10. c) 10% of total quantity (to nearest whole number) of a particular type and size of valve, where the total quantity of a particular type and size of valve is more than 40	
1.12.00	Steam Trap	2 numbers for each type and size	
1.13.00	Control valves (complete assy)	one (1) no. complete for floor coil heaters one (1) no. complete for suction heaters	
1.14.00	Pressure reducing valve	One (1) no.	
1.15.00	Neoprene rubber unloading hoses with end connections complete hose)	Ten (10) Nos.	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X800MW)		TECHNICAL SPECIFICATION SECTION-VI, PART-F BID DOC. NO. CS-9585-001-2	MANDATORY SPARES CHAPTER-11 FUEL OIL PAGE 2 OF 4

CLAUSE NO.	LIST OF MANDATORY SPARES FOR FUEL OIL		
2.00.00	CONTROL AND INSTRUMENTATION ITEMS		
2.01.00	MEASURING INSTRUMENTS		
	1	Electronic Transmitters	
		Transmitters of all types and model no. (for the measurement of Pressure, differential pressure flow, level, etc.)	10% or 1 no. of each type and model whichever is more.
	2	Temperature elements	
	(i)	RTD's*, Thermocouples	10% or 2 no. of each type, make and model
	(ii)	Thermowell**	10% or 2 no. of each type, make and model
		* (With head assembly, terminal block and nipple)	
		**(to be divided into various insertion lengths in proportion to main population)	
	3	Local Indicators like temperature gauges, pressure gauges, differential pressure gauges, flow gauges etc.	5% or 1 no. of each type, make and model
	4	Process Actuated Switch Devices Includes all types of Pressure, differential pressure, flow, temperature, level switch Devices	5% or 1 no. of each type, make and model
2.02.00	PROCESS CONNECTION PIPING (FOR IMPULSE PIPING/TUBING, SAMPLING PIPING/TUBING AND AIR SUPPLY PIPING AS APPLICABLE)		
	1	Valves	10% or 1 no. of each type, make and model
	2	2 way, 3way, 5way valve manifolds	10% or 1 no. of each type, make and model
	3	Fittings	10% or 1 no. of each type, make and model
	4	Purge Meters	5% or 1 no. of each type, make and model whichever is more

CLAUSE NO.	LIST OF MANDATORY SPARES FOR FUEL OIL		एनटीपीसी NTPC										
2.03.00	----- <table><tr><th>ITEM</th><th>QUANTITY</th></tr><tr><td colspan="2"> ----- </td></tr><tr><td>5 Filter Regulator</td><td>20% or 2 nos. of each type, make and model whichever is more</td></tr><tr><td colspan="2">ELECTRICAL ACTUATORS</td></tr><tr><td>1 Actuators</td><td>10% (or) 1 no. of each type, model and rating, whichever is more.</td></tr></table>			ITEM	QUANTITY	-----		5 Filter Regulator	20% or 2 nos. of each type, make and model whichever is more	ELECTRICAL ACTUATORS		1 Actuators	10% (or) 1 no. of each type, model and rating, whichever is more.
	ITEM	QUANTITY											

	5 Filter Regulator	20% or 2 nos. of each type, make and model whichever is more											
	ELECTRICAL ACTUATORS												
1 Actuators	10% (or) 1 no. of each type, model and rating, whichever is more.												
Note :													
One (1) set means total numbers as required for one complete replacement for one equipment.													

EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X800MW)	TECHNICAL SPECIFICATION SECTION-VI, PART-F BID DOC. NO. CS-9585-001-2	MANDATORY SPARES CHAPTER-11 FUEL OIL	PAGE 4 OF 4
---	---	--	----------------

CLAUSE NO.	MANDATORY SPARES			
	MANDATORY SPARES FOR FUEL HANDLING PUMP HOUSE			
Part C				
S.no.	Item Description		Quantity	
1	HFO pressurizing pump motor		1 no.	
2	LDO pressurizing pump motor		1 no.	
3	Drain oil pump motor		1 no.	
	MANDATORY SPARES FOR AIR CONDITIONING SYSTEM			
Part C				
S.no.	Item Description		Quantity	
1	SCREW COMPRESSOR CHILLING UNIT motor		1 no.	
	MANDATORY SPARES FOR VFD for CEP			
S.no.	Item Description		Quantity	
1	HV Bushing with metal parts and gaskets for VFD Transformer		-1 No. of each rating	
2	LV Bushing with metal parts and gaskets for VFD Transformer (if applicable)		-1 No. of each rating	
3	WTI with contacts for VFD transformer		-1 No. of each rating	
4	Electronic cards (a) Control modules (b) I/O module (c) Power supply modules (d) Gate module including gate transformer		1 nos. of each type & rating	
5	Power device (Thyristor, IGBT etc.)		No. of devices in one bridge leg	
6	Over voltage limiter and surge suppressor network		1 Set	
7	Semi conductor fuses for Power device (Thyristor, IGBT etc.)		1 Set	
8	Power & Control fuse		25% of installed quantity	
9	Control Transformer		1 nos. of each type & rating	
10	Contact/Breaker		1 no.	
11	CT/VT		1 nos. of each type & rating	
12	Indicating lamps		100% of each type & rating	
13	Auxiliary contactors & relays		1 no. of each type & rating	
14	Panel mounted meters		1 no.	
15	Indicating lamp holder full set		15% of each type and colour	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X800MW)		TECHNICAL SPECIFICATION SECTION-VI, PART-F BID DOC. NO. CS-9585-001-2 Page 366 of 598	MANDATORY SPARES CHAPTER-14 ELECTRICAL	PAGE 31 OF 31

CLAUSE NO.	LIST OF MANDATORY SPARES FOR DM & PT																											
14) <u>Ventilation System</u> <table><tr><th>S.N.</th><th>Name of Items</th><th>Unit</th><th>Qty</th></tr><tr><td>1</td><td>Pre filters & Fine filters</td><td>Set</td><td>1 Set of each type/size/model</td></tr><tr><td></td><td></td><td></td><td></td></tr></table> 15) <u>LET System</u> <table><tr><th>S.N.</th><th>Name of Items</th><th>Unit</th><th>Qty</th></tr><tr><td>1</td><td>Pack of Lamella Clarifier</td><td>Set</td><td>1</td></tr><tr><td>2</td><td>Oil Skimmer (Waste Water Collection Sump)</td><td>Set</td><td>1</td></tr></table>					S.N.	Name of Items	Unit	Qty	1	Pre filters & Fine filters	Set	1 Set of each type/size/model					S.N.	Name of Items	Unit	Qty	1	Pack of Lamella Clarifier	Set	1	2	Oil Skimmer (Waste Water Collection Sump)	Set	1
S.N.	Name of Items	Unit	Qty																									
1	Pre filters & Fine filters	Set	1 Set of each type/size/model																									
S.N.	Name of Items	Unit	Qty																									
1	Pack of Lamella Clarifier	Set	1																									
2	Oil Skimmer (Waste Water Collection Sump)	Set	1																									
CONTROL & INSTRUMENTATION-PT PLANT																												
Sl. No.	ITEM		QUANTITY																									
1.00.00	MEASURING INSTRUMENTS																											
1)	Electronic Transmitters																											
(i)	Transmitters of all types and model. (for the measurement of Pressure, differential pressure, flow, level, etc.) including local indication (if applicable)		10 % or 1 no. of each type and model whichever is more																									
2)	Temperature elements																											
(i)	Temperature Transmitter		10 % or 1 no. of each type and model whichever is more																									
(ii)	RTD's*		1 no. of each type																									
(iii)	Thermo well		1 no. of each type																									
	* (With head assembly, terminal block and nipple)		** (to be divided into various insertion lengths in proportion to main population)																									
3)	Local Indicators (Non-Electrical type) -As applicable for the package as per the following items																											
(i)	Temperature gauges		1 no. of each range and type																									
(ii)	Pressure gauges		1 no. of each range and type																									
(iii)	Differential Pressure Gauges,		1 no. of each range and type																									
(iv)	Level gauges		1 no. of each range and type																									

EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X800MW)	TECHNICAL SPECIFICATION SECTION-VI, PART-F BID DOC. NO. CS-9585-001-2	MANDATORY SPARES CHAPTER-05 WS-DM & PT	PAGE 7 OF 24
---	---	--	-----------------

PATRATU VIDYUT UTPADAN NIGAM LIMITED

3X800MW PVUNL PATRATU TPP PHASE-1

TECHNICAL SPECIFICATION

FOR

FUEL OIL HANDLING SYSTEM

SECTION – IB

**SPECIFIC TECHNICAL SPECIFICATION
ELECTRICAL PORTION**



**BHARAT HEAVY ELECTRICALS LTD
POWER SECTOR PROJECT ENGINEERING MANAGEMENT
PPEI, NOIDA-INDIA**



TITLE :
ELECTRICAL EQUIPMENT SPECIFICATION
FOR
FUEL OIL HANDLING SYSTEM
3X800 MW PVUNL PATRATU TPP PHASE-1

SPECIFICATION NO.
VOLUME NO. : II-B
SECTION :
REV NO. 00 : DATE : 15.06.2018
SHEET : 1 OF 3

TECHNICAL SPECIFICATION

FOR

FUEL OIL HANDLING SYSTEM
(ELECTRICAL PORTION)

	TITLE : ELECTRICAL EQUIPMENT SPECIFICATION FOR FUEL OIL HANDLING SYSTEM 3X800 MW PVUNL PATRATU TPP PHASE-1	SPECIFICATION NO.
		VOLUME NO. : II-B
		SECTION :
		REV NO. 00 : DATE : 15.06.2018
		SHEET : 2 OF 3

1.0 EQUIPMENT & SERVICES TO BE PROVIDED BY BIDDER:

- a) Services and equipment as per “Electrical Scope between BHEL and Vendor”.
- b) Any item/work either supply of equipment or erection material which have not been specifically mentioned but are necessary to complete the work for trouble free and efficient operation of the plant shall be deemed to be included within the scope of this specification. The same shall be provided by the bidder without any extra charge.
- c) Supply of mandatory spares as specified in the specifications of mechanical equipments.
- d) Electrical load requirement for FUEL OIL HANDLING SYSTEM .
- e) All equipment shall be suitable for the power supply fault levels and other climatic conditions mentioned in the enclosed project information.
- f) Bidder to furnish list of makes for each equipment at contract stage, which shall be subject to customer/BHEL approval without any commercial and delivery implications to BHEL
- g) Various drawings, data sheets as per required format, Quality plans, calculations, test reports, test certificates, operation and maintenance manuals etc shall be furnished as specified at contract stage. All documents shall be subject to customer/BHEL approval without any commercial implication to BHEL.
- h) Motor shall meet minimum requirement of motor specification.
- i) Vendor to clearly indicate equipment locations and local routing lengths in their cable listing furnished to BHEL.
- j) Cable BOQ worked out based on routing of cable listing provided by the vendor for “ both end equipment in vendor’s scope”shall be binding to the vendor with +10 % margin to take care of slight variation in routing length & wastages.

2.0 EQUIPMENT & SERVICES TO BE PROVIDED BY PURCHASER FOR ELECTRICAL & TERMINAL POINTS:

Refer “Electrical Scope between BHEL and Vendor”.

3.0 DOCUMENTS TO BE SUBMITTED ALONG WITH BID

- 3.1 The electrical specification without any deviation from the technical/quality assurance requirements stipulated shall be deemed to be complied by the bidder in case bidder furnishes the overall compliance of package technical specification in the form of

	TITLE : ELECTRICAL EQUIPMENT SPECIFICATION FOR FUEL OIL HANDLING SYSTEM 3X800 MW PVUNL PATRATU TPP PHASE-1	SPECIFICATION NO.
		VOLUME NO. : II-B
		SECTION :
		REV NO. 00 : DATE : 15.06.2018
		SHEET : 3 OF 3

compliance certificate/No deviation certificate.

- 3.2 No technical submittal such as copies of data sheets, drawings, write-up, quality plans, type test certificates, technical literature, etc, is required during tender stage. Any such submission even if made, shall not be considered as part of offer.

4.0 List of enclosures :

- a) Electrical scope between BHEL & vendor
- b) Customer (NTPC) specification for Motors
- c) Customer (NTPC) cabling spec (to be referred by vendor for their scope of work (as per Electrical scope between BHEL & vendor)).
- d) Quality plan for motors & NTPC quality assurance
- e) Datasheet A & C (Annexure- I)
- f) List of Mandatory Spares (refer mechanical specification)
- g) Sub vendor List for Motors & other Electrical items (Annexure-III)
- h) Electrical Load data format (Annexure –IV)
- i) BHEL cable listing format (Annexure –V)

STANDARD ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR

PACKAGE : FUEL OIL SYSTEM

SCOPE OF VENDOR: SUPPLY, ERECTION & COMMISSIONING OF VENDOR'S EQUIPMENT

PROJECT: 3X800 MW PATRATU STPS EXPANSION PH-I

S.NO	DETAILS	SCOPE SUPPLY	SCOPE E&C	REMARKS
1	415V MCC	BHEL	BHEL	240 V AC (supply feeder)/415 V AC (3 PHASE 4 WIRE) supply shall be provided by BHEL based on load data provided by vendor at contract stage for all equipment supplied by vendor as part of contract. Any other voltage level (AC/DC) required will be derived by the vendor.
2	Local Push Button Station (for motors)	BHEL	BHEL	Located near the motor.
3	Power cables, control cables and screened control cables for a) both end equipment in BHEL's scope b) both end equipment in vendor's scope c) one end equipment in vendor's scope	BHEL BHEL BHEL	BHEL Vendor BHEL	1. For 3.b) & c): Sizes of cables required shall be informed by vendor at contract stage (based on inputs provided by BHEL) in the form of cable listing. Finalisation of cable sizes shall be done by BHEL. Vendor shall provide lugs & glands accordingly. 2. Termination at BHEL equipment terminals by BHEL. 3. Termination at Vendor equipment terminals by Vendor.
4	Junction box for control & instrumentation cable	Vendor	Vendor	Number of Junction Boxes shall be sufficient and positioned in the field to minimize local cabling (max 10-12 mtrs) and trunk cable.
5	Any special type of cable like compensating, co-axial, prefab, MICC, optical fibre etc.	Vendor	Vendor	Refer C&I portion of specification for scope of fibre Optical cables if used between PLC/ microprocessor & DCS.
6	Cable trays, accessories & cable trays supporting system 100/ 50 mm cable trays/ Conduits/ Galvanised steel cable troughs for local cabling	BHEL Vendor	BHEL Vendor	Local cabling from nearby main route cable tray (BHEL scope) to equipment terminal (vendor's scope) shall be through 100/ 50 mm. cable trays/ conduits/ Galvanised steel cable troughs, as per approved layout drawing during contract stage.
7	Cable glands ,lugs and bimetallic strip for equipment supplied by Vendor	Vendor	Vendor	1. Double compression Ni-Cr plated brass cable glands 2. Solder less crimping type heavy duty tinned copper lugs for power and control cables.
8	Conduit and conduit accessories for cabling between equipment supplied by vendor	Vendor	Vendor	Conduits shall be medium duty, hot dip galvanised cold rolled mild steel rigid conduit as per IS: 9537.
9	Lighting	BHEL	BHEL	
10	Equipment grounding (including electronic earthing) & lightning protection	BHEL	BHEL	Refer note no. 4 for electronic earthing

STANDARD ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR

PACKAGE : FUEL OIL SYSTEM

SCOPE OF VENDOR: SUPPLY, ERECTION & COMMISSIONING OF VENDOR'S EQUIPMENT

PROJECT: 3X800 MW PATRATU STPS EXPANSION PH-I

S.NO	DETAILS	SCOPE SUPPLY	SCOPE E&C	REMARKS
11	Below grade grounding	BHEL	BHEL	
12	LT Motors with base plate and foundation hardware	Vendor	Vendor	Makes shall be subject to customer/ BHEL approval at contract stage.
13	Mandatory spares	Vendor	-	Vendor to quote as per specification.
14	Recommended O & M spares	Vendor	-	As specified elsewhere in specification
15	Any other equipment/ material/ service required for completeness of system based on system offered by the vendor (to ensure trouble free and efficient operation of the system).	Vendor	Vendor	
16	a) Input cable schedules (Control & Screened Control Cables) b) Cable interconnection details for above c) Cable block diagram	Vendor Vendor Vendor	- - -	Cable listing for Control and Instrumentation Cable and electronic earthing cable in enclosed excel format shall be submitted by vendor during detailed engineering stage.
17	Electrical Equipment & cable tray layout drawings	Vendor	-	a. In case, vendor's Fuel oil pump house building is located as combined with Heating & Pumping building (BHEL-TRICHY), cable tray/trench layout inside combined building shall be prepared by BHEL-PEM. Vendor to furnish drawing (both in print form as well as in AUTOCAD) of Fuel oil pump house layout clearly indicating all pumps, panels, JB's etc. which require cabling along with their terminal box/location/ Foundation etc. b. In case, vendor's Fuel oil pump house building is separate from Heating & Pumping building (BHEL-TRICHY), vendor shall prepare & submit cable tray/trench & equipment layout (both in print form as well as in AUTOCAD) of the complete Fuel oil pump house building indicating location and identification of all equipment requiring cabling for BHEL review & approval. Vendor to ensure the cable tray lay out shall confirm to NFPA (National fire prevention act)/TAC (Tariff advisory committee) applicable for hazardous area classification.

STANDARD ELECTRICAL SCOPE BETWEEN BHEL AND VENDOR**PACKAGE : FUEL OIL SYSTEM****SCOPE OF VENDOR: SUPPLY, ERECTION & COMMISSIONING OF VENDOR'S EQUIPMENT****PROJECT: 3X800 MW PATRATU STPS EXPANSION PH-I**

S.NO	DETAILS	SCOPE SUPPLY	SCOPE E&C	REMARKS
18	Electrical Equipment GA drawing	Vendor	-	For necessary interface review.

NOTES:

1. Make of all electrical equipment/ items supplied shall be reputed make & shall be subject to approval of BHEL/customer after award of contract.
2. All QPs shall be subject to approval of BHEL/customer after award of contract without any commercial implication.
3. In case the requirement of Junction Box arises on account of Power Cable size mis-match due to vendor engineering at later stage, vendor shall supply the Junction Box for suitable termination.
4. Vendor shall indicate location of Electronic Earth pit in their Civil assignment drawing.

SUB-SECTION – B-07

MOTORS

**EPC PACKAGE FOR
PATRATU SUPER THERMAL POWER STATION EXPANSION
PHASE –I (3X 800MW)**

**TECHNICAL SPECIFICATION
SECTION – VI, PART-B
BID DOC NO. : CS-9585-001-2**

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	MOTORS			
1.00.00	GENERAL REQUIREMENTS			
1.01.00	For the purpose of design of equipment/systems, an ambient temperature of 50 deg. Centigrade and relative humidity of 95% (at 40 deg C) shall be considered. The equipment shall operate in a highly polluted environment.			
1.02.00	All equipment shall be suitable for rated frequency of 50 Hz with a variation of +3% & -5%, and 10% combined variation of voltage and frequency unless specifically brought out in the specification.			
1.03.00	Contractor shall provide fully compatible electrical system, equipment, accessories and services.			
1.04.00	All the equipment, material and systems shall, in general, conform to the latest edition of relevant National and international Codes & Standards, especially the Indian Statutory Regulations.			
1.05.00	Paint shade shall be as per RAL 5012 (Blue) for indoor and outdoor equipment.			
1.06.00	The responsibility of coordination with electrical agencies and obtaining all necessary clearances for contractors equipment and systems shall be under the contractor scope.			
1.07.00	Degree of Protection			
	Degree of protection for various enclosures as per IEC60034-05 shall be as follows:-			
	i) Indoor motors	-	IP 54	
	ii) Outdoor motors	-	IP 55	
	iii) Cable box-indoor area	-	IP 54	
	iv) Cable box-Outdoor area	-	IP 55	
2.00.00	CODES AND STANDARDS			
	1) Three phase induction motors	:	IS/IEC:60034	
	2) Single phase AC motors	:	IS/IEC:60034	
	3) Crane duty motors	:	IS:3177, IS/IEC:60034	
	4) DC motors/generators	:	IS/IEC:60034	
	5) Energy Efficient motors	:	IS 12615, IEC: 60034-30	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2		SUB-SECTION-B-07 MOTORS
				PAGE 1 OF 10

CLAUSE NO.	TECHNICAL REQUIREMENTS			
6.00.00 6.01.00 6.01.01 6.01.02 6.01.03 6.01.04 6.02.00 6.02.01 6.02.02 6.03.00	41 deg.C over inlet cooling water maximum temperature of 39 deg.C for thermal class 90 (Y) wet wound Boiler circulation pump motor. OPERATIONAL REQUIREMENTS Starting Time For motors with starting time upto 20 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be at least 2.5 secs. more than starting time. For motors with starting time more than 20 secs. and upto 45 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be at least 5 secs. more than starting time. For motors with starting time more than 45 secs. at minimum permissible voltage during starting, the locked rotor withstand time under hot condition at highest voltage limit shall be more than starting time by at least 10% of the starting time. Speed switches mounted on the motor shaft shall be provided in cases where above requirements are not met. Torque Requirements Accelerating torque at any speed with the lowest permissible starting voltage shall be at least 10% motor full load torque. Pull out torque at rated voltage shall not be less than 205% of full load torque. It shall be 275% for crane duty motors. Starting voltage requirement (a) Up to 85% of rated voltage for ratings below 110 KW (b) Up to 80% of rated voltage for ratings from 110 KW to 200 KW (c) Up to 85% of rated voltage for ratings from 201 KW to 1000 KW (d) Up to 80% of rated voltage for ratings from 1001 KW to 4000 KW (e) Up to 75 % of rated voltage for ratings above 4000KW Except AOP & JOP motors running on D.G emergency supply, starting voltage shall be 80%.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2	SUB-SECTION-B-07 MOTORS	PAGE 3 OF 10

CLAUSE NO.	TECHNICAL REQUIREMENTS				
7.00.00	DESIGN AND CONSTRUCTIONAL FEATURES				
7.01.00	Suitable single phase space heaters shall be provided on motors rated 30KW and above to maintain windings in dry condition when motor is standstill. Separate terminal box for space heaters & RTDs shall be provided. However for flame proof motors, space heater terminals inside the main terminal box may be acceptable.				
7.02.00	All motors shall be either Totally enclosed fan cooled (TEFC) or totally enclosed tube ventilated (TETV) or Closed air circuit air cooled (CACA) type. However, motors rated 3000KW or above can be Closed air circuit water cooled (CACW). The method of movement of primary and secondary coolant shall be self-circulated by fan or pump directly mounted on the rotor of the main motor as per IEC 60034-6. However VFD driven motors can be offered with forced cooling type with machine mounted fan or pump driven by separate electric motor. Motors and EPB located in hazardous areas shall have flame proof enclosures conforming to IS: 2148 as detailed below				
7.03.00	(a)	Fuel oil area	:	Group – IIB	
	(b)	Hydrogen generation	:	Group - IIC or (Group-I, Div-II as per plant area NEC) or (Class-1, Group-B, Div-II as per NEMA / IEC60034)	
	Winding and Insulation				
	(a)	Type	:	Non-hygroscopic, oil resistant, flame resistant	
	(b)	Starting duty	:	Two hot starts in succession, with motor initially at normal running temperature.	
7.04.00	(c)	11kV & 3.3 kV AC motors	:	Thermal class 155 (F) insulation. The winding insulation process shall be total Vacuum Pressure Impregnated i.e. resin poor method. The lightning Impulse & intertern insulation surge withstand level shall be as per IEC-60034 part-15. However winding insulation for wet wound Boiler circulation pump motor shall be thermal class 90 (Y) or better.	
	(d)	240VAC, 415V AC & 220V DC motors	:	Thermal Class (B) or better	
	Motors rated above 1000KW shall have insulated bearings to prevent flow of shaft currents.				
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2		SUB-SECTION-B-07 MOTORS	PAGE 4 OF 10

CLAUSE NO.	TECHNICAL REQUIREMENTS				
7.05.00	Motors with heat exchangers shall have dial type thermometer with adjustable alarm contacts to indicate inlet and outlet primary air temperature.				
7.06.00	Noise level for all the motors shall be limited to 85dB (A) except for BFP motor for which the maximum limit shall be 90 dB(A). Vibration shall be limited within the limits prescribed in IS/IEC 60034-14. Motors shall withstand vibrations produced by driven equipment. HT motor bearing housings shall have flat surfaces, in both X and Y directions, suitable for mounting 80mmX80mm vibration pads.				
7.07.00	In HT motors, at least four numbers simplex / two numbers duplex platinum resistance type temperature detectors shall be provided in each phase stator winding. Each bearing of HT motor shall be provided with dial type thermometer with adjustable alarm contact and preferably 2 numbers duplex platinum resistance type temperature detectors.				
7.08.00	Motor body shall have two earthing points on opposite sides.				
7.09.00	11 KV motors shall be offered with Separable Insulated Connector (SIC) as per IEEE 386. The offered SIC terminations shall be provided with protective cover and trifurcating sleeves. SIC termination kit shall be suitable for fault level of 25 KA for 0.17 seconds.				
7.10.00	3.3 KV motors shall be offered with dust tight phase separated double walled (metallic as well as insulated barrier) Terminal box. Suitable termination kit shall be provided for the offered Terminal box. The offered Terminal Box shall be suitable for fault level of 250 MVA for 0.12 sec. Removable gland plates of thickness 3 mm (hot/cold rolled sheet steel) or 4 mm (non-magnetic material for single core cables) shall be provided.				
7.11.00	The spacing between gland plate & center of terminal stud shall be as per Table-I.				
7.12.00	All motors shall be so designed that maximum inrush currents and locked rotor and pullout torque developed by them at extreme voltage and frequency variations do not endanger the motor and driven equipment.				
7.13.00	The motors shall be suitable for bus transfer schemes provided on the 11kV, 3.3 kV /415V systems without any injurious effect on its life.				
7.14.00	For motors rated 2000 KW & above, neutral current transformers of PS class shall be provided on each phase in a separate neutral terminal box.				
7.15.00	The size and number of cables (for HT and LT motors) to be intimated to the successful bidder during detailed engineering and the contractor shall provide terminal box suitable for the same.				
<table><tr><td>EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)</td><td>TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2</td><td>SUB-SECTION-B-07 MOTORS</td><td>PAGE 5 OF 10</td></tr></table>		EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2	SUB-SECTION-B-07 MOTORS	PAGE 5 OF 10
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2	SUB-SECTION-B-07 MOTORS	PAGE 5 OF 10		

CLAUSE NO.	TECHNICAL REQUIREMENTS			
8.00.00	The ratio of locked rotor KVA at rated voltage to rated KW shall not exceed the following (without any further tolerance) except for BFP motor. (a) 50 kW to 110 kW : 11.0 (b) From 110 KW & upto 200 KW : 9.0 (c) Above 200 KW & upto 1000KW : 10.0 (d) From 1001KW & upto 4000KW : 9.0 (e) Above 4000KW : 6 to 6.5			
9.00.00	CW motor shall be designed with minimum power factor of 0.8 at design duty point.			
10.00.00	TYPE TEST			
10.01.00	HT MOTORS			
10.01.01	The contractor shall carry out the type tests as listed in this specification on the equipment to be supplied under this contract. The bidder shall indicate the charges for each of these type tests separately in the relevant schedule of Section - VII- (BPS) and the same shall be considered for the evaluation of the bids. The type tests charges shall be paid only for the test(s) actually conducted successfully under this contract and upon certification by the employer's engineer.			
10.01.02	The type tests shall be carried out in presence of the employer's representative, for which minimum 15 days notice shall be given by the contractor. The contractor shall obtain the employer's approval for the type test procedure before conducting the type test. The type test procedure shall clearly specify the test set–up, instruments to be used, procedure, acceptance norms, recording of different parameters, interval of recording, precautions to be taken etc. for the type test(s) to be carried out.			
10.01.03	In case the contractor has conducted such specified type test(s) within last ten years as on the date of bid opening, he may submit during detailed engineering the type test reports to the employer for waiver of conductance of such test(s). These reports should be for the tests conducted on the equipment similar to those proposed to be supplied under this contract and test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. The employer reserves the right to waive conducting of any or all the specified type test(s) under this contract. In case type tests are waived, the type test charges shall not be payable to the contractor.			
10.01.04	Further the Contractor shall only submit the reports of the type tests as listed in "LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED "and carried out within last ten years from the date of bid opening. These reports should be for			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2	SUB-SECTION-B-07 MOTORS	PAGE 6 OF 10

CLAUSE NO.	TECHNICAL REQUIREMENTS			
10.01.05	the test conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client. However if the contractor is not able to submit report of the type test(s) conducted within last ten years from the date of bid opening, or in the case of type test report(s) are not found to be meeting the specification requirements, the contractor shall conduct all such tests under this contract at no additional cost to the employer either at third party lab or in presence of client/ employer's representative and submit the reports for approval. LIST OF TYPE TESTS TO BE CONDUCTED The following type tests shall be conducted on each type and rating of HT motor (a) No load saturation and loss curves upto approximately 115% of rated voltage (b) Measurement of noise at no load. (c) Momentary excess torque test (subject to test bed constraint). (d) Full load test (subject to test bed constraint) (e) Temperature rise test at rated conditions. During heat run test, bearing temp., winding temp., coolant flow and its temp. shall also be measured. In case the temperature rise test is carried at load other than rated load, specific approval for the test method and procedure is required to be obtained. Wherever ETD's are provided, the temperature shall be measured by ETD's also for the record purpose.			
10.01.06	LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED The following type test reports shall be submitted for each type and rating of HT motor (a) Degree of protection test for the enclosure followed by IR, HV and no load run test. (b) Terminal box-fault level withstand test for each type of terminal box of HT motors only. (c) Lightning Impulse withstand test on the sample coil shall be as per clause no. 4.3 IEC-60034, part-15 (d) Surge-withstand test on interturn insulation shall be as per clause no. 4.2 of IEC 60034, part-15			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2	SUB-SECTION-B-07 MOTORS	PAGE 7 OF 10

CLAUSE NO.	TECHNICAL REQUIREMENTS			
10.02.00	LT Motors			
10.02.01	LT Motors supplied shall be of type tested design. During detailed engineering, the contractor shall submit for employer's approval the reports of all the type tests as listed in this specification and carried out within last <i>ten</i> years from the date of bid opening. These reports should be for the test conducted on the equipment similar to those proposed to be supplied under this contract and the test(s) should have been either conducted at an independent laboratory or should have been witnessed by a client.			
10.02.02	However if the contractor is not able to submit report of the type test(s) conducted within last ten years from the date of bid opening, or in the case of type test report(s) are not found to be meeting the specification requirements, the contractor shall conduct all such tests under this contract at no additional cost to the employer either at third party lab or in presence of client/ employer's representative and submit the reports for approval.			
10.02.03	LIST OF TESTS FOR WHICH REPORTS HAVE TO BE SUBMITTED The following type test reports shall be submitted for each type and rating of LT motor of above 50 KW only 1. Measurement of resistance of windings of stator and wound rotor. 2. No load test at rated voltage to determine input current power and speed 3. Open circuit voltage ratio of wound rotor motors (in case of Slip ring motors) 4. Full load test to determine efficiency power factor and slip. 5. Temperature rise test. 6. Momentary excess torque test. 7. High voltage test. 8. Test for vibration severity of motor. 9. Test for noise levels of motor(Shall be limited as per clause no 7.06.00 of this section) 10. Test for degree of protection and 11. Over speed test.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2	SUB-SECTION-B-07 MOTORS	PAGE 8 OF 10

CLAUSE NO.	TECHNICAL REQUIREMENTS				
10.03.00 10.04.00	12. Type test reports for motors located in fuel oil area having flame proof enclosures as per IS 2148 / IEC 60079-1				
	All acceptance and routine tests as per the specification and relevant standards shall be carried out. Charges for these shall be deemed to be included in the equipment price.				
	The type test reports once approved for any projects shall be treated as reference. For subsequent projects of NTPC, an endorsement sheet will be furnished by the manufacturer confirming similarity and “No design Change”. Minor changes if any shall be highlighted on the endorsement sheet.				
	TABLE - I				
	DIMENSIONS OF TERMINAL BOXES FOR LV MOTORS				
	Motor MCR in KW		Minimum distance between centre of stud and gland plate in mm		
	UP to 3 KW		As per manufacturer's practice.		
	Above 3 KW - upto 7 KW		85		
	Above 7 KW - upto 13 KW		115		
	Above 13 KW - upto 24 KW		167		
Above 24 KW - upto 37 KW		196			
Above 37 KW - upto 55 KW		249			
Above 55 KW - upto 90 KW		277			
Above 90 KW - upto 125 KW		331			
Above 125 KW-upto 200 KW		203			
For HT motors the distance between gland plate and the terminal studs shall not be less than 500 mm.					
PHASE TO PHASE/ PHASE TO EARTH AIR CLEARANCE:					
NOTE: Minimum inter-phase and phase-earth air clearances for LT motors with lugs installed shall be as follows:					
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2		SUB-SECTION-B-07 MOTORS	PAGE 9 OF 10

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	Motor MCR in KW UP to 110 KW Above 110 KW and upto 150 KW Above 150 KW	Clearance 10mm 12.5mm 19mm		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATION SECTION – VI, PART-B BID DOC NO. : CS-9585-001-2		SUB-SECTION-B-07 MOTORS PAGE 10 OF 10

SUB-SECTION – B-09

CABLING

**EPC PACKAGE FOR
PATRATU SUPER THERMAL POWER STATION EXPANSION
PHASE –I (3X 800MW)**

**TECHNICAL SPECIFICATION
SECTION – VI, PART-B
BID DOC NO. : CS-9585-001-2**

CLAUSE NO.	TECHNICAL REQUIREMENTS 		
1.00.00 1.01.00	CODES AND STANDARDS All standards, specifications and codes of practice referred to herein shall be the latest editions including all applicable official amendments and revisions as on date of opening of bid. In case of conflict between this specification and those (IS codes, standards, etc.) referred to herein, the former shall prevail. All work shall be carried out as per the following standards/ codes as applicable . IS:513 Cold rolled low carbon steel sheets and strips. IS:802 Code of practice for the use of Structural Steel in Overhead Transmission Line Towers. IS:1079 Hot Rolled carbon steel sheet & strips IS:1239 Mild steel tubes, tubulars and other wrought steel fittings IS:1255 Code of practice for installation and maintenance of power cables upto and including 33 KV rating IS:1367 Part-13 Technical supply conditions for threaded Steel fasteners. (Hot dip galvanized coatings on threaded fasteners). IS:2147 Degree of protection provided by enclosures for low voltage switchgear and control gear IS:2309 Code of Practice for the protection of building and allied structures against lightning. IS:2629 Recommended practice for hot dip galvanising of iron & steel IS:2633 Method for testing uniformity of coating on zinc coated articles. IS:3043 Code of practice for Earthing IS:3063 Fasteners single coil rectangular section spring washers. IS:6745 Methods for determination of mass of zinc coating on zinc coated iron & steel articles. IS:8308 Compression type tubular in- line connectors for aluminium conductors of insulated cables IS:8309 Compression type tubular terminal ends for aluminium conductors of insulated cables. IS:9537 Conduits for electrical installation. IS:9595 Metal - arc welding of carbon and carbon manganese steels - recommendations. IS:13573 Joints and terminations for polymeric cables. BS:476 Fire tests on building materials and structures IEEE:80 IEEE guide for safety in AC substation grounding IEEE:142 Grounding of Industrial & commercial power systems		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION	Page 1 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS 		
	DIN 46267 (Part-II) Non tension proof compression joints for Aluminium conductors. DIN 46329 Cable lugs for compression connections, ring type ,for Aluminium conductors BS:6121 Specification for mechanical Cable glands for elastomers and plastic insulated cables. Indian Electricity Act. Indian Electricity Rules. 1.02.00 Equipment complying with other internationally accepted standards such as IEC, BS, DIN, USA, VDE, NEMA etc. will also be considered if they ensure performance and constructional features equivalent or superior to standards listed above. In such a case, the Bidder shall clearly indicate the standard(s) adopted, furnish a copy in English of the latest revision of the standards alongwith copies of all official amendments and revisions in force as on date of opening of bid and shall clearly bring out the salient features for comparison. 2.00.00 DESIGN AND CONSTRUCTIONAL FEATURE 2.01.00 Inter Plant Cabling 2.01.01 Interplant cabling for main routes shall be laid along overhead trestles/duct banks. Cables from main plant to switchyard control room shall be laid in overhead trestles or duct bank. In case of Duct banks, pull-pits shall be filled with sand and provided with a PCC covering. Directly buried cables, if essential ,shall not have concentration of more than 4 cables in one route. All buried cables, Cables for switchyard and CHP shall be armoured 2.01.02 Transformer yard In transformer yard cables shall be laid in overhead trestle. The main cable routes coming out from Main plant building and crossing the Transformer yard shall be laid in overhead trestles. In transformer yard, trestle height for rail/road crossing shall be suitable for movement of Generator Transformer with bushing. 2.01.03 Trenches PCC flooring of built up trenches shall be sloped for effective drainage with sump pits and sump pumps. 2.01.04 No sub zero level cable vault/trenches shall be provided below control building/switchgear rooms in main plant. 2.01.05 Cable Vault Clear access passage of at least 750mm wide & 2.1 mt clear heights shall be provided at entrances and along the cable trays in cable vault. Wherever the passage is through cable routes & across the cable tray the clear height shall not be less than 1.5 mts. Cable vaults shall be provided with adequate drainage facilities for drainage of fire water. Each cable vault should have at least two doors. Exit signs shall be provided near doors for personnel escape in case of emergency		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
2.01.06	Boiler Area Two separate cable routes one on each side shall be provided for each boiler unit. Cables for on set of auxiliaries such as ID, FD, PA fan & half of the coal mills shall be routed in one route & for other set of auxiliaries through other route. Cable trays in boiler & ESP area shall be supported from the boiler and ESP structures. The same shall be coordinated with SG/ESP contractor. Cable trays in these areas shall be in vertical formation to avoid dust accumulation. No cable trenches shall be provided in boiler/ESP area.		
2.01.07	Turbine Hall Area a)Two separate cable routes shall be provided for cable routing of working and standby drives or different set/group (say 50% capacity) of auxiliaries.		
2.01.08	OffSite Area In offsite pumphouses, overhead cable tray arrangement shall be followed. However cable trenches may be considered below switchgear/mcc. Trestle In fuel oil pump house, overhead cable tray arrangement shall be provided. RCC trenches provided in MCC room shall be separated from fuel oil area to avoid oil accumulation.		
2.01.09	The cable slits to be used for motor/equipment power/control supply shall be sand filled & covered with PCC after cabling.		
2.01.10	Sizing criteria, derating factors for the cables shall be met as per respective chapters. However for the power cables, the minimum conductor size shall be 6 sq.mm. for aluminium conductor and 2.5 sq.mm. for copper conductor cable.		
2.01.11	Conscious exceptions to the above guidelines may be accepted under special conditions but suitable measures should be taken at such location to: - Meet all safety requirements - Safeguard against fire hazards, mechanical damage, flooding of water, oil accumulation, electrical faults/interferences, etc		
3.00.00	EQUIPMENT DESCRIPTION		
3.01.00	Cable trays, Fittings & Accessories		
3.01.01	Cable trays shall be ladder/perforated type as specified complete with matching fittings (like brackets, elbows, bends, reducers, tees, crosses, etc.) accessories (like side coupler plates, etc. and hardware (like bolts, nuts, washers, G.I. strap, hook etc.) as required. Cable tray shall be ladder type for power & control cables and perforated for instrumentation cables.		
3.01.02	Cable trays, fittings and accessories shall be fabricated out of rolled mild steel sheets free from flaws such as laminations, rolling marks, pitting etc. These (including hardware) shall be hot dip galvanized as per Clause No. 3.13.00 of this chapter.		
3.01.03	Cable trays shall have standard width of 150 mm, 300 mm & 600 mm and standard lengths of 2.5 metre. Thickness of mild steel sheets used for fabrication of cable trays and fittings shall be 2 mm. The thickness of side coupler plates shall be 3 mm.		
3.01.04	Cable troughs shall be required for branching out few cables from main cable route. These shall be U-shaped, fabricated of mild steel sheets of thickness 2 mm and shall be hot dip		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION
			Page 3 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS 		
3.02.00 3.02.01 3.02.02 3.02.03	galvanised as per Clause No. 3.13.00 of this chapter. Troughs shall be standard width of 50 mm & 75 mm with depth of 25 mm Support System for Cable Trays Cable tray support system shall be pre-fabricated out of single sheet as per enclosed tender drawings. Support system for cable trays shall essentially comprise of the two components i.e. main support channel and cantilever arms. The main support channel shall be of two types : (i) C1:- having provision of supporting cable trays on one side and (ii) C2:-having provision of supporting cable trays on both sides. The support system shall be the type described hereunder a. Cable supporting steel work for cable racks/cables shall comprise of various channel sections, cantilever arms, various brackets, clamps, floor plates, all hardwares such as lock washers, hexagon nuts, hexagon head bolt, support hooks, stud nuts, hexagon head screw, channel nut, channel nut with springs, fixing studs, etc. b. The system shall be designed such that it allows easy assembly at site by using bolting. All cable supporting steel work, hardwares fittings and accessories shall be prefabricated factory galvanised. c. The main support and cantilever arms shall be fixed at site using necessary brackets, clamps, fittings, bolts, nuts and other hardware etc. to form various arrangements required to support the cable trays. Welding of the components shall not be allowed. However, welding of the bracket (to which the main support channel is bolted) to the overhead beams, structural steel, insert plates or reinforcement bars will be permitted. Any cutting or welding of the galvanised surface shall be brushed and red lead primer, oil primer & aluminium paint shall be applied d. All steel components, accessories, fittings and hardware shall be hot dip galvanised after completing welding, cutting, drilling and other machining operation. e. The typical arrangement of flexible support system is shown in the enclosed drawings and described briefly below: The main support channel and cantilever arms shall be fabricated out of 2.5 thick rolled steel sheet conforming to IS 1079. f. Cantilever arms of 320 mm, 620mm and 750 mm in length are required, and shall be as shown in the enclosed drawing. The arm portion shall be suitable for assembling the complete arm assembly on to component constructed of standard channel section. The back plate shall allow sufficient clearance for fixing bolt to be tightened with tray in position. g. Support system shall be able to withstand • weight of the cable trays • weight of the cables (75 Kg/Metre run of each cable tray) • Concentrated load of 75 Kg between every support span. • Factor of safety of minimum 1.5 shall be considered. The size of structural steel members or thickness of sheet steel of main support channel and cantilever arms and other accessories as indicated above or in the enclosed drawings are indicative only. Nevertheless, the support system shall be designed by the bidder to fully meet the requirements of type tests as specified. In case the system fails in the tests, the components design modification shall be done by the Bidder without any additional cost to		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)	TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION	Page 4 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	the Employer. The bidder shall submit the detailed drawings of the system offered by him alongwith the bid.			
3.03.04	FOR COAL HANDLING PLANT THE FOLLOWING SHALL ALSO BE APPLICABLE:			
	a) All overhead cable routes shall be along the route of the conveyor gallery on separate supporting structures and cables shall be laid in vertical trays. The bottom of the steel shall be such that the existing facilities, movement of trucks/human beings etc. does not get affected. The cable trestle shall have a minimum 600mm clear walk way and shall have maintenance platforms as required. The bottom of the steel supporting structure shall be generally at 3.0M above the grade level except for rail/road crossings where it shall be at 8.0M above grade level. Tap offs from the overhead cable trestle can be through shallow trenches with prior approval of the Employer. Directly buried cable, if essential, shall not have concentration of more than 4 cables on one route. b) Cable trenches shall be provided only in Switchgear/MCC rooms. c) Cables shall not be routed through the conveyor galleries except for the equipment located in the conveyor galleries for a particular conveyor i.e. protection switches, receptacles etc. d) Cables for PCS and BSS shall be routed along the conveyors through GI conduits.			
3.04.00	Pipes, Fittings & Accessories			
3.03.01	Pipes offered shall be complete with fittings and accessories (like tees, elbows, bends, check nuts, bushings, reducers, enlargers, coupling caps, nipples etc.) The size of the pipe shall be selected on the basis of maximum 40% fill criteria			
3.03.02	GI Pipes shall be of medium duty as per IS: 1239			
3.03.03	Duct banks shall be High Density PE pipes encased in PCC (10% spare of each size, subject to minimum one) with suitable water-proof manholes.			
3.03.04	Hume pipes shall be NP3 type as per IS 458.			
3.04.00	Junction Boxes			
3.04.01	Junction box shall be made of Fire retardant material. Material of JB shall be Thermoplastic or thermosetting or FRP type. The box shall be provided with the terminal blocks, mounting bracket and screws etc. The cable entry shall be through galvanized steel conduits of suitable diameter. The JB shall have suitable for installing glands of suitable size on the bottom of the box. The JB shall be suitable for surface mounting on ceiling/structures. The JB shall be of grey color RAL 7035. All the metal parts shall be corrosion protected. Junction box surface should be such that it is free from crazings, blisterings, wrinkling, colour blots/striations. There should not be any mending or repair of surface. JB's will be provided with captive screws so that screws don't fall off when cover is opened. JB's mounting brackets should be of powder coated MS. Type test reports for the following tests shall be furnished:- (a) Impact resistance for impact energy of 2 Joules (IK07)as per BS EN50102 (b) Thermal ageing at 70deg C for 96 hours as per IEC60068-2-2Bb. (c) Class of protection shall be IP 55.			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION	Page 5 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS	
	(d) HV test.	
3.04.02	Terminal blocks shall be 1100V grade, of suitable current rating, made up of unbreakable polyamide 6.6 grade. The terminals shall be screw type or screw-less (spring loaded) / cage clamp type with lugs. Marking on terminal strips shall correspond to the terminal numbering in wiring diagrams. All metal parts shall be of non-ferrous material. In case of screw type terminals the screw shall be captive, preferably with screw locking design. All terminal blocks shall be suitable for terminating on each side the required cables/wire size. All internal wiring shall be of cu. Conductor PVC wire.	
3.05.00	Terminations & Straight Through Joints	
3.05.01	Termination and jointing kits for 33kV, 11 kV, 6.6 KV and 3.3 kV grade XLPE insulated cables shall be of proven design and make which have already been extensively used and type tested. Termination kits and jointing kits shall be Pre-moulded type or heat shrinkable type. Further Cold shrinkable type termination and jointing kits are also acceptable. The Cold shrinkable type kits shall be type tested as per relevant standards. Calculation to withstand the required fault level shall also be furnished in case of cold shrinkable type kits. 33 kV, 11 kV, 6.6 KV and 3.3kV grade joints and terminations shall be type tested and Type test reports as per IS:13573 Part-II and IEC60502 shall be furnished. Also, heat shrink material shall comply with requirements of ESI 09-13 (external tests). Critical components used in cable accessories shall be of tested and proven quality as per relevant product specification/ESI specification. Cable joints and terminations should be with FRLS properties as per IEC 60754-1&2. Kit contents shall be supplied from the same source as were used for type testing. The kit shall be complete with the tinned copper solderless crimping type cable lugs & ferrule or mechanical connectors (wherein bolts are tightened that shear off at an appropriate torque) as per DIN standard suitable for aluminium compacted conductor cables. (Tender drg. no 0000-211-POE –A-51-RA of cable lug attached at the end of this chapter)..	
3.05.02	Straight through joint and termination shall be capable of withstanding the fault level of 21 KA for 0.12 Sec. with dynamic peak of 52 KA for 33 KV system & of 40 kA for 0.12 sec with a dynamic peak of 100 kA for 11 kV, 6.6 KV & 3.3 KV system. Straight through joints shall have provisions for shield connection and earthing wherever required and complete with all accessories and consumables suitable for storage without deterioration at a temperature of 50 deg. C with shelf life of more than five years. 1.1 kV grade straight through joints shall also be of proven design	
3.05.03	1.1 KV grade Straight Through Joint shall be of proven design.	
3.06.00	Cable glands	
3.06.01	Cable shall be terminated using double compression type cable glands. Testing requirements of Cable glands shall conform to BS:6121 and gland shall be of robust construction capable of clamping cable and cable armour (for armoured cables) firmly without injury to insulation. Cable glands shall be made of heavy duty brass machine finished and nickel chrome plated. Thickness of plating shall not be less than 10 micron. All washers and hardware shall also be made of brass with nickel chrome plating Rubber components shall be of neoprene or better synthetic material and of tested quality. Cable glands shall be suitable for the sizes of cable supplied/erected.	
3.07.00	Cable lugs/ferrules	
3.07.01	Cable lugs/ferrules for power cables shall be tinned copper solderless crimping type suitable for aluminium compacted conductor cables. Cable lugs and ferrules for control cables shall be tinned copper type. The cable lugs for control cables shall be provided with insulating	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2
		SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION
		Page 6 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS			
	sleeve and shall suit the type of terminals provided on the equipments. Cable lugs and ferrule shall conform to DIN standards.			
3.08.00	Trefoil clamps			
3.08.01	Trefoil clamps for single core cables shall be pressure die cast aluminum or fibre glass or nylon and shall include necessary fixing accessories like G.I. nuts, bolts, washers, etc. Trefoil clamps shall have adequate mechanical strength to withstand the forces generated by the peak value of maximum system short circuit current.			
3.09.00	Cable Clamps & Ties			
3.09.01	The cable clamps/ties required to clamp multicore cables shall be of SS-316 material, 12mm wide, polyester coated ladder lock type. The clamps/ties shall have self locking arrangement & shall have sufficient strength. The cable clamps/ties shall be supplied in finished individual pieces of suitable length to meet the site requirements.			
3.10.00	Receptacles			
3.10.01	Receptacles boxes shall be fabricated out of MS sheet of 2mm thickness and hot dipped galvanized or of die-cast aluminium alloy of thickness not less than 2.5 mm. The boxes shall be provided with two nos. earthing terminals, gasket to achieve IP55 degree of protection, terminal blocks for loop-in loop-out for cable of specified sizes, mounting brackets suitable for surface mounting on wall/column/structure, gland plate etc. The ON-OFF switch shall be rotary type heavy duty, double break, AC23 category, suitable for AC supply. Plug and Socket shall be shrouded Die-cast aluminium. Socket shall be provided with lid safety cover. Robust mechanical interlock shall be provided such that the switch can be put ON only when the plug is fully engaged and plug can be withdrawn only when the switch is in OFF position. Also cover can be opened only when the switch is in OFF position. Wiring shall be carried out with 1100 V grade PVC insulated stranded aluminium/copper wire of adequate size. The Terminal blocks shall be of 1100 V grade. The Terminal blocks shall be of 1100 V grade made up of unbreakable polyimide 6.6 grade with adequate current rating and size. The welding receptacles shall be provided with inbuilt ELCB rated for suitable adjustable mA sensitivity ranging from 30-300 mA			
3.12.00	Cable Drum Lifting Jack			
	The jack for cable drum lifting shall be of screw type with 10 ton capacity. The cable drum jacks shall be manufactured from fabricated steel. The spindles supplied with the cable drum jack shall be manufactured using BSEN-24 grade steel bar with locking collars. Jack nests shall be of SG cast steel. Cable drum jack supplied shall have undergone load testing and reports for the same shall be submitted. At least Two Nos. of jacks shall be supplied for NTPC use. Contractor has to make arrangements for his own jacks for cable reeling/unreeling under his scope of installation.			
3.13.00	Galvanising			
3.13.01	Galvanising of steel components and accessories shall conform to IS:2629 , IS4759 & IS:2633. Additionally galvanising shall be uniform, clean smooth, continuous and free from acid spots.			
3.13.02	The amount of zinc deposit over threaded portion of bolts, nuts, screws and washers shall be as per IS:1367 . The removal of extra zinc on threaded portion of components shall be carefully done to ensure that the threads shall have the required zinc coating on them as specified			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION	Page 7 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS		
3.14.00	Welding		
3.14.01	The welding shall be carried out in accordance with IS:9595. All welding procedures and welders qualification shall also be followed strictly in line with IS:9595		
4.00.00	INSTALLATION		
4.01.00	Cable tray and Support System Installation		
4.01.01	Cables shall run in cable trays mounted horizontally or vertically on cable tray support system which in turn shall be supported from floor, ceiling, overhead structures, trestles, pipe racks, trenches or other building structures.		
4.01.02	Horizontally running cable trays shall be clamped by bolting to cantilever arms and vertically running cable trays shall be bolted to main support channel by suitable bracket/clamps on both top and bottom side rails at an interval of 2000 mm in general. For vertical cable risers/shafts cable trays shall be supported at an interval of 1000mm in general. Fixing of cable trays to cantilever arms or main support channel by welding shall not be accepted. Cable tray installation shall generally be carried out as per the approved guidelines/ drawings. Vendor shall design the support system along with tray, spacing etc in line with tray loadings/drawings.		
4.01.03	The cantilever arms shall be positioned on the main support channel with a minimum vertical spacing of 300 mm unless otherwise indicated.		
4.01.04	The contractor shall fix the brackets/ clamps/ insert plates using anchor fasteners. Minimum size of anchor fasteners shall be M 8 X 50 and material shall be stainless steel grade 316 or better. Anchor fastener shall be fixed as recommended by manufacturer and as approved by site engineer. For brick wall suitable anchor fasteners shall be used as per the recommendations of manufacturer. Make of anchor fasteners subject to QA approval and the same shall be finalized at pre-award stage.		
4.01.05	All cable way sections shall have identification, designations as per cable way layout drawings and painted/stenciled at each end of cable way and where there is a branch connection to another cable way. Minimum height of letter shall be not less than 75 mm. For long lengths of trays, the identification shall be painted at every 10 meter. Risers shall additionally be painted/stenciled with identification numbers at every floor.		
4.01.06	In certain cases it may be necessary to site fabricate portions of trays, supports and other non standard bends where the normal prefabricated trays, supports and accessories may not be suitable. Fabricated sections of trays, supports and accessories to make the installation complete at site shall be neat in appearance and shall match with the prefabricated sections in the dimensions. They shall be applied with one coat of red lead primer, one coat of oil primer followed by two finishing coats of aluminium paint.		
4.02.00	Conduits/Pipes/Ducts Installation		
4.02.01	The Contractor shall ensure for properly embedding conduit pipe sleeves wherever necessary for cabling work. All openings in the floor/roof/wall / cable tunnel/cable trenches made for conduit installation shall be sealed and made water proof by the Contractor.		
4.02.02	GI pull wire of adequate size shall be laid in all conduits before installation. Metallic conduit runs at termination shall have two lock nuts wherever required for junction boxes etc.		
4.02.03	Conduit runs/sleeves shall be provided with PVC bushings having round edge at each end. All conduits/pipes shall have their ends closed by caps until cables are pulled. After cables are pulled, the ends of conduits/pipes shall be sealed with Glass wool/Cement Mortar/Putty to prevent entrance of moisture and foreign material		
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION
			Page 8 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS												
4.02.04	Exposed conduit/pipe shall be adequately supported by racks, clamps, straps or by other approved means. Conduits /pipe support shall be installed square and true to line and grade with an average spacing between the supports as given below, unless specified otherwise <table><tr><th>Conduit /pipe size (dia).</th><th>Spacing</th></tr><tr><td>Upto 40 mm</td><td>1 M</td></tr><tr><td>50 mm</td><td>2.0 M</td></tr><tr><td>65-85 mm</td><td>2.5 M</td></tr><tr><td>100 mm and above</td><td>3.0 M</td></tr></table>			Conduit /pipe size (dia).	Spacing	Upto 40 mm	1 M	50 mm	2.0 M	65-85 mm	2.5 M	100 mm and above	3.0 M
Conduit /pipe size (dia).	Spacing												
Upto 40 mm	1 M												
50 mm	2.0 M												
65-85 mm	2.5 M												
100 mm and above	3.0 M												
4.02.05	For bending of conduits, bending machine shall be arranged at site by the contractor to facilitate cold bending. The bends formed shall be smooth.												
4.03.00	Junction Boxes Installation												
4.03.01	Junction boxes shall be mounted at a height of 1200mm above floor level or as specified in the drawings and shall be adequately supported/mounted on masonry wall by means of anchor fasteners/ expandable bolts or shall be mounted on an angle, plate or other structural supports fixed to floor, wall, ceiling or equipment foundations.												
4.04.00	Cable Installation												
4.04.01	Cable installation shall be carried out as per IS:1255 and other applicable standards.												
4.04.02	For Cable unloading, pulling etc following guidelines shall be followed in general: a) Cable drums shall be unloaded, handled and stored in an approved manner on hard and well drained surface so that they may not sink. In no case shall be drum be stored flat i.e. with flange horizontal. Rolling of drums shall be avoided as far as possible. For short distances, the drums may be rolled provided they are rolled slowly and in proper direction as marked on the drum. In absence of any indication, the drums may be rolled in the same direction as it was rolled during taking up the cables. For unreeling the cable, the drum shall be mounted on suitable jacks or on cable wheels and shall be rolled slowly so that cable comes out over the drum and not from below. All possible care shall be taken during unreeling and laying to avoid damage due to twist, kink or sharp bends. Cable ends shall be provided with sealed plastic caps to prevent damage and ingress of moisture. b) While laying cable, ground rollers shall be used at every 2 meter interval to avoid cable touching ground. The cables shall be pushed over the rollers by a gang of people positioned in between the rollers. Cables shall not be pulled from the end without having intermediate pushing arrangements. Pulling tension shall not exceed the values recommended by cable manufacturer. Selection of cable drums for each run shall be so planned so as to avoid using straight through joints. Care should be taken while laying the cables so as to avoid damage to cables. If any particular cable is damaged, the same shall be repaired or changed to the satisfaction of Project Manager.												
4.04.03	Cables shall be laid on cable trays strictly in line with cable schedule . Where specific cable layouts are not shown on drawings, Contractor shall route these as directed by the Project Manager												
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION										
			Page 9 of 20										

CLAUSE NO.	TECHNICAL REQUIREMENTS	
4.04.04	Power and control cables shall be laid on separate tiers inline with the approved guidelines/drawings. The laying of different voltage grade cables shall be on different tiers according to the voltage grade of the cables. In horizontal tray stacks, H.T. cables shall be laid on top most tier and cables of subsequent lower voltage grades on lower tiers of trays. Single core cable in trefoil formation shall be laid with a distance of four times the diameter of cable between trefoil center lines and clamped at every two metre. All multicore cables shall be laid in touching formation. Power and control cables shall be secured fixed to trays/support with cable clamps/ties with self locking arrangement. For horizontal trays arrangements, multicore power cables and control cables shall be secured at every five meter interval. For vertical tray arrangement, individual multicore power cables and control cables shall be secured at every one meter. After completion of cable laying work in the particular vertical tray, all the control cables shall be binded to trays/supports by cable clamps/ties with self locking arrangement at every five meter interval and at every bend. Fibre Optical cable shall be laid in trenches/trays or as decided by Employer.	
4.04.05	Bending radii for cables shall be as per manufacturer's recommendations and IS:1255.	
4.04.06	Where cables cross roads/rail tracks, the cables shall be laid in hume pipe/ HDPE pipe.	
4.04.07	No joints shall be allowed in trip circuits, protection circuits and CT/PT circuits. Also joints in critical equipment in main plant area shall not be permitted. Vendor shall identify and accordingly procure the cable drum length.	
4.04.08	In each cable run some extra length shall be kept at suitable point to enable one LT/two HT straight through joints to made, should the cable develop fault at a later stage. Control cable termination inside equipment enclosure shall have sufficient lengths so that shifting of termination in terminal blocks can be done without requiring any splicing.	
4.04.09	Wherever few cables are branching out from main trunk route troughs shall be used.	
4.04.10	Wind loading shall be considered for designing support as well Cable trays wherever required.	
4.04.11	Where there is a considerable risk of steam, hot oil or mechanical damage cable routes shall be protected by barriers or enclosures.	
4.04.12	The installation work shall be carried out in a neat workman like manner & areas of work shall be cleaned of all scraps, water, etc. after the completion of work in each area every day. Contractor shall replace RCC/Steel trench covers after the Installation work in that particular area is completed or when further work is not likely to be taken up for some time.	
4.04.13	Separation At least 300mm clearance shall be provided between: - HT power & LT power cables, - LT power & LT control/instrumentation cables,	
4.04.14	Segregation 1) Segregation means physical isolation to prevent fire jumping. 2) All cables associated with the unit shall be segregated from cables of other units. 3) Interplant cables of station auxiliaries and unit critical drives shall be segregated in such a way that not more than half of the drives are lost in case of single incident of fire. Power and control cables for AC drives and corresponding emergency AC or	
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2
		SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION
		Page 10 of 20

CLAUSE NO.	TECHNICAL REQUIREMENTS		एनटीपीसी NTPC								
4.04.15	DC drives shall be laid in segregated routes. Cable routes for one set of auxiliaries of same unit shall be segregated from the other set.										
	4)	In switchyard, control cables of each bay shall be laid on separate racks/trays.									
	Minimum number of spare cores required to be left for interconnection in control cables shall be as follows:										
	Minimum number of spare cores required to be left for interconnection in control cables shall be as follows:										
	<table><thead><tr><th>No. of cores in cable</th><th>No. of spare cores</th></tr></thead><tbody><tr><td>2C,3C</td><td>NIL</td></tr><tr><td>5C</td><td>1</td></tr><tr><td>7C-10C</td><td>2</td></tr><tr><td>14C and above</td><td>3</td></tr></tbody></table>		No. of cores in cable	No. of spare cores	2C,3C	NIL	5C	1	7C-10C	2	14C and above
No. of cores in cable	No. of spare cores										
2C,3C	NIL										
5C	1										
7C-10C	2										
14C and above	3										
4.04.16	Directly Buried Cables										
	a)	Cable trenches shall be constructed for directly buried cables. Construction of cable trench for cables shall include excavation, preparation of sieved sand bedding, riddled soil cover, supply and installation of brick or concrete protective covers, back filling and compacting, supply and installation of route markers and joint markers. Laying of cables and providing protective covering shall be as per IS:1255 and the enclosed drawings showing cabling details.									
	b)	RCC cable route and RCC joint markers shall be provided wherever required. The voltage grade of the higher voltage cables in route shall be engraved on the marker. Location of underground cable joints shall be indicated with cable marker with an additional inscription "Cable Joint". The marker shall project 150 mm above ground and shall be spaced at an interval of 30 meters and at every change in direction. They shall be located on both sides of road crossings and drain crossings. Top of cable marker/joint marker shall be sloped to avoid accumulation of water/dust on marker.									
4.04.17	Cable tags shall be provided on all cables at each end (just before entering the equipment enclosure), on both sides of a wall or floor crossing, on each duct/conduit entry, and at every 20 meters in cable tray/trench runs. Cable tags shall also be provided inside the switchgear, motor control centers, control and relay panels etc. where a number of cables enter together through a gland plate. Cable tag shall be of rectangular shape for power cables and control cables. Cable tag shall be of 2 mm thick aluminum with number punched on it and securely attached to the cable by not less than two turns of 20 SWG GI wire conforming to IS:280. Alternatively, the Contractor may also provide cable tags made of nylon, cable marking ties with cable number heat stamped on the cable tags. The cable tag requirements mentioned above shall prevail over Tag requirements mentioned elsewhere in this document for HT power, LT power & control cables.										
4.04.18	While crossing the floors, unarmoured cables shall be protected in conduits upto a height of 500 mm from floor level if not laid in tray.										
4.05.00	Cable Terminations & Connections										
4.05.01	The termination and connection of cables shall be done strictly in accordance with cable termination kit manufacturer" instructions, drawings and/or as directed by Project Manager. Cable jointer shall be qualified to carryout satisfactory cable jointing/termination. Contractor										
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION								
			Page 11 of 20								

CLAUSE NO.	TECHNICAL REQUIREMENTS	एनटीपीसी NTPC	
	shall furnish for review documentary evidence/experience reports of the jointers to be deployed at site.		
4.05.02	Work shall include all clamps, fittings etc. and clamping, fitting, fixing, plumbing, soldering, drilling, cutting, taping, preparation of cable end, crimping of lug, insulated sleeving over control cable lugs, heat shrinking (where applicable), connecting to cable terminal, shorting and grounding as required to complete the job to the satisfaction of the Project Manager.		
4.05.03	The equipment will be generally provided with undrilled gland plates for cables/conduit entry. The Contractor shall be responsible for punching of gland plates, painting and touching up. Holes shall not be made by gas cutting. The holes shall be true in shape. All cable entry points shall be sealed and made vermin and dust proof. Unused openings shall be effectively sealed by 2mm thick aluminium sheets.		
4.05.04	Control cable cores entering control panel/switchgear/MCC/miscellaneous panels shall be neatly bunched, clamped and tied with self locking type nylon cable ties with de interlocking facility to keep them in position.		
4.05.05	All the cores of the control cable to be terminated shall have identification by providing ferrules at either end of the core, each ferrule shall be indelible, printed single tube ferrule and shall include the complete wire number and TB number as per the drawings. The ferrule shall fit tightly on the core. Spare cores shall have similar ferrules with suffix sp1, sp2, ---etc along with cable numbers and coiled up after end sealing.		
4.05.06	All cable terminations shall be appropriately tightened to ensure secure and reliable connections.		
5.00.00			
5.01.00			
5.02.00			
5.03.00			
5.04.00			
EPC PACKAGE FOR PATRATU SUPER THERMAL POWER STATION EXPANSION PHASE-I (3X 800MW)		TECHNICAL SPECIFICATIONS SECTION VI, PART-B BID DOC. NO.:CS- 9585-001-2	SUB SECTION- B-09 CABLING, EARTHING & LIGHTNING PROTECTION
			Page 12 of 20

QP FOR MOTORS BELOW 55KW (LV)

		QUALITY PLAN		CUSTOMER :		PROJECT			SPECIFICATION :			
				BIDDER/ VENDOR :		TITLE			NUMBER :			
		SHEET 1 OF 2		SYSTEM		QUALITY PLAN NUMBER PED-506-00-Q-006, REV-01			SPECIFICATION TITLE			
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/ METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	SECTION VOLUME III			
									P	W	V	REMARKS
1	2	3	4	5	6	7	8	9	10			11
1.0	ASSEMBLY	1.WORKMANSHIP	MA	VISUAL	100%	MANUF'S SPEC	MANUF'S SPEC	-DO-	2	-	-	
		2.DIMENSIONS	MA	-DO-	-DO-	MFG. DRG./ MFG. SPEC.	MFG. DRG./ MFG. SPEC.	-DO-	2	-	-	
		3.CORRECTNESS COMPLETENESS TERMINATIONS/ MARKING/COLOUR CODE	MA	VISUAL	100%	MFG.SPEC./ RELEVANT IS	MFG.SPEC. RELEVANT IS	-DO-	2	-	-	
2.0	PAINTING	1.SHADE	MA	VISUAL	SAMPLE	MANUFR'S SPEC/BHEL SPEC./RELEVANT STANDARD	BHEL SPEC. SAME AS COL.7	LOG BOOK	2	-	-	
3.0	TESTS	1.ROUTINE TEST INCLUDING SPECIAL TEST AS PER BHEL SPEC.	MA	-DO-	100%	IS-325/ BHEL SPEC./ DATA SHEET	SAME AS COL.7	TEST REPORT	2	1		NOTE -1 & NOTE-3
		2.OVERALL DIMENSIONS & ORIENTATION	MA	MEASUREMENT & VISUAL	100%	APPROVED DRG/DATA SHEET	APPROVED DRG/DATA SHEET & RELEVANT IS	INSPN. REPORT	2	1	-	NOTE -1 & NOTE-3
BHEL			PARTICULARS		BIDDER/VENDOR							
			NAME									
			SIGNATURE									

		QUALITY PLAN		CUSTOMER :			PROJECT			SPECIFICATION :		
				BIDDER/ :			TITLE			NUMBER :		
		SHEET 2 OF 2		VENDOR			QUALITY PLAN			SPECIFICATION :		
		SYSTEM			NUMBER PED-506-00-Q-006, REV-01			TITLE :				
		ITEM AC ELECT. MOTORS BELOW 55KW (LV)			SECTION			VOLUME III				
SL. NO.	COMPONENT/OPERATION	CHARACTERISTICS CHECK	CAT.	TYPE/METHOD OF CHECK	EXTENT OF CHECK	REFERENCE DOCUMENT	ACCEPTANCE NORM	FORMAT OF RECORD	AGENCY			REMARKS
1	2	3	4	5	6	7	8	9	P	W	V	11
		3.NAMEPLATE DETAILS	MA	VISUAL	100%	IS-325 & DATA SHEET	IS-325 & DATA SHEET	INSPN. REPORT	2	1	-	
NOTES: 1 ROUTINE TESTS ON 100% MOTORS SHALL BE DONE BY THE VENDOR. HOWEVER, BHEL SHALL WITNESS ROUTINE TESTS ON RANDOM SAMPLES. THE SAMPLING PLAN SHALL BE MUTUALLY AGREED UPON 2 WHERE EVER CUSTOMER IS INVOLVED IN INSPECTION, (1) SHALL MEAN BHEL AND CUSTOMERS BOTH TOGETHER. 3 FOR EXHAUST/VENTILATION FAN MOTORS OF RATING UPTO 1.5KW , ONLY ROUTINE TEST CERTIFICATES SHALL BE FURNISHED FOR SCRUTINY. <u>Legends for Inspection agency</u> 1. BHEL/CUSTOMER 2. VENDOR (MOTOR MANUFACTURER) 3. SUB-VENDOR (RAW MATERIAL/COMPONENTS SUPPLIER) P. PERFORM W. WITNESS V. VERIFY												
BHEL			PARTICULARS			BIDDER/VENDOR						
			NAME									
			SIGNATURE									
			DATE						BIDDER'S/VENDORS COMPANY SEAL			