

BILL OF QUANTITY

Name of Project : 400/132 KV Switchyard , Adilabad
Name of Work : Civil Work of Switchyard Surfacing

S.No.	Description of Item	Quantity	Unit	Unit Rate(Rs)	Amount(Rs)
1	Providing and laying stone aggregate in switch yard areas in 75mm thick layer using 20 mm aggregates size in bottom layer and 75mm thick layer using 40mm size aggregate in top layer making overall thickness of stone aggregate as 150mm. Before laying the stone aggregates , the yard surface shall be treated with antiweed treatment all complete as per Customer's specification clause 7.07.00, section VI Part-B Sub Section D-01 Civil Works and direction of Engineer in Charge. (The rate shall be inclusive of all materials ,labour,loading,unloading and surface preparation,compaction, micro grading etc. required for aggregate laying and antiweed treatment)	52730	sqm		
	Total Amount				