

BILL OF QUANTITY**Name of Project** : 765kV/400kV AGRA UPPTCL (NEW) SUBSTATION**Name of Work** : SITE LEVELLING WORK

S.No.	Description of Item	Unit	Quantity	Unit Rate (Rs)	Amount (Rs)
1	SITE LEVELLING WORK				
(a)	Earthwork in excavation & filling in all types of soil in open areas/nallas/ channels, to the required slopes, shapes, levels, elevations and profile, including trimming of bottom and slopes of excavation, loading/unloading, transporting excavated material, stacking serviceable material within a lead of 1 km. from the levelling Boundary, disposal of unserviceable material in disposal areas , filling in low lying areas, bailing out rain (dewatering), pumping, removal of slush, preparing embankments/marginal banks, loosening, dressing, spreading material in layers not exceeding 200mm, as per direction of Engineer-in-Charge, water flooding, compacting to achieve 95% consolidation at optimum moisture content, finishing etc. all complete, for all leads within the leveling boundary and all lifts, with all labour, material, tools, tackles and equipment, safeguards and incidentals, as necessary, as per drawings, specification and directions of the Engineer-in-Charge.	Cum	375000		