

BILL OF QUANTITY & PRICE SCHEDULE**Name of Project****: 400kV SWITCHYARD AT BELLARY -III****Name of Work****:METAL SPREADING WORKS IN 400kV
SWITCHYARD .**

S.No.	Description of Item	Quantity	Unit	Unit Rate(Rs)	Amount(Rs)
1	Providing and laying stone aggregate in switch yard areas in 75mm thick layer using 40mm aggregates size on top and 75mm thick layer using 20mm size aggregate below making overall thickness of stone aggregate as 150mm. Before laying the stone aggregates, The yard surface shall be treated with antiweed treatment all complete as per direction of engineer in charge. (the rate shall be inclusive of all materials, labor, loading, unloading and surface preparation, levelling upto 30cm undulations etc required for aggregate laying and antiweed treatment).	25000	sqm	217.00	5425000.00

**TRANSMISSION BUSINESS GROUP
(SUB- CONTRACTS MANAGEMENT)
TBG - NOIDA**

**PRICE SCHEDULE FORMAT
(ANNEXURE-A)**

**SUB: EXECUTION AND HANDING OVER OF METAL SPREADING
WORKS IN 400KV SWITCHYARD AT BELLARY-III IN
KARNATAKA**

- (a) I/ We hereby agree to execute the above work at ----- % (in figure)
----- (in words) Above/ Below the rates of items given in BOQ for
civil works (Annexure-I) of subject tender.

NOTE:

1. In case of discrepancy in rates in figure and words, the minimum will be taken into account by BHEL.

Date:
Place

Signature of tenderer
Name & Designation of authorized person(s) with seal