

**BILL OF QUANTITY CUM PRICE SCHEDULE**

Name of Project :

765/400/220 KV PGCIL SUB-STATION (NEW) AT  
BANASKANTHA IN GUJRAT

Name of Work :

ANTIWEED, PCC AND STONE SPREADING  
WORKS IN THE SWITCHYARD

S. No.	Description of Item	Quantity	Unit	Unit Rate (Rs)	Amount (Rs)
1	Antiweed treatment in switchyard area including micro leveling, dressing, compaction, effectiveness test of antiweed chemical, etc all complete as per Technical Specification and instruction of Engineer-in-charge including cost of all labour, materials, T&P, etc.	295300	Sqm	12.76	3768028.00
2	Providing & laying in position plain cement concrete (PCC) of 1:5:10 (1 cement : 5 coarse sand : 10 brick aggregate 40mm nominal size) with a layer of cement slurry of mix 1:6 (1 cement : 6 Fine Sand) over PCC layer as per Technical Specification, Drawings and instruction of Engineer-in-charge including cost of all labour, materials, T&P, etc. <b>Note:-</b> the contractor shall have option to use graded stone aggregate 40mm nominal size in place of brick aggregate without any extra cost to BHEL.	22200	cum	2026.96	44998512.00
3	Supplying and spreading stone aggregates of 40mm nominal size (ungraded single size) in switchyard over yard PCC as per drawing and specification all complete including cost of all labour, materials, T&P, etc. but excluding the cost of PCC. Final compacted thickness of the stone aggregate layer shall be 100mm uniformly.	92000	Sqm	76.20	7010400.00

**TOTAL (Rs)****55776940**

<b>ANNEXURE-II</b>
--------------------

**TRANSMISSION BUSINESS GROUP  
(SUB- CONTRACTS MANAGEMENT)  
TBG - NOIDA**

**PRICE SCHEDULE FORMAT**

**SUB: EXECUTION AND HANDING OVER OF STONE SPREADING WORK OF 765/400/220KV  
SUBSTATION AT BANASKANTHA IN GUJARAT**

- (a) I/ We hereby agree to execute the above work at ----- % (in figure)  
----- (in words) Above / Below/ At Par the rates of items given in BOQ  
for stone spreading work (Annexure-I) of subject tender.

**NOTE:**

1. In this annexure the tenderer shall quote a percentage above or below the rates shown in the Bill of Quantities of stone spreading works (Annexure-I). The percentage quoted shall be clearly written both in words and figures In case of discrepancy in rates in figure and words, the minimum will be taken into account by BHEL.
2. The quoted percentage will apply to the individual items uniformly.

Date:

Place

Signature of tenderer

Name & Designation of authorized person(s) with seal

**ANNEXURE-III****Summary of prices for execution and handing over of Stone Spreading Work of 765/400/220kV substation at Banaskantha in Gujarat**

<b>Sl No.</b>	<b>Description</b>	<b>Amount (Rs.)</b>
1	Total amount as per the rates in BOQ for execution and handing over of Stone Spreading Work of 765/400/220kV substation at Banaskantha in Gujarat (Annexure-I)	557,76,940
2	Value of percentage above/below/At par (As indicated in Price Schedule Format, Annexure-II ) applicable to the total amount of BOQ (Annexure-I)	.....% above/below/At par
3	<b>Total cost for execution and handing over of Stone Spreading Work of 765/400/220kV substation at Banaskantha in Gujarat after consideration of percentage above/below/at par</b>	