

BOQ CUM PRICE SCHEDULE**Name of Project :765/400/220 KV PGCIL BHUJ POOL SS (NEW) AT BHUJ IN GUJRAT****Name of Work :ANTIWEED, PCC AND STONE SPREADING WORKS IN THE SWITCHYARD**

S. No.	Description of Item	Quantity	Unit	Unit Rate (Rs)	Value (Rs)
1	Antiweed treatment in switchyard area including micro leveling, dressing, compaction, effectiveness test of antiweed chemical, etc all complete as per Technical Specification and instruction of Engineer-in-charge including cost of all labour, materials, T&P, etc.	54942	Sqm	20.80	1142793.60
2	Providing & laying in position plain cement concrete (PCC) of 1:5:10 (1 cement : 5 coarse sand : 10 brick aggregate 40mm nominal size) with a layer of cement slurry of mix 1:6 (1 cement : 6 Fine Sand) over PCC layer as per Technical Specification, Drawings and instruction of Engineer-in-charge including cost of all labour, materials, T&P, etc. Note:- the contractor shall have option to use graded stone aggregate 40mm nominal size in place of brick aggregate without any extra cost to BHEL.	4121	cum	2635.00	10858835.00
3	Supplying and spreading stone aggregates of 40mm nominal size (ungraded single size) in switchyard over yard PCC as per drawing and specification all complete including cost of all labour, materials, T&P, etc. but excluding the cost of PCC. Final compacted thickness of the stone aggregate layer shall be 100mm uniformly.	92410	Sqm	136.00	12567760.00
4	Transporting of surplus excavated earth of all kinds, left out by other contractor, to a designated place away from the site and spreading & leveling or disposal of the same as per Instruction of Engineer-in-charge, etc. within a lead of 1.0 km including loading, transportation, unloading, compaction, etc. all complete.	150	Cum	129.29	19393.50
Total Amount (Rs)- Excluding GST					245,88,782

ANNEXURE-II

**TRANSMISSION BUSINESS GROUP
(SUB- CONTRACTS MANAGEMENT)
TBG - NOIDA**

PRICE SCHEDULE FORMAT

SUB: TENDER FOR “EXECUTION AND HANDING OVER BALANCE CIVIL WORKS OF ANTIWEED, PCC AND STONE SPREADING WORKS FOR 765/400/220KV PGCIL BHUJ POOL SUB-STATION (NEW) AT BHUJ IN GUJARAT ON RISK AND COST BASIS”.

TENDER NO.:- TBSM/BHUJ/BAL_CIVIL/PKG-VI/ R&C/TENDER DATE: 26.06.2019

(a) I/ We hereby agree to execute the above work at ----- % (in figure).....
----- (in words) Above / Below/ At Par the rates of items given in BOQ
(Annexure-I) of subject tender.

NOTE:

1. In this annexure the tenderer shall quote a percentage above/ below/At Par the rates shown in the Bill of Quantities (Annexure-I) of subject tender. The percentage quoted shall be clearly written both in words and figures In case of discrepancy in rates in figure and words, the minimum will be taken into account by BHEL.
2. The quoted percentage will apply to the individual items uniformly.

Date:
Place

Signature of tenderer
Name & Designation of authorized person(s) with seal

ANNEXURE-III

(Summary Of Prices)

**EXECUTION AND HANDING OVER BALANCE CIVIL WORKS OF ANTIWEED, PCC AND STONE SPREADING WORKS
FOR 765/400/220KV PGCIL BHUJ POOL SUB-STATION (NEW) AT BHUJ IN GUJARAT ON RISK AND COST BASIS**

Sl No.	Description	Amount (Rs.)
1	Total amount as per the rates in BOQ for " Execution and handing over balance civil works of Antiweed, PCC and Stone spreading works for 765/400/220kV PGCIL Bhuj pool sub-station (new) at Bhuj in Gujarat on risk and cost basis " (Annexure-I)	245,88,782.00
2	Value of percentage above/below/at par (As indicated in Price Schedule Format, Annexure-II) applicable to the total amount of civil work (Sl. no. 1 above)% above/below/ at par
3	Total amount after consideration of percentage above/below/ at par.	