

Annexure CTM

Cable Trench Material - work for BOLTED and Welded TYPE (As applicable) GI Rack / Tray for cable trenches in Switchyard, GIS Hall & Control Room Building as per doc. no. TB-397-316-019 Rev 00.

Following works deemed included in the scope and not being payable separately - Welding of racks, installation of cantilever arms, back plate, angle fitting, clamp for single / double channel, cutting of vertical supports C1 and C2 as per requirement ,base plate for single / double channel, beam clamp, tray fixing clamp, screw, nut bolt, anchor bolt, floor / ceiling / beam / columns support, Side runner for cable tray, side coupler, pvc end cap, earthing clamp, tray clamp etc. complete in all respect are deemed included in the scope. Cable rack assembly will be of 1/2/3/4 tier. (Bolted and Welded type Cable Rack/Tray material/Hardware , Nut Bolt, fasteners shall be free issued by BHEL.) Cutting , drilling, punching, minor civil works also included in the scope. Minor welding and application of protective / zinc rich paint on welded surface is also included in the scope.