

2X660 MW UDANGUDI STPP STAGE-1
ANNEXURE-1 : BOQ CUM UN PRICE SCHEDULE FOR DC BATTERY CHARGER PACKAGE
TENDER ENQUIRY NO.: PE/PG/UDN/E-6188/2019 DATED 01.05.2019

S. No.	Item code	Item Description	Unit	Quantity	Remarks	HSN code	UNIT EX-WORKS PRICE (DUTY PACKED) (INR) (1)	% OF TOTAL EX WORKS (SA) (MENTION RATE HERE)	AMOUNT IN (INR) (3B) (2X3A)	TOTAL PRICES (as works + freight) (INR) (4)	APPLICABLE GST RATE IN % ON TOTAL EX WORKS + FREIGHT BOTH (INR) (5)	TOTAL PRICE F.O.R Prices with bases (INR) (6) (4+5)
1	508-12010-A	220V FLOAT-CUM-BOOST CHARGER1, 220V DC, 500A (MAIN PLANT)	NOS	6	LEAD ACID BATTERY (2X1500 AH)	8504						
2	508-12011-A	220V FLOAT-CUM-BOOST CHARGER2, 220V DC, 50A (WATER TREATMENT & RO PLANT)	NOS	2	LEAD ACID BATTERY (78AH) WITH TAP CELL	8504						
3	508-12012-A	220V FLOAT-CUM-BOOST CHARGER3, 220V DC, 50A (SEA WATER INTAKE SYSTEM)	NOS	2	LEAD ACID BATTERY (78AH) WITH TAP CELL	8504						
4	508-12001-A	BATTERY FUSE BOX										
4.1		BATTERY FUSE BOX (MAIN PLANT)	NOS	4	BATTERY FUSE BOX OF ADEQUATE RATING AS PER LOAD DUTY CYCLE (ANNEXURE-II OF SPECIFICATION). MINIMUM RATING 1000A.	8504						
4.2		BATTERY FUSE BOX (WATER TREATMENT & RO PLANT)	NOS	1	BATTERY FUSE BOX OF ADEQUATE RATING AS PER LOAD DUTY CYCLE (ANNEXURE-II OF SPECIFICATION). MINIMUM RATING 32A.	8504						
4.3		BATTERY FUSE BOX (SEA WATER INTAKE SYSTEM)	NOS	1	BATTERY FUSE BOX OF ADEQUATE RATING AS PER LOAD DUTY CYCLE (ANNEXURE-II OF SPECIFICATION). MINIMUM RATING 32A.	8504						
5	508-12005-A	DISCHARGE RESISTOR										
5.1		DISCHARGE RESISTOR (MAIN PLANT)	NOS	2	DISCHARGE RESISTOR WITH SHUNT SUITABLE FOR 10HRS DISCHARGE RATE FOR 3000 AH LEAD ACID BATTERY (TWO PARALLEL STRINGS OF 1500AH BATTERY)	8504						
5.2		DISCHARGE RESISTOR(WATER TREATMENT & RO PLANT)	NOS	1	DISCHARGE RESISTOR WITH SHUNT SUITABLE FOR 10HRS DISCHARGE RATE FOR 78 AH LEAD ACID BATTERY (SINGLE STRING OF 78AH BATTERY)	8504						
5.3		DISCHARGE RESISTOR (SEA WATER INTAKE SYSTEM)	NOS	1	DISCHARGE RESISTOR WITH SHUNT SUITABLE FOR 10HRS DISCHARGE RATE FOR 78 AH LEAD ACID BATTERY (SINGLE STRING OF 78AH BATTERY)	8504						
6	508-12006-A	E & C SPARES										
6.1		E & C SPARES FOR FLOAT CUM BOOST CHARGER (MAIN PLANT) AT BOQ S. NO. 1	SET	1								
6.1.1		FUSE LINK WITHOUT HOLDER										
a		AC 1/2 HRC FUSE LINK	NOS	6		8504						
b		GLASS FUSE	NOS	6		8504						
c		CONTROL HRC FUSE LINK	NOS	6		8504						
d		RECTIFIER FUSE LINK	NOS	6		8504						
e		FILTER CAPACITOR FUSE LINK	NOS	6		8504						
f		DC O/P FUSE LINK	NOS	6		8504						
6.1.2		INDICATING LAMP										
a		AC 1/2 LAMP RED COLOR	NOS	6		8504						
b		AC 1/2 LAMP YELLOW COLOR	NOS	6		8504						
c		AC 1/2 LAMP BLUE COLOR	NOS	6		8504						
d		DC O/P LAMP	NOS	6		8504						
6.2		E & C SPARES FOR FLOAT CUM BOOST CHARGER (WATER TREATMENT & RO PLANT) AT BOQ S. NO. 2	SET	1		8504						
6.2.1		FUSE LINK WITHOUT HOLDER										
a		AC 1/2 HRC FUSE LINK	NOS	6		8504						
b		GLASS FUSE	NOS	6		8504						
c		CONTROL HRC FUSE LINK	NOS	6		8504						
d		RECTIFIER FUSE LINK	NOS	6		8504						
e		FILTER CAPACITOR FUSE LINK	NOS	6		8504						
f		DC O/P FUSE LINK	NOS	6		8504						
6.2.2		INDICATING LAMP										
a		AC 1/2 LAMP RED COLOR	NOS	6		8504						
b		AC 1/2 LAMP YELLOW COLOR	NOS	6		8504						

Amogh

2X660 MW UDANGUDI STPP STAGE-1
ANNEXURE-1 : BOQ CUM UN PRICE SCHEDULE FOR DC BATTERY CHARGER PACKAGE
TENDER ENQUIRY NO.: PE/PG/UDN/E-6188/2019 DATED 01.05.2019

S. No.	Item code	Item Description	Unit	Quantity	Remarks	HSN code	UNIT EX-WORKS PRICE (DULY PACKED) (INR) (1)	TOTAL EX-WORKS PRICE (DULY PACKED) (INR) (2)	FREIGHT CHARGES (8)	TOTAL PRICES (on works + freight) (INR) (4)	APPLICABLE GST RATE IN % ON TOTAL EX WORKS + FREIGHT BOTH (INR) (5)	GST RATE IN % ON TOTAL EX WORKS + FREIGHT (SA) (MENTION RATE HERE) (INR) (5B)	TOTAL AMOUNT IN (INR) (5B)+(4)+(5A)	TOTAL PRICE F.O.R Prices with taxes (INR) (6)
c		AC I/P LAMP BLUE COLOR	NOS	6		8504								
d		DC O/P LAMP	NOS	6		8504								
6.3		E & C SPARES FOR FLOAT CUM BOOST CHARGER (SEA WATER INTAKE SYSTEM) AT BOQ S. NO. 1	SET	1										
6.3.1		FUSE LINK WITHOUT HOLDER	NOS	6		8504								
a		AC I/P HRC FUSE LINK	NOS	6		8504								
b		GLASS FUSE	NOS	6		8504								
c		CONTROL HRC FUSE LINK	NOS	6		8504								
d		RECTIFIER FUSE LINK	NOS	6		8504								
e		FILTER CAPACITOR FUSE LINK	NOS	6		8504								
f		DC O/P FUSE LINK	NOS	6		8504								
6.3.2		INDICATING LAMP	NOS	6		8504								
a		AC I/P LAMP RED COLOR	NOS	6		8504								
b		AC I/P LAMP YELLOW COLOR	NOS	6		8504								
c		AC I/P LAMP BLUE COLOR	NOS	6		8504								
d		DC O/P LAMP	NOS	6		8504								
7	508-12024-A	TYPE TEST	LOT	1										
7.1		HEAT RUN TEST	SET	2		9987								
					HEAT RUN TEST TO BE CONDUCTED ON ONE CHARGER OF EACH RATING (I.e. TEST TO BE CONDUCTED ON 1 NO. CHARGER AT BOQ S. NO. 1 AND 1 NO. CHARGER AT BOQ S. NO. 2 & 3 TOGETHER)									
8	508-12020-A	SUPV OF EAC	SET	1										
					1 VISIT & 4 DAYS EACH FOR UNIT-1 MAIN PLANT, UNIT-2 MAIN PLANT, WATER TREATMENT & RO PLANT, SEA WATER INTAKE REFER NOTE - 1, 2 & 3									
8.1		LUMP SUM CHARGES PER VISIT FOR ENGINEER (EXCEPT DAILY CHARGES)	VISIT	4		9987								
8.2		LUMP SUM DAILY CHARGES FOR ENGINEER	DAYS	16		9987								
9	508-12000-B	MANDATORY SPARES												
		(* One set corresponds to actual quantity of components and devices as installed for the environment at Site)												
9.1		MANDATORY SPARES FOR FLOAT CUM BOOST CHARGER (MAIN PLANT) AT BOQ S. NO. 1	SET	1										
a		ELECTRONIC CARDS (WITH ALL COMPONENTS MOUNTED)	SET (OF EACH TYPE & RATING)	1		8504								
b		FUSES	NOS (OF EACH TYPE & RATING)	4		8504								
c		SCR	NOS (OF EACH TYPE & RATING)	6		8504								
d		BLOCKING DIODE	SET (OF EACH TYPE & RATING)	6		8504								
e		POTENTIOMETER	SET (OF EACH TYPE & RATING)	3		8504								
f		MCCB	SET (OF EACH TYPE & RATING)	10 % OF EACH TYPE & RATING		8504								
g		LEDs LAMPS	NOS (OF EACH TYPE & RATING)	5		8504								
9.2		MANDATORY SPARES FOR FLOAT CUM BOOST CHARGER (WATER TREATMENT & RO PLANT) AT BOQ S. NO. 2	SET	1										
a		ELECTRONIC CARDS (WITH ALL COMPONENTS MOUNTED)	SET (OF EACH TYPE & RATING)	1		8504								

August

2X660 MW UDANGUDI STPP STAGE-1

ANNEXURE-1 : BOQ CUM UN PRICE SCHEDULE FOR DC BATTERY CHARGER PACKAGE

TENDER ENQUIRY NO.: PE/PG/UDN/E-6188/2019 DATED 01.05.2019

S. No.	Item code	Item Description	Unit	Quantity	Remarks	HSN code	UNIT EX-WORKS PRICE (DULY PACKED) (INR) (1)	TOTAL EX-WORKS PRICE (DULY PACKED) (INR) (2)	% OF TOTAL EX WORKS (3A) (MENTION RATE HERE)	AMOUNT IN (INR) (3B) = (2X3A)	TOTAL PRICES (in works + freight) (INR) (4) = (2+3B)	APPLICABLE GST RATE IN % ON (TOTAL EX WORKS + FREIGHT) BOTH (5)	TOTAL PRICE F.O.R Prices with taxes (INR) (6) = (4+5B)
b		FUSES	NOS (OF EACH TYPE & RATING)	4		8504							
c		SCR	NOS (OF EACH TYPE & RATING)	6		8504							
d		BLOCKING DIODE	SET (OF EACH TYPE & RATING)	6		8504							
e		POTENTIOMETER	SET (OF EACH TYPE & RATING)	3		8504							
f		MCOB	SET (OF EACH TYPE & RATING)	10 % OF EACH TYPE & RATING		8504							
g		LEDs LAMPS	NOS (OF EACH TYPE & RATING)	5		8504							
9.3		MANDATORY SPARES FOR FLOAT CUM BOOST CHARGER (SEA WATER INTAKE SYSTEM) AT BOO.S. NO. 3	SET	1									
a		ELECTRONIC CARDS (WITH ALL COMPONENTS MOUNTED)	SET (OF EACH TYPE & RATING)	1		8504							
b		FUSES	NOS (OF EACH TYPE & RATING)	4		8504							
c		SCR	NOS (OF EACH TYPE & RATING)	6		8504							
d		BLOCKING DIODE	SET (OF EACH TYPE & RATING)	6		8504							
e		POTENTIOMETER	SET (OF EACH TYPE & RATING)	3		8504							
f		MCOB	SET (OF EACH TYPE & RATING)	10 % OF EACH TYPE & RATING		8504							
g		LEDs LAMPS	NOS (OF EACH TYPE & RATING)	5		8504							
TOTAL IN FIGURES													
TOTAL IN WORDS													

NOTE:

- 1) AMOUNT PAYABLE FOR ENGINEER PER VISIT TO SITE = VISIT CHARGES AS PER SL. NO. 8.1 ABOVE + (DAILY CHARGES AS PER SL. NO. 8.2 ABOVE X NO. OF DAYS AT SITE) (TO BE CERTIFIED BY BHEL SITE).
- 2) THE VISIT CHARGES SHALL BE INCLUSIVE OF CHARGES OF AIR FARE/TRAIN FARE, BOARDING/LODGING, LOCAL CONVENIENCE, MEDICAL, INSURANCE ETC.
- 3) SITE VISIT CHARGES SHALL BE APPLICABLE FOR ANY VISIT MADE BY VENDOR AT SITE AFTER RECEIVING THE INSTRUCTION FROM BHEL FOR DEPUTATION OF VENDOR REPRESENTATIVE. THE VISIT CAN BE CALLED FOR SUPERVISION OF COMMISSIONING & TESTING ETC.
- 4) ALL CABLE GLANDS & LUGS AT CHARGER, FUSE BOX & DISCHARGE RESISTOR END ARE IN BIDDER'S SCOPE.

Handwritten signature and date: 01/05/2019