

TENDER SPECIFICATION NO

Sl NO	Tender Specification Number	Unit Number & Project
1	BHE/PW/PUR/MANUT-STR Pkg-E (U-1&2) /1460	Package-E (Unit-1&2)
2	BHE/PW/PUR/MANUT-STR Pkg-F (U-3&4)/1461	Package-F (Unit-3&4)

Package E: All structural works of STG building; Mill & Bunker Bay; Interconnecting gallery ESP control room structure; CW Pump House; CW Treatment Str; **Compressor Building; Raw Water Pump House** and sheds/access ways/ platforms etc within the battery limits of plant area up to final painting and handing over to civil/mechanical/electrical agencies for **Unit# 1 & 2 (Common works like pipe/cable racks shall be divided equally) AT 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana**

Package F: All structural works of STG building; Mill & Bunker Bay; Interconnecting gallery ESP control room structure; CW Pump House; CW Treatment Str; **Permanent Store Building; Clarified Water Pump House** and sheds/access ways/ platforms etc within the battery limits of plant area up to final painting and handing over to civil/mechanical/electrical agencies for **Unit# 3 & 4 (Common works like pipe/cable racks shall be divided equally) AT 4 X 270 MW Thermal Power Station, Manuguru, Distt-Khammam, Telangana**

Volume 1 E – Technical Specification Section-C, Section D and Plot Plan

TENDER SPECIFICATIONS CONSISTS OF:

- **Notice Inviting Tender**
- **Volume 1 A - Technical Conditions of Contract,**
- **Volume 1 B - Special conditions of Contract,**
- **Volume 1 C - General conditions of Contract**
- **Volume 1 D - Forms & Procedures**
- **Volume 1 E – Technical Specification Section-C, Section D and Plot Plan**



Bharat Heavy Electricals Limited
(A Government of India Undertaking)
Power Sector - Western Region
345-Kingsway, Nagpur-440001

Date
Seal and Signature
Place

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 1 OF 79


**TELANGANA STATE ELECTRICITY
CORPORATION LIMITED (TSGENCO)
4X270MW BHADRADRI TPS**

**TECHNICAL SPECIFICATIONS
(EXCEPT CHIMNEY)**

CIVIL STRUCTURAL & ARCHITECTURAL WORKS

PE-TS-411-600-C001

SECTION C



**Bharat Heavy Electricals Limited
Project Engineering Management
PPEI Building, Power Sector,
Plot No. 25, Sector 16A,
Noida-201301**

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 2 OF 79

CONTENTS

CONTENTS	3
1.0 GENERAL.....	6
1.1 SCOPE	6
1.2 SITE INFORMATION	7
1.2.1 SITE LOCATION	7
1.2.2 SITE LEVELLING AND GRADING	7
1.2.3 SOIL CONDITION AND GROUND WATER LEVEL	8
1.2.4 SEISMIC LOCATION	8
1.2.5 WIND PRESSURE	8
1.2.6 REFERENCE LEVEL	8
2.0 REFERENCES, CODES AND STANDARDS.....	8
2.1 BIS CODES AND REFERENCES	8
3.0 LOADS AND LOAD COMBINATIONS.....	16
3.1 DEAD LOADS (DL)	16
3.2 IMPOSED LOADS (IL)	17
3.3 WIND LOAD	21
3.4 SEISMIC LOADS	21
3.5 EARTH PRESSURE LOADS	21
3.6 TEMPERATURE LOADS	21
3.7 EQUIPMENT LOAD	22
3.8 CRANE, MONORAIL AND ELEVATOR LOADS	22
3.9 LOAD COMBINATIONS	23
3.10 LOAD COMBINATIONS FOR UNDERGROUND STRUCTURES	24
3.11 SPECIAL STRUCTURES	25
4.0 DESIGN METHODOLOGY	26
4.1 REINFORCED CONCRETE STRUCTURES	26
4.1.1 GENERAL	26
4.1.2 FOUNDATION AND UNDERGROUND STRUCTURES	29
4.1.3 TANK FOUNDATIONS	31
4.1.4 MACHINE FOUNDATIONS	31

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001	
		VOLUME	
		SECTION	
		REV.NO.	0 14.05.2015
		SHEET	3 OF 79

4.1.5	LIQUID RETAINING STRUCTURES	33
4.1.6	RAW WATER RESERVOIR	33
4.2	STEEL STRUCTURES	34
4.2.1	MATERIALS	34
4.2.2	FRAMING	35
4.2.3	CONNECTIONS	36
4.2.4	DESIGN	38
4.2.5	PERMISSIBLE DEFLECTIONS	39
4.2.6	MINIMUM THICKNESS & SIZES OF ELEMENTS	41
4.2.7	SLENDerness RATIO	41
4.2.8	PAINTING	41
4.2.9	REQUIREMENTS FOR SPECIFIC STRUCTURES	41
4.3	DESIGN PHILOSOPHY	42
4.3.1	POWER HOUSE STRUCTURE (TURBO GENERATOR / DEAERATOR BAY)	42
4.3.2	ELECTRICAL BAY	40
4.3.3	PIPE AND CABLE RACKS AND PIPE PEDESTALS	40
4.3.4	MILL AND BUNKER BAY	40
4.4	DRAINAGE AND SEWERAGE	40
4.4.1	SURFACE DRAINAGE	40
4.4.2	STORM WATER DRAINAGE SYSTEM	41
4.4.3	PLANT EFFLUENT DRAINAGE (OILY WASTE/PROCESS WASTE DRAINAGE)	42
4.4.4	SEWAGE DISPOSAL	42
4.4.5	BUILDINGS - WATER SUPPLY SYSTEM	42
4.5	CABLE TRENCHES	43
4.6	PAVING / GRADE SLAB	43
4.7	ROAD & DRAIN	44
4.8	FENCING	44
4.9	PLINTH PROTECTION	44
4.10	GROUTING/ENCASEMENT	44
4.11	DAMP PROOFING	45
5.0	BRIEF DESCRIPTION OF STRUCTURES IN POWER PLANT	46
5.1	POWER HOUSE BUILDING	46
5.2	MILL AND BUNKER BAY STRUCTURE	46
5.3	ESP CONTROL ROOM	46
5.4	TRANSFORMER YARD	47
5.5	MISC BUILDING/STRUCTURE	48
6.0	GENERAL REQUIREMENT OF BUILDINGS	50
6.1	ARCHITECTURAL CONCEPTS AND DETAILS	50
6.2	ROOF ACCESS	51
6.3	PLATFORMS AND WALKWAYS	51
6.4	STAIRS & LADDERS	51
6.5	VERTICAL HEAD ROOM	51
6.6	GUARD RAIL / HAND RAILS	51
6.7	EDGE PROTECTION	52

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 4 OF 79

6.8	ANCHOR BOLTS AND INSERT PLATES	52
6.9	EXPANSION / CONSTRUCTION JOINTS	52
6.10	BRICK MASONRY / STONE MASONRY	53
6.11	WATER PROOFING & PAINTING OF UNDERGROUND STRUCTURES	53
6.12	ROLLING SHUTTERS	57

7.0 FINISHES.....57

7.1	PLASTERING	57
7.2	DOORS, WINDOWS AND VENTILATORS	58
7.3	GLAZING	59
7.4	ACID ALKALI RESISTANT LINIFINISHESNG	59
7.5	FLOORING & FLOOR FINISHES	59
7.6	FALSE CEILING	60
7.7	SCHEDULE OF FINISHES	61

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 5 OF 79

1.0 **GENERAL**

1.1 **SCOPE**

The scope includes civil, structural and architectural works of the following areas/structures/buildings.

- Topographical Survey
- Geo-Technical Investigation
- Leveling and Grading
- Power House including AC Plant & MCC control building
- Mill and Bunker Bay including bunkers
- Foundation for TG, Mills, ESP, FD/ID/PA Fans, Boiler & Boiler auxiliary foundations, Duct supporting column foundations and miscellaneous equipments.
- Transformer Yard including transformer foundation, fire barrier wall etc.
- Chimney
- Raw water reservoir and Raw water pump house
- Clarified water cum Fire water reservoir
- ESP Control Building
- FO System including fuel oil pump house, LDO/HFO tank foundation and dyke area.
- CW System including fore-bay basin, CW-duct, CW-pump house including maintenance bay and electrical annex.
- Fire Station Building.
- Main Plant Paving
- Service Building
- Canteen Building
- Admin building and gate Complex
- Permanent Store building
- DM Plant including DM regeneration, DM plant building, DMW Storage Tank foundation and paving etc.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	6	OF 79

- CW Treatment Building
- Compressor Building
- Chlorination Building
- Pipe and Cable Rack
- ETP Sumps.
- Chemical dosing.
- Watch Towers
- Rain Water Harvesting pits
- Plant Road and drains.
- Sanitary Sewer including inspection pits, manholes and foundation for skid mounting plant.
- Civil works for Complete Plant Water System
- Weigh Bridge
- DG Building

1.1.1 The criteria furnished in this document shall govern the design of Civil, Structural and Architectural works of buildings, structures and yard facilities related to the proposed project, indicated in Section 1.1 only.

This document covers the general description of structural framing system, applicable design codes and standards, specific design criteria, design loads and combinations, design methodology and characteristics of construction materials to be adopted for the structures indicated above.

1.2 SITE INFORMATION

1.2.1 Site Location

The plant site is located at 10 km from Manuguru town and 20 km from Manuguru railway station and nearest airport is Vijaywada which is about 220km from site.

1.2.2 Grade level

Finished Graded Level (FGL) for entire plant area shall be at least 1 m above HFL. However FGL will be finalized after topographical/contour survey data considering minimum levelling and grading works.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	7	OF 79

1.2.3 Soil Condition and Ground Water Level & HFL

Type of foundation, depth, safe bearing capacity etc., shall be as per the approved Geotechnical report. HFL of the plot is at RL (+) 65.465 m (based on area boundary survey drawing manuguru TPP- Boundary-4000-1).

1.2.4 Seismic Location

The project site lies in zone III as defined in IS: 1893 (Part 1)-2002. All the structures shall be designed complying with the requirements specified in IS: 1893 (Part-1) -2002 and (Part-4) - 2005.

1.2.5 Wind Pressure

Wind force on structures has been considered as per the provisions of IS: 875 (Part-3) - 1987. The basic wind speed of 44 m/sec at a height of 10m above the ground level and wind assumed to blow in any direction and the most unfavorable condition shall be considered for design.

1.2.6 Reference Level

All elevations shall be marked with reference to Finished Ground Floor elevation of Power House building as EL (±) 0.000m.

In the Boiler, ESP and Chimney Area, paving top shall be at EL(-)0.20 m and main road levels in Boiler Area shall be EL(-)0.20 m.

Transformer yard paving top shall be EL(-)0.10 m .

2.0 REFERENCES, CODES AND STANDARDS

Structural design shall be developed on the basis of the standard codes and documents listed below.

All designs shall generally be prepared in accordance with Bureau of Indian Standards (BIS) codes of practice unless specified elsewhere.

2.1 BIS CODES AND REFERENCES

The analysis, design and construction for structural and civil works shall be in accordance with the BIS codes/standards or equivalent International codes.

2.1.1 EARTHWORK

IS: 1498

Classification and identification of soils for General Engineering Purposes.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 8 OF 79

2.1.2 LOADS

IS: 875	Code of Practice for design loads (other than earthquake) for buildings and structures (All parts)
IS: 1911	Schedule of Unit Weights of building materials
IS: 1893	Criteria for earthquake resistant design of structure (All parts)

2.1.3 FOUNDATIONS AND SOIL ENGINEERING

IS: 1080	Code of Practice for design and construction of shallow foundations on soils (other than raft, ring and shell)
IS: 1904	Code of Practice for design and construction of foundations in soils (General requirements)
IS: 2911	Code of Practice for design and construction of pile foundations (All parts)
IS: 2950	Code of Practice for design and construction of raft foundations
IS: 2974	Code of Practice for design and construction of machine foundations (All parts)
IS: 8009	Code of Practice for calculation of settlement of foundations (All parts)
IS: 9556	Code of Practice for design and construction of diaphragm walls
IS: 11089	Code of Practice for design and construction of ring foundation
IS: 13301	Guidelines for vibration isolation for machine foundations.

2.1.4 REINFORCED CEMENT CONCRETE

IS: 383	Specification for Coarse and fine aggregate from natural sources for concrete
---------	---

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 9 OF 79

IS: 432	Specification for Mild steel and Medium tensile steel bars
IS: 455	Specification for Portland Slag Cement
IS: 456	Code of Practice for plain and reinforced concrete
IS: 458	Specification for pre cast concrete pipes
IS: 1443	Code of practice for laying and finishing of cement concrete flooring tiles
IS: 1566	Specification for Hard drawn wire fabric for concrete reinforcement.
IS: 1786	Specification for high strength deformed steel bars and wires for concrete reinforcement.
IS: 1834	Hot applied sealing compounds for joints in concrete
IS: 2502	Code of Practice for bending and fixing of bars for concrete reinforcement
IS: 3370	Code of Practice for concrete structures for storage of liquids (All parts)
IS: 3414	Code of Practice for design and installation of joints in buildings
IS: 3935	Code of Practice for composite construction
IS: 4326	Code of Practice for earthquake resistant design and construction of buildings.
IS: 4948	Welded steel wire fabrics for general use
IS: 4995	Criteria for design of reinforced concrete bins for storage of granular and powdery materials (All parts)
IS: 5525	Recommendation for detailing of reinforcement in reinforced concrete works
IS: 8112	Specification for 43 grade Ordinary Portland cement
IS: 12269	Specification for 53 grade Ordinary Portland cement

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 10 OF 79

IS:11384	Code of Practice for composite construction in structural steel and concrete
IS:11682	Criteria for design of RCC staging for Overhead water tanks
IS:13920	Code of Practice for ductile detailing of reinforced concrete structures subjected to seismic forces.
BS: 8007	British Standard Code of practice for design of concrete structures for retaining aqueous liquid.

2.1.5 STRUCTURAL STEEL

IS: 800-1984	Code of Practice for general construction in steel
IS: 806	Code of Practice for use of steel tubes in general building construction
IS: 808	Dimensions for hot rolled steel beam, column channel and angle section
IS: 813	Scheme of symbols for welding
IS: 816	Code of Practice for use of metal arc welding for general construction in mild steel
IS: 919	Recommendations for limits and fits for engineering.
IS: 1024	Code of Practice for use of welding in bridges and structures subjected to Dynamic loading
IS: 1161	Steel tubes for structural purposes
IS: 1239	Mild steel tubes, tubular and other wrought steel fittings (all parts)
IS: 1363	Black hexagonal bolts, nuts and locknuts (dia 6 to 39 mm) and black hexagon screws (dia 6 to 24 mm) [All parts]
IS: 1364	Precision and semi-precision hexagon bolts, screws, nuts and locknuts (dia. range 6 to 39 mm). [all parts]
IS: 1365	Slotted counter sunk head screws (dia range 1.6 to 20 mm).
IS: 1730	Dimensions for steel plate, sheet and strip for

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 11 OF 79

structural and general engineering purpose.

IS: 2016	Plain Washers
IS: 2062	Structural steel (fusion welding quality)
IS: 3502	Specification for steel chequered plates
IS: 3589	Seamless or electrically welded steel pipes for water, gas and sewage.
IS: 3613	Acceptance tests for wire-flux combinations for submerged-arc welding of structural steels.
IS: 4000	Code of Practice for High strength bolts in steel structures
IS: 4759	Hot dip zinc coatings on structural steel and other allied products
IS: 4923	Hollow Steel sections for structural use
IS: 7215	Tolerances for fabrication of steel structures
IS: 7280	Base-wire electrodes for sub-merged arc welding of structural steels
IS: 8500	Structural steel - micro alloyed (medium and high strength qualities).
IS: 8640	Recommendations for dimensional parameters for industrial building
IS: 9178	Criteria for design of steel bins for storage of bulk material (All parts).
IS: 12843	Tolerances for erection of steel structures

2.1.6 MASONRY

IS: 1077	Specification for Common Burnt Clay Building Bricks
IS: 1905	Code of Practice for structural use of unreinforced masonry
IS: 2185	Specification for Concrete Masonry units (All parts)
IS: 2212	Code of Practice for brickwork

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 12 OF 79

IS: 2185

Concrete Masonry units (All parts - Hollow & Solid concrete blocks)

IS: 4860

Specification for Acid Resistant Bricks

IS: 12894

Specification for Pulverized Fuel Ash (Fly Ash) Lime Bricks

2.1.7 DOORS, WINDOWS AND VENTILATORS

IS: 1038

Steel doors, windows and ventilators

IS: 1361

Steel windows for industrial buildings

IS: 1948

Aluminium doors windows and ventilators

IS: 1949

Aluminium windows for industrial building

IS: 2835

Transparent sheet glass for glazing and framing purposes

IS: 3103

Code of practice for Industrial ventilation.

IS: 3548

Code of practice for glazing in buildings

IS: 3614

Specification for Fire check doors.

IS: 4351

Specification for Steel door frames.

IS: 6248

Metal rolling shutters and rolling grills.

2.1.8 ROOF AND FLOORING

IS: 809

Rubber flooring materials for general purposes

IS: 1195

Bitumen mastic for flooring

IS: 1237

Cement concrete flooring tiles

2.1.9 WATER PROOFING

IS: 1322

Bitumen felts for waterproofing and damp proofing

IS: 1346

Code of practice for waterproofing of roofs with bitumen felts

IS: 3067

Code of practice for general design, details and preparatory work for damp proofing and water proofing of buildings.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 13 OF 79

2.1.10 WATER SUPPLY, DRAINAGE AND SEWERAGE

IS: 1172	Code of basic requirements for water supply, drainage and sanitation
IS: 1742	Code of practice for building drainage
IS: 2065	Code of practice for water supply in buildings
IS: 5329	Code of practice for sanitary pipe work above ground for buildings
IS: 12251	Code of practice for Drainage of Building Basement

2.1.11 MISCELLANEOUS

SP-6	Handbook for Structural Engineers (all parts)
SP-7	National Building Code of India
SP-16	Design Aids for reinforced concrete to IS: 456-1978
SP-20	Handbook on masonry design and construction
SP-22	Explanatory handbook on codes on earthquake engineering (IS 1893-1975 and IS: 4326-1976)
SP-24	Explanatory handbook on Indian Standard code of Practice for plain and reinforced concrete (IS: 456-1978)
SP-25	Handbook on causes and prevention of cracks in buildings
SP-32	Handbook on functional requirements of industrial buildings
SP-34	Handbook of concrete reinforcement and detailing (SCIP)
SP-35	Handbook on Water Supply and Drainage
SP-38	Handbook on Typified designs for structures with Steel roof trusses (With & without cranes)
SP-40	Handbook on Structures with Steel Portal frames (without cranes)

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 14 OF 79

SP-47	Handbook on Structures with Steel Lattice Portal frames (without cranes)
SP-64	Explanatory handbook on IS Code of Practice for Design loads (other than earthquake) for buildings and structures (Part 3 – wind load IS 875 – Part 3 – 1987)
IRC: 15	Code of Practice for construction of concrete roads
IRC: 19	Standard specification and Code of Practice for Water Bound Macadam
IRC: 36	Recommended Practice for the Construction of Earth Embankments for Road Works
IRC: 37	Guidelines for the design of flexible pavements
IRC: 101	Guidelines for design of continuously reinforced Concrete pavement with elastic joints
IRC: SP - 042	Guidelines on Road drainage

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 15 OF 79

3.0 LOADS AND LOAD COMBINATIONS

All structures will be designed for the most critical combinations of dead loads, imposed loads, equipment loads, crane loads, steam piping (static and dynamic) and other piping loads, wind loads, seismic loads, temperature loads and any other loading condition which can occur during the design life of the facility.

3.1 DEAD LOADS (DL)

Dead loads consist of the weights of the structure complete with floors, roof, finishes, fixtures, partitions, wall panels, etc.

3.1.1 The following unit weight of material shall be considered for computation of loads. Loads given in IS: 875 (part-I) shall be made use of for material not listed below.

Materials	Unit weight
Plain cement concrete	24 kN/m ³
Reinforced cement concrete	25 kN /m ³
Structural steel	78.5 kN /m ³
Brick work	19 kN /m ³
Cement plaster	21 kN /m ³
Floor Finish	24 kN /m ³
Coal	12 kN /m ³
Fly Ash	16 kN /m ³
Bottom Ash	16 kN /m ³

:

3.1.2 Following will be considered for evaluation of dead loads:

- Load of RCC slab wherever concrete floors are provided
- Floor finish of 40/50 mm laid over RCC Slab
- Other area flooring will consist of removable electro forged grating/ chequered plate.
- Beams & Columns as per actual size
- Wall cladding loads.
- Self-weight of supporting structure/facilities

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 16 OF 79

3.2 IMPOSED LOADS (IL)

The loads considered as imposed loads are live loads, dust loads, minor equipment loads, cable trays, small pipe racks / hangers (not exceeding 2.5 kN/m²), erection loads, operation / maintenance loads and loads produced by personnel, movable equipment and other items placed on the structure, but not permanently attached to it. Imposed loads for design at various floors in different areas will generally be considered as given below.

Imposed/Live loads will consist of uniform live loads and equipment live loads. Uniform live loads are assumed unit loads which are sufficient to provide for movable and transitory loads, such as the weight of people, portable equipment and tools, equipment, or parts which may be moved over or placed on floors during maintenance operations. These uniform live loads will not be considered on floor areas which will be permanently covered with equipment. In the absence of equipment load, the predefined LL to be considered for whole area for the design of foundation, column & mainframe beams. The floor beams may be designed for the equipment load.

Equipment live loads are calculated based upon the actual weight and size of the equipment and parts to be placed on floors during dismantling and maintenance or to be temporarily placed on or moved over floor during installation. Floors and supporting members, which are subject to heavy equipment loads, will be designed on the basis of the weight of the equipment or specifically defined loads and the erection loads wherever required. Each member in the floor which may carry these loads will be designed for the heaviest piece or pieces of equipment arranged in the most critical position. These loads will also be compared with the superimposed loads given below. Higher of the two will be adopted for analysis and design.

Steam Piping Load: The loads superimposed on structure by piping hangers and at the restraint points will be considered. However, pipe dynamic forces at hanger location / restraint points will not be considered to act simultaneously, in that direction with seismic forces.

POWER HOUSE BUILDING

S. NO.	AREA	LOAD (KN/m ²)
1.	GROUND FLOOR	
	Unloading Bay	30 KN/m ²
	Other areas	15 KN/m ²
2.	Mezzanine Floor	15 KN/m ² plus hung loads
3.	Operating Floor	
	TG Lay-down Area	30 KN/m ² plus hung loads or actual load furnished by equipment supplier whichever is higher

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 17 OF 79

	Rotor removable Area	30 KN/m ² plus hung loads or actual load furnished by equipment supplier whichever is higher. Rotor removal area beams shall also be checked for half the rotor load at the center of the beam
	Other areas	15 KN/m ² plus hung loads
4.	Heavy equipments	As per actual loading

Control building

S. NO.	AREA	LOAD (KN/m ²)
1.	Control room floor	10 KN/m ² plus hung loads
2.	Switch gear floor	15 KN/m ² plus hung loads
3.	Cable spreader floor	7.5 KN/m ² plus hung loads

Mill Building

S. NO.	AREA	LOAD (KN/m ²)
1.	Ground Floor	25 KN/m ²
2.	Feeder , tripper floor	15 KN/m ² + hung loads + 0.5(dust load)

Auxiliary Buildings

S. NO.	AREA	LOAD (KN/m ²)
1.	Ground Floor	10 KN/m ²
2.	Cable Spreader Floor	7.5 KN/m ²
3.	Pump House Operating Floor	15 KN/m ²
4.	Switchgear room	15 KN/m ²
5.	Non-operational area	As per IS:875(part 2)
6.	MCC room	15 KN/m ²
7.	Battery room	10 KN/m ²
8.	Air washer room , A/C plant	10 KN/m ²
9.	AHU room	10 KN/m ²
10.	All other Floors/grating /stair	5 KN/m ²

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 18 OF 79

Non Plant Buildings

S. NO.	AREA	LOAD (KN/m ²)
1.	Floors with equipment	10 KN/m ²
2.	All other floors	5 KN/m ²

Underground Structures/Trenches/pits

Minimum surcharge shall be 15 kN/Sq.m. For structures in vicinity of roads and heavy vehicular movement surcharge shall be considered as applicable as per loading specified elsewhere in this specification. Trenches/pits inside building shall be designed for a surcharge equal to Live Load intensity of Ground Floor or 15 kN/Sq.m whichever is greater. In Boiler area and other outdoor areas within Power Block, the minimum surcharge shall be 20 kN/Sqm.

Covers for Trenches / Channels

Self-weight of top slab and a uniformly distributed load of 4.0 kN/Sqm on each panel, or one 0.75 central point, whichever is critical, shall considered. At road crossings, the covers shall be designed for vehicular movements as per IRC standards

Roads

Design of roads shall be in accordance with Indian Road Congress standard IRC-37.

Road Culverts and its allied structures including R.C.C. Pipe Crossings & Road Crossing of Trenches

Road culverts and its allied structures including R.C.C. Pipe Crossings & Road Crossing of Trenches shall be designed for Class `AA' loading (wheeled and tracked both) and to be checked for Class `A' loading as per IRC standards.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 19 OF 79

GENERAL

S. NO.	AREA	LOAD (KN/m ²)
1.	Stairs, Landings and Balconies	5.0 KN/m ²
2.	Toilets	2.0 KN/m ²
3.	Chequered plates, grating floors etc	5.0 KN/m ²
4.	RCC Floors (General)	5.0 KN/m ²
5.	Flat Roofs (Accessible)	1.5 KN/m ²
6.	Flat Roofs (Non- Accessible)	0.75 KN/m ²
7.	Inclined Roofs	As per IS: 875 (Part-2)
8.	Walkways (General)	5.0 KN/m ²
9.	Walkways of Conveyor Galleries	5.0 KN/m ²

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 20 OF 79

3.3 WIND LOAD

Wind loading will be in accordance with Indian Standard Code IS:875 (Part 3) for a basic wind speed of 44 m/sec. upto a height of 10 metres above mean ground level. Terrain Category-2 shall be considered for all structures.

Risk coefficient (k1) shall be considered as 1.07 for all structures

3.4 SEISMIC LOADS

The lateral forces will be established in accordance with the recommendations of IS:1893-1984 of Indian Code of practice. The site falls in Zone- III as identified in the map in IS:1893-2002. Analysis and design of structures shall be carried out accordingly taking into consideration the factors related to soil characteristics and importance of the structure together with the basic seismic co-efficient as per provision of Indian code.

Importance factor and response reduction factor shall be taken as per IS:1893(part I & IV).

Response spectrum method shall be used for seismic analysis as per IS : 1893 .

3.5 EARTH PRESSURE LOADS

Earth pressure for all underground structures shall be calculated using coefficients of earth pressure at rest, coefficient of active or passive earth pressure (whichever is applicable). However, for design of substructure of pump house, cold water basin of cooling water and underground liquid storage tanks earth pressure at rest shall be considered.

In addition to earth pressure and ground water pressure, etc., surcharge load shall also be considered for the design of all underground structures including channels, sumps, cable & pipe trenches, etc., to take into account the vehicular traffic in the vicinity of the structure. Intensity of Surcharge Load shall be as described elsewhere in this specification.

3.6 TEMPERATURE LOADS

The effect of temperature loads shall be considered for design of structural frames. For temperature loading calculation the temperature variation shall be considered as 2/3rd of the difference in the mean of the daily maximum ambient temperature during the hottest month of the year (OC) and mean of the daily minimum ambient temperature during the coldest month of the year (OC). The structure shall be designed to withstand stresses due to 50% of the total temperature variation. Expansion and contraction due to changes of temperature of materials of structure

shall be considered and adequate provision shall be made for the effects produced as

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 21 OF 79

per provision in the relevant IS codes.

Mean Daily minimum ambient temperature during coldest month of the year = 11.5° C

Mean Daily maximum ambient temperature during hottest month of the year = 45.1° C

3.7 EQUIPMENT LOAD

i) Loadings (both static and dynamic) of major equipments, including boiler, turbine-generator, boiler feed pumps, feed water heaters, de-aerator, PA, FD & ID fans, Coal Mill obtained from the manufacturer's certified drawings of the specified equipment to be furnished. Where design of structures supporting minor equipment other than those included above has to proceed, the loadings will be estimated from similar jobs or catalog data.

ii) All equipment, tank and piping design loadings will include Hydraulic Testing loads.

iii) Air and gas duct loadings will include weight of insulation, duct attachments, dust accumulation loads, seismic, wind and other loads as applicable.

iv) Crane girders and supporting columns will be designed for vertical and horizontal forces (including impact forces) as developed from the crane weights and wheel loads. Unless otherwise specified, the vertical and horizontal loadings will conform to the applicable sections of the IS specifications.

v) Weight of equipments, ducts, tanks, pipes, conduits etc. supported by structure shall include maximum possible loading conditions i.e. flooded material contents and associated impacts, test loadings, anchorage and constraint effects.

vi) All structural components shall be designed to accommodate anticipated concentrated loads which will or may be applied during the life of the plant.

Where both concentrated and uniform loads cannot act simultaneously, the structure or component shall be analyzed for both conditions of loading and shall be designed for most critical condition.

viii) Lay down areas in the Turbine Hall shall be investigated for concentrated loads resulting from equipment components to be stored during erection and maintenance operation. Where live load allowance is inadequate to permit storing of such equipment components, the design live load shall be increased to permit such use or the area shall be restricted by identifying lay down areas for specific components, each area to be identified by permanent marking.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 22 OF 79

3.8 CRANE, MONORAIL AND ELEVATOR LOADS

Crane girders and supporting columns shall be designed for vertical and horizontal forces (including impact forces) as per crane vendor data. All lifting beams, monorails shall have design loads increased for impact factor. Vertical impact force and surge force in lateral and longitudinal direction shall be taken as per following.

3.8.1 Crane loads

- i) For vertical force, an impact factor of 25% of the maximum crane wheel load.
- ii) A lateral crane surge of 10% of the weight of the trolley plus the lifted load applied at the top of each rail..
- iii) A longitudinal surge of 5% of the maximum static wheel loads of the crane applied at the top of the rail in the longitudinal direction.

3.8.2 Monorail loads

- i) Impact factor of 10% of lifted load hoist for rail and support design
- ii) Impact factor of 25% of the lifted load for electrical hoist for rail and support design

3.8.3 Elevator loads

- i) 100% of the lifted load plus the equipment weight for the elevator support beams.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 23 OF 79

3.9 Load Combinations

While designing consideration shall be given to the following load combinations :

- i) DL + LL
- ii) DL + LL + PL + Equip (+/-) TL
- iii) DL + LL + PL + Equip + Cb + CtLA(+/-) CS (+/-) TL
- iv) DL + LL + PL + Equip + Cb + CtLB(+/-)CS (+/-) TL
- v) 0.9DL(+/-)EL (for DL only) (+/-) TL
- vi) 0.9DL (+/-) WL1 (+/-) TL
- vii) 0.9DL (+/-)WL2 (+/-)TL
- viii)DL +* LL + PL + Equip + Cb + Ct(+/-) EL (+/-)TL(* Appropriate portion of LL which is considered for working out EL shall only be taken)
- ix) DL + LL + PL + Equip + Cb + CtL1(+/-) (CS1+WL1(+/-)TL
- x) DL + LL + PL + Equip + Cb + CtL1(+/-) (CS1+WL2) (+/-)TL

Where the above loads are :

DL = Dead load of structures, floors, walls etc.
LL = General live load on floors
PL = Pipe Load
Equip = Equipment loads
Cb = Crane Bridge
Ct = Crane trolley positioned at middle of bridge
CtLA = Crane trolley + Load near one row
CtLB = Crane trolley + Load near other row
CtL1 = Crane trolley + Half load lifted at centre of bridge
CS = Crane surge for full load
CS1 = Crane surge for half load lifted
WL1 = Wind load from left to right
WL2 = Wind load from right to left
EL = Earthquake load
TL = Temperature load

Appropriate allowable increase in permissible stresses as per IS codes, may be taken only under normal loads along with wind and seismic conditions. However, members which are designed primarily to resist wind, no increase in wind permissible stresses will be permitted. Applicable load factors to be used for design of RCC structures by Limit State Method as per IS:456.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 24 OF 79

3.10 LOAD COMBINATIONS FOR UNDERGROUND STRUCTURES

Following loading conditions shall be considered in addition to the loading from superstructure for the design of sub structure of pump house, channels, sumps, tanks, reservoirs, trenches and other underground structures.

Only liquid pressure from inside and no earth pressure and ground water pressure and surcharge pressure from outside (applicable only to the structures which are liable to be filled with water or any other liquid).

Earth pressure, surcharge pressure and ground water pressure from outside and no water pressure from inside.

Base slab of the pump house shall be designed for the condition of different combinations of pump sumps being empty during maintenance stages with ground water table up to the finished grade level. Intermediate dividing piers of pump sumps and partition walls in channel shall be designed considering water on one side only and the other side being emptied for maintenance.

Design shall also be checked against buoyancy due to ground water during construction and operation stage. Minimum factor of safety as per IS:3370 against buoyancy shall be ensured considering empty condition ignoring superimposed loads.

3.11 SPECIAL STRUCTURES

The following densities shall be considered for design of coal bunkers:

- a) For volume calculations : 8.0 kN/cum
- b) For Structural design : 12.0 kN/cum

Coal bunker shall be designed as per criteria specified in IS:9178 (Part I&II)

4.0 DESIGN METHODOLOGY

Wind and seismic forces shall not be considered to act simultaneously.

For the design of main plant structures during seismic condition, the Deaerator Feed

Water Tank shall be considered full up to operating level. However, for other load combinations, Deaerator Feed Water Tank in flooded condition shall be considered.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 25 OF 79

`Lifted Load' of crane shall not be considered during seismic condition.

For design of all underground structures/foundations, ground water table shall be considered at the Finished Ground Level..

In Turbine Bay, horizontal wind girders between A-row and B-row columns must be provided below Mezzanine and Operating floor at gable ends to transmit wind load from gable columns.

PTFE bearing shall be provided where horizontal loads not to be transferred.
For calculation of seismic load, equipment load shall be considered as Dead Load.

Gratings / chequered plates shall not be considered as restraining members for compression flange of beams/girders. Diaphragm action shall also be not considered in design. Adequate horizontal bracings to be provided.

4.1 REINFORCED CONCRETE STRUCTURES

4.1.1 GENERAL

Reinforced concrete structures will be moment resisting frames along both longitudinal & transverse directions. The suspended slab will be considered as continuous over secondary beam and will not form part of the framing system. RCC structures/members will be designed as per the provisions of IS: 456 using limit state method, unless use of working stress method is specifically mentioned elsewhere in this document.

Design strength of materials and design loads shall be calculated using appropriate partial safety factors over characteristic strength and characteristic loads as per IS: 456.

Mix design concrete will be used for all areas other than lean concrete work and plain cement concrete work where nominal/volume mix may be permitted.

Water retaining RCC Structures will be designed in accordance to IS: 3370 (Code of practice for concrete structures for the storage of liquids) by Working Stress Method.

The grade of concrete for various structures shall be as follows;

- Mass concrete filling
- PCC below T G Foundations, Fan foundations

M7.5

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 26 OF 79

	and all vibratory foundations / Screed concrete	M10
➤	PCC below Paving(general) incl plinth protection	M10
➤	RCC in grade slabs	M25
➤	Boiler area paving	M20
➤	RCC for Super Structure works in structural Steel buildings / Trench slab and wall	M25
➤	RCC in foundations/ Water retaining Structures	M25
➤	RCC for Super Structure works in RCC building	M25
➤	RCC for T G raft, Mill, BFP & fan foundations	M30
➤	Precast RCC Trench Covers	M25
➤	Encasement of Base plate/Steel columns/ Wall beams	M20
➤	RCC for TG top deck and columns	M35
➤	Drain/cable trench	M25

Minimum cement content, maximum water cement ratio and minimum grade of concrete shall be considered as per IS: 456-2000 for structures not mentioned above.

Minimum cover to reinforcement shall be as per Table 16 of IS: 456-2000 for mild exposure condition. Minimum fire rating of 2 hours shall be considered where fire hazard is expected and accordingly minimum cover shall be increased if required to meet the requirements as per Table 16A of IS:456-2000.

MATERIALS

Cement: Ordinary Portland cement (Grade 53) of approved manufacturer conforming to IS: 12269 and Ordinary Portland Cement (Grade 43) conforming to IS 8112 will preferably be used. However other types of cement such as Portland slag cement conforming to IS: 455 & Portland pozzolana cement confirming to IS: 1489 may also be used except for in TG Foundation top deck and sub-structures including foundation raft, major machine foundation like PA/FD/ID FANS, MILLS,BFP etc where OPC grade 53/43 shall necessarily be used.

Reinforcing Steel: Reinforcing steel will be TMT bars of grade Fe-500 conforming to IS: 1786.

Aggregates: Coarse aggregate for concrete will be chemically inert, hard, strong

durable against weathering, of limited porosity, and free from deleterious materials. It

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 27 OF 79

will be properly graded. Coarse aggregates will be either crushed gravel or stone. Aggregates will meet the requirement of IS: 383.

Admixtures: Plasticizers-cum-retarder type admixture will generally be added to concrete for promoting workability in addition to retard setting time for mass concreting work.

Water: Water used for cement concrete, mortar, plaster, grout curing, washing of coarse aggregates, soaking of bricks etc. will be clean and free from oil, acids, alkalis, organic matters or other harmful substances in such amounts that may impair the strength or durability of the structure.

The following minimum thickness of the structural elements shall be followed:

- Suspended floor / slab / walkways / canopy slabs, etc 125 mm
- Ground floor slab (non-suspended) 150 mm
- Water Retaining slabs / walls 200 mm
- Cable / pipe trenches / underground pits /
Launder walls and base slab 125 mm
- All footings (including raft foundations) 300 mm
- Parapets 125 mm
- Sunshades at edge 75 mm
- Pre cast louvers / fins 50 mm
- Pre cast trench cover slabs / floor slabs / louvers 75 mm
- Paving 100 mm
- Basement walls and base slab 200 mm
- Silo / bin walls 200 mm
- Underground reservoir
- Below ground water table 200 mm
- Above ground water table 150 mm

Minimum heights for pedestals for steel columns shall be as follows:

- i) Top of pedestals for building structures will be kept at a lower level so that column base plate together with gussets and stiffeners remain below finished floor level

(FFL). The column bases as well as column section shall be encased in concrete above FFL as per following:

- a) Open area : 300mm above paved level
- b) Covered area : 150mm above FFL

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 28 OF 79

ii) Stairs and ladder pedestal will be kept 200mm above the FFL

iii) Pedestals to steel columns for equipment structures:

- | | |
|------------------------------|--|
| a) Equipment in open area | : as required (minimum 300 mm) |
| b) Equipment in covered area | : as required (minimum 150 mm) |
| c) Structures and equipment | : as per vendors data
supplied by vendor subject
to min as specified above |

4.1.2 FOUNDATION AND UNDERGROUND STRUCTURES

4.1.2.1 Foundation for all main plant structure i.e. Power House Building, Boiler, ESP, Mill and Bunker Bay, Transformer Foundations, Air compressor, and other auxiliary buildings shall be decided based on loading arrangement, load intensity and soil strata. Design of foundation at various levels shall be dependent upon the safe bearing capacity at that level and on the basis of recommendation furnished in the Geotechnical Investigation report.

Foundations will be designed for the most critical combinations of forces and moments, resulting from all possible combinations of the various loading from the structural system. No major foundations will rest on filled up ground. The effect of water table will be considered and the foundation will be checked for overturning for minimum and maximum vertical loads. The foundation sections will be sized and reinforced adequately for bending moments and shear stresses.

4.1.2.2 All foundations including machine/equipment foundations will be of RCC block/frame foundations as the case may be. All foundations will be designed in accordance with relevant parts of IS: 2974 and IS: 456 by limit state method. Raft foundation will be designed as per IS: 2950.

4.1.2.3 For design of Foundations and underground structures including trenches etc., ground water level shall be considered up to the finished grade level.

4.1.2.4 Stability : The following minimum safety factors for stability checks of foundations shall be used:

- | | |
|-------------------|-----|
| 1. Overturning | 1.4 |
| 2. Sliding | 1.4 |
| 3. Uplift | |
| a) Normal loading | 1.4 |

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 29 OF 79

b) Hydrostatic forces 1..2

Where dead load provides restoring forces, only 0.9 times dead load shall be considered. Imposed loads shall not be considered as the restoring force.

4.1.2.5 Minimum cover to Foundation Bolts

Minimum distance from the centerline of foundation/anchor bolt to the edge of pedestal shall be maximum of the following:

Clear distance from the edge of base plate/base frames to the outer edge of the pedestal shall be minimum 50mm.

Clear distance from the face of pocket to the outer edge of pedestal shall be 75mm.

Clear distance from the edge of sleeve of anchor plate to the edge of pedestal shall be 75mm.

4.1.2.6 Permissible settlement of Foundation

For open foundations, the permissible settlement and differential settlement shall be governed by IS: 1904 and IS: 8009. However, total settlement will be restricted to the following.

a) Foundations for main power house columns, Boiler, Mills, bunker, TP's : 25mm

b) Foundation for other structures including ESP with Isolated/strip footing of width up to 6.0M : 40mm

c) Foundation for other structures with Footings greater than 6.0M (raft) : 75 mm

4.1.2.7 Levelling and grading: Each layer of filling shall be watered and thoroughly compacted with proper moisture content and such equipment's as may

be required to obtain a minimum of 95% of its maximum dry density as determined by standard Proctor's test as per IS: 2720 part-VII or 85% of relative density as per IS:2720 part-XIV as specified. Moisture content of the fill material shall be controlled near optimum moisture content during compaction.

4.1.2.8 Backfilling: Backfilling around foundation and bottom of pipes, thrust blocks etc shall be carried out with approved material in layers not exceeding 30 cm thickness and each layer shall be compacted to 90% standard proctor density for cohesive soil and to 75% of relative density for non-cohesive soils.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 30 OF 79

4.1.3 TANK FOUNDATIONS

The Storage tanks/Day tanks will be resting on hydraulically compacted clear river sand, in layers of 500 mm maximum thickness, topped with 150 thk PCC. PCC layer will be topped with 50 thk. Anti-corrosive asphalt layer, which in turn is topped with 50 thk. Premix carpet. The entire sand fill along with toppings will be confined within a RCC ring beam of appropriate design.

4.1.4 MACHINE FOUNDATIONS

This section outlines the design philosophy and construction aspects of foundations for the following equipments;

- ✓ ID/FD/PA/SEAL AIR Fan Foundations & TG Foundation
- ✓ Boiler Feed pump foundations,
- ✓ Bowl Mill foundations and
- ✓ Miscellaneous Machine foundations.

4.1.4.1 For the foundations of TG & Fans (ID, FD, PA & Seal Air etc.), Boiler feed pump, Bowl Mill, detailed static and dynamic analysis will be performed. The static analysis will include operating conditions load cases and abnormal loads like, maximum unbalance and seismic forces. Unbalanced loads for normal operating condition as given by machine manufacturers or as specified in IS: 2974 whichever is more conservative shall be used. Vibration isolation system shall not be provided in any of rotating foundation except for ID fan foundation

4.1.4.2 The dynamic analysis will consist of free vibration analysis and forced vibration analysis. Frequency separation criteria and amplitude criteria as laid down in IS: 2974 and/or DIN 4024 and/or VDI 2056 or as required by the machine manufacturer will be satisfied. RCC design will be done by working stress method for all machine foundations as per IS: 2974. Minimum reinforcement will be governed by the requirements specified in IS: 2974 as well as IS: 456.

4.1.4.3 All block foundation supporting rotating equipments and resting on soil will be designed using the elastic half space theory and/or Barkan's method. The mass of the RCC block will not be less than 2.5 times the mass of the machine. Dynamic analysis will be carried out to calculate natural frequencies in all the modes including coupled modes

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 31 OF 79

and to calculate vibration amplitudes. Frequency and amplitude criteria as laid down in the relevant codes and/or by machine manufacturer will be satisfied. Minimum reinforcement will be governed by the requirements specified in IS: 2974 and IS: 456.

4.1.4.4 The analysis and design of machine foundations will be carried out to ensure the following.

- Compliance with the manufacturer's requirements.
- No resonance phenomenon of a disturbing nature to machine operation should exist at the normal running speed.
- Calculations to be performed for dynamic as well as static cases for reinforced concrete block type pedestals.

4.1.4.5 Bowl mills shall be supported on conventional block type R.C.C foundations. All machine foundation shall be separated from adjoining building / foundations. Isolation joints shall be given all round to isolate the machine foundation from the grade slab..

4.1.4.6 Foundation Sizing: The outline plan dimensions of foundations as given by the machine supplier will be adopted. The height of foundation will be selected after taking into consideration soil strata and operating level of the machine. The eccentricity of common CG of machine and foundation with respect to the centroid of base area should not exceed 5% of the corresponding base dimensions of foundation.

4.1.4.7 For other types of machines, most suitable type of foundations will be provided. For the foundations supporting minor equipment weighing less than one ton or if the mass of the rotating parts is less than one hundredth of the mass of the foundation, no dynamic analysis is necessary. Foundation for pumps, and minor rotating equipment etc., are usually in the form of solid block foundations, resting on the ground or on a floor of the building.

At such machine supports, floor may be thickened and extra reinforcement provided. Rubber or neoprene pads under some of these machines to reduce transmission of vibrations to the supporting floor shall be provided if required.

4.1.5 LIQUID RETAINING STRUCTURES

RCC water retaining structure like storage tanks, reservoirs, etc., shall be leak proof and designed as un-cracked section with limiting steel stresses in accordance with IS: 3370 (Part I to IV) by working stress method.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 32 OF 79

Water channels and substructure of pump houses shall be designed as cracked section with limiting crack width to 0.1mm and limiting steel stresses as per IS: 3370 (Part I to IV) by working stress method for concrete face away from water/liquid. For faces in contact with water/liquid the structure shall be designed as uncracked section in accordance with IS:3370 (part 1 to IV) by working stress method.

All water retaining/ storage structures shall be designed assuming liquid upto the height of wall irrespective of provision of any over flow arrangement. Pressure relieving devices may be used and 50% release in water uplift pressure through pressure release valves may be considered in design. PRV shall not be used for clarified water tank. In all liquid structures, PVC water bars shall be provided at each construction/ expansion joint. The sequence of construction shall also be specified on drawings showing construction joints.

Screed layer of concrete grade M10 and of minimum 100 mm thickness shall be provided below all water retaining structures.

All underground water retaining/conveying system structures shall have plasticiser cum waterproofing cement additives conforming to IS:9103. In addition, limits on permeability as given in IS:2545 shall also be met with. The concrete surface of these structures in contact with soil shall be provided with minimum two coats of bituminous painting of grade 85/25 conforming to IS:702 @ 1.7 kg/sqm (minimum) for water / damp proofing. Storm water drains shall not be provided with bituminous paint and weep holes also shall not be provided in storm water drains.

4.1.6

Raw Water Reservoir: The capacity of raw water reservoir shall be for 7 days with minimum capacity of 6.00 Lakhs cu.m. Shape, size and detail of the same shall be as per approved drawings. The reservoir shall be provided with a free board as per requirements of IS: 10635, but in no case, the same shall not be less than 1000 mm. The reservoir shall have two compartments with separate inlet and outlet arrangement. The reservoir embankment shall be made in earthwork with side slopes 1V : 2H (minimum). The reservoir embankment shall be designed and constructed as an earthen dyke founded on natural ground with proper foundation. The entire area, top soil shall be increased to the required level as per actual conditions to totally removal of all vegetation, organic matters, roots, soft spots etc. Required slush removal sump, provision for deep sump shall be provided in the pumping suction to ensure the pumping head. Also, a suitable spillway arrangement shall be provided to take care of any heavy storm event. The bund shall have adequate width on top to form the road for vehicle movement with minimum width as 4.0 m. bituminous road shall be constructed as per IRC. On the down

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 33 OF 79

stream slope of the embankment, turfing shall be provided with a provision of Toe drain. The bund with impervious geo-membrane (LDPE 500 micron thick) layer on water contain face including base. 150 mm thick sand blanket is recommended below the geo-membrane bottom as a cushion. The reservoir shall be provided with 50 mm thick precast concrete tiles of M20 grade concrete over LDPE film / sand planked lining. The protective layer over LDPE shall be provided over entire bed and side slopes. Material to be used for bund construction shall be as per IS: 1498. Top layer of reservoir basin sub grade shall be compacted to at least 95% of Standard Proctor density by vibro compaction equipment or by any other suitable equipment

4.2 STEEL STRUCTURES

4.2.1 MATERIALS

Structural Steel: Structural steel will be straight sound, free from twists, cracks, flow, laminations and all other defects. Structural steel shall confirm to IS:2062 for rolled members or plates. Structural steel shall conform to Grade A of IS 2062 for rolled steel members or plates up to 20mm thickness. For plates from 20mm to 40mm thickness steel conforming to Grade BR (killed and rolling normalized) of IS 2062. For plates above 40mm thickness steel conforming to Grade BR (killed and furnace normalised) of IS 2062.

Material: Structural steel shapes, plates, and appurtenances for general use will conform to Indian Standards IS: 800 with minimum yield strength of 250 MPa. Connection bolts will confirm to relevant IS codes.

Steel Grating: All indoor gratings shall be electro forged type and outdoor gratings shall be welded type. Minimum thickness of grating shall be 40mm for indoor installation and 32mm for outdoor installation. The opening size shall not be more than 30mm x 100mm. The minimum thickness of the main bearing bar shall be 6 mm. All gratings shall be hot dip galvanized @ 610 gm/sqm.

Guard rail /Handrail: For powerhouse building upto operating floor + half landing, main stair & lobby shall have 40mm diameter stainless steel railing with minimum 3mm thick SS posts & decorative minimum 3mm thick seamlessly joined SS handrails. Stainless steel pipe handrail in shall be of approved design to meet the functional requirement as well as very good aesthetic appearance. For any other RCC stairs of non-plant buildings 20mm square MS bar post with suitable MS flat and anodized aluminium handrails are to be provided. For any other floor of power house building, plant & non

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 34 OF 79

plant buildings unless otherwise indicated in the specification the post and handrails of stairs, railing, etc will be 32mm nominal bore GI pipes of medium grade conforming to IS: 1161 / IS 1239.

Chequered Plate: Chequered plate shall conform to IS: 3502 and shall be minimum 6 mm thickness over plane. Steel for chequered plates shall conform to Grade 'A' of IS: 2062.

Stainless Steel: Stainless steel liner in the Coal Bunkers will be 3.15 mm thick & of grade AISI – 304, Finish Grade 2B (Cold Rolled, Annealed & Pickled and Skin passed) will be provided on the inner faces, Hoppers and mouth of the Hoppers, without allowing any projections in coal flow path. while coal bunker will be made of MS plate.

4.2.2 FRAMING

All steel framed structures shall be either “rigid frame” or “simple space frames” or a combination of two.

Lateral forces shall be resisted by stiff jointed moment connections in rigid frame. The column bases shall generally be fixed to concrete foundation pedestal by providing moment resistant base detail.

Simple space frame design utilizes single-span beam systems, vertical diagonal bracing at main column lines and horizontal bracing at the roof and major floor levels. Most of the plants' steel buildings shall be designed as simple space frame structures. The turbine building design shall be a combination of rigid frame in transverse direction and simple frame in longitudinal direction.

Pipe rack shall consist of rigid main frame in transverse direction spaced longitudinally as required. In longitudinal direction, pipe rack shall be divided into sections of suitable length with an anchor bay. The main transverse frames shall be connected with longitudinal beams which will transmit horizontal forces to braced anchor bays. The pipe and cable rack bridge structure shall be adequately rigid to carry the forces from pipelines at anchor points without undue deflection so that pipelines are really anchored at the anchor points.

Concrete floors shall be considered to provide continuous lateral support to the top (compression) flange of the support beams. Suitable shear connectors shall be welded to the top of the top flange of all secondary beams to ensure the lateral support.. Grating/chequered plate floor shall neither be considered to provide lateral support to the top flange of supporting beams nor to provide a shear diaphragm. Adequate lateral support and horizontal bracing shall be provided as required.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 35 OF 79

Floors for vibrating machines of all kind together with supporting framework shall be adequately braced in both horizontal and vertical planes. Floors or structure supporting mechanical equipment shall be designed to minimize vibration, avoid resonance and maintain alignment and level.

Columns shall be designed to support the load combination which produces the maximum stress ratio. Exterior columns shall be designed to resist wind moments between braced elevations as appropriate. Columns shall also be designed to resist moments caused by discontinuous vertical bracing work points.

4.2.3 CONNECTIONS

Shop connections will be by welding, preferably by submerged arc welding. Field connections for light members such as purlins, girt and inaccessible beams, will be done by MS bolts with nuts. All other connections will be designed with welding / high strength friction grips bolts, as necessary.

IS: 816 and IS: 9595 shall be followed for welding of structures.

Connection of vertical bracings with connecting members and diagonal truss members shall be designed for full tensile capacity of the bracings.

Size of fillet weld for flange to web connection for built up column section will be as follows:

Full shear capacity for box section.

80% of full shear capacity or actual shear (if indicated in drawings) or 0.5 times of the web thickness whichever is more for I section. Weld will be double fillet.

All welds will be continuous. The minimum size of fillet weld will be as per relevant IS code.

Shear connections shall be designed for 75% of section strength for rolled sections and 80% of section strength for built up section or rolled section with cover plates.

Design shear force should be more than actual shear.

Moment connections between beam and column will be designed for 100% of moment capacity of the beam section.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 36 OF 79

All butt welds shall be full penetration butt welds.

Connection of base plate & gusset members with the columns will be done considering that total load gets transferred through weld.

All splicing work shall be of full strength. Shop splicing for all sections other than rolled sections shall be carried out by full penetration butt welds. Shop splicing of all rolled sections shall be carried out using web and flange cover plate.

Following connections will be provided during erection :

1.) Welded Connection

- Connection of secondary beam to main beam
- Connection of bracing to column
- Connection of bracing to longitudinal tie beam
- Connection of longitudinal tie beam to column
- Connection of spandrel beam to column
- Connection of other secondary structures

2.) HSFG Connection (Grade 8.8 bolts)

- Splicing of column/transverse frame beam/ longitudinal tie beam
- Connection of Crane Girder to column
- Connection between crane girders
- Other major connections

3.) Bearing Type Connection (HT bolts Grade 8.8)

- All removable type connections
 - M.S. bolts (Grade 4.6)
- Purlins, stairs, wall beams etc

4.2.4 DESIGN

The design of steel structures will be done by linear elastic method as per the provision of IS: 800-1984. Individual members of the frames will be designed for load combinations for moment, axial force, shear force and torsion. Wind and seismic loads will not be considered to act simultaneously in transverse or longitudinal direction as per IS 1893-2002. The gable end columns of Power House building will be designed for

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 37 OF 79

wind and axial loads considering base as fixed and restraints provided by wind girder at operating floor and roof levels. The secondary beams will be designed as simply supported beams between the main beams of frames. The secondary beams supporting various RCC slabs without cut outs/openings will be designed as composite beam with channel type shear connectors and will be designed as per the provisions in IS: 11384 for composite construction.

All buildings/structures shall be framed structure. Basic consideration for structural framing shall be stability, rigidity, building uses, ease of fabrication / erection and overall economy. Additional bracings / moment connections shall be used to assure stability of structures. Structure shall be designed such that the surface of all parts shall be accessible for inspection, cleaning, painting and maintenance.

Crane gantry girders shall be single web plate girder of welded construction with bearing and intermediate stiffeners. Crane girder shall be designed as simply supported and of single span length. Chequered plate shall be used for gantry girder walkway flooring. For lifting / monorails beams ISMB sections shall be preferred and the bottom flange of all beams shall be checked separately for distortion and reinforced / braced suitably if required.

Base plate shall be fixed on foundation pedestal with grouting. For large base plates necessary grout holes shall be provided for escape of air. All anchor bolts for fixing steel columns to foundation shall be embedded in foundation during concreting itself..

4.2.5 PERMISSIBLE DEFLECTIONS

The permissible deflections of various steel members under normal loading conditions shall be as specified below. For calculation of deflections in structures and individual members, dynamic effects shall not be considered unless specified otherwise. Also, no increase in deflection limits shall be allowed when wind or seismic load are acting concurrent with normal loading conditions.

4.2.5.1 Vertical Deflection

For beams supporting dynamic equipment	Span / 500
For beams supporting floors / masonry	Span / 325
For beams supporting pipes (pipe racks)	Span / 400
Purlins and side runners supporting sheets	Span / 250

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001			
		VOLUME			
		SECTION			
		REV.NO.	0	14.05.2015	
		SHEET	38	OF	79
For grating and chequered plates		Span / 250 subject to a maximum of 6 mm			

For crane gantries or any member subjected to dynamic loads, the maximum deflection under dead load and live load excluding impact shall not exceed the following values:

For manually operated cranes & monorails	Span / 500
For electric overhead cranes.	
Upto 50 t capacity	Span / 750
Over 50 t capacity	Span / 1000

4.2.5.2 Horizontal Deflection

The permissible horizontal deflections shall be as given below unless specified otherwise.

Single storey building	Height / 325
Pipe rack columns	Height / 200
Open structures	Height / 200
Crane gantry girder due to surge	Span/2000 limited to maximum of 15mm
Building main columns at crane rail level due to action of crane surge load only	Height/2500 limited to 10 mm
Open gantry columns at crane rail level due to action of crane surge load only	Height/4000 limited to 10 mm

Provisions of IS: 800-1984 and relevant IS Code shall be followed for limiting deflections of structural elements not listed above.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 39 OF 79

4.2.6 MINIMUM THICKNESS & SIZES OF ELEMENTS

4.2.6.1 Minimum Thickness

The minimum thickness of various components of a structure and hot rolled sections shall be as follows. The minimum thickness of rolled shapes shall mean flange thickness regardless of web thickness. Structural steel members exposed to significantly corrosive environment shall be increased suitably in thickness or suitably protected otherwise as per good practice and sound engineering judgment in each instance.

- | | |
|---|---|
| a) Trusses, purlins, girts and bracing | 6 mm |
| b) Columns and beams | 8 mm |
| c) Gussets | 8 mm |
| d) Stiffeners | 8 mm |
| e) Base plates | 10 mm & above |
| f) Chequered plates | 6 mm o/p & above |
| g) Grating Flats | 3 mm for secondary bars and 6 mm for main / edge bars |
| h) Minimum thickness of structural members other than gratings and chequered plates directly exposed to weather and inaccessible for painting and maintenance | 8 mm |

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	40	OF 79

4.2.6.2 Minimum Sizes: The flange width of purlins for those supporting roof sheeting and wall cladding shall not be less than 50 mm. Width of steel rolled section connected to other member shall be at least 50mm. The depth of beams for platform of all structures shall not be less than 125 mm.

4.2.7 SLENDERNESS RATIO

The Slenderness ratio of main members in tension, compression or bending shall be in accordance with IS: 800.

4.2.8 PAINTING

All structural steel should be painted with 2 coats of zinc phosphate primer and finished with Synthetic enamel paint of approved make and colour.

All steel structure shall receive two primer coats and two finish coats of painting. First coat of primer shall be given after fabrication, before dispatch to site for erection, after surface preparation as described below. The second coat of primer shall be applied after erection and final alignment of erected structures. Two finish coats shall be applied after the second primer coat.

Steel surface which is to be painted shall be cleaned of dust and grease and heavier layers of rust shall be removed by chipping prior to actual surface preparation. The surface shall be abrasive blasted to Sa-2½ finish as per SIS 05-5900. Primer paint shall be inorganic Zinc phosphate of approved brand. Dry film thickness of each primer coat shall be 25 microns minimum.

Providing and applying two coats of synthetic enamel paint with minimum 50 micron total dry film thickness (DFT) of approved make and shade to achieve an even shade over steel sections already having primer coats and keeping overall DFT with primer not less than 110 microns.

4.2.9 REQUIREMENTS FOR SPECIFIC STRUCTURES

4.2.9.1 Coal bunkers

Design of the bunkers shall be as per IS: 9178. Plates shall be cut to the maximum width to reduce the number of horizontal joints. Vertical joints shall be staggered. All vertical joints above bunker supporting zones and both vertical and horizontal joint below the zone shall be inspected by radiography to ensure quality. Trial assembly of the bunker including hopper shall be made at least for one bunker before commencing regular fabrication of the bunkers..

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	41	OF 79

Stainless steel liner in the coal Bunkers will be 4.0 mm thick & of grade SS: 409M, Finish Grade 2B (Cold Rolled, Annealed & Pickled and Skin passed) will be provided on the inner faces of entire inclined portion of Hoppers and mouth of the Hoppers, without allowing any projections in coal flow path. The suitable electrodes' classification as per AWS will be as followed for welding of stainless steel to stainless steel & for welding of stainless steel to mild steel.

The coal pressure distribution in the bunker walls and hopper will be calculated as per the guideline laid in IS: 9178.

4.3 DESIGN PHILOSOPHY

4.3.1 POWER HOUSE STRUCTURE (TURBO GENERATOR / DEAERATOR BAY)

The Main Power House structure will be moment resisting frame in the transverse direction and will have fixed base. The structure will be braced in longitudinal direction. In the longitudinal direction, the structure will be continuous for the total length of one unit of the power house. Adopting twin columns between the two units of Power house buildings, expansion gap shall be provided.

Columns inside TG bay (auxiliary structures around TG) will be fixed at base and have shear connection with beams supporting R.C.C floor at operating floor level & mezzanine floor level. Beams in transverse direction will have connection with TG bay main columns.

Analysis of Main Frame of the Main Power House: The structural steel main frame will be analyzed as space frame with fixed base. The frame will be subjected to dead load, live load, crane load, equipment load, wind load and seismic load. Structural analysis will be carried out for the different load combinations as specified elsewhere. For the main frame subjected to seismic load, the analysis will be carried out using the response spectrum method using at least five modes of vibration as per IS: 1893-2002.

The structural steel main frame in the longitudinal direction will be analyzed and designed as braced structure with all the applied external forces resisted through axial tension or compression.

Individual members of the frames shall be designed for various load combinations for moment, axial force, shear force and torsion. The gable end columns shall be designed for wind and axial loads considering base as fixed and restraints provided by the wind girder at operating floor and roof girder levels. The secondary beams shall be designed as simply supported beams between the main beams of frames.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001			
		VOLUME			
		SECTION			
		REV.NO.	0	14.05.2015	
		SHEET	42	OF	79

4.3.2 Electrical Bay

The electrical bay will consist of areas for the cable spreader, switchgear floor, Control Room floor and MCC Floor. It will be supported on structural steel frame work with moment connection in transverse direction and bracings in longitudinal direction.

4.3.3 PIPE AND CABLE RACKS AND PIPE PEDESTALS

Pipe and Cable racks will be latticed steel structure on RCC foundations decided on the basis of Geotechnical Investigation Report. At road crossings the minimum height clearance will be 8 m.

The racks shall generally be designed as braced in the transverse direction below the bottom most rack level and rigid above the level since bracing will interfere with pipe / cables. Longitudinal direction they are braced generally in the centre of an expansion unit. Expansion joint shall be provided whenever there is a change in direction and where length of the rack exceeds 150 meters. Access ladder shall be provided at suitable locations. Where so specified 600 mm wide chequered plate platform will be provided in the cable rack portion for maintenance purpose.

4.3.4 MILL AND BUNKER BAY

The framing shall be of structural steel. This shall be designed as a moment connected framing in the transverse direction and braced in the longitudinal direction. These structures primarily support coal bunkers, coal feeders and tripper arrangement to feed coal into the coal bunker. The structure shall be designed to have a Moment connection at the base of the frame.

4.4 DRAINAGE AND SEWERAGE

4.4.1 SURFACE DRAINAGE

All the paved and unpaved areas will be adequately drained. The paved areas will be sloped towards the nearest drains with a slope of 1 in 100. The surface drainage from uncontaminated areas will be connected to the nearest storm water drains through rectangular drains. Contaminated area surface drainage will be connected through a separate network. Run off coefficient for paved and unpaved areas will be taken as 0.9 and 0.6 respectively.

4.4.2 STORM WATER DRAINAGE SYSTEM

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	43	OF 79

A network of open rectangular or pipe drain will be constructed for efficient discharge of storm water. The drains shall be constructed of RCC. Minimum clear width of the drains shall be 300mm and minimum depth of drain shall be 300mm. NP3 class pipe culverts will be provided under road and railway crossings.

For pipe drains, concrete pipes of class NP2 will be used. However, for road and rail crossing, concrete pipes of class NP3 will be used. Manholes will be provided at 30m intervals along the length, at connection points and at every change of alignment, gradient or diameter of pipeline. Hume pipe of 150mm diameter shall be provided below each road at every 50m and of 600mm diameter at every 300mm and also at all turnings for maintenance purpose. The runoff collected by the above drains will be suitably discharged at a suitable location at plant boundary.

The plant storm water drainage will be designed taking into account the finished grade levels of the plant and invert levels of existing drains(if any), area drainage pattern within and outside plant area, intensity of rainfall @50mm/hr considering heaviest fall in 24 hrs(As per climatological table furnished by customer). The slope shall not be milder than 1 in 1000 and maximum velocity in open drain shall be limited to 1.8 m/s. However a self-cleansing velocity of 0.6m/s shall be ensured.

Drains inside the building will have minimum 40mm thick grating covers. In areas where heavy equipment loads would be coming, pre-cast RCC covers will be provided in place of steel grating.

Open RCC rectangular section shall be provided for all drains.. In areas where vehicular loads would be coming, pre-cast RCC covers of suitable thickness without perforations and designed for the vehicular loading will be provided.

In the buildings suitable arrangement for draining out water collected from equipment blow downs, leakages, floor washings, fire fighting etc. will be provided for each floor with suitable floor drains. Water from roof surface shall be removed by a system of Roof Drain Heads, rainwater down comers and necessary fixtures. The roof of power house shall be provided with a slope of 1

in 100 in one direction in A-B bay and sloping towards A - row.

Garland drains of minimum 300 mm wide shall be provided all around the buildings to lead away roof drainage to the plant drainage system. Plinth protection shall be provided between the building wall and drains with appropriate slope.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	44	OF 79

Minimum earth cover of 450mm shall be provided over drainage pipes in paved areas.

4.4.3 PLANT EFFLUENT DRAINAGE (OILY WASTE/PROCESS WASTE DRAINAGE)

The oily / process waste shall be collected and drained through a separate sewer system consisting of cast iron pipes in the paved area and concrete pipe class NP2 in other area. Manholes shall be provided at junctions of pipes.

The minimum dia of pipe shall be 150 mm for C.I pipe and 300 mm for concrete pipes. The pipes shall be adequately sloped and shall carry the flow to Neutralising pit / oil water separator / guard pond of effluent treatment plant as the case may be.

4.4.4 SEWAGE DISPOSAL

All buildings with toilets shall be connected to the sewage treatment plant with a proper sewage disposal network.

Pipe connecting toilet facilities to manholes shall be pipes of, cast iron in paved area whereas in other area hume pipes shall be provided, of minimum size 100 mm dia. Pipes connecting various manholes in the power block area shall be having a minimum dia of 150 mm.

Sewers shall have such slope as to ensure effective discharge. Manholes shall be provided along the sewers at 30 m intervals, at junctions and at changes of gradient or alignment.

4.4.5 BUILDINGS - WATER SUPPLY SYSTEM

Roof water tanks of adequate capacity, depending on the number of users for 12 hours requirement will be provided on the roof of buildings as required. Polyethylene water storage tank conforming to IS: 12701 will be used. The tanks will be complete with fittings including float valve, stop cock etc.

Galvanized MS pipe of medium class conforming to IS: 1239 will be used for internal piping works for potable water supply.

4.5 CABLE TRENCHES

The slab and walls of cable trenches shall be constructed using concrete grade M25 and pre-cast removable RCC cover (with lifting arrangement) will be

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	45	OF 79

constructed using concrete grade M25. Each precast removable RCC cover shall not weigh more than 75 kg and shall be provided with lifting hooks. Proper drainage of trenches shall be provided.

The cable trench walls will be designed for the following loads:

1. Triangular earth pressure + Uniform surcharge pressure of 20 kN/m².
2. Cable trench covers will be designed for self-weight of top slab and concentrated load of 200 Kg at center of span on each panel.
3. Cable trench crossing the road/rails will be designed for class AA loading of IRC/relevant IS code and should be checked for transformer loading. Lifting hooks will be provided in the pre-cast covers.
4. Cable trenches will be blocked at the ends if required with RCC walls.

Trenches located inside the building will be covered with removable chequered plate covers.

Where the cable trench connects to a building, R.C.C duct banks with PVC / HDPE conduits for running cables will be provided. These conduits shall be sealed with fire resistant sealing compound after cables are laid to prevent ingress of water into the building and to avoid spreading of fire.

4.6 **PAVING / GRADE SLAB**

RCC Grade Slab / Boiler area paving : Minimum 150 mm thick (with minimum reinforcement of 8 dia (HYSD) @ 300 c/c both ways top & bottom) over an underbed as specified herein will be provided for areas mentioned below. Underbed will consist of preparation and consolidation of sub-grade to the required level, laying of stone soling of 230mm compacted thickness with 63mm and down aggregate with interstices filled with selected sand followed by 75mm thick M10 PCC

Area between main plant building and ESP, ID, FD fan will be provided with paving. This paving will have regular configuration with boundaries of the block extending minimum 2 m from the outermost face of the equipment/structures.

1. For Ground floor of all buildings - Grade slab shall be provided
2. Two meter wide corridor along the entire width of TG & Deaerator bay at both the gable ends - Paving shall be provided
3. Complete Transformer yard area between A-row of main power house and

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	46	OF 79

fencing of transformer yard – Paving shall be provided.

4.7 ROAD & DRAIN

The main road to the Power Plant shall originate from the main approach road. The main road shall be 12M wide(carriage way width 10M) with 1M wide shoulder on either side to accommodate large trucks movement .The 10M wide road shall be provided upto service building from the main gate.

Other roads may be of double lane of 7.5M wide (carriage way width) and single lane of 3.75M wide with 1M wide shoulder on either side for both, depending on the location.

Branch roads may be of single lane and 3.75 meter wide with 1meter wide berm on either side.

The minimum recommended road section is as follows :

Sub-base : Sub base shall consist of stones of 150 mm maximum size in two layers compacted to a thickness of 230 mm.

Base : Base shall have a thickness of 225 mm consisting of 3 layers of 75 mm each (compacted thickness).

Topping : The bituminous surfacing shall consist of wearing course of premix carpet 20 mm thick (with seal coat on top) over binder course of 55 mm thick Bituminous Macadam.

Initially only water bound macadam surface shall be constructed and after completion of bitumen topping shall be carried out .

All roads should designed in accordance with IRC 37-2001.

DRAINAGE

Open RCC rectangular drains shall be provided for storm water. The thickness of sides & bottom shall be minimum 100 mm or as per design considerations whichever is higher. RCC culverts shall be provided for road and rail crossing. Drains shall be provided on both sides of the roads except patrol road where drains will be only one side.

Inside surface of the drain will have smooth neat cement finish over with screed

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001			
		VOLUME			
		SECTION			
		REV.NO.	0	14.05.2015	
		SHEET	47	OF	79

concrete. Invert of the drain shall be decided in such a way that the water can easily be discharged to the recommended nearest outfall outside the plant boundary. The minimum slope of the drain shall be 1:1000 longitudinally to take care of the silting problems. It is recommended to maintain the maximum velocity within 1.2 m/sec..

4.8 FENCING

4.8.1 Minimum 2.4m high fencing above toe wall shall be provided around transformer yard. Other areas where fencing is necessary it shall comprise of PVC coated galvanised chain linked fencing of minimum 8 gauge (including PVC coating) with barbed wire for remaining height shall be provided for areas as per safety requirements.

4.8.2 Access in fencing wherever required shall be with steel gates

4.9 Plinth Protection

All buildings will be provided with 1000 mm wide and 75mm thick reinforced cement concrete M25 paving all around on the outside. The plinth protection will be laid over prepared sub-grade and base formed with 100 mm thick compacted sand bed with broken bricks, or rubble laid to a thickness of 75 mm. RCC drains by the side of plinth protection for catering the storm water from roofs and adjacent area will be provided.

4.10 Grouting/Encasement

Grout shall be flow able, and no shrinkable kind. Grouting shall be done with Conbextra GPX-2 of 'Fosroc' or equivalent for Equipment foundations and Conbextra GP-1 or equivalent for all structural column bases. For pipe-supports grouting shall be done with 1:1:2 cement-sand - 6mm down stone chips

4.11 Damp Proofing

Damp proof course in a thickness of 40mm and consisting of cement concrete 1:1.5:3 with minimum of 2% admixture of approved water proofing compound shall be provided at plinth level for masonry walls in super structure.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001			
		VOLUME			
		SECTION			
		REV.NO.	0	14.05.2015	
		SHEET	48	OF	79

4.9 Watch Tower

Watch tower shall be provided at the change of alignment of boundary wall and the inter distance of 500 mtr (approx.).

5.0 BRIEF DESCRIPTION OF STRUCTURES IN POWER PLANT

5.1 POWER HOUSE BUILDING

Main power house framing is of structural steel. Columns and framing beams are of built-up section. Main power house comprises of Turbo Generator bay and Electrical bay.

Turbo-Generator Bay: Roof in turbo-generator bay (A-B bay) will be with cast-in-situ RCC slab laid over metal decking sheet as a permanent shuttering.

Other Areas: Casting of RCC roof slab will be done with the provision of removable shuttering.

Flooring: The floor slab will be designed as cast-in-situ RCC slabs with removable shuttering unless mentioned elsewhere. The minimum thickness of RCC slabs will be 150mm. Floor finish of 40mm thickness will be provided over the RCC slab. Type of floor finish will be as per the functional requirements of different areas and facilities. Floor finish that will preferably be adopted for important areas will be as per Finish schedule described elsewhere. TG bay will have RCC floors at finished floor levels (FFL) at EL+8.500 and EL +13.500.

For Fire barrier wall, RCC fire barrier wall shall be provided for the transformer in front of power house. Brick partition walls will be 115mm thick. Bricks shall be burnt clay bricks or fly ash bricks of class designation 7.5 conforming to IS 12894 having 75 kg/Sqcm compressive strength shall be used for brick work. Metal cladding shall be of prefabricated, prepainted and insulated metal sheet of Luxalon or equivalent.

5.2 Roofing : The gradient for the roof of Turbine bay will be provided either in steel structure or by use of screed concrete of M10 grade. Water proofing treatment for roof shall be provided as per Clause 6.11.

Rain water down comers shall be GI pipes conforming to IS: 1239 for Power house building. Rain water down take pipes shall be provided one per bay near each column location on both A and C row for Power House building.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001			
		VOLUME			
		SECTION			
		REV.NO.	0	14.05.2015	
		SHEET	49	OF	79

5.3 MILL AND BUNKER BAY STRUCTURE

The framing shall be of structural steel. This shall be designed as a moment connected framing in the transverse direction and braced in the longitudinal direction. These structures primarily support coal bunkers, coal feeders and tripper arrangement to feed coal into the coal bunker

Mills are to be located on the ground floor. Mill foundations are to be designed as a dynamic block.

Mill maintenance platform is provided with chequered plate or gratings over steel framing with hand rails all-round. Feeder floor shall be of RCC supported on structural steel framework.

Tripper floor is provided immediately above the bunker. Tripper roof shall be of RCC supported on structural steel frame work. An RCC parapet or steel handrail shall be provided for the tripper roof. An access stair or ladder shall be provided from tripper floor to roof in each unit.

5.4 ESP CONTROL ROOM

This shall be a steel framed structure. The building houses cable vault, toilet, staircase, switch gear rooms, control rooms and AHU room. An auxiliary transformer yard with fencing and gate shall be provided adjoining to the building. Side cladding shall be of brick wall with wall in front of transformer yard made sufficiently thick to satisfy fire rating as per TAC regulations.

5.5 TRANSFORMER YARD

Transformer yard will be provided with foundations for transformers & other equipment, cable trenches and fencing. The transformer yard will be provided with the chain link PVC coated galvanized chain link fencing of minimum 8 gauge supported by steel posts. Gravel will be filled in transformer oil and water collecting pits. The transformer yard area will be provided with RCC paving. Fire barrier wall will be provided between the adjacent transformers and fire wall will be provided in the adjacent buildings on the wall facing the transformers as per TAC requirements.

Transformer yard pit will be leveled to proper slopes for drainage towards sump. Sump will be connected to the nearest drainage system after passing through oil water separator.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 50 OF 79

The total transformer area shall be paved with 150 mm thick RCC paving over 230 mm thick rubble soling.

5.6 MISCELLANEOUS BUILDINGS/STRUCTURES

SL.No.	Building Name	Description
1.	Service Building	RCC structure with brick cladding. Total area of 4000 sqm (approx)
2.	Clarified water pump house	RCC sump with structural steel framework above FFL only superstructure with brick cladding with RCC roof over deck sheeting.
3.	CW pump house	RCC sump with structural steel framework, superstructure with brick cladding and RCC floor slabs and roof
4.	CW Treatment	Steel Shed
5.	ESP Control room	Steel structure frame with brick cladding RCC floor slabs and roof.
6.	Compressor house	Steel Building
7.	Chemical Lab	RCC structure with brick cladding.
9.	Fuel oil Pressurizing pump house	RCC structure with brick cladding.
11.	Administrative building	RCC structure with brick cladding. G+1 Structure of total area 2500 sqm.
12	Canteen	RCC structure with brick cladding. One floor of 40m x 18m (excluding corridor and portico). The main dining area shall have the arrangement to seat minimum 150 people at one time. In addition

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 51 OF 79

		there shall be a separate executive dining area to accommodate about minimum 25 executive and separate dining area for women for 25 nos.
13	Fire Water Tank Foundations	RCC ring wall.
14	Fuel Oil Storage Tank Foundations	RCC ring wall.
15	Pipe and Cable Trestles	Structural Steel super structure with RCC foundation.
16.	Raw water pump house	Steel Structure
17.	Fire station	G+1 RCC structure with brick cladding.20m x 15m x 4.0m (ht) of each floor. Additional 2 Nos fire tender parking area
18	Permanent Store Building	RCC columns with brick cladding and steel truss roof. Area 30m x 15m-15 No.s
19	CW Treatment Building	Steel shed with side open
20	Security Building	RCC structure with brick cladding of 300 sqm floor area
21	Parking sheds	Parking sheds shall be provided as mentioned below apart from bus parking for 3No.

Parking Requirement

Sl. No.	Location	Car parking (No.s)	Two Wheeler Parking (No.s)
1	Administrative Building	5	50
2	Service Building	20	200
3	Canteen	10	100
4	Chemical lab	--	10

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.			SPECIFICATION NO. PE-DC-411-600-C001		
				VOLUME		
				SECTION		
				REV.NO.	0	14.05.2015
				SHEET	52	OF 79
	5	Security Building	2	20		
	6	Permanent store building	--	50		
	7	CW pump house	--	10		
	8	Ash Pump House area	2	20		
	9	Coal Handling area	2	20		

6.0 GENERAL REQUIREMENT OF BUILDINGS

The design and construction of buildings, structures etc. shall take in to account the functional requirements for operation and maintenance of all equipment and its users. The following details indicted will generally apply for all buildings and structures.

6.1 ARCHITECTURAL CONCEPTS AND DETAILS

Architectural scheme components viz shape, form, colour, and basic materials for interior and exterior architecture, will generally conform to that described herein and match with local practice and surroundings.

6.2 ROOF ACCESS

For roofs more than 8m above grade or if major equipments are placed over the roof, shall have access from a proper staircase. Minimum 1000 mm wide access path with tiles shall be provided to approach equipment on roof. For other roofs cage ladder or staircase as appropriate shall be provided.

6.3 PLATFORMS AND WALKWAYS

6.3.1 Platforms shall be provided to all major equipment, not directly accessible from the floors, for maintenance. Platforms located close to each other shall be connected with walkways.

6.3.2 All steel platforms above grade level shall be constructed with kick plates at edge of the platform to prevent tools or materials from falling off.

6.3.3 Continuous walkway with hand rails shall be provided along the crane girder level in the TG building. Approach to EOT crane shall be ensured by Cage ladder or staircase.

6.4 STAIRS & LADDERS

6.4.1 STEEL STAIRS

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 53 OF 79

All steel staircases shall normally have minimum clear width (back to back of stringer) of 1000 mm and minimum inclination with horizontal of 35.7 degree. However, in case of space restriction, minimum 250 mm wide treads of chequered plate/grating, with suitable nosing, and spaced equally so as to restrict the rise to maximum 180 mm and successive landing shall not be more than 5 m.

6.4.2 STEEL LADDERS

Ladders shall be provided to platforms, walkways, instruments and equipments which do not require frequent access. Ladders shall preferably be vertical and its angle with vertical shall not exceed 5 Degree.

Ladders shall be of minimum 450 mm clear width with 20 mm dia. MS rungs spaced at 300 mm (maximum).

Ladders shall be provided with a safety cage wherever required starting at 2.5 m above the lower landing level.

6.4.3 RCC STAIRS

All stairs shall have riser of minimum 150 to 180 mm and a minimum tread of 250 mm. However, for administration building riser shall be limited to 150 mm tread width of 300 mm. Minimum width of stairs shall be 1200 mm generally. No staircase shall have more than 15 risers in one flight. Aluminium angle nosing with minimum 50 x 25 x 3 angle shall be provided for edge protection of RCC stairs.

6.5 VERTICAL HEAD ROOM

All accessible areas will be provided with a minimum clear headroom as follows, unless otherwise specified.

1. Finished floor to ceiling (Buildings)	:	3000 mm
2. Doors, walkways, platforms	:	2100 mm
3. False ceiling to office areas/stairs	:	2400 mm
4. Cat walkways above false ceiling	:	1000 mm
5. Safety cage for cage ladders	:	2500 mm
6. Access for forklift trucks	:	2800 mm
7. Roads / railway crossings	:	8000 mm
8. Cable and pipe racks (except road/rail crossing)	:	3000 mm

6.6 GUARD RAIL / HAND RAILS

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	54	OF 79

Guard rail will be a two-rail system with the top rail 1000 mm above the walkway/platform/floor surface and the intermediate rail 500 mm below the top rail. Guard rail post spacing will be proportioned to the length of the protected horizontal opening, but will not exceed 1500mm centre-to-centre of posts.

6.7 EDGE PROTECTION

Wherever possible around floor openings an RCC Kerb of 100 mm wide 150 mm high shall be provided. All concrete edges, where breakage of concrete corner is expected shall be provided with edge angles e.g. around the cut-outs / openings in floor slab, edges of drains supporting grating covers, edges of manholes supporting covers and supporting edges of pre-cast covers etc.

6.8 ANCHOR BOLTS AND INSERT PLATES

Anchor bolts shall be designed for tension and shear, for embedded length of the anchor bolts and pipe sleeves. Shear and crushing strength of concrete shall also be checked. Increase in allowable stress for loading including seismic and wind loads shall not be permitted in design of anchor bolts.

Insert plates shall be designed / checked for shear and bending moment. All lugs shall be checked for tension. Bond strength of concrete shall be checked. Lugs using steel bars shall preferably be fillet welded to the plate to transfer full strength of the lug.

6.9 EXPANSION / CONSTRUCTION JOINTS

Expansion and construction joints shall be provided wherever required. All expansion and construction joints of water retaining structures in RCC shall be made water tight using PVC ribbed water stops with central bulb. However, kicker type (externally placed) PVC water stops may be used for the base slabs and in other areas where it is required to facilitate concreting. The minimum thickness of PVC water stops shall be 6 mm and minimum width 225 mm. At other joints these shall be 150 mm wide. Two part polysulphide sealant conforming to IS: 12118 shall be used for sealing of joints in contact with water. For other cases, bitumen sealing compound conforming to IS: 1834 can be used. Preformed bitumen impregnated fibre board conforming to IS: 1838 shall be used as joint filler.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	55	OF 79

6.10 BRICK MASONRY

Brick works

- Internal and external : 230 mm thick fly ash brick wall with 1:6 Cement-Sand mortar. All Brick work as mentioned in this document shall be with Fly Ash Bricks unless noted otherwise.
- Half brick thick wall : 1:4 cement: Sand mortar with 2 nos. 6 mm dia M.S. rod in every fourth layer.
- One third brick wall : 1:3 cement: sand mortar with 2 nos. 6 mm dia M.S. rod at every alternate layer.

6.11 WATER PROOFING

Roof Waterproofing

Roof water proofing treatment shall be as follows :

- For roofs with structural slope :

The cleaning and preparation of the substrate to which the elastomeric membrane is applied must be carried out thoroughly to leave a sound base for the application. Any laitance present on the surface must be removed mechanically. Release oil and other contaminants which may impair adhesion must be removed.

Over the finished well prepared sloped surface of RCC slab, application of elastomeric membrane shall be a single component the liquid, cold applied, elastomeric polyurethane based, that cures by reaction with atmospheric moisture to form a tough but flexible waterproofing membrane. It is elastomeric, seamless waterproof membrane applied in 2 coats to a DFT of 1.2 mm thick having a elongation capacity of over 600% and average tensile strength of 1 MPa, tear resistance as per GBT 19250-2003 >20N/m. The material shall comply with – ASTM C 836 National Std. of Canada 37.58 – M86 by CGSB. over the entire surface of waterproofing membrane laying a separation layer of non-woven polypropylene geo-textile of 120 gsm followed by application of rigid insulation board expanded polystyrene BASF PERIPOR of BASF or similar approved for thermal insulation as per HVAC requirement shall be laid over the

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001			
		VOLUME			
		SECTION			
		REV.NO.	0	14.05.2015	
		SHEET	56	OF	79

finished separation layer of geotextile. The insulation board shall have interlocking tongue-groove arrangement. The insulation board shall have the following specifications;

- Colour: Orange
- Thickness: 50 mm
- Compressive strength: 200-220 kN/m²
- Thermal Conductivity (K): 0.034 W/mK
- Thermal Transmittance (U): 0.5-0.6 W/m² oC
- Water Absorption (% vol): <0.1% (by total immersion)

The top surface of the rigid polystyrene block of Peripore of BASF or similar approved shall be finished with pressed precast concrete tiles (size minimum 600 mm x 600 mm) of 20 mm thick on 15 mm thick cement plaster (1:4) which laid over 120 gsm non-woven polypropylene geo-textile separation layer. Provision for thermal expansion of roofing tiles shall be kept by providing an expansion gap in both directions filled up with polysulphide joint sealant. The expansion gap shall be provided in the cement sand mortar under bed layer also.

ii) For roofs having no structural slope: The cleaning and preparation of the substrate to which the elastomeric membrane is applied must be carried out thoroughly to leave a sound base for the application. Any laitance present on the surface must be removed mechanically. Release oil and other contaminants which may impair adhesion must be removed.

Over the finished well prepared flat surface of RCC slab, application of elastomeric membrane shall be a single component the liquid, cold applied, elastomeric polyurethane based, that cures by reaction with atmospheric moisture to form a tough but flexible waterproofing membrane. It is elastomeric, seamless waterproof membrane applied in 2 coats to a DFT of 1.2 mm thick having a elongation capacity of over 600% and average tensile strength of 1 MPa, tear resistance as per GBT 19250-2003 >20N/m. The material shall comply with –

ASTM C 836 National Std. of Canada 37.58 – M86 by CGSB. over the entire surface of SONOSHIELD HLM 5000R waterproofing membrane laying a separation layer of non-woven polypropylene geo-textile of 120 gsm followed by application of rigid insulation board expanded polystyrene BASF PERIPOR for thermal insulation as per HVAC requirement shall be laid over the finished separation layer of geotextile. The insulation board shall have interlocking tongue-groove arrangement. The insulation board shall have the following specifications :

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	57	OF 79

- Colour: Orange
- Thickness: 50 mm
- Compressive strength: 200-220 kN/m²
- Thermal Conductivity (K): 0.034 W/mK
- Thermal Transmittance (U): 0.5-0.6 W/m² oC
- Water Absorption (% vol): <0.1% (by total immersion)

The top surface of the rigid polystyrene block of Peripore shall be finished with pressed precast concrete tiles (size minimum 600 mm x 600 mm) of 20 mm thick on screed concrete mix (1:2:4) grading having minimum 25 mm thickness at the lowest point of the slope over R.C.C. slab and shall be laid as per the slope laid over 120 gsm non-woven polypropylene geo-textile separation layer. Provision for thermal expansion of roofing tiles shall be kept by providing an expansion gap in both directions filled up with polysulphide joint sealant. The expansion gap shall be provided in the cement sand mortar under bed layer also.

iii) For other plant and non Plant buildings rigid insulating board (expanded / extruded polystyrene block) as per HVAC requirement shall be laid over screed concrete mix (1:2:4) grading having minimum 25mm thickness at the lowest point of the slope over R.C.C. slab and shall be laid as per the slope specified elsewhere in the specification. Top surface of rigid insulating board shall be finished with 15mm thick cement plaster (1:4) which shall be laid over Geo-textile membrane layer. Over the finished surface APP Bitumen membrane as specified below shall be laid and top of the Bitumen membrane shall be finished with pressed precast concrete tiles (size minimum 600 mm x 600 mm) of 20 mm thickness on 15 mm thick cement: sand (1:4) mortar underbed. Provision for thermal expansion of roofing tiles shall be kept by providing an expansion gap in both directions filled up with polysulphide joint sealant. The expansion gap shall be provided in the cement sand mortar underbed layer also.

- a) APP modified Bituminous Polyester reinforced waterproofing membrane of Sika® WP Shield-104 P or similar approved shall be manufactured from a rich mixture of bitumen and selected polymers blended together to obtain excellent heat resistant, flexibility, UV resistance. Modified bitumen then coated onto a dimensionally stable carrier to obtain excellent tensile strength, tear and puncture resistance.
- b) APP membrane shall conform to Conforms to: UEAtc, ASTM D146, DIN52123, ASTM D36, ASTM D5, UEAtc, ASTM D 5147, ASTM D4799.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	58	OF 79

c) Technical Data

- Chemical Base APP modified Bituminous Polyester
- Thickness 4mm
- Unit weight 4.40 kg/m²(According to UEAtc)

d) Mechanical / Physical Properties

- Tensile Strength (L/T) N/SCM - 800/600 (According to UEAtc,ASTM D146)
- Elongation at break (L/T) - 40/50 - (According to UEAtc,ASTM D146)
- Resistance to water pressure - No leakage - (According to DIN52123)
- Carrier (Polyster) weight- 180 g/m²
- Softening Point - 145 oC - (According to ASTM D36)
- Penetration - 15-25 at 25oC d mm-(According to ASTM D5)
- Tear resistance (L/T) N-170/180- -(According to UEAtc)
- Water Absorption% (BSP)- <0.15-(According to ASTM D 5147)
- Heat Resistance- No Flow at 100oC-
- Resistance to Aging after 2000 hrs (Weather –O- Meter)- No Delamination- (According to ASTM D4799)

e) Concrete, mortar surfaces must be clean, free from grease, oil, and loosely adhering particles. Steel and iron surfaces must be free from scale, rust, grease and oil. All surfaces must be as true as possible.

f) Bituminous primer is to be applied to a clean, smooth and dry surface by brush, roller or spray. The material is to be Unrolled and align and re rolled correctly before torching. Overlaps should be minimum 100 mm. Gas burner is to be used to heat the substrate and thermo fusible film on the underside on lower face of membrane. When the thermo- fusible film melts after torching, the membrane is ready to stick. The membrane should be Rolled forward and press firmly against the substrate to bond. Both the overlaps shall be heated and the round tipped trowel shall be used for heating the same to smoothen and press into seam.

g) All angles and abutments should be sealed with extra care to ensure full

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	59	OF 79

bondage. The edges should be sealed well into the grooves.

iv) For Liquid, cold-applied PU elastomeric waterproofing membrane system shall be a single component the liquid, cold applied, of elastomeric polyurethane base that cures by reaction with atmospheric moisture to form a tough but flexible waterproofing membrane of BASF's SONOSHIELD HLM 5000R or similar approved. It is elastomeric, seamless waterproof membrane applied in 2 coats to a DFT of 1.2 mm thick having a elongation capacity of over 600% and average tensile strength of 1 MPa, tear resistance as per GBT 19250-2003 >20N/m. The material shall comply with – ASTM C 836 National Std. of Canada 37.58 – M86 by CGSB.

Note : Waterproofing materials should be applied by the manufacturer authorised applicators only.

6.12 Rolling Shutters: Rolling shutters as per IS:6248 with suitable operating arrangement (manual, mechanical and /or electric) according to size shall be provided in buildings to facilitate handling and transportation of equipment. The curtains of rolling shutter will be of interlocking scrolls made of hot rolled double dipped galvanized steel lath section of 18swg tested mild steel strips at 75mm rolling centers, locked with galvanized malleable iron clips. The bottom lath will be coupled to a locked plated fabricated from 3 mm thick galvanized steel plate and security riveted with stiffening angles.

7.0 FINISHES

7.1 Plastering

a. Exterior & rough side of interior brick wall :

20mm thick minimum sand faced plaster in two layers with 1:4 cement sand mortar of 12mm thick first layer and 1:3 cement sand mortar with 8mm second layer. Where external finish will require rich plastering for special finish plaster shall be of 1:4/1:3.

b. Interior wall : 12 mm thick with 1:4 cement- sand mortar:

c. Ceiling : 6 mm thick with 1:3 cement- sand mortar shall be provided to all exposed ceilings

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	60	OF 79

7.2 DOORS, WINDOWS AND VENTILATORS

- Generally hollow metal (steel) flush doors with pressed steel frame shall be provided for plant and utility areas.
- Solid core factory made wooden flush doors in hard wood frame shall be used in interior office areas. Aluminium doors shall be provided in at entrances and important areas.
- Rolling steel shutters shall be used where frequent use is not envisaged and large openings are required. Operation shall be manual/mechanical/electrical depending on the size of opening.
- Special areas like control rooms and other special areas shall be provided with minimum 15 micron pre-coated i.e. colour anodised aluminium glazed partitions with air lock facilities having two sets of doors preferably double door system.
- Minimum 2 hour Fire rated doors with panic bar shall be provided in cable spreader rooms and other areas having fire hazard and also to all fire exists as per TAC requirement.
- Doors shall be provided at appropriate location to prevent dust ingress from outside.
- Wooden panel doors shall be provided for toilet entrance and toilet internal doors shall be solid core PVC.
- Weather stripping shall be provided to all outside doors as well as air conditioned areas and all other doors where dust-free environment is required.

In Powerhouse building, full glazed windows of sliding type ventilators in minimum 15 micron anodized aluminium window frame shall be provided with 4 to 6 mm thick (depending on the size of panel) clear float glass and 6 mm thick clear wired/laminated glass where required from safety point of view. For an operating floor of Power House, structural glazing may be considered as an important façade element.

In other areas aluminium windows with 4 mm thick clear float glass shall be provided. The window area shall be so decided so as to allow adequate natural ventilation and light.

Note: Glass thickness and member sizes of Aluminium Glazed doors and windows shall be designed by the manufacturer and to be submitted for approval before execution.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	61	OF 79

7.3 GLAZING

- a) Glazing in Control room between A.C. and non-A.C. areas shall be insulating glass consisting of two 6 mm thick toughened float glass sheet hermetically sealed and separated by 12 mm gap for thermal insulation. Clear glass shall be provided where clear view is required. In other areas tinted glass may be provided.
- b) 4 mm thick ground glass shall be provided for toilets.
- c) Glazing between two A.C. areas shall be with 6 mm thick clear float glass.
- d) All glazing shall be in aluminium frame having 15-micron colour anodised.
- e) 6mm thick Wired / laminated glass shall be used for windows / ventilators at higher level for safety.
- f) 24mm thick insulated double glazing having 6mm thick tinted heat-reflecting type float glass on outer side and 6mm thick clear float glass on inner side with 12mm air gap & hermetically sealed shall be mounted on 15 micron coloured anodised aluminium frame suitable for structural glazing system.

7.4 ACID ALKALI RESISTANT LINING

- 7.4.1 25mm thick acid and alkali proof tiles will be laid over acid and alkali proof epoxy mortar under bed shall be provided for Battery room, battery charger room, degasser area, chemical house floor etc. Similar tiles over chemical resistant silica based epoxy mortar shall be used as dadoing above floor level. Ceiling will be painted with chemical resistant epoxy paint.

7.5 FLOORING & FLOOR FINISHES

- 7.5.1 The floor slabs will be designed as cast-in-situ RCC slabs with removable shuttering unless mentioned otherwise. The nominal thickness of RCC slabs will be 150 mm.
- 7.5.2 The nominal total thickness of floor finish will be 40/50 mm i.e. underbed & topping. The floor will be laid on already laid and matured concrete base.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	62	OF 79

7.5.3 The finished floor level of toilet areas shall be kept 12 mm below as that of the surrounding area. Toilet area slabs will be made water tight by suitable water proofing treatment.

7.5.4 Floor finishes will be as per Finish schedule of this specification

7.5.5 Skirting in general will be 150 mm high. Dado in toilets, will be upto 2.1m. height from finished floor level. Skirting and Dado will match with the floor finish.

7.6 FALSE CEILING

Aluminium pre-painted/Powder coated false ceiling, either lineal panel system or aluminium tile/plank system for control rooms and other important areas, with suspension system as per manufacturer's details shall be used.

Areas like office space or where specified Mineral Fibre Based Acoustic Ceiling Board either Armstrong or similar to Armstrong in aluminium snap grid suspension system as per manufacturer's specification shall be provided. As an alternative Moisture & Fire Resistant Gypsum Board false ceiling system of Saint Gobain Gyproc India Ltd or similar manufacturer may be used.

Unimportant areas Calcium Silicate Board/Tiles false ceiling shall be of HILUX or AEROLITE or Fibre Cement Board of EVEREST Industries Ltd shall be used.

The false ceiling work shall take care of all illumination, fire detection & fighting, HVAC and all other service requirement. False ceiling shall be provided with 25 mm thick insulation of resin bonded mineral wool conforming to IS: 8183. Wherever under-deck insulation is required the insulation shall be 50 mm thick resin bonded rigid mineral wool / polystyrene block with protective aluminium foil lining.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 63 OF 79

7.7 SCHEDULE OF FINISHES

7.7.1 INTERIOR FINISH SCHEDULE FOR POWER HOUSE BUILDING

BUILDING/ AREA	FLOORING/SKIRTING/ DADO	WALL	CEILING
T.G. Hall Area	Overall 50mm thick flooring shall be finished with 18 mm thick polished Granite for unloading areas and walkways shall be demarcated with 75 mm wide and 18 mm thick Granite stone (black) on both sides of Granite finished walkways.	Granite tiles/10mm thick high polished decorated coloured background 1st quality digital series dual charged glazed tiles of size not less than 18"x12" shall be provided for inner faces of all four sides walls of operating floor TG hall and columns (by encasing structural steel columns along A-row and both gable ends with brick masonry for 3.0mts height above operating floor) up to bottom of window lintel level or 1.80mts height from operating floor level whichever is high and balance portion of brick wall shall be painted with two coats of plastic emulsion paint over primer and white cement putty. A row and gable end shall have double skin metal cladding system above brick masonry wall. Synthetic enamel paint up to 1.50mts	T.G. Hall – anti-corrosive paint to metal deck and all metal works. Acrylic Distemper on exposed plastered ceiling (without false ceiling). Aluminium panel pattern false ceiling for false ceiling areas

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001
			VOLUME
			SECTION
			REV.NO. 0 14.05.2015
		SHEET 64 OF 79	
		height and acrylic emulsion paint for balance height for all other floors of STG building.	
Switchgear Room, MCC Room,	Electric insulated flexible PVC sheet as per IS: 15625-2006 to be laid over heavy duty IPS flooring. Overall thickness shall be 50mm. pattern.	Synthetic enamel paint upto 1.50mts height from floor level and balance portion with plastic emulsion paint over primer and white cement putty.	Acrylic Distemper
2 Control Rooms, Control Equipment Room, Computer Rooms, etc. Other than Main Control Room.	Non-skid, fully vitrified, 10 mm thick non-porous, homogenous, abrasion resistant, floor tiles similar to 'MARBONITE', FERRASTONE' of " BOSS Profile Ltd", "RESTILE", ENDURA" of H&R jonson (India) Pvt. Ltd, "Kajaria" profile Ltd", of minimum size minimum 600 mm x 600 mm x 9~10 mm of approved colour and shall be laid over concrete floor with laying compound strictly as per manufacturer's specification. Total thickness of the flooring shall be 50mm thick including the thickness of the tiles and under bed.	Vitrified tiles dadoing up to false ceiling level in UCB control room and annexure room shall be provided. Front portion of the UCB control room facade above glass panelling a suitable combination of Aluminium composite panel (ACP)/granular textured paint may be used. Columns, bracings or any other element within the room as the case may be shall be clad with polyester coated 3mm thick Aluminium Composite Panels (Aluminium thickness minimum 0.2mm) of approved make or composite panelling of approved pattern upto the false ceiling level.	Gypsum board plaster false ceiling for control room and annexure rooms. The false ceiling work shall take care of all illumination, fire detection & fighting, HVAC and all other service requirement.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001	
		VOLUME	
		SECTION	
		REV.NO. 0	14.05.2015
		SHEET 65 OF 79	
3 All office areas, Conference Room and other important areas.	10/11 mm thick non-skid fully vitrified dual charged tiles of minimum size 600 mm x 600 mm similar to 'MARBONITE', FERRASTONE' of " BOSS Profile Ltd", "RESTILE", ENDURA" of H&R jonson (India) Pvt. Ltd, "Kajaria" profile Ltd", (overall 40 mm thick) laid in pattern with different colour of tiles.	Acrylic emulsion paint over white cement putty.	Acoustic precoated aluminium alloy panelled ceiling (600x600mm panels) stove enamelled on both sides on pre coated aluminium grid system. Acrylic emulsion paint over white cement putty in areas without false ceiling with necessary lighting arrangements for illumination shall be provided.
4 Access floor where required	Minimum 600 mm high false floor with adjustable metal supporting system and fire resistant floor panels finished with antistatic vinyl flooring and matching skirting		
5 Stairs & Lobby	Kota stone/equivalent slab in general.	Coloured 6mm thick(min) ceramic tiles up to 1.50mts height and Acrylic emulsion Paint over white cement putty for balance height.	Acrylic Distemper Paint
Main Stair & Landing	Aranga White marble slab//makarana pink / Jaishalmir Yellow and Baroda green combination 25 mm thick (min.) with larger possible size to be approved by the owner.	Acrylic emulsion paint over white cement putty.	Acrylic emulsion paint over white cement putty.
Lift lobby	Aranga White marble slab/makarana pink / Jaishalmir yellow and Baroda green combination 25 mm thick (min.) with larger possible	Granite slab cladding	Aluminium plank panelled pattern false ceiling.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001
			VOLUME
			SECTION
			REV.NO. 0 14.05.2015
			SHEET 66 OF 79
	size to be approved by the owner.		
6 Battery Room & Battery Charger Room, UPS Room	Minimum 20 mm thick acid and alkali resistant vitrified tiles "ENDURA" Or similar set in and jointed with epoxy mortar (overall 40 mm thick)	20mm thick acid resistant tiles over bitumen primer up to 1.20mts height	Acid/Alkali resistant epoxy paint for balance height.
7 Chemical Feed Station	Minimum 20 mm thick acid and alkali resistant vitrified tiles "ENDURA" or similar Minimum 37mm thick Acid /Alkali resistant brick, set in and jointed with epoxy mortar (overall 40 mm thick) .	20mm thick acid resistant tiles over bitumen primer up to 1.20mts height.	Acid/Alkali resistant epoxy paint for balance height.
8 AHU Rooms, Air Washer Rooms, Cable Spreader Rooms & all other service areas	50 mm thick heavy-duty cement concrete floor with metallic hardener.	Synthetic enamel paint up to 1.50mts height and acrylic emulsion paint for balance height over white cement	Acrylic Distemper Paint
9 Toilet and other wet areas	Minimum 10 mm thick non-skid vitrified tile of make 'MARBONITE', FERRASTONE' of " BOSS Profile Ltd", "RESTILE", ENDURA" of H&R jonson (India) Pvt. Ltd, "Kajaria" profile Ltd", of minimum size 400 mm x 400 mm (overall 40 mm thick) with glazed ceramic tile of same make dado topped with 50 mm wide matching moulded ceramic trims. Dado height shall be full height starting from finish floor level.	1st quality coloured glazed ceramic tiles of minimum 5 mm thickness up to 100 mm higher than lintel level starting from finish floor level. And balance portion with Acrylic emulsion paint over white cement putty.	Acrylic emulsion paint over white cement putty. Aluminium false ceiling where required.
10 Oil Spillage area	Non-skid self-leveling epoxy over IPS (overall 40 mm thick)	Epoxy paint.	Epoxy paint.
11 Electrical Switchgear Room, MCC Room, etc	Electric insulated flexible PVC sheet as per IS: 15625-2006 to be laid over heavy duty IPS flooring. Overall thickness	Synthetic enamel paint up to 1.50mts height and acrylic emulsion paint for	Acrylic Distemper

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001	
			VOLUME	
			SECTION	
			REV.NO.	0 14.05.2015
		SHEET	67	OF 79
		shall be 40mm.	balance height over white cement putty.	
12 All other general areas except operating floor	Overall 50 mm thick heavy-duty concrete floor (IPS) with metallic hardener or 40mm thick steelcrete tiles finish.	Synthetic enamel paint up to 1.50mts height and acrylic emulsion paint for balance height over white cement putty.	Acrylic Distemper	

7.7.2 Interior Finish Schedule For Auxiliary Plant Buildings

1 Mill Building	50 mm thick heavy duty cement concrete floor with metallic hardener and matching skirting	Metal cladding	Synthetic enamel paint
2 ESP Control Building	10 mm thick non-skid fully vitrified tiles of make "MARBONITE", "FERRASTONE" of minimum size 600 mm x 600 mm (overall 40 mm thick) laid in pattern for Control room. Other areas 50mm thick heavy duty IPS flooring with metallic hardener. MCC & Switchgear rooms shall have flexible electric insulated PVC synthetic sheet finish over IPS.	Acrylic emulsion paint over white cement putty for control room and Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint over white cement putty for balance height for Other areas	Pre-coated aluminium panelled (600mmx600mm size) ceiling "Luxalon" or "INTERARCH" in air-conditioned areas. Acrylic Distemper paint in other areas.
3 Chemical House	Minimum 20 mm thick acid and alkali resistant vitrified tile "ENDURA" or Minimum 37mm thick Acid /Alkali resistant brick, set in and jointed with epoxy mortar (overall 50 mm thick) along with 2100 mm high dado of same tile having 20mm thickness. Where required, other areas with 50mm thick heavy duty flooring with	20mm thick acid resistant tiles over bitumen primer up to 1.20mts height and Acid/Alkali resistant epoxy paint for balance height	Chemical resistant paint for acid & alkali resistant area and other areas with Acrylic Distemper paint.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001		
			VOLUME		
			SECTION		
			REV.NO.	0 14.05.2015	
		SHEET	68	OF	79
		metallic hardener.	in acid & alkali prone area and rest with Acrylic emulsion paint paint		
4 Raw Water Pump House & Electrical Building	50 mm thick heavy duty cement concrete floor with metallic hardener and matching skirting	Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint with white cement putty for balance height	Acrylic Distemper		
5 HFO & LDO Forwarding Pump House	Self-levelling epoxy floor paint on oily areas and heavy duty IPS flooring with hardener in balance areas.	-Do-	Acrylic Distemper Paint		
6 CW, ACW Pump House	50 mm thick heavy duty cement concrete floor with metallic hardener and matching skirting	-Do-	-Do-		
7 CW, ACW Pump House	50 mm thick heavy duty cement concrete floor with metallic hardener and matching skirting	-Do-	-Do-		
8 Misc. Pump Houses/ Fire Water Pump House/ Clarified water pump house	-Do-	-Do-	-Do-		
9 DM plant					
a) Plant area	Minimum 20 mm thick acid and alkali resistant Vitrified tile of “ENDURA” or similar set in and jointed with epoxy mortar (overall 40mm thick).	20mm thick acid resistant tiles over bitumen primer up to 1.20mts height and Acid/Alkali resistant epoxy paint for balance height in acid & alkali	Chemical resistant paint for acid & alkali resistant area.		

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001	
			VOLUME	
			SECTION	
			REV.NO. 0 14.05.2015	
			SHEET 69	OF 79
			prone area and rest with Acrylic emulsion paint	
b) MCC Room	50 mm thick heavy duty cement concrete floor with metallic hardener or flexible electric insulated PVC synthetic sheet finish and matching skirting.		Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint with white cement putty for balance height	Acrylic Distemper Paint
c) Control room and offices	10/11 mm thick non-skid fully vitrified tiles of make "MARBONITE" minimum size 600 mm x 600 mm (overall 40 mm thick) laid in pattern for Control room and offices.		Acrylic emulsion paint over white cement putty.	Gypsum Board / Clacium Silicate Board or tiles false ceiling with insulation on top.
d) Laboratories	Minimum 20 mm thick acid and alkali resistant tile set in and jointed with epoxy mortar (overall 40mm thick) along with 2100mm high dado of same tile.		Acid / Alkali resistant paint in acid & alkali prone area.	Acid / Alkali resistant paint in acid & alkali prone area.
e) Toilet	10 mm thick non-skid fully vitrified tiles of make "MARBONITE" "FERRASTONE" of minimum size 400 mm x 400 mm (overall 40 mm thick) laid in pattern with 5 mm thick glazed ceramic tile dado of same make topped with 50 mm wide matching ceramic trims. Height of dado shall be full height.		1st quality coloured glazed ceramic tiles of minimum 5 mm thickness up to 100 mm higher than lintel level starting from finish floor level. And balance portion with Acrylic emulsion paint over white cement putty.	Acrylic Distemper Paint
10 CW Chlorination Building	Minimum 20 mm thick acid and alkali resistant vitrified tile "ENDURA" or minimum 37mm thick Acid /Alkali resistant brick, set in		Chemical resistant paint in acid & alkali prone area and	Chemical resistant paint for acid & alkali resistant area

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001		
			VOLUME		
			SECTION		
			REV.NO.	0 14.05.2015	
		SHEET	70	OF	79
		and jointed with epoxy mortar (overall 50 mm thick) along with 2100 mm high dado of same tile having 20mm thickness. Where required, other areas with 50mm thick heavy duty flooring with metallic hardener.	rest with Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint over white cement putty for balance height	and other areas with Acrylic Distemper paint.	
11 CW Chemical Treatment Building		-Do-	-Do-		
12 Condensate Transfer Pump House		50 mm thick heavy duty cement concrete floor with metallic hardener and matching skirting	Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint for balance height	Acrylic Distemper	

7.7.3 Interior Finish Schedule For Non Plant Buildings

1 Service building/Administrative building			
a) Entry cum reception lounge, VIP lounge, Main meeting/ conference room	Suitable and approved combination shed of marble slab and strips shall be used	Two coats of Acrylic Emulsion paint of approved colour shall be applied over a coat of approved primer on the masonry surface prepared with white cement putty.	Aluminium panelled (600x600mm size) acoustic false ceiling with glass wool insulation on top similar to LUXALON of Hunter Douglas or "INTERARCH" having approved colour with stove enamel finish, integrated

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001	
			VOLUME	
			SECTION	
			REV.NO.	0 14.05.2015
		SHEET	71	OF 79
				with light fixtures, HVAC grills and other ceiling mounted accessories, complete in all respect with metal suspension system, trims, profiles etc.
b) Other floors/ office area etc.	10/11 mm thick non-skid fully vitrified tiles of make "MARBONITE", "FERRASTONE", "Kajaria" of minimum size 600 mm x 600 mm (overall 40 mm thick) laid in pattern with matching shirting of same make	- Do -	Gypsum board or Acoustic pre-coated aluminium alloy panelled ceiling (600x600mm panels) stove enamelled on both sides on pre coated aluminium grid system false ceiling of approved make as per specification	
c) For staircase and Corridors	Steps – risers & tread, stair skirting, corridor floor should be combination of Aranga white marble and Abu green marble. Wall cladding of Elevator Lobby shall be of polished granite slab of light grey shed or colour as approved by the owner.	Two coats of Acrylic Emulsion paint of approved colour shall be applied over a coat of approved primer on the masonry surface	Acrylic Distemper paint colour super white.	

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001			
		VOLUME			
		SECTION			
		REV.NO.	0 14.05.2015		
		SHEET	72	OF	79
			prepared with white cement putty.		
d) Toilet & pantry	Minimum 10 mm thick non-skid vitrified tile, of minimum size 400 mm x 400 mm (overall 40 mm thick) with glazed ceramic tile of same make dado topped with 50 mm wide matching moulded ceramic trims. Dado shall be 100 mm higher than lintel level starting from finish floor level.		1st quality coloured glazed ceramic tiles of minimum 5 mm thickness up to 100 mm higher than lintel level starting from finish floor level. And balance portion with Acrylic emulsion paint over white cement putty.		False ceiling shall be perforated aluminium stove enamel finished panels of size 600x600mm
e) AHU room, store Generator room, Electrical room, Etc:	50 mm thick heavy duty cement concrete floor with metallic hardener and matching skirting.		Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint with white cement putty for balance height		Acrylic Distemper paint
2 Canteen Building					
a) Kitchen, Dining hall etc.	10/11 mm thick non-skid fully vitrified tiles of make "MARBONITE",FERRASTONE"		1st quality coloured		Acrylic Distemper

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001	
			VOLUME	
			SECTION	
			REV.NO.	0 14.05.2015
			SHEET	73 OF 79
		of minimum size 600 mm x 600 mm (overall 40 mm thick) laid in pattern with 5 mm thick glazed ceramic tile dado of same make topped with 50 mm wide matching ceramic tiles. Dado shall be full height for Kitchen and 1500mm. high for other areas. All counter for Kitchen and service areas shall have Polished Granite slab over RCC slab or Kadapa stone	glazed tiles of minimum 6/7 mm thickness up to 1.20mts height and balance height with Acrylic emulsion paint over primer and white cement putty	paint over white cement putty. Airconditioned areas shall have Acoustic precoated aluminium alloy panelled ceiling (600x600mm panels) stove enamelled on both sides on pre coated aluminium grid system false ceiling of approved make as per specification
b) Other areas	Kota stone/equivalent flooring and skirting		Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint with white cement putty for balance height	Acrylic Distemper paint
c) Toilet & wash areas	10/11 mm thick non-skid fully vitrified tiles of make "MARBONITE", "FERRASTONE" of minimum size 400 mm x 400 mm over IPS floor (overall 40 mm thick) laid in pattern with 5 mm thick glazed ceramic tile dado of same make topped with 50 mm wide matching ceramic trims. Height of dado shall be 100mm higher than the lintel level starting from floor finish level.		1st quality coloured glazed ceramic tiles of minimum 5 mm thickness up to 100 mm higher than lintel level	Acrylic Distemper paint

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001			
			VOLUME			
			SECTION			
			REV.NO.	0 14.05.2015		
			SHEET	74	OF	79
			starting from finish floor level. And balance portion with Acrylic emulsion paint over white cement putty.			
3 Permanent Store & Inflammable Store Building	50 mm thick heavy-duty cement concrete floor with metallic hardener and matching skirting. For office areas & AC stores vitrified tiles shall be used.	Acrylic emulsion paint with white cement putty for office & AC store areas and Synthetic enamel paint up to 1.50mts height and Acrylic emulsion paint with white cement putty for balance height for other areas	Acrylic Distemper paint over white cement putty. Offices and Airconditioned areas shall have Acoustic precoated aluminium alloy panelled ceiling (600x600mm panels) stove enamelled on both sides on pre coated aluminium grid system false ceiling of approved make as per specification			
4 Main Gate Complex	Overall 40 mm thick Kota stone/equivalent slab flooring	Acrylic emulsion paint over white cement putty	Acrylic emulsion paint over white cement putty			
5 Weigh Bridge	10/11 mm thick non-skid fully vitrified tiles	Synthetic	Acrylic			

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.		SPECIFICATION NO. PE-DC-411-600-C001	
			VOLUME	
			SECTION	
			REV.NO.	0 14.05.2015
			SHEET	75 OF 79
Control room	of make "MARBONITE", "FERRASTONE" of size 600 mm x 600 mm (overall 40 mm thick) laid in pattern with 5 mm thick glazed ceramic tile dado of same make topped with 50 mm wide matching ceramic trims	enamel paint up to 1.50mts height and Acrylic emulsion paint with white cement putty for balance height	Distemper paint	
7 Fire Station				
a) Office area, Toilet, Stores, Training room, Kitchen / Dining area, Dormitory,	"10/11 mm thick non-skid fully vitrified tiles of make "MARBONITE", "FERRASTONE" of minimum size 600 mm x 600 mm (overall 40 mm thick) laid in pattern for office, dormitory area with 150 high matching skirting with 5 mm thick glazed ceramic tile dado of approved make topped with 50 mm wide matching ceramic trims 2200mm. High."	Acrylic emulsion paint	Acrylic emulsion paint	
b) Fire tender parking area and equipment store	50mm thick heavy duty IPS flooring with metallic hardener with matching skirting. or Paving with 65/70 mm thick pressed interlocking precast blocks	Cement paint and for equipment store Acrylic Distemper all be used	Parking area cement paint and for equipment store Acrylic Distemper shall be used.	
8 Watch Tower	IPS flooring with Cement Skirting	Acrylic Distemper, Epoxy paint over exposed steel structure.	Acrylic Distemper, Epoxy paint over exposed steel structure.	
9 Car & Scooter parking shed and Cycle parking shed	Mimimum 50mm thick coloured and polished interlocking concrete tiles with pattern as approved by the owner, set on sand bed over PCC underbed. Parking near Administrative block shall have vitrified tiles suitable for parking.		Polycarbonate roof sheeting over RCC framed structure.	

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	76	OF 79

7.7.4 EXTERIOR AND GENERAL FINISH SCHEDULE

Cladding for Power house:

Providing and fixing of double skin insulated wall cladding system comprising of profiled external sheet manufactured out of 0.55mm TCT (Total Coated Thickness) permanently colour coated zincalume steel (150 gsm. zinc – aluminium alloy coating total of both sides as per AS 1397: 1993) having 300 Mpa yield strength. The colour coating shall comprise of SMP / super polyester XRW (as per AS/NZS – 2728: 1997 category 3). The inner sheeting shall be 0.50mm/0.6mm TCT of SMP / super polyester XRW (as per AS/NZS – 2728: 1997 category 3) coated zincalume steel 150 gsm. (Zinc – aluminium alloy coating mass total of both sides as per AS 1397:1993) having 550 Mpa yield strength or 180gsm galvanised of 240 mpa. The colour coating shall comprise of 20 microns finish coat over a 5-micron primer coat on the exposed side and a back coat of 5 microns over a primer coat of 5 micron on the reverse side. The external sheet shall have 500mm cover width, 47mm high crests at 250mm centres with special male / female side laps and anti-siphoning feature to prevent leakage. The inner sheet shall have 980mm cover width 28mm high crests at 195mm centres with special male / female side laps and anti-siphoning features to prevent leakages. The inner sheet shall be fixed to the structure by means of self drilling fasteners no. 12-24 x 25 mm conforms to AS: 3566 Class-3 long at valley. Sub-girts of size 50mm x 50mm x 50mm manufactured out of 16G GI (1.6mm GI) 'Z' shape would be fixed the inner sheeting on face side at runner locations and outer sheeting shall be fixed with the help of concealed compatible interlocking clips and wafer head zinc coated self drilling fasteners / screws 4.2 x 25mm long on to the sub-girts. The clips shall be concealed and no fasteners are to penetrate the external sheeting. An insulation of 50mm thick Rockwool insulation (Rockloyd-300) of density 48KG/M3 conforming to IS:8183 shall be provided and fixed to the inner sheet and between the two sheets as per the specification. Wherever single skin metal cladding shall be used over

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001		
		VOLUME		
		SECTION		
		REV.NO.	0	14.05.2015
		SHEET	77	OF 79

brickwork, the material shall be same as the outer skin of insulated metal cladding system.

Approved make:

LLOYD Insulations (India) Ltd,
Tata Blue Scope Steel, CRIL,
Metecno or similar approved.

7.8 The epoxy systems

On the prepared substrate, one coat of a solvent free, resin based dispersion, Primer shall be applied. Density of the primer is around 1kg/lit and the mixing ratio of two components, Comp A and B : 1:2.5 by weight. Over the primed surface, epoxy modified cementitious self _levelling floor topping shall be laid maintaining the thickness of 2mm. The mixing ratio of three component Comp.A :Comp.B: Comp.C: 1:2.5:17 by weight, compressive strength at 30°C approx. 45N/mm² after 28days, the mortar density is around 2.2 kg/lit.

Priming should be done again with a primer of two component product, comp. A: comp. B: 4:1 (By weight). Prior to mixing of these two components, only comp. A shall be stirred mechanically. When all of part B is added to part A, the mix is to be stirred for 3 minutes until a smooth consistency is achieved. Finally, after drying of the primer, two coats of high-build, slightly thixotropic, chemical resistant epoxy protective coating shall be applied as the top coat. Minimum 2 coats are required. This is two component products, comp. A: comp. B: 3:1 (by weight). The mixed density is 1.5kg/lit at 270 C. The system shall be allowed for curing for 3 days.

Approved Make :

Sika India (P) Ltd., BASF or
similar approved.

7.9 Anti corrosive paint: Self Priming, Single Pack, Elastomeric (450% elongation), thermoplastic, fire retardant, Coating skin tensile strength 18 to 21 kg. Per sq. Cm. Antifungal, antibacterial, anticorrosive, nontoxic graft Co-polymer coating of Meta Chem Paints & Adhesive Pvt. Ltd or similar approved.

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 78 OF 79

7.10 False Ceiling :

Aluminium pre-painted false ceiling, either lineal panel system or aluminium tile/plank system

Approved make:

LUXALON by Hunter Douglas, LLOYD, Armstrong, INTERARCH or similar approved.

In other air-conditioned areas 12.5 mm Gypsum board/Mineral fibreboard /Calcium Silicate Board / Fibre Cement Board ceiling with aluminium grid will be used.

Approved make:

Saint Gobain Gyproc India Ltd, Armstrong, AMF, Everest, HILUX, Aerolite or similar approved.

7.11 For T.G. Hall (operating floor) Granite / Kota stone/equivalent flooring finish will be as follows:

Minimum 18~20 mm thick polished Granite/ Kota stone/equivalent slab or 600x600 mm tiles to be used over minimum 30 mm thick under-bed. Stones shall be hard, sound, homogeneous and dense in texture and free from flaws. Angles and edges shall be true, square, and free from chipping and surface shall be plane. The slabs shall preferably be machine cut to the required dimensions. Tolerance of + 5 mm in dimensions and + 2 mm in thickness will be allowed. During laying the slabs the edges of the slab shall be buttered with slurry of cement, mixed with pigment matching the colour of the stone slabs. Just before handing over the surface shall be dusted with oxalic acid at the rate of 0.33 gm. Per. Sq.m. water sprinkled on to it and finished by buffing with felt or Hessian bobs.

7.12 For battery room, battery charger room, chemical laboratories, chlorination room etc., the areas handling corrosive liquids, overall 40 mm thick Acid and

	TITLE: - 4X 270 MW Manuguru TPS SPECIFICATIONS FOR CIVIL, STRUCTURAL AND ARCHITECTURAL WORKS.	SPECIFICATION NO. PE-DC-411-600-C001
		VOLUME
		SECTION
		REV.NO. 0 14.05.2015
		SHEET 79 OF 79

Alkali resistant vitrified tiles flooring with 20mm thick tiles with silica based epoxy mortar shall be used. Acid and Alkali resistant vitrified tiles with silica based epoxy mortar up to 2.1M height from finished floor level shall be used as dado. Acid and Alkali resistant paint shall be applied up to the ceiling level above Acid and Alkali resistant tiles dado. Ceiling shall also be painted with Acid & Alkali resistant paint.

Approved Make : ENDURA of Jhonson, Chemstone
of BOSS Profiles Ltd, RESTILE
Ceramics Ltd. or similar approved.

Paints : ICI, ASIAN Paints, Berger or
similar approved

- 7.13** All areas of toilet, including W.C and urinal shall have vitrified ceramic tiles floor. Dado shall be of glazed tiles of minimum 5/6 mm thickness up to 100 mm higher than lintel level starting from finish floor level.

Approved Make : Ferrastone/Hardstone of BOSS
Profiles Ltd, RESTILE Ceramics
Ltd. , Marbonite, Kajaria, Nitco,
Endura of H R Jonson, or similar
approved.

- 7.14** For MCC and Switchgear rooms flexible electric insulated PVC synthetic sheet as per IS: 15652 2006 of Suntex Insulatic Pvt Ltd or similar shall be applied.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015


SHEET Page 1 of 361

**TELANGANA STATE ELECTRICITY
CORPORATION LIMITED (TSGENCO)
4X270MW BHADRADRI TPS**

**TECHNICAL SPECIFICATIONS
(EXCEPT CHIMNEY)**

CIVIL STRUCTURAL & ARCHITECTURAL WORKS

**PE-TS-411-600-C001
SECTION D
TECHNICAL SPECIFICATION(S)**



Bharat Heavy Electricals Limited

**Project Engineering Management
Power Sector, PPEI BUILDING
SECTOR 16A, NOIDA-201301**



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 2 of 361

INTRODUCTION

Bhadrachalam TPS(4X270MW) is being set up by Telangana State Power Generation Corporation Limited (TSGENCO) at Bhadrachalam in Manuguru District. .

The Bidder shall acquaint himself by a visit to the site, if felt necessary, with the conditions prevailing at site before submission of the bid. The information given here in under is for general guidance and shall not be contractually binding on BHEL/Owner. All relevant site data /information as may be necessary shall have to be obtained /collected by the Bidder.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 3 of 361

TABLE OF CONTENTS

D1	EARTHWORK IN EXCAVATION AND BACKFILLING
D2	CEMENT CONCRETE (PLAIN & REINFORCED)
D3	CARPENTARY & JOINERY
D4	ROOF AND UNDERGROUND STRUCTURES WATER PROOFING, INSULATION AND ALLIED WORKS
D5	METAL DOORS, WINDOWS, VENTILATORS, LOUVERS ETC.
D6	GLASS AND GLAZING
D7	ROLLING STEEL SHUTTERS AND GRILLS
D8	MISCELLANEOUS METAL
D9	MASONRY AND ALLIED WORKS
D10	FINISH TO MASONRY AND CONCRETE
D11	PAINTING, WHITEWASHING, POLISHING
D12	FLOOR FINISH AND ALLIED WORKS
D13	SHEET WORK IN ROOF AND SIDING
D14	SUSPENDED CEILING
D15	WATER SUPPLY, DRAINAGE AND SANITATION
D16	ROADS AND DRAINAGE
D17	FABRICATION OF STRUCTURAL STEEL WORK
D18	ERECTION OF STRUCTURAL STEEL WORK
D19	ROOF DECKING
D20	FALSE FLOORING
D21	PILLING
D22	SITE LEVELLING & GRADING



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 4 of 361

SECTION - D

SUB-SECTION – D1

EARTHWORK IN EXCAVATION AND BACKFILLING



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 5 of 361

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	CODES AND STANDARDS
3.00.00	EXECUTION
4.00.00	TESTING AND ACCEPTANCE CRITERIA
5.00.00	RATES AND MEASUREMENTS
6.00.0	INFORMATION TO BE SUBMITTED BY THE BIDDER



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 6 of 361

TECHNICAL SPECIFICATION

FOR EARTHWORK IN EXCAVATION AND BACKFILLING

1.00.00 SCOPE

This specification covers earth work excavation in all types of soil, soft rock and hard rock including setting out, clearing and grubbing, shoring, dewatering, back filling around foundations/pipelines to grade, watering, compaction of fills, testing, approaches, disposal of surplus earth, protective fencing, lighting etc relevant to the structures and locations covered under this contract.

1.01.00 Work To Be Provided By The Contractor

The work to be provided for by the contractor unless specified otherwise shall include but not be limited to the following.

- a) Supplying and providing all labour, supervision services including as required under statutory labour regulations, materials, scaffolding, equipments, tools and plants, transportation etc required for the work.
- b) Preparation and submission of working drawings showing the approaches, slopes, berms, shoring, sumps for dewatering including drainage, space for temporary stacking of soils, disposal area, fencing etc and all other details as may be required by the engineer.
- c) Carrying out sampling and testing on fill materials/fills to assess the quality/moisture content/degree of compaction and submission of the test results whenever required by the engineer.
- d) Design, construction and maintenance of Magazine of proper capacity for storage of explosives for blasting work and removal of the same after completion of the work etc.

1.02.00 Work to be provided by others

No work under this specification will be provided by any agency other than the contractor unless specifically mentioned elsewhere in the contract.

2.00.00 Codes and Standards

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes unless specified otherwise.

IS: 1200 Method of measurement of building and civil engineering



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 7 of 361

works, Part-I: Earthwork

- IS: 2720 Method of test for soils (Relevant parts)
- IS: 3764 Excavation work - Code of safety
- IS: 4081 Safety code for blasting and related drilling operations
- IS: 4701 Indian Standard Code of Practice for earthwork on Canals
- IS: 6922 Criteria for safety and design of structures subject to underground blasts

In case of conflict between this specification and those (IS Codes) referred to herein, the former shall prevail. In case any particular aspect of work is not covered specifically by this specification/IS Codes, any other standard practice as may be specified by the engineer shall be followed.

2.01.00 Conformity with Designs

The contractor shall carry out the work as per the approved drawings, specification and as directed by the engineer.

2.02.00 Materials

2.02.01 General

All materials required for the work shall be of the best commercial variety and approved by the engineer.

2.02.02 Material for Excavation

For the purpose of identifying the various strata encountered during the course of excavation, the following classifications are to be followed.

a) Soil

It include all type of soil including laterite and moorum etc with/without any percentage of kankars which can be excavated by normal means such as shovel, pick axe, crow bar, spade etc and those which do not fall under clause 2.02.02 (b) and (c) etc.

b) Soft Rock

It include the rocks (including weathered rock) which are removable by splitting with the help of crow bar, pick axe, wedges, pavement breakers, pneumatic tools, hammers or such implements etc and not requiring blasting (for excavation) in the opinion of the engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 8 of 361

c) Hard Rock

It includes the rocks, which require blasting for excavation in the opinion of the engineer. Where blasting is prohibited for any reasons, the excavation shall be carried out by chiselling or any other method as approved by the engineer. The mere fact that the contractor resorts to blasting shall not classify the soft rock under hard rock.

However, the engineer's decision on the type of strata encountered during excavation shall be the final and binding on the contractor.

2.02.03 Material for Filling

Material to be used for back filling shall be free from vegetations, roots, salts, rubbish, lumps, organic matter and any other harmful chemicals etc and shall be got approved by the engineer. Normally excavated earth shall be used for back filling. In case such earth contains deleterious salts, the same shall not be used. All clods of earth shall be broken or removed. Where the excavated material is mostly rock and if filling with the same is permitted by the engineer in writing, then the filling with rock shall be done in the following manner. The boulders shall be broken into pieces not exceeding 150mm size in any direction and mixed with fine materials consisting of decomposed rock, moorum or any approved earth to fill the voids as far as possible and the mixture shall then be used for filling.

In case the earth required for backfilling is over and above the earth available from the compulsory excavations within the project area, then borrow areas for obtaining suitable fill material shall be arranged by the contractor himself from outside the plant boundary limits and all expenses including royalties, taxes, duties etc shall be borne by him. The selected earth from the borrow areas shall be got approved by the engineer. The borrowed material shall be free from roots, vegetations, decayed organic matter, harmful salts and chemicals, free from lumps and clods etc. The contractor shall obtain and submit necessary clearances/permissions from the concerned authorities for the borrow areas/materials acquired to the engineer.

If specified, the back filling shall be done with clean well-graded sand from approved quarries free from harmful and deleterious materials.

2.03.00 Quality Control

All works shall confirm to the lines, levels, grades, cross sections and dimensions shown on the approved drawings and/or as directed by the engineer. The contractor shall establish and maintain quality control for the various aspects of the work, method of construction, materials and equipments used etc. The quality control operation shall include but not be limited to the following.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 9 of 361

Sl. No.	Activity	Check
1	Lines, levels & grades	a) By periodic surveys b) By establishing markers, boards etc
2	Back filling	(a) On quality of fill material (b) On moisture content of back fill (c) On degree of compaction achieved

3.00.00 EXECUTION

The contractor shall prepare and submit the detailed drawings/schemes for excavation and back filling works as proposed to be executed by him showing the dimensions as per the construction drawings and specification adding his proposal of slopes, shoring, approaches, dewatering, drainage, berms and compaction etc within 15 days of award of the contract to the engineer for approval.

3.01.00 Setting out

On receiving the approval from the engineer with modifications and corrections if any, the contractor shall set out the work from the control points furnished by the engineer and fix permanent points and markers for ease of periodic checking as the work proceeds. These permanent points and markers shall be fixed at the interval as prescribed by the engineer and shall be got checked and certified by the engineer after whom the contractor shall proceed with the work. It should be noted that this checking by the engineer prior to the start of the work will in no way relieve the contractor of his responsibilities of carrying out the work to true lines, levels and grades as per the drawings and specification. If any errors are noticed in the contractor's work at any stage, the same shall be rectified by the contractor at his own risk and cost.

3.02.00 Clearing and Grubbing etc

The area to be excavated shall be cleared out of fences, trees, logs, stumps, bushes, vegetation, rubbish, slush etc. Trees upto 300mm girth shall be uprooted. Trees above 300mm girth to be cut shall be approved by the engineer and marked. Cutting of trees shall include removing roots as well. After the tree is cut and roots taken out, the pot holes formed shall be filled with good earth in 250mm layers and compacted unless directed otherwise by the engineer. The trees shall be cut in to suitable pieces as instructed by the engineer. Before earthwork is started, all the spoils, unserviceable materials and rubbish shall be burnt or removed and disposed to the approved disposal area(s) as specified by the engineer. Useful materials, saleable timber, fire woods etc shall be the property of the owner and shall be stacked properly at the worksite in a manner as directed by the engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 10 of 361

3.03.00 Excavation for Foundations and Trenches

3.03.01 General

All excavation shall be done to the minimum dimensions as required for the safety and working facility. In each individual case, the contractor shall obtain prior approval of the engineer for the method he proposes to adopt for the excavation including dimensions, side slopes, shoring, dewatering, drainage and disposal etc. This approval however shall not in any way make the engineer responsible for any consequent loss or damage. The excavation must be carried out in the most expeditious and efficient manner. All excavation in open cuts shall be made true to the line, slopes and grades as shown on the drawings or as directed by the engineer. No material shall project within the dimension of minimum excavation lines marked. Boulders (if any) projecting out of the excavated surfaces shall be removed if they are likely to be a hindrance to the work/workers in the opinion of the engineer.

Method of excavation shall in every case be subject to the approval of the engineer. The contractor shall ensure the stability and safety of the excavation, adjacent structures, services and works etc including the safety of the workmen. If any slip occurs, the contractor shall remove all the slipped materials from the excavated pit without any extra cost to the engineer/owner. All loose boulders and semi detached rocks which are not inside but so close to the area to be excavated and may liable to fall or otherwise endanger the workmen, equipment of the work etc during excavation in the opinion of the engineer shall be stripped off and removed away from the area of excavation. The method to be used for removal shall be such that it should not shatter or render unstable or unsafe the portion, which was originally sound and safe. In case any material not required to be removed initially but later to become loose or unstable in the opinion of the engineer shall also be promptly and satisfactorily removed.

The rough excavation may be carried out upto a maximum depth of 150 mm above the final level. The balance shall be excavated with special care. If directed by the engineer, soft and undesirable spots shall be removed even below the final level. The extra excavation shall be filled up as instructed by the engineer. If the excavation (in all types of soil and rock) is done to a depth greater than that shown on the drawing or as directed by the engineer, the excess depth up to the required level shall be filled with cement concrete not leaner than 1:4:8 or richer as directed by the engineer at the own risk and cost of the contractor. In case where excavation in soil, soft rock (including weathered rock) and hard rock are involved, the excavation in each stratum shall be carried out separately with the approved methodology and as per the instructions of the engineer.

All excavated materials such as rock, boulders, bricks, dismantled concrete blocks etc shall be the property of the owner and shall be stacked separately as



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 11 of 361

directed by the engineer. All gold, silver, oil, minerals, archeological and other findings of importance, trees cut or other materials of any description and all precious stones, coins, treasures, relics, antiquities and other similar things which may be found in or upon the site shall be the property of the owner and the contractor shall duly preserve the same to the satisfaction of the engineer/owner. The contractor shall deliver the same to such person or persons as may be authorized or appointed from time to time by the owner to receive the same.

Prior to starting the excavation, the ground level at the location shall be checked jointly with the engineer.

3.03.02 Excavation in All Type of Soil and in Soft Rock

The excavation in all type of soil, soft rock including decomposed rock etc shall be carried out as per the approved proposal and as directed by the engineer. The work shall be carried out in a workmanlike manner without endangering the safety of nearby structures/services or works and without causing hindrance to any other activities in the area. Foundation pits shall not be excavated to the full depth unless construction is imminent. The last 150mm depth shall be excavated once concreting work is imminent. At the discretion of the engineer, the full depth may be excavated and the bed be covered with lean concrete as specified after watering and compacting the bed. As the excavation reaches the required dimensions, lines, levels and grades etc, the work shall be got checked and approved by the engineer. In cases where deterioration of the ground, upheaval, slips etc are expected, the engineer may order to suspend the work at any stage and instruct the contractor to carry out the protection works before the excavation will be restarted.

3.03.03 Excavation in Hard Rock

Hard rocks shall normally be excavated by means of blasting. In case where blasting is prohibited for any reasons, the excavation shall be carried out by chiselling or any other approved method as directed by the engineer. Personnel deployed for rock excavation shall be protected from all hazards such as loose rock/boulder rolling down and from general slips of excavated surfaces. Where the excavated surface is not stable against sliding, necessary supports such as props, bracings or bulkheads shall be provided and maintained during the period of construction. Where the danger of falling loose rock/boulder from the excavated surfaces deeper than 2m exist, steel mesh anchored to the lower edge of the excavation and extending over and above the rock face adequate to retain the dislodged material shall be provided and maintained.

3.03.04 Blasting

a) General



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 12 of 361

Storage, handling and use of explosives shall be governed by the current explosive rules/regulations laid down by the Central and the State Governments. The contractor shall ensure that these rules/regulations are strictly adhere to. The following instructions are also to be strictly followed and the instructions wherever found in variance with the above said rules/regulations, the former (instructions) shall be superseded with the later (above said rules/regulations).

No child under the age of 16 and no person who is in a state of intoxication shall be allowed to enter the premises where explosives are stored nor they shall be allowed to handle the explosives. The contractor shall obtain licence from the District Authorities for undertaking the blasting work as well as for obtaining and storing the explosives as per Explosives Rules, 1940 corrected upto date. The contractor shall purchase the explosives, fuses, detonators etc only from a licensed dealer and shall be responsible for the safe custody and proper accounting of the explosive materials. The engineer or his authorized representative shall have the access to check the contractor's store of explosives and his accounts at any time. It is the full responsibility of the contractor to transport the explosives as and when required for the work in a safe manner to the work spot.

Further, the engineer may issue modifications, alterations and new instructions from time to time. The contractor shall comply with the same without these being made a cause for any extra claim.

b) Materials

All materials such as explosives, detonators, fuses, tamping materials etc proposed to be used in the blasting operation shall have the prior approval of the engineer. Only explosives of approved make and strength are to be used. The fuses known as instantaneous fuse must not be used. The issue of fuse with only one protective coat is prohibited. The fuse shall be sufficiently water resistant as to be unaffected when immersed in water for 30 minutes. The rate of burning of the fuse shall be uniform and shall be not less than 4 seconds per inch of length with 10% tolerance on either side. Before use, the fuse shall be inspected. Moist, damaged or broken ones shall be discarded. When the fuses are in stock for long, the rate of burning of fuses shall be tested before use. The detonators shall be capable of giving an effective blasting of the explosives. Moist and damaged detonators shall be discarded.

c) Storage of Explosives

The current Explosive Rules shall govern the storage of explosives. Explosives shall be stored in a clean, dry and well-ventilated magazine to be specially built for the purpose. Under no circumstances should a



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 13 of 361

magazine be erected within 400m of the actual work site or any source of fire. The space surrounding the magazine shall be fenced and the ground inside shall be kept clear and free from trees, bushes etc. The admission to this fenced space shall be through a single gate only and no person shall be allowed without the permission of the officer-in-charge. The clear space between the fence and the magazine shall not be less than 90m. The magazine shall be well drained. Two lightning conductors, one at each end shall be provided to the magazine. The lightning conductors shall be tested once in every year.

Explosives, fuses and detonators shall each be separately stored. Cases of explosives must be kept clear of the walls and floors for free circulation of air on all sides. Special care shall be taken to keep the floor free from any grains of explosives. Cases containing explosives shall not be opened inside the magazine and the explosives in open cases shall not be received into a magazine. Explosives which appear to be in a damaged or dangerous condition are not to be kept in any magazine but must be removed without delay to a safe distance and be destroyed.

Artificial light, matches, inflammable materials, oily cotton, rag waste and articles liable to spontaneous ignition shall not be allowed inside the magazine. Illumination shall be obtained from an electric storage battery lantern. No smoking shall be allowed within 100m distance from any magazine.

Magazine shoes without nails shall be used while entering the magazine. The persons entering the magazine must put on the magazine shoes, which shall be provided at the magazine for this purpose and should be careful

- * not to put their feet on the clean floor unless the magazine shoes on.
- * not to touch the magazine shoes on ground outside the clean floor.
- * not to allow any dirt or grit to fall on the clean floor.

Persons with bare feet shall dip their feet in water before entering the magazine and then step directly from the tub to the clean floor. No person having article of steel or iron with/on him shall be allowed to enter the magazine. Workmen shall be examined before entering the magazine to check none of the prohibited articles are with them. A brush broom shall be kept in the lobby of the magazine for cleaning the magazine. Cleaning shall be done immediately after each occasion whenever the magazine is opened for receipt, delivery or inspection of the explosives.

The mallets, levers, wedges etc for opening the barrels or cases shall be of wood. The cases of explosives are to be carried by hand and shall not be rolled or dragged inside the magazine. Explosives which have been issued and returned to the magazine are to be issued first; otherwise those which



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 14 of 361

have been stored long in the store are to be issued first. Neither the magazine shall be opened nor any person shall be allowed in the vicinity of the magazine during any dust storm or thunderstorm. All magazines shall be officially inspected at definite intervals and a record of such inspections shall be kept.

d) Carriage of Explosives

Detonators and explosives shall be transported separately to the blast site. Explosives shall be kept dry and away from the direct rays of the sun, artificial lights, steam pipes or heated metal and other sources of heat. Before explosives are removed, each case or package shall be carefully examined to ascertain that it is properly closed and shows no sign of leakage.

No person except the driver shall be allowed to travel on the vehicle conveying explosives. No explosive shall be transported in a carriage or vessel unless all iron or steel therein the carriage or vessel which are likely to contact the package containing explosives are effectually covered with lead, leather, wood, cloth or any other suitable material. No light shall be carried on the vehicle carrying explosives and no operation connected with the loading, unloading and handling of explosives shall be conducted after sunset.

e) Use of Explosives

The contractor shall appoint an agent who shall personally superintend the firing and all operations connected therewith. The contractor shall satisfy himself that the person so appointed is fully acquainted with his responsibilities.

Holes for charging the explosives shall be drilled with pneumatic drills and the drilling pattern shall be so planned that the rock pieces after blasting will be suitable for handling. The hole diameter shall be of such a size that the cartridges can easily pass down through them and any undue force is not required during charging. Charging operation shall be carried out by or under the personal supervision of the shot firer. Wrappings shall never be removed from the explosive cartridges. Only one cartridge at a time shall be inserted in a hole and wooden rods shall only be used for loading and stemming the shot holes. Only such quantities of explosives as are required for a particular work shall be brought to the work site. Should any surplus remain when all the holes have been charged shall be carefully removed to a point at least 300m away from the firing point.

The authorized shot firer himself shall make all the connections. The shot firing cable shall not be dragged along the ground to avoid any damage to the insulation. The shot firing cable shall be tested each time for its continuity and possible short-circuiting. The shot firer shall always carry



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 15 of 361

the exploder handle with him until he is ready to fire shots. The number of shots fired at a time shall not exceed the permissible limits. Before any blasting is carried out it shall be ensured that all workmen, vehicles and equipment on the site are cleared from an area of minimum 300m radius from the firing point or as required by the statutory regulations at least 10 minutes before the time of firing by sounding a warning siren and the area shall be encircled by red flags.

The explosives shall be fired by means of an electric detonator placed inside the cartridge. For simultaneous firing of a number of charges, the electric detonators shall be connected with the exploder through the shot firing cable in a simple series circuit. Due precautions shall be taken to keep the firing circuit insulated from the ground, bare wires, rails, pipes or any other path of stray current etc and keep the lead wires short circuited until it is ready to fire. Any kink in the detonator leading wire shall be avoided. For simultaneous firing of a large number of shot holes, use of cordtex may be done. An electric detonator attached to its side with adhesive tape shall initiate cordtex connecting wire or string. Blasting shall only be carried out at certain specified times to be agreed jointly by the contractor and the engineer.

At least five minutes after the blast has been fired in case of electric firing or as stipulated in the regulations, the authorized shot firer shall return to the blast area and inspect carefully the work and satisfy himself that all the charged holes have exploded. Cases of misfired unexploded charges shall be exploded by drilling a parallel fresh hole at a distance of not less than 600mm from the misfired hole and by exploding a new charge. The authorized shot firer shall be present during the removal of debris as it may contain unexploded explosives near the misfired hole. The workmen shall not return to the site of firing until at least half an hour after firing.

Where blasting is to be carried out in proximity of other structures, controlled blasting by drilling shallow shot holes and proper muffling arrangements with steel plates loaded with sand bags etc shall be used on top of the blast holes to prevent the rock fragments from causing any damage to the adjacent structures and other properties. Adequate safety precautions as per building byelaws, safety codes, statutory regulations etc shall be taken during blasting operations.

f) Restrictions in Blasting

- a) Blasting which may disturb or endanger the stability, safety or quality of the adjacent structures/foundations shall not be permitted.
- b) Blasting within 200m of a permanent structure or construction work in progress shall not be permitted.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 16 of 361

- c) Progressive blasting shall be limited to two third of the total remaining depth of excavation.
- d) No large scale blasting operations will be resorted to when the excavation reaches the last one metre and only small charge preferably black powder may be allowed so as not to shatter the parent rock
- e) The last blast shall not be more than 0.50 m in depth.
- f) In rocky formations, at locations where specifically indicated or ordered in writing by the engineer, the use of explosives shall be discontinued and chiselling shall complete excavation or any other suitable method as approved by the engineer.

3.03.05 Disposal

The excavated spoils shall be disposed of in any (or all) of the following manner as directed by the engineer.

- a) By using it straightway for backfilling.
- b) By stacking it temporarily to use for backfilling at a later date during execution of the contract.
- c) i) By either spreading
or
ii) By spreading and compacting at designated disposal areas.
- d) By selecting the useful material and stacking it neatly in designated areas as indicated by the engineer for use in backfilling by some other agency.

3.03.06 Disposal of Surplus Materials

All surplus material from excavation shall be removed and disposed of from the excavation site to the designated disposal area indicated by the engineer. All good and sound rocks obtained from excavations and all assorted materials of dismantled structures are the property of the owner and if the contractor wants to use it, he shall have to obtain it from the engineer at a mutually agreed rate. All sound rocks and other assorted materials like excavated bricks etc shall be stacked separately.

3.03.07 Protection

The contractor shall notify the engineer as soon as the excavation is expected to be completed within a day so that he shall inspect it at the earliest. Immediately after approval of the engineer, the excavation must be covered up in a shortest possible time. But in no case the excavation shall be covered up or worked on before approval by the engineer. Excavated material shall be



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 17 of 361

placed 1.5m or half the depth (of excavation) whichever is more from the edge of the excavation or further away if directed by the engineer. Excavation shall not be carried out below the foundation level of the structure close by until the required precautions are taken. Adequate fencing is to be made enclosing the excavation. The contractor shall protect all the underground services exposed during excavation. All existing surface drains in the work area shall be suitably diverted by the contractor before taking up excavation to maintain the working area neat and clean.

3.03.08 Dewatering

All excavation shall be kept free of water and slush. Grading in the vicinity shall be controlled to prevent the surface water running into the excavations. The contractor shall remove any water inclusive of rain water and subsoil water etc accumulated in the excavation by pumping or other means as approved by the engineer and keep the excavations dewatered and/or lower the subsoil water level to 300mm below the founding level until the construction of foundation and backfilling are completed in all respects.

Sumps made for dewatering must be kept clear of the foundations. The engineer's prior approval on the method of pumping to be adopted shall be taken; but in any case, the pumping arrangement shall be such that there shall be no movement or blowing in of subsoil due to the differential head of water during pumping.

3.03.09 Timber Shoring

Close or open type timber shoring as approved by the engineer depending on the nature of sub-soil, depth of pit or trench and the type of timbering shall be adopted. Timbers made out of approved quality shall only be used. It shall be the responsibility of the contractor to take all necessary steps to prevent the sides of trenches and pits from collapsing.

a) Close Timbering

Close timbering shall be done by completely covering the sides of the trenches and pits generally with short, upright members called "polling boards". These shall be of 250mm wide (min.) and 40mm thick (min.) sections as directed by the engineer. The boards shall generally be placed vertically in pairs, one on each side of the cut and shall be kept apart (maximum spacing is limited to 1.20m) by horizontal walers of strong wood cross strutted with wooden struts or as directed by the engineer. The length of wooden struts shall depend on the width of the trench or pit.

In case where the soil is very soft and loose, the boards shall be placed horizontally against the sides of excavation and supported by vertical walers, which shall be strutted to similar timber pieces on the opposite face of the trench or pit. The lowest board supporting the sides shall be taken



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 18 of 361

into the ground. No portion of the vertical side of the trench or pit shall remain exposed to avoid any slipping out of earth.

The withdrawal of the timber shall be done very carefully to prevent the collapse of the pit or trench. It shall be started from one end and preceded systematically to the other end. Concrete or masonry shall not be damaged during the removal of the timber. No claim shall be entertained for any timber, which cannot be withdrawn and is lost or buried.

b) Open Timbering

In case of open timbering, vertical board of 250mm wide (min.) and 40mm thick (min.) shall be spaced sufficiently apart to leave unsupported strips of maximum 500mm average width. The detailed arrangement, size of timber and the spacing etc shall be subjected to the approval of the engineer. In all other respects, the specification for close timbering shall apply to open timbering as well.

3.03.10 Treatment of Slips

The contractor shall take all precautions to avoid high surcharges and provide proper surface drainage to prevent flow of water over the sides of the excavations. These precautions along with proper slopes, berms, shoring and control of ground water should cause no slips to occur. If however slips still occur, the same shall be removed by the contractor with his own risk and cost.

3.04.00 Backfilling

3.04.01 General

The material to be used for backfilling shall be approved by the engineer which shall be obtained directly from the excavation, from the nearby areas where excavation work by the same agency is in progress, from the temporary stacks of excavated spoils or from the borrow pits as directed by the engineer. The material shall be free from lumps and clods, roots and vegetations, harmful salts and chemicals, organic materials etc.

In locations where sand filling is required, the sand used should be clean, well graded and be of the quality normally acceptable for use in concrete.

3.04.02 Filling and Compaction in Pits and Trenches all Around the Structures

As soon as the work in foundation has been accepted, the spaces around the foundation in pits and trenches shall be cleared of all debris, brick bats, mortar droppings etc and filled with approved earth in layers not exceeding 250mm (in loose thickness). Each layer (loose) shall be watered, rammed and properly compacted to the required degree to the satisfaction of the engineer. Earth shall be compacted with approved mechanized compaction machine. Usually,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 19 of 361`

no manual compaction shall be allowed unless specifically permitted by the engineer. The moisture content of the fill material during compaction shall be controlled near to its optimum moisture content so as to obtain the required degree of compaction. The final surface shall be trimmed and levelled to proper profile as desired by the engineer.

3.04.03 Plinth Filling

The plinth shall be filled with earth in layers not exceeding 250mm (in loose thickness) and each layer shall be watered and compacted to the required degree with approved compaction machine or manually if specifically permitted by the engineer. When the filling reaches the finished level, the surface shall be flooded with water for at least 24 hours, allowed to dry and then rammed and compacted in order to avoid any settlement at a later stage. The finished surface of fill shall be trimmed to the slope intended to be provided for the floor.

3.04.04 Filling in Trenches for Water Pipes and Drains

Filling in trenches for pipes and drains shall be commenced as soon as the joints of pipes and drains have been tested and passed. Where the trenches are excavated in soil, the filling shall be done with earth on the sides and top of pipes in layers not exceeding 150mm, watered, rammed and compacted taking care that no damage is caused to the pipe below.

In case of trenches excavated in rock, the filling upto a height of 300mm or the diameter of the pipe whichever is more above the crown of the pipe or barrel shall be done with fine material such as earth, moorum, disintegrated rock or ash as per the availability at site and shall be filled in compacted layers not exceeding 150mm. The remaining filling shall be done in layers with the mixture of boulders (of size not exceeding 150mm) and fine material as specified elsewhere in the specification. Each layer shall be watered, rammed and compacted to the required degree and to the satisfaction of the engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 20 of 361

3.04.05 Filling in Disposal Area

Surplus materials from excavation which are not required for backfilling shall be disposed of in the designated disposal areas. The spoils shall not be dumped haphazardly but should be spread in layers approximately 250mm thick when loose, watered and compacted with the help of compacting equipment as per the directions of the engineer. In wide areas, rollers shall be employed and compaction shall be done to the satisfaction of the engineer at the optimum moisture content, which shall be checked and controlled by the contractor. In certain cases the engineer may direct the contractor to dispose the surplus materials without compaction, which can be done by tipping the spoils from a high bench neatly maintaining a proper level and grade of the bench.

3.05.00 Approaches and Fencing

The contractor should provide and maintain proper approaches for the workmen and inspection. The roads and approaches around the excavation should be kept clear at all times so that there is no hindrance to the movement of men, material and equipment of various agencies connected with the project. Sturdy and elegant fencing is to be provided around the top edge of the excavation as well as around the bottom of the fill at the surplus disposal area where dumping from a high bench is in progress.

3.06.00 Lighting

Full-scale area lighting is to be provided if night work is permitted or directed by the engineer. If no night work is in progress, red warning lights should be provided at the corners of the excavated pit and the edges of the fill.

4.00.00 TESTING AND ACCEPTANCE CRITERIA

4.01.00 Excavation

On completion of excavation, the dimension of the pits will be checked as per the drawings after the pits are completely dewatered. The work will be accepted after all undercuts have been set right and all over excavations are filled back to the required lines, levels and grades by placing ordinary cement concrete of 1:4:8 proportion and/or richer and/or by compacted earth as directed by the engineer. The choice of the grade of concrete will be a matter of unfettered discretion of the engineer. Over excavation of the sides shall be made good by the contractor while carrying out the backfilling. The excavation work will be accepted after the above requirements are fulfilled and all the temporary approaches encroaching inside the excavation have been removed.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 21 of 361

4.02.00

Backfilling

The degree of compaction required will be as per the stipulation laid down in IS: 4701 and the actual method of measuring the degree of compaction will be as decided by the engineer. The work of back filling will be accepted after the engineer is satisfied with the degree of compaction achieved.

5.00.00

RATES AND MEASUREMENTS

5.01.00

Rates

- a) The item of work in the schedule of quantities describes the work very briefly. The various items of the schedule of quantities shall be read in conjunction with the corresponding section in the technical specification including amendments and additions if any. For each item in the schedule of quantities, the bidder's rate shall include all the activities covered in the description of the items as well as for all necessary operations in detail as described in the technical specification.
- b) No claims shall be entertained if the details shown on the released for construction drawings differ in any way from those shown on the tender drawings.
- c) The unit rate quoted shall include minor details which are obviously and fairly intended and which may not have been included in these documents but are essential for the satisfactory completion of the work.
- d) The bidder's quoted rate shall be inclusive of supplying and providing all labour, men, materials, equipments, tools and plants, supervision, services, approaches, schemes etc.
- e) In case blasting in hard rock is envisaged, the unit rate quoted for earthwork shall include the cost of storage and safety arrangements for the materials required for blasting. No separate payment will be made on this account.

5.02.00

Measurements

Method of measurements are specified in the proceeding sections. Where not so specified, the latest version of IS: 1200, Part-1 shall be applicable.

- a) The length, breadth and depth shall be measured correct to the nearest centimetre if measurements are taken by tape. Rounding of numerical shall be as per relevant IS Codes. If the measurements are taken with staff and level, the levels shall be recorded correct to 5mm. The area and volume shall be worked out in square meter and cubic meter respectively correct to the nearest of two decimal places.
- b) For earthwork in excavation, the ground levels shall be taken before and after completion of the work in the actually excavated area. The quantity of earthwork in excavation shall be computed from these levels in cubic meter.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 22 of 361

- c) Where soft rock and hard rock are mixed, the measurement shall be done as follows. The two types of rock shall be stacked separately and measured in stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in the stacks. If the sum of net quantity of the two types of rock so arrived exceeds the total quantity of the excavation, then the quantity of each type of rock shall be worked out from the total quantity (from excavation) in the ratio of net quantities in stack measurements of the two types of rock. If stacking is not feasible, the method as suggested by the engineer shall be followed.
- d) Where soil, soft rock and hard rock are mixed, the measurement shall be done as follows. The soft and hard rock shall be removed from the excavated material and stacked separately and measured in stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in stacks. The difference between the entire excavation and the sum of the quantities of soft and hard rock so arrived shall be taken as soil.

6.00.00 INFORMATION TO BE SUBMITTED BY THE BIDDER

6.01.00 With Tender

Detail of equipments and machineries proposed to be used for excavation, backfilling and compaction shall be submitted along with the tender.

6.02.00 After Award

After award of the contract the successful bidder shall submit the following for approval.

- a) Within 30 days of the award of contract, the contractor shall submit a detailed programme of the work as proposed to be executed giving completion dates of excavation for the various foundations and the time required for backfilling and compaction after completion of foundation for the structures. The earthwork programme shall be planned in accordance with the foundation programme. The programme should also show how the excavation and backfilling quantities will be balanced minimizing the temporary stacking of spoils. It is to be noted that the engineer even after initial approval of the programme may instruct the contractor to enhance or to retard the progress of work during the actual execution in order to match with the progress of foundations. The initial programme being submitted by the contractor should have sufficient flexibility to take care of such reasonable variations.
- b) Within 15 days of the award of contract, the contractor shall submit the drawings for earth work in excavation and backfilling showing detail of slopes, shoring, approaches, sump pits, dewatering lines, fencing etc for the approval of the engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 23 of 361`

SECTION - D

SUB-SECTION – D2

CEMENT CONCRETE (PLAIN & REINFORCED)



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 24 of 361`

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	GENERAL
3.00.00	INSTALLATION
4.00.00	SAMPLING AND TESTING
5.00.00	ACCEPTANCE CRITERIA
6.00.00	RATES AND MEASUREMENTS
7.00.00	LIST OF I.S.: CODES AND STANDARDS FOR REFERENCE



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 25 of 361

SUB-SECTION – D II

CEMENT CONCRETE (PLAIN & REINFORCED)

1.00.00 SCOPE

1.01.00 General

This specification covers all the requirements, described hereinafter for general use of Plain and Reinforced Cement Concrete work in Structures and locations, cast-in-situ or precast, and shall include all incidental items of work not shown or specified but reasonably implied or necessary for the completion of the work. Special requirements for structures such as reinforced concrete chimney, cooling towers, etc. have been covered under the respective specifications. Those specifications shall be used in conjunction with this specification.

1.02.00 IS: 456 shall form a part of this specification and shall be complied with unless permitted otherwise. For any particular aspect not covered by this Code, appropriate Code, specifications and/or replacement by any International code of practice as may be specified by the Engineer shall be followed. All codes and Standards shall conform to its latest revisions. A list of IS codes and Standards is enclosed hereinafter for reference. However, should the list be not exhaustive and does not cover any aspect of the work, then relevant Indian and, in its absence, relevant International code shall apply.

2.00.00 General

2.01.00 Work to be provided for by the Contractor

The work to be provided for by the Contractor, unless otherwise specified shall include but not be limited to the following

- a) Furnish all labour, supervision, services including facilities as may be required under statutory labour regulations, materials, forms, templates, supports, scaffolds, approaches, aids, construction equipment, tools and plants, transportations, etc. required for the work.
- b) Prepare Bar bending Schedules for reinforcement bars showing the positions and details of spacers, supports, chairs, hangers etc.
- c) Prepare working drawings of formworks, scaffolds, supports, etc.
- d) Prepare shop drawings for various inserts, anchors, anchor bolts, pipe sleeves, embedments, hangers, openings, frames etc.
- e) Prepare detailed drawings of supports, templates, hangers, etc. required for installation of various embedments like inserts, anchor bolts, pipe sleeves,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 26 of 361

frames, joint seals, frames, openings etc.

As decided by the Engineer some or all of the drawings & schedules prepared under item (b) to (e) above will have to be submitted for approval.

- f) Submit for approval detailed schemes of all operations required for executing the work, e.g. material handling, Concrete mixing, Placement of concrete, Compaction, curing, services, Approaches, etc.
- g) Design and submit for approval concrete mix designs required to be adopted on the job.
- h) Furnish samples and submit for approval results of tests of various properties of the following:
 - i) The various ingredients of concrete
 - ii) Concrete
 - iii) Embedments
 - iv) Joint seals
- i) Provide all incidental items not shown or specified in particular but reasonably implied or necessary for successful completion of the work in accordance with the drawings and specifications.
- j) For supply of certain materials normally manufactured by specialist firms, the Contractor may have to produce, if directed by the Engineer, a guarantee in approved Performa for satisfactory performance for a reasonable period as may be specified, binding both the manufacturers and the Contractor, jointly and severally.

2.02.00 Work by others

No work under this specification will be provided by any agency other than the Contractor unless specifically mentioned elsewhere in the contract.

2.03.00 Information to be submitted by the Tenderer

2.03.01 With Tender

The following technical information's are required with the tender:

- a) Source and arrangement of processing of aggregates proposed to be adopted.
- b) Type of plant and equipment proposed to be used.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 27 of 361

c) Names of firms with which association is sought for to execute the special items of work in the contract.

d) Types of formwork proposed to be used.

2.03.02

After Award

The Contractor shall submit the following information and data including samples where necessary, progressively during the execution of the contract.

a) Programme of Execution

Within 30 days of the award of contract, the Contractor will submit a Master Programme for completion of the work.

This Master Programme may have to be reviewed and updated by the Contractor, quarterly or at more frequent intervals as may be directed by the Engineer depending on the exigencies of the work.

Detailed day-to-day Programme of every month is to be submitted by the Contractor before the end of the previous month.

b) Samples

Samples of the following materials and any other materials proposed to be used shall be submitted as directed by the Engineer, in sufficient quantities free of cost, for approval. The Engineer for future reference will preserve approved samples. The approval of the Engineer shall not, in any way, relieve the Contractor of his responsibility of supplying materials of specified qualities:

i) Coarse and fine aggregates.

ii) Admixtures.

iii) Plywood for Formwork.

iv) Embedded and anchorage materials as may be desired by the Engineer.

v) Joint sealing strips and other*waterproofing materials.

vi) Joint filling compounds.

vii) Foundation quality Rubber Pads.

c) Design Mix

Design mix as per specification giving proportions of the ingredients,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 28 of 361

sources of aggregates and cement, along with test results of trial mixes as per relevant I.S., is to be submitted to the Engineer for his approval before it can be used on the works.

d) Bar Bending Schedules

Bar Bending Schedules in accordance with Clause 2.01.00 (b) and 3.16.01 of this specification.

e) Detailed Drawings and Designs of Formworks to be used

Detailed design data and drawings of standard formworks to be used as per clause 2.01.00 (c).

f) Detailed Drawings for Templates & Temporary Supports for embedment
As per Clause 2.01.00 (e).

g) Mill Test Reports for Cement & Reinforcing Steel.

h) Inspection Reports

The Engineer in accordance with Clause 2.04.00 of this specification may desire inspection Reports in respect of Formwork and Reinforcement and any other item of work as.

i) Test Reports

Reports of tests of various materials and concrete as required under Clause 4.0: SAMPLING & TESTING of this specification or as directed by the Engineer.

j) Any other data, which may be required as per this specification or as directed by the Engineer.

2.04.00

Conformity with Design

The Contractor will prepare checklists in approved Form, which will be called "Pour Cards". These Pour Cards will list out all items of work involved. The Contractor will inform the Engineer, sufficiently in advance, whenever any particular pour is ready for concreting. He shall accord all necessary help and assistance to the Engineer for all checking required in the pour. On satisfying himself that all details are in accordance to the drawings and specifications, the engineer will give written permission on the same Pour Cards allowing the contractor to commence placement of concrete. Details of all instructions issued by the Engineer and the records of compliance by the Contractor, deviations allowed by the Engineer and any other relevant information will be written on accompanying sheets attached to the Pour Cards. The Pour Cards along with accompaniments will be handed over to the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 29 of 361

Engineer before starting placement of concrete. One of the mix designs developed by the Contractor as per the I.S. Specifications and established to the satisfaction of the Engineer by trial mixes shall be permitted to be used by the Engineer, the choice being dictated by the requirements of designs and workability. The methods of mixing, conveyance, placement, vibration, finishing, curing, protection and testing of concrete will be as approved or directed by the Engineer.

2.05.00 Materials to be used

2.05.01 General Requirement

All materials whether to be incorporated in the work or used temporarily for the construction shall conform to the relevant IS Specifications unless-stated otherwise and be of best approved quality.

2.05.02 Cement

Ordinary Portland cement of grade-43 as per IS:8112/fly ash based Portland puzzolona cement conforming to IS:1489 (Part-1) shall preferably be used in reinforced/plain cement concrete works for all areas other than for the critical structures identified below. However, other types of cement such as ordinary Portland cement conforming to IS:269, Portland slag cement conforming to IS:455 respectively can be used under special circumstances. Cement used in all concrete mixes shall be in general of grade 33/43 unless design requires a higher grade. Ordinary Portland cement shall be used for following structure.

- a) TG foundation top deck and sub structures including raft.
- b) Spring Supporting decks of all machine foundations.
- c) Structures requiring grade of concrete of M30 and above.

In special cases, Rapid Hardening Portland Cement, Low Heat Cement, Sulphate resistant cement, high strength Ordinary Portland Cement etc. may be permitted or directed to be used by the Engineer.

For Brickwork, plaster, flooring and other finishing works, ordinary Portland cement of 33/43 grade shall be used.

2.05.03 Coarse Aggregate

Aggregate of sizes ranging between 4.75 mm and 150 mm will be termed as Coarse Aggregate. Coarse aggregate for concrete shall be chemically inert, hard, strong durable against weathering, of limited porosity, and free from deleterious materials. It shall be properly graded. Coarse aggregates shall be either crushed gravel or stone. All aggregates shall meet the requirement of IS:383:1970. Only Coarse Aggregate from, approved quarries and conforming to IS-383 will be allowed to be used on the works. Petrographic test shall be



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 30 of 361

carried out by the contractor free of cost for checking the quality of rock from quarry. This test shall be repeated by the Contractor free of cost for change in quarry or as directed by the Engineer. The results shall be checked for reactivity of silica in aggregate with alkalis of cement.

2.05.04 Fine Aggregate

Aggregate smaller than 4.75 mm and within the grading limits and other requirements set in IS: 383 are termed as Fine Aggregate or Sand. Only Fine Aggregate from approved sources and conforming to the above IS Specification will be allowed to be used in works. Sand shall be hard, durable, clean and free from adherent coatings or organic matter and clay balls or pellets. Sand when used as fine aggregate in concrete shall conform to IS:383. For plaster, it shall conform to IS:1542 and for masonry work to IS:2116.

2.05.05 Water

Water for use in Concrete shall be clear and free from injurious oils, acids, alkalis, organic matter, salt, silts, or other impurities. Generally, IS: 3550 will be followed for routine tests. Acceptance of water shall be as per IS: 456.

2.05.06 Admixture

Only admixtures of approved quality will be used when directed or permitted by the Engineer. The different types of admixtures, which may be necessary to satisfy the concrete mix and the design requirement, shall be as per IS-9103 and may be one of the followings:

- a) Accelerating admixture
- b) Retarding admixture
- c) Water reducing admixture
- d) Air entraining admixture

The contractor shall inform the Engineer about the type of admixture which he is planning to use in different areas within the scope of work for the approval of the Engineer. The admixture shall be of proven make and from a reputed manufacturer. It should not have any adverse effect on strength, durability of concrete and reinforcement. Super plasticizers conforming to IS: 9103 or ASTM C-494 shall only be used as admixture having the above properties either individually or in a combination as per the direction of the Engineer.

2.05.07 Reinforcement

Reinforcement shall be as per relevant IS Specification as mentioned in the Contract/Drawing/Instructions. All bars above 10 mm dia. shall be of tested



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 31 of 361

quality.

2.06.00 Storage of Materials

2.06.01 General

All materials shall be so stored as to prevent deterioration or intrusion of foreign matter and to ensure the preservation of their quality and fitness for the work. Any material, which has deteriorated or has been damaged or is otherwise considered defective by the Engineer, shall not be used for concrete and shall be removed from site immediately, failing which, the Engineer shall be at liberty to get the materials removed and the cost incurred thereof shall be realised from the Contractor's dues. The Contractor shall maintain upto-date accounts of receipt, issue and balance (stack wise) of all materials. Storage of materials shall conform to IS: 4082.

2.06.02 Cement

Sufficient space for storage, with open passages between stacks, shall be arranged by the Contractor to the satisfaction of the Engineer.

Cement shall be stored off the ground in dry, leak proof, well-ventilated warehouses at the works in such a manner as to prevent deterioration due to moisture or intrusion of foreign matter.

Cement shall be stored in easily countable stacks with consignment identification marks. Consignments shall be used in the order of their receipts at site. Sub-standard or partly set cement shall not be used and shall be removed from the site, with the knowledge of the Engineer, as soon as it is detected.

2.06.03 Aggregates

Aggregates shall be stored on raised surface constructed by providing planks or steel plates or on concrete or brick masonry pavement. Each size shall be kept separated with wooden or steel or concrete or masonry bulkheads or in separate stacks and sufficient care shall be taken to prevent the material at the edges of the stock piles from getting intermixed. Stacks of fine and coarse aggregates shall be kept sufficiently apart with proper arrangement of drainage. The aggregates shall be stored in easily measurable stacks of suitable depths as may be directed by the Engineer.

2.06.04 Reinforcement

Reinforcing steel shall be stored consignment-wise and size-wise off the ground and under cover, if desired by the Engineer. It shall be protected from rusting, oil, grease, and distortions.

If necessary, the reinforcing steel may be coated with cement wash before



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 32 of 361

stacking to prevent scale and rust at no extra cost to the Owner. The stacks shall be easily measurable. Steel needed for immediate use shall only be removed from storage.

2.07.00

Quality Control

Contractor shall establish and maintain quality control for different items of work and materials as may be directed by the Engineer to assure compliance with contract requirements and maintain and submit to the Engineer records of the same. The quality control operation shall include but not be limited to the following items of work:

- a) Admixture: Type, quantity, physical, and chemical properties that affects strength, workability, and durability of concrete.

For air entraining admixtures, dosage to be adjusted to maintain air contents within desirable limits.
- b) Aggregate: Physical, chemical and mineralogical qualities. Grading, moisture content and impurities.
- c) Water: Impurities tests.
- d) Cement: Tests to satisfy relevant IS Specifications.
- e) Formwork: Material, shapes, dimensions, lines, elevations, surface finish, adequacy of form, ties, bracing and shoring and coating.
- f) Reinforcement: Shapes, dimensions, length of splices, clearances, ties and supports. Quality and requirement of welded splices.

Material tests or Certificates to satisfy relevant IS Specification.
- g) Grades of Concrete: Usage and mix design, testing of all properties.
- h) Batching & Mixing: Types and capacity of plant, concrete mixers and transportation equipment.
- i) Joints: Locations of joints, water stops and filler materials. Dimension of joints, quality, and shape of joint material and splices.
- j) Embedded and



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 33 of 361

Anchorage Items: Material, shape, location, setting.

- k) Placing: Preparation, rate of pouring, weather limitations, time intervals between mixing and placing and between two successive lifts, covering over dry or wet surfaces, cleaning and preparation of surfaces on which concrete is to be placed, application of mortar/slurry for proper bond, prevention of cold joint, types of chutes or conveyors.
- l) Compaction: Number of vibrators, their prime mover, frequency and amplitude of vibration, diameter and weight of vibrators, duration of vibration, hand-spreading, rodding and tamping.
- m) Setting of base & Bearing plates: Lines, elevations, and bedding mortar.
- n) Concrete Finishes: Repairs of surface defects, screening, floating, steel trowelling and brooming, special finishes.
- o) Curing: Methods and length of time.

Copies of records and tests for the items noted above, as well as, records of corrective action taken shall be submitted to the Engineer for approval as may be desired.

3.00.00

INSTALLATION

All installation requirements shall be in accordance with IS: 456 and as supplemented or modified herein or by other best possible standards where the specific requirements mentioned in this section of the specification do not cover all the aspects to the full satisfaction of the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 34 of 361

3.01.00 Washing and Screening of Aggregates

Washing and screening of coarse and fine aggregates to remove fines, dirt, or other deleterious materials shall be carried out by approved means as desired by the Engineer.

3.02.00 Admixture

All concrete shall be designed for normal rate of setting and hardening at normal temperature. Variations in temperature and humidity under different climatic conditions will affect the rate of setting and hardening, which will, in turn, affect the workability and quality of the concrete. Admixtures including plasticisers of approved make may be used with the Engineer's approval in accordance with IS-456 to modify the rate of hardening, to improve workability or as an aid to control concrete quality. The Engineer reserves the right to require laboratory test or use test data, or owner satisfactory reference before granting approval. The admixture shall be used strictly in accordance with the manufacturer's directions and/or as directed by the Engineer.

3.03.00 Grades of Concrete

Concrete shall be in one of the grades designated in IS: 456. Grade of concrete to be used in different parts of work shall be as shown on the drawing. In case of liquid retaining structures, IS: 3370 will be followed. Minimum cement content shall be as per IS: 456.

3.04.00 Proportioning and Works Control

3.04.01 General

“Design Mix Concrete” and “Nominal Mix Design” is defined as follows for use in this specification:

- a) Proportioning of ingredients of concrete made with preliminary tests by designing the concrete mix. Such concrete shall be called "Design Mix Concrete".
- b) Proportioning of ingredients of concrete made without preliminary tests adopting nominal concrete mix. Such concrete shall be called "Nominal Mix Concrete".

As far as possible, design mix concrete shall be used on all concrete works. Nominal mix concrete, in grades M-15 or lower only may be used if shown on drawings or approved by the Engineer. In all cases the Proportioning of ingredients and works control shall be in accordance with IS: 456 and shall be adopted for use after the Engineer is satisfied regarding its adequacy and after obtaining his approval in writing.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 35 of 361

3.04.02

Mix Design Criteria

Concrete mixes will be designed by the Contractor to achieve the strength, durability, and workability necessary for the job, by the most economical use of the various ingredients. In general, the design will keep in view the following considerations

- a) Consistent with the various other requirements of the mix, the quantity of water should be kept at the lowest possible level.
- b) The nominal maximum size of coarse aggregate shall be as large as possible within the limits specified.
- c) The various fractions of coarse and fine aggregates should be mixed in such a proportion as to produce the best possible combined internal grading giving the densest and most workable mix.
- d) The finished concrete should have adequate durability in all condition, to withstand satisfactorily the weather and other destruction agencies, which it is expected to be subjected to in actual service.
- e) The mix design shall have required workability and characteristic strength as per IS: 456. The quantity of cement, aggregates, and admixtures shall be determined by mass.

The requirement of adequate structural strength is catered for by the choice of proper grade of concrete in structural design. The Contractor will strictly abide by the same in his design of concrete mix installation. Various trials shall be given by the contractor with specific cement content on each trial. In some cases, plasticizers and other admixtures may be necessary to achieve the desired results.

3.05.00

Strength Requirements

The strength requirements of both design mix and nominal mix concrete where ordinary Portland Cement or Portland Blast furnace slag cement is used, shall be as per IS: 456. All other relevant clauses of IS: 456 shall also apply.

3.06.00

Minimum Cement Content

The minimum cement content for each grade of concrete shall be as per IS: 456. Contractor has to consider actual environmental exposure condition at site. Based on various tests results and as per



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 36 of 361

Engineer, the environment condition shall be adopted for which minimum cement content shall be considered. No extra payment shall be made on account of any variation in environment condition.

- a) Sufficient number of trial mixes (to be decided by the Engineer) will be taken at the laboratory for the various designs and graphs of w/c ratio Vs crushing strengths at various ages will be plotted.
- b) All tests will be done in presence of the Engineer who shall be the final authority to decide upon the adoption of any revised minimum cement content. The Contractor will always be responsible to produce quality concrete of the required grade as per the acceptance criteria of IS: 456.
- c) The Engineer will always have the unquestionable right to revise the minimum cement content as decided above, if, in his opinion, there is any chance of deterioration of quality on account of use of lower cement content or any other reason.

3.07.00 Water-Cement Ratio

The choice of water-cement ratio in designing a concrete mix will depend on:-

- a) The requirement of strength.
- b) The requirement of durability.

3.07.01 Strength Requirement

In case of "Design Mix Concrete" the water-cement ratio of such value as to give acceptable test results as per IS: 456, will be selected by trial and error. The values of water-cement ratios for different grade and mix designs will have to be established after conducting sufficiently large number of preliminary tests in the laboratory to the satisfaction of the Engineer. Frequent checks on test will have to be carried out and the water-cement ratios will be revised if the tests produce unsatisfactory results. Notwithstanding anything stated above the Contractor's responsibility to produce satisfactory test results and to bear all the consequences in case of default remains unaltered.

In case of nominal mix concrete, the maximum water-cement ratio for different grades of concrete is specified in Table-5 of IS: 456 and no tests are necessary. The acceptance test criterion for nominal mix concrete shall be as per IS: 456.

3.07.02 Durability Requirement



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 37 of 361

Tables 4 & 5 of IS: 456 give the maximum water-cement ratio permissible from the point of view of durability of concrete subjected to adverse exposure to weather, sulphate attacks, and contact with harmful chemicals. Impermeability may also be an important consideration.

Whenever the water-cement ratio dictated by Durability consideration is lower than that required from strength criteria, the former should be adopted.

In general the water cement ratio between 0.4 and 0.45 will be desirable to satisfy the durability requirement and from the consideration of impermeability of concrete. The contractor may propose lower water cement ratio as mentioned above by addition of a suitable plasticizer/super-plasticizer. Trial mix shall be carried out accordingly. However, the contractor has to propose specifically along with field trials in the event of lower cement content if found suitable along with a plasticizer.

3.08.00 Workability

The degree of workability necessary to allow the concrete to be well consolidated and to be worked into the corners of formwork and around the reinforcement and embedments and to give the required surface finish shall depend*on the type and nature of structure and shall be based on experience and tests. The usual limits of consistency for various types of structures are given below:

TABLE-V
LIMITS OF CONSISTENCY

Degree of workability	Slump in mm with Standard Cone as per IS: 1199		Use for which concrete is suitable
	Min.	Max.	
Very low	0	25	Large Mass concrete structure with heavy compaction equipments, roads
Low	25	50	Uncongested wide and shallow R.C.C. structures
Medium	50	100	Deep but wide R.C.C. structures with congestion of reinforcement and inserts
High	100	150	Very narrow and deep R.C.C. structures with congestion due to



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 38 of 361

reinforcement and inserts.

Note: Notwithstanding anything mentioned above, the slump to be obtained for work in progress shall be as per direction of the Engineer.

With the permission of the Engineer, for any grade of concrete, if the water has to be increased in special cases, cement shall also be increased proportionately to keep the ratio of water to cement same as adopted in trial mix design for each grade of concrete. No extra payment will be made for this additional cement.

The workability of concrete shall be checked at frequent intervals by slump tests.

3.09.00 Size of coarse Aggregates

The maximum size of coarse aggregates for different locations shall be as follows unless otherwise directed by the Engineer

Very narrow space	- 12 mm
Reinforced concrete Except foundation	- 20 mm
Ordinary Plain concrete and Reinforced concrete foundations	- 40 mm
Mass concrete	- 80 mm
Lean concrete	- 40 mm

Grading of coarse aggregates for a particular size shall conform to relevant I.S. Codes and shall also be such as to produce a dense concrete of the specified proportions, strength and consistency that will work readily into position without segregation.

Coarse aggregate will normally be separated into the following sizes and stacked separately in properly designed stockpiles

80 mm to 40 mm, 40 mm to 20 mm and 20 mm to 5 mm. In certain cases it may be necessary to further split the 20 mm to 5 mm fraction into 20 mm to 10 mm and 10 mm to 5 mm fractions.

This separation of aggregates in different size fractions is necessary so that they may be remixed in the desired proportion to arrive at a correct internal grading to produce the best mix.

3.09.01 Temperature control of concrete in top decks of machine foundations (i.e. of



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 39 of 361

TGs, BFPs, Fans and Mills):

The temperature of fresh concrete shall not exceed 25°C when placed. A suitable measuring device for measuring the temperature of concrete as approved by the Engineer shall be used. For maintaining the limiting temperature of the 25°C, crushed ice shall be used as mixing water. The ice shall be formed of water conforming IS: 456. The Contractor shall establish the quantity of crushed ice to be mixed in order to achieve the limiting temperature of 25°C.

3.09.02 Base raft of Turbo Generator foundations and top decks of all machine foundations shall be cast in a continuous operation without any construction joint.

3.10.00 Mixing of Concrete

Ingredients of the concrete mix shall be measured by weight. Concrete shall always be mixed in mechanical mixer. Water shall not normally be charged into the drum of the mixer until all the cement and aggregates constituting the batch are already in the drum and mixed for at least one minute. Mixing of each batch shall be continued until there is a uniform distribution of the materials and the mass is uniform in colour and consistency, but in no case shall mixing be done for less than 2 (two) minutes and at least 40 (forty) revolutions after all the materials and water are in the drum. When absorbent Aggregates are used or when the mix is very dry, the mixing time shall be extended as may be directed by the Engineer. Mixers shall not be loaded above their rated capacity as this prevents thorough mixing.

The entire contents of the drum shall be discharged before the ingredients for the next batch are fed into the drum. No partly set or remixed or excessively wet concrete shall be used. Such concrete shall be immediately removed from site. Each time the work stops, the mixer shall be thoroughly cleaned & when the next mixing commences, the first batch shall have 10% additional cement at no extra cost to the Owner to allow for loss in the drum.

Regular checks on mixer efficiency shall be carried out as directed by the Engineer as per IS: 4634 on all mixers employed at site only those mixers whose efficiencies are within the tolerances specified in IS: 1791 will be allowed to be employed.

Batching Plant shall conform to IS: 4925. The measuring gauges of batching plant shall be periodically calibrated for which the contractor shall provide standard weights. The accuracy of all gauges shall be within limits prescribed by the Engineer.

When hand mixing is permitted by the Engineer, for unimportant out of the way locations in small quantities, it shall be carried out on a water-tight platform and care shall be taken to ensure that mixing is continued until the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 40 of 361

mass is uniform in colour and consistency. In case of hand-mixing, 10% extra cement shall be added to each batch at no extra cost to the owner.

3.11.00 Conveying Concrete

Concrete shall be handled and conveyed from the place of mixing to the place of laying as rapidly as practicable by approved means and placed and compacted in the final position before the initial setting of the cement starts. Concrete should be conveyed in such a way as will prevent segregation or loss of any of the ingredients. For long distance haulage, agitator cars of approved design will be used. If, in spite of all precautions, segregations does occur during transport, the concrete shall be properly re-mixed before placement. During very hot or cold weather, if directed by the Engineer, concrete shall be transported in deep containers, which will reduce the rate of loss of water, by evaporation or loss of heat. If necessary, the container may have to be covered and insulated. Conveying equipments for concrete shall be well maintained and thoroughly cleaned before, commencement of concrete mixing. Such equipments shall be kept free from set concrete.

3.12.00 Placing and Compacting Concrete

Where specifically covered, the relevant I.S. Code will be followed for the procedure of surface preparation, placement, consolidation, curing, finishes, repairs and maintenance of concrete. If, however, there is no specific provision in relevant I.S. code for any particular aspect of work, any other standard code of practice, as may be specified by the Engineer, will be adopted. Concrete may have to be placed against the following types of surfaces:

- a) Earth foundation
- b) Rock foundation
- c) Formwork
- d) Construction joint in concrete or masonry

The surface on or against which concrete is to be placed has to be cleaned thoroughly. Rock or old construction joint has to be roughened by wire brushing, chipping, sand blasting or any other approved means for proper bond. All cuttings, dirt, oil, foreign and deleterious material, laitance, etc. are to be removed by air water jetting or water at high pressure. Earth foundation on which direct placement of concrete is allowed, will be consolidated as directed by the Engineer such that it does not crumble and get mixed up with the concrete during or after placement, before it has sufficiently set and hardened.

Formwork, reinforcement, preparation of surface, embedments, joint seals etc., shall be approved in writing by the Engineer before concrete is placed. As far



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 41 of 361

as possible, concrete shall be placed in the formwork by means approved by the Engineer and shall not be dropped from a height or handled in a manner which may cause segregation. Any drop over 1500 mm shall have to be approved by the Engineer.

Rock foundation or construction joint will be kept moist for at least 72 hours prior to placement. Concrete will be placed always against moist surface but never on pools of water. In case the foundation cannot be dewatered completely, special procedure and precaution, as directed by the Engineer will have to be adopted.

Formwork will be cleaned thoroughly and smeared lightly with form oil or grease of approved quality just prior to placement.

A layer of mortar of thickness 12 mm of the same or less w/c ratio and the same proportion as that of the concrete being placed or cement slurry will be spread thoroughly on the rock Foundation or construction joint just prior to placement of concrete.

After concrete has been placed, it shall be spread, if necessary & thoroughly compacted by approved mechanical vibration to maximum, subsidence without segregation and thoroughly worked around shape. Vibrators shall not be used for pushing concrete into adjoining areas. Vibrators must be operated by experienced workmen and the work carried out as per relevant IS Code of Practice: In thin members with heavy congestion of reinforcement or other embedments, where effective use of internal vibrator is, in the opinion of the Engineer, doubtful, in addition to immersion vibrators the contractor may have to employ form vibrators conforming to IS: 4656. For slabs and other similar structures, the contractor will additionally employ screed vibrator as per IS: 2506. Hand tamping may be allowed in rare cases, subject to the approval of the Engineer. Care must be taken to ensure that the inserts, fixtures, reinforcement, and formwork are not displaced or distorted during placing & consolidation of concrete.

The rate of placement of concrete shall be such that no cold joint is formed and fresh concrete is placed always against green Concrete, which is still plastic and workable. No concrete shall be placed in open, during rains. During rainy season, no placement in the open is to be attempted unless sufficient tarpaulins or other similar protective arrangement for completely covering the still green concrete from rain is kept at the site of placement. If there has been any sign of washing of cement and sand, the entire affected concrete shall be removed immediately. Suitable precautions shall be taken in advance to guard against rains before leaving the fresh concrete unattended. No accumulation of water shall be permitted on or around freshly laid concrete.

Slabs, beams, and similar members shall be poured in one operation, unless otherwise instructed by the Engineer. Mouldings, throating, drip course, etc.,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 42 of 361

shall be poured as shown on the drawings or as directed by the Engineer. Holes shall be provided and bolts, sleeves, anchors, fastenings, or other fixtures shall be embedded in concrete as shown on the drawings or as directed by the Engineer. Any deviation there from shall be set right by the Contractor at his own expense as instructed by the Engineer.

In case the forms or supports get displaced during or immediately after the placement and bring the concrete surface out of alignment beyond tolerance limits, the Engineer may direct to remove the portion and reconstruct or repair the same -at the Contractor's expense.

The Engineer shall decide upon the time interval between two placements of concrete of different ages coming in contact with each other, taking in consideration the degree of maturity of the older concrete, shrinkage, heat dissipation and the ability of the older concrete to withstand the load imposed upon it by the fresh placement.

Once the concrete is deposited, consolidated and finished in its final position, it shall not be distributed.

3.13.00 Construction Joints and Cold Joints

3.13.01 Construction Joints

It is always desirable to complete any concrete structure by continuous pouring in one operation. However, due to practical limitation of methods and equipment and certain design considerations, construction joints are formed by discontinuing concrete certain predetermined stages. These joints will be formed in a manner specified in the drawings/Instruction.

Vertical construction joints will be made with rigid stop-board forms having slots for allowing passage of reinforcement rods and any other embedments and fixtures that may be shown. Next stage concrete shall be placed against construction joint as per clause 3.12.

Where the location of the joints are not specified, it will be in accordance with the following:

- a) In a column, the joint shall be formed 75 mm below the lowest soffit of the beam framing into it.
- b) Concrete in a beam shall preferably be placed without a joint, but if Provision of a joint is unavoidable, the joint shall be vertical and at the middle of the span.
- c) A joint in a suspended floor slab shall be vertical and at the middle of the span and at right angles to the principal reinforcement.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 43 of 361

- d) Feather-edges in concrete shall be avoided while forming a joint.
- e) A construction joint should preferably be placed in a low-stress zone and at right angles to the direction of the principal stress.
- f) In case the Contractor proposes to have a construction joint anywhere to facilitate his work, the proposal should be submitted well in advance to the Engineer for study and approval without which no construction joint will be allowed.

3.13.02 Cold Joint

An advancing face of a concrete pour, which could not be covered by fresh concrete before expiry of initial setting time (due to an unscheduled stoppage or delay on account of breakdown in plant, inclement weather, low rate of placement or any other reason), is called a cold joint. The Contractor should always remain vigilant to avoid cold joints.

If, however, a cold joint is formed due to unavoidable reasons, the following procedure shall be adopted for treating it:

- a) If the concrete is so green that it can be removed manually and if vibrators can penetrate the surface without much effort, fresh concrete can be placed directly against the old surface. The old concrete should be covered by fresh concrete as quickly as possible and the joint thoroughly and systematically vibrated.
- b) In case concrete has hardened a bit more than (a) but can still be easily removed by a light hand pick, the surface will be raked thoroughly and the loose concrete removed completely without disturbing the rest of the concrete in depth. A rich mortar layer 12 mm in thickness, will be placed on the cold joint fresh concrete shall be placed on the mortar layer and the joint will be thoroughly and systematically vibrated penetrating the vibrator deep into the old layer of concrete.
- c) In case the concrete at the joint has become so stiff that it cannot be remoulded and mortar or slurry does not raise in spite of extensive vibration, the joint, will be left to harden for at least 12 - 24 hrs. It will then be treated as a regular construction joint, after cutting the concrete to required shape and preparing the surface as described under clause 3.12.

3.14.00 Repairs, Finishes, and Treatment of Concrete surfaces

- 3.14.01** Adequate and sound concrete surfaces, whether formed or unformed, can be obtained by employing a concrete mix of proper design, competent formwork, appropriate methods of handling, placing, and consolidation by experienced workmen.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 44 of 361

Unsound concrete resulting from improper mix design, incompetent methods, equipment and formwork, poor workmanship and protection will not be accepted and will have to be dismantled, removed and replaced by sound concrete at the Contractor's cost. The Engineer may, at his sole discretion, allow to retain concrete with minor defects provided the Contractor is able to repair it by approved methods at no extra cost to the Owner, All concrete work shall be inspected by the Contractor immediately after the forms are removed & he will promptly report occurrence of any defects to the Engineer. All repair works will be carried out as per the instructions and in the presence of the Engineer or his representative. Generally, repair work will consist of any or all of the following operations:

- a) Sack rubbing with mortar and stoning with carborundum stone.
- b) Cutting away the defective concrete to the required depth shape.
- c) Cleaning of reinforcement & embedments. It may be necessary to provide an anti-corrosive coating on the reinforcement.
- d) Roughening by sand blasting or chipping.
- e) Installing additional reinforcement/welded mesh fabric.
- f) Dry packing with stiff mortar.
- g) Plastering, guniting, shotcreting etc.
- h) Placing and compacting concrete in the void left by cutting out defective concrete.
- i) Grouting with cement sand slurry of 1:1 mix.
- j) Repairing with a suitable mortar either cement or resin modified mortars.
- k) Polymer modified patching and adhesive repair & mortar for beams & columns.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 45 of 361

3.14.02 Finishing unformed Surface

The contractor shall provide normal finishes in unformed surfaces which can be achieved by screeding, floating, trowelling etc. A few typical and common cases of treatment of concrete surface are cited below

a) Floor

Whenever a non-integral floor finish is indicated, the surface of reinforced concrete slab shall be struck off at the specified levels and slopes and shall be finished with a wooden float fairly smooth removing all laitance. No over trowelling, to obtain a very smooth surface, shall be done, as it will prevent adequate bond with the subsequent finish. If desired by the Engineer, the surface shall be scored and marked to provide better bond.

Where monolithic finish is specified or required, concrete shall be compacted and struck off at the specified levels and slopes with a screed, preferably a vibrating type and then floated with a wooden float. Steel trowelling is then started after the moisture film and shine have disappeared from the surface and after the concrete has hardened enough to prevent excess of fines and water to rise to the surface but not hard enough to prevent proper finishing of aberrations. Steel trowelling properly done will flatten and smoothen sandy surface left by wooden floats and produce a dense surface free from blemishes, ripples, and trowel marks.

A fine textured surface that is not slick and can be used where there is likelihood of spillage of oil or water can be obtained by trowelling the surface lightly with a circular motion after initial trowelling keeping the steel trowel flat on the surface.

To provide a better grip the Engineer may instruct marking the floor in a regular geometric pattern after initial trowelling.

b) Beans, Columns & Walls

If on such or any other concrete structure it is intended to apply plaster or such concrete surfaces against which brickwork or other allied works are to be built, the Contractor shall hack the surface adequately as soon as the form is stripped off so that proper bond can develop. Pattern, adequacy, and details of such hacking shall meet with the approval of the Engineer, who shall be informed to inspect such surfaces before they are covered up.

3.15.00 Protection and Curing of concrete

Newly placed concrete shall be protected by approved means from rain, sun, and wind. Concrete placed below the ground level shall be protected against



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 46 of 361

contamination from falling earth during and after placing. Concrete placed in ground containing deleterious substances, shall be protected from contact with such ground, or with water draining from such ground, during placing of concrete and for a period of at least three days, or as otherwise instructed by the Engineer. The ground water around newly poured concrete shall be kept to an approved level by pumping out or other adequate means of drainage to prevent floatation or flooding. Steps, as approved by the Engineer, shall be taken to protect immature concrete from damage by debris, excessive Loadings, vibration, abrasion, mixing with earth or other deleterious materials, etc. that may impair the strength and durability of the concrete.

As soon as the concrete has hardened sufficiently, it shall be covered either with sand, hessian, canvas, or similar materials and kept continuously wet for at least 14 (fourteen) days after final setting. Curing by continuous sprinkling of water will be allowed if the Engineer is satisfied with the adequacy of the arrangements made by the Contractor. Quality of water for curing shall be as per IS: 456.

If permitted by the Engineer, liquid curing compound may be used for prevention of premature water loss in concrete and thereby effecting curing of concrete. This type of curing compound shall be sprayed on newly laid concrete surfaces to form a thin film barrier against premature water loss without disturbances to normal setting action. The curing compound shall be emulsified paraffin based and shall comply with ASTM requirements for acceptance.

The curing compound shall be applied following the final finishing operation and immediately after disappearance of water from concrete surface. It is important not to apply the curing compound when standing water is still present on concrete.

The contractor shall arrange for the manufacturer's supervision at no extra cost.

The Contractor shall remain extremely vigilant and employ proper equipment and workmen under able supervision for curing. The Engineer's decision regarding the adequacy of curing is final. In case the Engineer notices any lapse on the part of the Contractor, he will inform the Contractor or his supervisor verbally or in writing to correct the deficiency in curing. If no satisfactory action is taken by the Contractor within 3 (three) hours of issuance of such instruction, the Engineer will be at liberty either to employ sufficient means through any agency to make good the deficiency and recover the cost thereof from the Contractor, or deduct certain amount from contractor's payment for the part where inadequate curing was noticed entirely at the discretion of the Engineer.

3.16.00

Reinforcement



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 47 of 361

Mild steel round bars, TMT bars, Hot rolled deformed bars or cold twisted deformed bars as medium tensile or high yield strength steel, plain hard drawn steel wire fabric etc, will be used as reinforcement as per drawings and directions. In an aggressive environment an anti-corrosive coating on the reinforcement may be provided as per IS: 9077, as shown on the drawing or as directed by the Engineer.

3.16.01 Bar Bending Schedules

The Contractor shall prepare Bar Bending Schedules showing clearly the arrangements proposed by the Contractor to match available stock of reinforcing steel, progressively, starting within one week of receipt of approval on corresponding design of RCC structure. As decided by the Engineer, some or all the detailed drawings and schedules will have to be submitted for approval. Approval of such detailed drawings by the Engineer shall not relieve the Contractor of his responsibility for correctness nor of any of his obligations to meet the other requirements of the contract. The contractor for record and distribution shall submit six prints of the final drawings & schedules with one reproducible print.

3.16.02 Cleaning

All steel for reinforcement shall be free from loose scales, oil, grease, paint or other harmful matters immediately before placing the concrete.

3.16.03 Bending

Unless otherwise specified, reinforcing steel shall be bent in accordance with the procedure specified in IS: 2502 or as approved by the Engineer. Bends and shapes shall comply strictly with the dimensions corresponding with the final Bar Bending Schedules. Bar Bending Schedules shall be rechecked by the Contractor before any cutting, bending is done.

No reinforcement shall be bent when already in position in the work, without approval of the Engineer, whether or not it is partially embedded in concrete. Bars shall not be straightened in a manner that will injure the material. Rebending can be done only if approved by the Engineer. Reinforcing bars shall be bent by machine or other approved means producing a gradual and even motion. All the bars shall be cold bent unless otherwise approved. Bending hot at a cherry-red heat (not exceeding 845°C) may be allowed under very exceptional circumstances except for bars whose strength depends on cold working. Bars bent hot shall not be cooled by quenching.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 48 of 361

3.16.04 Placing in Position

All reinforcements shall be accurately fixed and maintained in position as shown on the drawings by such approved and adequate means like mild steel chairs and/or concrete spacer blocks. Bars intended to be in contact at crossing points, shall be securely tied together at all such points by No. 20 G annealed soft iron wire or by tack welding in case of Bar larger than 25 mm dia., as may be directed by the Engineer. Binders shall tightly embrace the bars with which they are intended to be in contact and shall be securely held. The vertical distance between successive layers of bars shall be maintained by provision of mild steel spacer bars. They should be spaced such that the main bars do not sag perceptibly between adjacent spacers. Before actual placing, the Contractor shall study the drawings thoroughly and inform the Engineer in case he feels that placement of certain bars is not possible due to congestion. In such cases he should not start placing any bar before obtaining clearance from the Engineer.

3.16.05 Welding

Lapping shall normally do splicing of reinforcement. For M.S. reinforcement bars, butt-welding may be done, if permitted by the Engineer, under certain conditions. The work should be done with suitable safeguards in accordance with relevant Indian Standards for welding of mild steel bars used in reinforced concrete construction as per IS: 2751 and IS: 456. Welded mesh fabrics conforming to IS: 1566 may also be used if specified in the Drawings. Welding of cold twisted High yield strength deformed bar shall not be allowed.

3.16.06 Control

The placing of reinforcements shall be completed well in advance of concrete pouring. Immediately before pouring, the reinforcement shall be examined by the Engineer for accuracy of placement and cleanliness. Necessary corrections as directed by him shall be carried out. Laps and anchorage lengths of reinforcing bars shall be in accordance with IS: 456, unless otherwise specified. The laps shall be staggered as far as practicable and as directed by the Engineer. Arrangements for placing concrete shall be such that reinforcement in position does not have to bear extra load and get disturbed. The cover for concrete over the reinforcements shall be as shown on the approved drawings unless otherwise directed by the Engineer. Where concrete blocks are used for ensuring the cover and positioning reinforcement, they shall be made of mortar not leaner than 1 (one) part cement to 2 (two) parts sand by volume and cured in a pond for at least 14 (fourteen) days. The type, shape, size and location of the concrete blocks shall be as approved by the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 49 of 361

3.17.00 Cold Weather Concreting

When conditions are such that the ambient temperature may be expected to be 5°C or below during the placing and curing period, the work shall conform to the requirement of IS: 456 and IS: 7861.

3.18.00 Hot Weather Concreting

When depositing concrete in very hot weather, the Contractor shall take all precautions as per IS: 7861 and stagger the work to the cooler parts of the day to ensure that the temperature of wet concrete used in massive structures does not exceed 38°C while placing. Positive temperature control by precooling, post cooling or any other method, if required, will have to be done by the contractor at no extra cost.

3.19.00 Concreting under water

When it is necessary to deposit concrete under water it shall be done in accordance with the requirements of IS: 456.

3.20.00 Form Work

3.20.01 General

If it is so desired by the Engineer, the contractor shall prepare, before commencement of actual work, designs and working drawings for formwork and centring and get them approved by the Engineer. The formwork shall conform to the shape, grade, lines, levels and dimensions as shown on the drawings.

Materials used for the formwork inclusive of the supports and centring shall be capable of withstanding the working load and remain undistorted throughout the period it is left in service. All supports and scaffolds should be manufactured from structural or tubular steel except when specifically permitted otherwise by the Engineer.

The centring shall be true to vertical, rigid and thoroughly braced both horizontally and diagonally. Rakers are to be used where forms are to support inclined members. The forms shall be sufficiently strong to carry without undue deformation, the dead weight and horizontal pressure of the concrete as a liquid as well as the working load. In case the contractor wishes to adopt any other design criteria, he has to convince the Engineer about its acceptability before adopting it. Where the concrete is vibrated, the formwork shall be strong enough to withstand the effects of vibration without appreciable deflection, bulging, distortion or loosening of its components. The joints in the formwork shall be sufficiently tight to prevent any leakage of slurry or mortar.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 50 of 361

To achieve the desired rigidity, tie bolts, spacer blocks, tie wires and clamps as approved by the Engineer shall be used but they must in no way impair the strength of concrete or cause stains or marks on the finished surface. Where there are chances of these fixtures being embedded, only mild steel and concrete of adequate strength shall be used. Bolts passing completely through liquid retaining walls/slabs for the purpose of securing and aligning the formwork shall not be used.

The formwork shall be such as to ensure a smooth uniform surface free from honeycombs, air bubbles, bulges, fins and other blemishes. Any blemish or defect found on the surface of the concrete must be brought to the notice of the Engineer immediately and rectified as directed by him.

For exposed interior and exterior concrete surfaces of beams, columns and wall, plywood or other approved form shall be thoroughly cleaned and tied together with approved corrosion-resistant devices. Rigid care shall be exercised in ensuring that all column forms are in true plumb and thoroughly cross-braced to keep them so. All floor and beam centring shall be crowned not less than 8 mm in all directions for every 5 metres span. The formwork should lap and be secured sufficiently at the lift joints to prevent bulges and offsets.

Temporary openings for cleaning, inspection and for pouring concrete shall be provided at the base vertical forms and at other places, where they are necessary and as may be directed by the Engineer. The temporary openings shall be so formed that they can be conveniently closed when required, during pouring operations without leaving any mark on the concrete.

3.20.02 Cleaning and Treatment of Forms

All parts of the forms shall be thoroughly cleaned of old concrete, wood shavings, saw dust, dirt and dust sticking to them before they are fixed in position. All rubbish, loose concrete, chippings, shavings, sawdust etc. shall be scrupulously removed from the interior of the forms before concrete is poured. Compressed air jet and/or water jet along with wire brushes brooms etc. shall be used for cleaning. The inside surface of the formwork shall be treated with approved non-staining oil or other compound before it is placed in position. Care shall be taken that oil or other compound does not come in contact with reinforcing steel or construction joint surfaces. They shall not be allowed to accumulate at the bottom of the formwork. The oiling of the formwork will be inspected just prior to placement of concrete and redone wherever necessary.

3.20.03 Design

The formwork shall be so designed and erected that the forms for slabs and the sides of beams, columns, and walls are independent of the soffits of beams and can be removed without any strain to the concrete already placed or affecting the remaining formwork.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 51 of 361

Removing any props or repropping shall not be done except with the specific approval of the Engineer. If formwork for column is erected for the full height of the column, one side shall be left open and built up in sections, as placing of concrete progress. Wedges, spacer bolts, clamps or other suitable means shall be provided to allow accurate adjustment and alignment of the formwork and to allow it to be removed gradually without jarring the concrete.

3.20.04 Inspection of Forms

Casting of Concrete shall start only after the formwork has been inspected and approved by the Engineer. The concreting shall start as early as possible within 3 (three) days after the approval of the formwork and during this period the formwork shall be kept under constant vigilance against any interference. In case of delay beyond three days, a fresh approval from the Engineer shall be obtained.

3.20.05 Removal of Forms

Formwork shall be kept in position after casting of concrete for a minimum period as mentioned in IS: 456, however the period of retaining form in position can be extended as per drawing, instruction of Engineer or as required for satisfactory completion of work without any extra cost. Before removing any formwork, the Contractor must notify the Engineer well in advance to enable him to inspect the concrete if the Engineer so desires.

The Contractor shall record on the drawing or in any other approved manner, the date on which concrete is placed in each part of the work and the date on which the formwork is removed there from and have this record checked and countersigned by the Engineer regularly. The Contractor shall be responsible for the safe removal of the formwork and any work showing signs of damage through premature removal of formwork or loading shall be rejected and entirely reconstructed by him without any extra cost to the Owner, The Engineer may, however, instruct to postpone the removal of formwork if he considers it necessary.

If any other type of cement other than ordinary Portland cement and Rapid hardening cement is used, the time of removal of forms shall be revised such that the strength of this cement at the time of removal of forms match with strength of Portland cement at the time of removal of form.

3.20.06 Tolerance

The formwork shall be so made as to produce a finished concrete, true to shape, lines, levels, plumb and dimensions as shown on the drawings subject to the following tolerances unless otherwise specified in this specification or drawings or directed by the Engineer:-



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 52 of 361

- For - a) Sectional dimension - ± 5 mm
b) Plumb - 1 in 1000 of height
c) Levels - ± 3 mm before any deflection has taken place

The tolerance given above are specified for local aberrations in the finished concrete surface & should not be taken as tolerances for the entire structure taken as a whole or for the setting and alignment of formwork, which should be as accurate as possible to the entire satisfaction of the Engineer. Any error, within the above tolerance limits or any other as may be specially set up by the Engineer, if noticed in any lift of the structure after stripping of forms, shall be corrected in the subsequent work to bring back the surface of the structure to its true alignment.

3.20.07 Re-use of Forms

Before re-use, all forms shall be thoroughly scraped, cleaned, joints and planes examined and when necessary repaired, and inside surface treated as specified hereinbefore. Formwork shall not be used/re-used if declared unfit or unserviceable by the Engineer.

3.20.08 Classification

Generally, the "ordinary" class formwork shall be used unless otherwise specified.

- a) **Ordinary:** These shall be used in places where ordinary surface finish is required and shall be composed of steel and/or approved good quality partially seasoned timber.
- b) **Plywood:** These shall be used in exposed surfaces, where specially good finish is required and shall be made of approved brand of heavy quality plywood to produce a perfectly uniform and smooth surface conforming to the shape described in the drawing with required grain texture on the concrete. Re-use may only be permitted after special inspection and approval by the Engineer. He may also permit utilization of used plywood for the "ordinary" class, if it is still in good condition.
- c) **Ornamental:** These shall be used where ornamental and curved surface are required and shall be made of selected best quality well seasoned timbers or of plywood, which can be shaped correctly.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 53 of 361

3.21.00 Opening, Chases, Grooves, Rebates, Blockouts etc.

The Contractor shall leave all openings, grooves, chases, etc. in concrete work as shown on the drawings or as specified by the Engineer.

3.22.00 Anchor Bolts, Anchors, Sleeves, Inserts, Hangers/Conduits/Pipe and other misc. Embedded Fixtures

The Contractor shall build into concrete work all the items noted below and shall embed them partly or fully as shown on drawings and secure the same as may be required. The materials shall be as specified and be of best quality available according to relevant Indian Standards of approved manufacture and to the satisfaction of the Engineer. Exposed surfaces of embedded materials are to paint with one coat of approved anti-corrosive paint and/or bituminous paint without any extra cost to the Owner. If welding is to be done subsequently on the exposed surface of embedded material, the paint shall be cleaned off the member to a minimum length of 50 mm beyond each side of the weld line.

Necessary templates, jigs, fixtures, supports etc. shall be used as may be required or directed by the Engineer.

Items to be embedded

- a) Inserts, hangers, anchors, frame around openings, manhole covers, frames, floor clips, sleeves conduits and pipes.
- b) Anchor bolts and plates for machinery, equipment and for structural steel work.
- c) Steel structurals to be left embedded for future extension, special connection etc.
- d) Dowel bars, etc. for concrete work falling under the scope of other contractors.
- e) Lugs or plugs for door and window frames occurring in concrete work.
- f) Flashing and jointing in concrete work.
- g) Any misc. embedments and fixture as may be required.

Correct location and alignment, as per drawings/instruction of all these embedded items shall be entirely the responsibility of the Contractor.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 54 of 361

3.23.00 Expansion and Isolation Joints

3.23.01 General

Expansion and isolation joints in concrete structures shall be provided at specific places as per details indicated on the drawings. The materials and types of joints shall be as specified hereinafter. In case of liquid retaining structures, additional precautions shall be taken to prevent leakage of liquids as may be specified on the drawings or as directed by the Engineer. All materials are to be procured from reliable manufacturers and must have the approval of the Engineer. Where it is the responsibility of the Contractor to supply the material, the Engineer may demand test certificates for the materials and/or instruct the Contractor to get them tested in an approved laboratory free of cost to the Owner. Joints shall be formed true to line, level, shape, dimension, and quality as per drawings and specifications. Prior approval of the method of forming the joints should be obtained from the Engineer before starting the work.

3.23.02 Bitumen Board/ Expanded Polystyrene Board

a) Bitumen Board

Bitumen impregnated fibreboard of approved manufacturer as per IS: 1838 may be used as fillers for expansion joints. It must be durable and waterproof. It shall be compressible and possess a high degree of rebound. The dimensions of the board should be equal to that of the joint being formed. It should, preferably be manufactured in one piece, matching the dimension of the joint and not prepared by cutting to size smaller pieces from larger boards at site. At the exposed end, the joint shall be sealed with approved sealing compound to a depth of at least 25 mm after application of an approved primer. The sealing compound and the primer shall be applied as specified by the manufacturer.

b) Expanded Polystyrene Boards

If required, commercial quality of expanded polystyrene products commonly used for thermal insulations may also be used as filler material in expansion joints. The thickness may vary from 12 mm to 50 mm. The material will have to be procured from reliable manufacturers as approved by the Engineer. The method of installations will be similar to that recommended by the manufacturers for fixing on cold storage walls. A coat of Bitumen paint may have to be applied on the board against which concrete will be placed.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 55 of 361

3.23.03 Joint sealing strips

Joint sealing strips may be provided at the construction, expansion, and isolation joints as a continuous diaphragm to contain the filler material and/or to exclude passage of water or any other material into or out of the structure. The sealing strips will be either metallic like G.I., Aluminums, or Copper, or non-metallic like rubber or P.V.C.

Sealing strips will not have any longitudinal joint and will be procured and installed in largest practicable lengths having a minimum number of transverse joints. The material is to be procured from reputed manufacturers having proven records of satisfactory supply of joint strips of similar make and shape for other jobs. The jointing procedure shall be as per the manufacturer's recommendations, revised if necessary, by the Engineer. The Contractor is to supply all labour and material for installation -including the material and tools required for jointing, testing, protection, etc. If desired by the Engineer, joints in rubber seals may have to be vulcanized.

a) Metal Sealing Strips

Metal sealing strips shall be either G.I., Aluminium or Copper and formed straight, U shaped, Z shaped or any other shape and of thickness as indicated in the drawing. The transverse joints will be gas welded using brass rods and approved flux and will be tested by an approved method to establish that it is leak proof. If required, longer lap lengths and different method of brazing which will render it leak proof, will be adopted by the Contractor. The edges shall be neatly crimped and bent to ensure proper bond with the concrete.

i) G.I. Strips

G.I. strips shall be minimum 1.5 mm thick and 150 mm in width unless specified otherwise. The standard of Galvanizing shall be as per relevant Indian Standards for heavy-duty work. At the joints, the overlapping should be for a minimum length of 50 mm.

ii) Aluminium Strips

Aluminium strips shall be minimum 18 SWG thick and 300 mm wide unless specified otherwise and shall conform to IS: 737 of 19000 grades or 31000 grade (Designation as per IS: 6051). A minimum lap of 50 mm length is required at the joints.

iii) Copper Strips

The Copper strips shall be minimum 18 SWC in thickness and 300 mm width unless specified otherwise and shall conform to the relevant Indian Standards. It should be cleaned thoroughly before use to expose



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 56 of 361

fresh surface, without any reduction in gauge. A minimum lap of 50 mm in length is required at the joints.

b) Non-metallic Sealing Strips

These will be normally in Rubber or P.V.C. Rubber or P.V.C. joint seals can be of shape having any combination of the following features:

- i) Plain
- ii) Central bulb
- iii) Dumb-bell or flattened ends
- iv) Ribbed and Corrugated Wings
- v) V shaped

As these types of seals can be easily handled in very large lengths unlike metal strips, transverse joints will be allowed only under unavoidable circumstances and with the specific approval of the Engineer. The method of forming these joints, laps etc. shall be as specified by the Manufacturer and/or as approved by the Engineer taking particular care to match the central bulbs & the edges accurately.

c) Rubber Sealing Strips

The minimum thickness of Rubber sealing strips shall be 3 mm and the minimum width 100 mm. The actual size and shape will be as shown in drawings or as directed by the Engineer. The material will be natural rubber and be resistant to corrosion, abrasion, and tear and also to attacks from the acids, alkalis and chemicals normally encountered in service. The physical properties will be generally as follows. The actual requirements may be slightly different as decided by the Engineer:

Specific Gravity	:	1.1 to 1.15
Shore Hardness	:	65A to 75A
Tensile Strength	:	25 - 30 N/Sq.mm
Maximum Safe Continuous Temperature	:	75°C
Ultimate Elongation	:	Not less than 350%

b) P.V.C., Sealing Strips



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 57 of 361

The minimum thickness of P.V.C. sealing strips will be 3 mm and the minimum width 100 mm. The actual size and shape will be as shown in drawings or as directed by the Engineer. The material should be of good quality Polyvinyl Chloride highly resistant to tearing, abrasion, and corrosion as well as to chemicals likely to come in contact with during use. The physical properties will generally be as follows. The actual requirements, which will be directed by the Engineer, may vary slightly

Specific Gravity	:	1.3 to 1.35
Shore Hardness	:	60A to SOA
Tensile Strength	:	10 - 15 N/Sq.mm
Maximum Safe Continuous Temperature	:	70 Deg.C
Ultimate Elongation	:	Not less than 275%

3.23.04 Bitumen Compound

When shown in drawing or directed, the gap in expansion joints shall be thoroughly cleaned and bitumen compound laid as per manufacturer's specifications. The compound to be used shall be of approved manufacture and shall conform to the requirements of IS: 1834.

3.23.05 Isolation Joints

Strong and tough alkathene sheet or equivalent, about 1 mm in thickness and as approved by the Engineer shall be used in isolation joints. It shall be fixed by an approved adhesive compound on the cleaned surface of the already set concrete to cover it fully. Fresh concrete shall be laid against the sheet, care being taken not to damage the sheet in any way.

3.23.06 Pad

Hard foundation quality rubber pads of required thickness and shapes shall be put below machine or other foundations as shown on the drawings. The rubber shall have a unit weight of 1500 Kg/Cu.m, a shore hardness - 65A to 70A and be of best quality of approved manufacture, durable, capable of absorbing vibration and must be chemically inert in contact with moist or dry earth or any other deleterious material expected under normal conditions.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 58 of 361

3.24.00 Grouting under Machinery or Structural Steel Bases

If required, grouting under base plates of machines or structural steel etc. shall be carried out by the Contractor. In general, the mix shall be 1 (one) part cement and 1 (one) part sand and just enough water to make it flow as required. The areas to be grouted shall be cleaned thoroughly with compressed air jet and/or with water in locations where accumulated surplus water can be removed. Where directed by the Engineer, 6 mm down stone chips may have to be used in the mix. Surface to be grouted shall be kept moist for at least 24 hours in advance. The grout shall be placed under expert supervision, so that there is no locked up air. Edges shall be finished properly. If specified on drawings, admixtures like Aluminium powder, "Ironite" etc. may have to be added with the grout in required proportions. Premixed non-shrink grout of approved manufacture having proper strength shall be used with Engineer's approval for important machineries.

3.25.00 Precast Concrete

The Specification for precast concrete will be similar as for the cast-in-place concrete described herein and as supplemented in this section. All precast work shall be carried out in a yard made for the purpose. This yard shall be dry, properly levelled and having a hard and even surface. If the ground is to be used as a soffit former of the units, it shall be paved with concrete or masonry and provided with a layer of plaster (1:2 proportion) with smooth neat cement finish or a layer of M.S. sheeting. Where directed by the Engineer, casting will have to be done on suitable vibrating table. The yard, lifting equipment, curing tank, finished material storage space etc. shall be designed such that the units are not lifted from the mould before 7 (seven) days of curing and can be removed for erection after 28 (twenty-eight) days of curing. The moulds shall preferably be of steel or of timber lined with G.I. sheet metal. The yard shall preferably be fenced.

Lifting hooks, where necessary or as directed by the Engineer, shall be embedded in correct position of the units to facilitate erection, even though they may not be shown on the drawings, and shall be burnt off and finished after erection.

Precast concrete units, when ready, shall be transported to site by suitable means approved by the Engineer. Care shall be taken to ensure that no damage occurs during transportation. All adjustments, leveling, and plumbing shall be done as per instructions of the Engineer. The Contractor shall render all help with instruments, materials, and men to the Engineer for checking the proper erection of the precast units.

After erection and alignment, the joints shall be filled with grout or concrete as per drawings. If centrings have to be used for supporting the precast units, they shall not be removed until the joints have attained sufficient strength and in no case before 14 (fourteen) days. The joint between precast roof planks



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 59 of 361

shall be pointed with 1:2 cement: sand mortar where called for in the drawings.

3.26.00 Waterproofing of Concrete Structure

3.26.01 General

Where required, waterproofing of concrete structures shall be ensured internally by suitable design of the concrete mix, addition of suitable admixtures in the concrete or mortar at the time of mixing and/or installing water bars at the joints. In addition to the above measures, the structures shall be made watertight by adopting "structural waterproofing" as per specification. The design, material, and workmanship shall conform to the relevant I.S. Codes where applicable. The Engineer's approval of the materials shall be obtained by the Contractor before procurement. If desired by the Engineer, test certificates for the materials and samples shall be submitted by the Contractor free of charge. The materials shall be of best quality available indigenously, fresh clean and suitable for the duties called upon.

3.26.02 Water Bar/Seal/Special Treatment of Construction Joint

Water bearing structures and underground structures may have water bar/seals installed at the joints. They may be metallic, rubber, or P.V.C. The materials and installation will be as described under Clause 3.23.3. Construction joint shall be provided as per clause 3.13.1 with or without water bar/seal as shown on the drawing. In case of water bars being used at the construction joint, fixing of the same has to be done carefully, so that the water bar is not disturbed during concreting. The construction joint shall also be treated by any one of the following methods.

Method 1: A surface retarder in the form of a thixotropic gel shall be applied on the joint surface of the previous pour in case of joint on the wall and in case of floor the same shall be applied on the formwork against which previous pour of concreting shall be done. The retarder may be liquid or paste form depending on the type of formwork. The formwork shall be removed within 24 hours after concreting. Within 2 hours of striking of the formwork the retarder shall be washed off with strong water jet to make surface rough and clean. Then a rich cement mortar using cement, sand and aggregates (maximum size 8 mm) along with synthetic rubber emulsion type water resistant bonding agent shall be applied for a depth of 50 mm just before pouring the next stage of concreting. In case of walls, the above bonding agent will be mixed with water, which will be used for making the cement mortar. The proportion of mixing of this bonding agent with water shall be as per manufacturer's specification. In case of floor joint, however, after washing of retarder a solvent free two-component epoxy resin-bonding agent will be used at the joint before the next pour of concrete. The above bonding agent shall have the following properties after 28 days



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 60 of 361

Compressive strength - 55 to 60 N/Sq.mm

Flexural strength - 5 to 30 N/sq.mm

Tensile strength - 15 N/Sq.mm (approx.)

Bonding strength to concrete - 3 N/Sq.mm (approx.)

Bonding strength to steel - 20 N/Sq.m (approx.)

The whole operation shall be done as per manufacturers specification. The contractor shall provide manufacturer's supervision at no extra cost to the owner.

Method 2: One row of threaded nozzles at regular intervals not exceeding 1.5 m centre to centre shall be placed in concrete along the construction joint during casting. Injection of cement water together with a suitable waterproof expanding grouting admixture of approved quality shall be done through the nozzles after the concrete has set to seal the voids in concrete near the construction joint in walls and slabs. The injection shall be done under pressure of approximately 2 to 4 kg/sq.cm. The nozzles shall be sealed off with suitable admixture after the injection is over. The whole operation shall be carried out as per manufacturer's specification and supervision. The cost of such manufacturer's supervision shall be borne by the contractor.

3.26.03 Waterproofing Admixtures

The waterproofing admixture for concrete and cement mortar/plaster shall conform to IS: 2645. The admixture shall not cause decrease of strength of concrete/plaster at any stage and it shall be free from chlorides and sulphates. The admixture shall not affect the setting time by more than 5%. The maximum permissible dosage of admixture will be 3% (three percent) by weight of cement, but a lower dosage will always be preferred. The product shall be stored in strong moisture proof packings. However, in case of important structures where M25 or higher grade concrete is specified, the use of melamine based, high range water reducing concrete admixture shall be used to provide a waterproof concrete, For achieving high strength concrete having cement content around 400 kg/cu.m. a melamine based super plasticizer will be preferable.

- a) In concrete: The admixtures shall be procured from reliable and reputed manufacturers and approved by the Engineer. The method of application and other details shall conform to the manufacturer's specification and/or as instructed by the Engineer. The Contractor shall have the services of the manufacturer's supervisor at no extra cost to supervise the work, if desired by the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 61 of 361

- b) In Plaster: The concrete surface, to be plastered, shall be hacked to Engineer's satisfaction, cleaned thoroughly and kept wetted for 24 hours. The plaster shall be in cement sand mortar mixed in proportion varying from 1:1 to 1:4 by volume along with the approved waterproofing admixture and laid in appropriate thickness and in layers not exceeding 15 mm/layer or as per manufacturer's specification. The additive shall be of quality and type approved by the Engineer. If desired by the Engineer, the Contractor shall have the work supervised by the manufacturer's supervisor at no extra cost. On completion, the Plastered surface shall be cured continuously for a minimum period of 14 days like concrete.

3.26.04 Structural waterproofing

- a) Nozzles spaced as required after the concrete is completed shall be drilled into surfaces to be rendered watertight. Non-shrink cement grout with waterproofing compound as per manufacturers specifications shall be injected under pressure to seal all voids. Special care shall be taken at joints by providing additional nozzles. The pressure grouting shall be done on the internal surface.

- b) External Treatment

Two layers of (1 : 4) plaster of 12 mm thick each with waterproofing compound as per manufacturer's specification shall be provided on outer surface of concrete underground structures.

3.26.05 Protective coating on Inside Surface.

Two coats of cement based two components polymer modified flexible protective and waterproofing slurry having 1 mm thick for each coat shall be applied on the walls/floor after proper surface preparation as mentioned above. The slurry shall be applied by brush.

3.26.06 Bitumen Felt: Application for Tanking

This specification shall cover laying the waterproof course on the outside and inside of the walls and bases of structures.

The materials shall conform to IS: 1322, and the workmanship to IS: 1609. The bitumen felt should be hessian base and/or fibre base as specified in Drawing. If required by the Engineer, tests as specified in relevant IS Codes shall be arranged by the Contractor without charging any extra to the Owner.

The Contractor shall execute this work in direct collaboration with one of the well known specialized firm approved by the Engineer.

Cleaning the surface, keeping it dry, providing, necessary corner fillets and cement rendering and cutting chases, etc. shall be done as per drawings and/or instructions. If any protective brickwork on/against concrete sub-bases or



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 62 of 361

walls are required, the same shall be provided. A twenty (20) years guarantee for satisfactory performances shall be given by the Contractor as well as his specialist sub-contractor jointly and severally, for this work. Free rectification of any defects noted in the work within this guarantee period will be carried out by the Contractor even if it is beyond the specified maintenance period of the contract as a whole.

3.26.07 Polyethylene Films: Application in Walls or base of structures

Waterproof treatment shall be applied as outlined and as per sequence given hereunder

- i) the concrete surface shall be made smooth with 12 mm cement plaster 1:6.
- ii) apply hot bitumen 80/100 grade (IS: 73-1961) at the rate of 1.0 Kg/Sq.m minimum
- iii) lay black polyethylene film 250-micron (IS: 2508-1977) with cut back bitumen adhesive in overlaps over hot bitumen surface, gently pressed, taking care not to puncture the film.

Alternatively, the overlaps shall be heat sealed by an electric iron having three parallel sealing bars. A long piece of plywood is to be placed below the polyethylene film to be heat-sealed. On the plywood a rubber gasket is to be laid to provide a cushion for better welding of the film. On the rubber padding, a cellophane tape is to be spread and on this the LDPE film, with 100 mm overlap, is to be stretched. On the overlapped film another cellophane tape is to be placed to prevent the heat sealer from sticking to the LDPE film. After this, the electric iron is to be pressed on the overlap joint for sufficient time so as to allow perfect welding. The operation is to be repeated for subsequent lengths of joints. After heat-sealing, the cellophane tape is to be removed and the joints are to be tested for leaks.

- iv) Lay 100 gm brown craft paper laminated with a layer of straight run bitumen,
- v) Lay hot bitumen 80/100 grade (IS: 73-1961) at 1.0 Kg/Sq.m minimum.
- vi) Lay 250-micron polyethylene film as second layer similar to
- vii) above.
- viii) Lay second layer of 100 gm. brown craft paper laminated similar to (iv) above.
- ix) Apply hot bitumen (straight run grade) to IS: 73-1961 at 1.0 Kg/Sq.m dusted with fine sand.
- x) Protecting with a layer of 75 mm plain cement concrete M-10, or a layer of



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 63 of 361

brick laid in cement mortar 1:6 in case of wall apply a 12 mm thick plaster as shown on the drawing or a protective brick wall in 1:6 cement mortar as shown on the drawing.

3.27.00 Protective Coating on Concrete Surface

3.27.01 On Foundation

The outside faces of foundation of important structures will be protected from adverse effect of soil/underground water, if shown on drawing by using rubber/bitumen emulsion protective coating of approved manufacturer.

4.00.00 SAMPLING AND TESTING

4.01.00 General

The Contractor shall carry out all sampling and testing in accordance with the relevant Indian Standards and as supplemented herein for the following items at his own cost unless otherwise specified in this specification. The Contractor shall get the specimens tested in a laboratory approved by the Engineer and submit to the Engineer the test results in triplicate within 3 (three) days after completion of the test.

4.02.00 Cement

Representative samples will be taken from each consignment of cement received from the manufacturer/supplier for carrying out the tests for fineness (by hand sieving), setting time and compressive strengths as per guidelines of IS: 269. Soundness Tests may also be required to be carried out if required by the Engineer. The Contractor shall carry out the tests without any expense to BHEL. No cement from a particular consignment/batch will be used on the works unless satisfactory 3 (three) days and 7 (seven) days test results for compressive strength are known. The Engineer and Contractor will jointly associate themselves with the tests irrespective of whether they are carried out by the BHEL or the Contractor. These tests are of great importance, as their results will have a bearing on the acceptance of concrete or otherwise as per the terms and conditions of the Contract.

4.03.00 Aggregates

The contractor shall carry out any or all the tests on aggregates as may be required by the Engineer in accordance with IS: 2386 PARTS-I to VIII. The acceptance criteria of the samples tested shall be in accordance with the requirements of the relevant Indian Standards.

4.04.00 Water

Sampling and Testing of water being used for concrete works as per IS: 3550



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 64 of 361

will be carried out by the Contractor at regular intervals and whenever directed by the Engineer. The acceptance criteria will be as per IS: 456.

4.05.00 Admixture

4.05.01 Air Entraining Agents

Initially, before starting to use A.E.A., relationship between the percentage of air entrained and the cylinder cube crushing strength vis-a-vis quantity of A.E.A. used for all types of concrete will be established by the Contractor by carrying out sufficiently large number of tests. After that, at regular intervals and whenever directed by the Engineer, the Contractor will check up the actual percentages of air entrained and corresponding crushing strengths to correlate with the earlier test results.

4.05.02 Other Admixtures

Tests for establishing the various properties of any other admixtures, which may be required to be added, shall be carried out by the Contractor.

4.06.00 Concrete

The sampling of concrete, making the test specimens, curing and testing procedure etc. shall be in accordance with IS: 516 and IS: 1199, the size of specimen being 15 cm cubes. Normally, only compression tests shall be performed but under special circumstances the Engineer may require other tests to be performed in accordance with IS: 516. Sampling procedure, frequency of sampling and test specimen shall conform to IS: 456. To control the consistency of concrete from every mixing plant, slump tests shall be carried out by the Contractor every two hours or as directed by the Engineer. Slumps corresponding to the test specimens shall be recorded for reference. The acceptance criteria of concrete shall be in accordance with IS: 456. Concrete work found unsuitable for acceptance shall have to be dismantled and replacement is to be done as per specification by the Contractor at his own cost. In the course of dismantling, if any damage is done to the embedded items or adjacent structures, the same shall be made good, free of charge by the Contractor, to the satisfaction of the Engineer.

5.00.00 ACCEPTANCE CRITERIA

5.01.00 Standard Deviation

Standard deviation shall be based on test results and determination of Standard deviation shall conform to IS: 456.

5.02.00 Acceptance Criteria

The strength requirements and acceptance criteria shall conform to IS: 456.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 65 of 361

5.03.00 Inspection and Core Tests

Inspection of concrete work immediately after stripping the formwork and core test of structures shall conform to IS: 456.

5.04.00 Load Test

Load tests of structural members as per IS: 456 may be required by the Engineer, when the strength of test specimen results falls below the required strength.

If the member shows evident failure, the Contractor shall make the structure adequately strong free of cost to BHEL.

The entire cost of load testing shall be borne by the Contractor. If a portion of the structure is found to be unacceptable, it shall be dismantled and replaced by a new structure as per specification. The entire cost of dismantling and replacement and restoration of the site being borne by the Contractor.

If, in the course of dismantling, any damage is done to the embedded items and or other adjacent structures, the same will be made good, free of charge by the Contractor to the satisfaction of the Engineer.

6.00.00 RATES AND MEASUREMENTS

6.01.00 Cast-in-situ Concrete

6.01.01 Rates

- a) The unit rates shall include the cost of labour, materials, equipment, handling, transporting, batching, mixing, placing in position, vibrating, compacting, finishing, curing, testing, etc. at all elevations. This shall also include the cost of using curing compound, whenever used.
- b) The unit rates shall include for all working conditions including in or under water, liquid, mud, in or under foul positions, under tides, and extreme weather conditions.
- c) The unit rates for exposed concrete works (including machine foundations) shall include all incidentals, rendering, smoothening with carborandum stone, finishing with a paste of cement sand mortar, curing, etc.
- d) The unit rates shall include for maintaining stability of structure during execution.
- e) Nothing extra shall be payable for the handling/mixing of extra cement on account of any reason or pouring of second stage concrete.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 66 of 361`

- f) Nothing shall be payable to the Contractor on account of facilities and arrangement provided by him for conducting ultrasonic pulse velocity tests or other relevant tests to ascertain grade and quality, etc. of the concrete, if required. In case of any defects, the Contractor shall rectify the same by cement/epoxy grout at his own cost.
- g) The unit rates for controlling of the temperature of concrete shall include storing and mixing of ice, water, cooling of aggregate etc.
- h) The quoted rate shall include the cost of making additional trial mixes, using the superplasticizer and mixing in concrete etc.

6.01.02

Measurements

- a) Actual volume of concrete work as executed or as per drawings issued, whichever is less shall be measured in cubic metres.
- b) No deductions shall be made for the following:
 - i) Opening upto 0.1 sq.m.
 - ii) Volume occupied by reinforcement, sleeves, anchor bolts, and similar items.
 - iii) Volume occupied by pipes, conduits, sheathing, etc. not exceeding 100 sq.cm. each in cross sectional area.
- c) The concrete works of different grades; below and above ground floor finished level shall be measured separately, unless otherwise specified in the schedule of items. Accordingly rates shall be applied for concrete in foundation for concrete below ground floor finished level and concrete in superstructure for concrete above ground floor finished level.
- d) For temperature control measures, measurement shall be done in terms of quantity of concrete in cum. in concreting of which the ice have been used or cooling of aggregates has been done to keep the temperature of freshly laid concrete to less than 25°C.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 67 of 361

6.02.00 Reinforcement

6.02.01 Rates

- a) The unit rates shall include for cover block, providing binding wire, welding, separator pieces between two or more layers of reinforcement required for keeping the steel in position, etc. at all elevations.
- b) No extra will be paid for transportation from stores, cleaning, straightening of steel, cutting, bending, binding with annealed wire, welding, tack welding, placing the reinforcement modification of already embedded reinforcement, if required, due to faulty fabrication or placement and other cost of tools and plants, materials, labours, return of unused steel to the store, etc.
- c) No extra shall be paid for preparing and getting approved bar bending schedules (including all revisions).
- d) Generally members are straight and have straight edges. However, for bending, binding, placing of reinforcement in any curved member in length or cross section or both, no extra payment shall be made.

6.02.02 Measurements

- a) Bar or any other type of reinforcement used like hard drawn steel wire fabric etc. for reinforced concrete shall be measured by weight in tonnes. The weight shall be arrived at by multiplying the actual or theoretical length measured along with standard hooks, cranks, bends, authorized laps, etc. whichever is less by the sectional weights. Claims for payment for this item shall be submitted with supporting documents giving the schedule of bars with sketches. The sectional weight to be adopted shall be IS Section weight. Nothing extra will be payable to the Contractor on account of, difference in weight, if any, due to different methods adopted for issue and measurement.
- b) Standard hooks, cranks, bends, authorised laps, supports, hangers and chairs which are covered in approved bar bending schedule shall be measured in tonnes.

6.03.00 Formwork and Staging

6.03.01 Rates

- a) The unit rates shall be inclusive of all staging, scaffolding, making the formwork watertight, etc. for all elevations and in all types of works.
- b) No separate payment shall be made for providing fillets, for rounding or chamfering at junctions, corners, etc.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 68 of 361

- c) The unit rates shall include the cost of labour, materials etc. and the extra time, which shall be required for the removal of shuttering/ support for satisfactory completion of work.
- d) No extra payment shall be made on account of difficulty, wastage etc. for placement/removal of formwork between the network of closely placed steel beams or for the lacing/bracing portions and ribbed slab constructions.
- e) Payment for curved shuttering shall be made for curved members/wall whose centerline radius in plan is less than 6m.
- f) If the contact surface area in pockets is less than or equal to 0.1 sq.m. in each case, payment shall be done under item for providing formwork in pockets.

6.03.02 Measurements

- a) Formwork for different classes (types) shall be measured separately as the actual surface in contact with the concrete and paid on area basis unless included in the rate for concrete. The unit of measurement shall be in sq.m.
- b) Openings upto 0.1 sq.m or boxing left for inserts etc. for facility of Contractor's work, shall be neglected as if nonexistent for the purpose of formwork measurement of surface in which the openings occur.

For suspended floor, no deduction shall be made for flange area of secondary steel beams.

- c) No measurement shall be taken for the formwork in pockets, openings, chases, blockouts, etc. in concrete, the contact surface area is less than or equal to 0.1 sq.m. in each case.
- d) For pockets, if the contact surface area is less than or equal to 0.1 sq.m. in each case, measurement shall be done under item for providing formwork in pockets.
- e) Formwork, if required, for joints shown on drawing or instructed by the Engineer, shall be paid for the 'leading side' only.

6.04.00 Embedded Parts

6.04.01 Rates

- a) The unit rate for erection of embedded steel parts, supplied by Engineer shall include transportation from Owner's store to the place of work, erection & installation including setting material in concrete, etc. complete.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 69 of 361

- b) The unit rate for MS pipe embedments and PVC pipe embedments shall include cutting, welding, fabrication, erection, embedding, and transportation to site. Unit rate shall also include the cost of the pipes.
- c) Rate for expansion fasteners shall include cost of fasteners, installation, and fixing including cost of washers and nuts.

6.04.02

Measurements

- a) The measurement of the embedded steel parts fabricated and installed by the Contractor shall be based on the calculated weight of steel sections in tonne corrected to second place of decimal.
- b) Embedded steel parts supplied by Owner and installed by Contractor Measurement shall be done for the net weight of the embedments installed in tonnes correct to second place of decimal.
- c) For PVC pipes/conduits, measurements shall be in quintals correct to second place of decimal for the net weight.
- d) For mild steel pipes, measurement shall be in quintals, correct to second place of decimal, for the net weight of the steel pipe supplied, fabricated, and installed.
- e) The lugs shall be measured in Kg. correct to second place decimal for the net weight.
- f) The expansion fasteners shall be measured in number according to tension capacity.
- g) The rails shall not be treated as embedded steel part and the track shall be measured in running metres along the centre line and paid for under separate item of work as specified in schedule of items. Other related civil items associated with the laying of track shall be measured separately and paid under respective items of works.

6.05.00

Groutings

6.05.01

Rates

Rate shall include the cost of surface preparation, admixtures, and curing.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 70 of 361

6.05.02

Measurements:

- a) Measurement shall be in cubic decimeters.
- b) Measurement for grouting shall be by volume of the block out, pockets or bolt hole upto the top surface of foundation concrete and shall be calculated from the dimensions shown on the drawings.
- c) Measurement for underpinning shall be by volume between the top surface of the foundation concrete and the underside of the base plate, the plan dimensions being as indicated on the drawings.
- d) No deduction shall be made for shims, bolts, shear keys and such other embedments.

6.06.00

Joints

6.06.01

Rates

The unit rate shall include all the activities described in the schedule of items.

6.06.02

Measurements

- a) Bitumen Board/Expanded polystyrene.

The measurement for bitumen board shall be based on actual finished surface area in square meters nearest to second decimal, for the specified thickness.

- b) Water Stops

The measurement for water stops shall be in running metres of actual length of the joint covered, for specified thickness, width, and shapes. No separate measurement shall be made for laps/splices for cross-joints and mitered joints.

- c) Metal Cover Strips

The measurement for Metal Cover Strips shall be based on actual finished surface area in square metres for the specified thickness.

- d) Vibration Damping Resilient Pads

The measurement for this item shall be in square metres for the specified thickness, measured correct to the second place of decimal, of the actual finished surface area.

6.07.00

Dismantling/Demolishing Work – RCC and PCC and Chipping of Concrete



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 71 of 361

6.07.01

Rates

The unit rates shall include the cost of all necessary propping, shoring, underpinning scaffolding, safety measures, temporary enclosures, disposal/stacking of serviceable/unserviceable materials, etc. for all types of work and for all grades of concrete.

In the case of dismantling/demolishing work, the cutting of reinforcement shall also be included in the rate.

In the case of chipping work, the cutting of reinforcement shall be paid separately.

6.07.02

Measurements

- a) Dismantling of PCC and RCC work shall be measured in cu.m separately. Measurement of all work, except hidden work shall be taken before execution of work and no allowance for increase in bulk shall be allowed. Specifications for deductions of voids, openings etc, shall be on the same basis as that employed for construction work.
- b) Chipping of concrete, making holes/pockets etc. shall be measured in cubic decimeters (i.e. 0.001 cu.m.).
- c) Cutting of reinforcement in chipping work for making of pockets and openings shall be measured in sq. cm. of cross-sectional area.

6.08.00

Precast Concrete

This clause shall be read in conjunction with relevant provisions specified elsewhere for cast in-situ Concrete.

6.08.01

Rates

- a) The unit rate shall include cost of preparation of casting yard, formwork, concrete and its casting, finishing as specified, setting filling of gaps between adjacent pre-cast concrete units with concrete, or cement mortar, curing, handling, erection, grouting, welding, preparation of supporting surface, etc.

6.08.02

Measurements

The measurement of pre-cast concrete members shall be on the basis of volume of concrete in cubic metres nearest to second place of decimal. No deduction shall be made for volume occupied by reinforcement/inserts/sleeves and for openings up to 0.1 sq.m. The setting of element with cement mortar shall not be measured separately The filling of concrete cement mortar



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 72 of 361`

between the gaps of adjacent precast units shall be considered while computing the volume of pre-cast concrete work and shall be paid for under this item itself.

7.00.00

LIST OF IS CODES AND STANDARDS FOR REFERENCE

All work under this specification shall, unless specified otherwise, conform to the latest revisions and/or replacements of the following or any other Indian Standard Specifications and Codes of Practice. In case any particular aspect of work is not specifically covered by Indian standard Specifications, any other standard practice, as may be specified by the Engineer, shall be followed:-

- IS: 73 - Indian Standard Specification for Paving Bitumen
- IS: 216 - Indian Standard Specification for Coal Tar Pitch
- IS: 383 - Indian Standard Specification for Coarse and Fine Aggregates from Natural Sources for Concrete
- IS: 432 - Indian Standard Specification for Mild Steel and Medium Tensile Steel Bars and Hard Drawn Steel Wire for concrete Reinforcement
- IS: 455 - Indian Standard Specification for Slag Cement
- IS: 456 - Indian Standard Code of Practice for Plain and Reinforced Concrete
- IS: 457 - Indian Standard Code of Practice for General Construction of Plain and Reinforced Concrete for Dams and other Massive Structures
- IS: 516 - Indian Standard Specification for Methods of Test for Strength of Concrete
- IS: 702 - Indian Standard specification for industrial bitumen.
- IS: 1199 - Indian Standard Specification for Methods of Sampling and Analysis of Concrete
- IS: 1322 - Indian Standard Specification for Bitumen Felts for Waterproofing and Damp-proofing
- IS: 1489 - Indian Standard Specification for Portland Pozzolona Cement



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 73 of 361

- IS: 1566 - Indian Standard Specification for hard drawn steel wire fabric for concrete reinforcement.
- IS: 1609 - Code of Practice for Laying Damp-proof Treatment using Bitumen Felts
- IS: 1786 - Indian Standard Specification for High Strength Deformed Steel Bars and Wires for Concrete Reinforcement.
- IS: 1791 - Indian Standard Specification for Batch Type Concrete Mixers.
- IS: 1838 - Indian Standard Specification for preformed fillers for expansion joints in concrete pavements and structures (non-extruding and resilient type).
- IS: 2185 - Indian Standard Specification for Hollow Cement Concrete Blocks
- IS: 2210 - Indian Standard Specification for Design of Reinforced Concrete shell Structures and Folded Plates
- IS: 2386 - Indian Standard Specification for Methods of Test for Aggregates for Concrete - Part-I to VIII
- IS: 2502 - Indian Standard Code of Practice for Bending and Fixing of Bars for Concrete Reinforcement
- IS: 2505 - Indian Standard Specification for Concrete Vibrators, Immersion Type
- IS: 2506 - Indian Standard Specification for Screed Board Concrete Vibrators
- IS: 2514 - Indian Standard Specification for Concrete Vibrating Tables
- IS: 2571 - Code of practice for laying in-situ cement concrete floors.
- IS: 2645 - Integral cement water proofing compound
- IS: 2722 - Indian Standard Specification for Portable Swing Weigh Batchers for Concrete (Single and Double Bucket type)
- IS: 2750 - Indian Standard Specification for steel scaffoldings.
- IS: 2751 - Code of Practice for Welding of Mild Steel Bars used for Reinforced Concrete Construction
- IS: 2770 - Indian Standard Specification for Method of Testing Bond in



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 74 of 361

Reinforced Concrete

- IS: 3025 - Indian Standard specification for Methods of Sampling and Test (Physical and Chemical) for Water used in Industry
- IS: 3067 - Code of practice for general design details and preparatory work for damp proofing and water proofing of building.
- IS: 3201 - Indian Standard Specification for Design and Construction of Precast Concrete Trusses
- IS: 3370 - Indian Standard Specification for Code of Practice for Concrete Structures for Storage of Liquids
- IS: 3414 - Code of practice for design and installation of joints in buildings.
- IS: 3550 - Indian Standard Specification for Method of Test for Routine Control for Water used in Industry
- IS: 3558 - Code of Practice for use of Immersion vibrators for Consolidating Concrete
- IS: 3696 - Safety Code for Scaffolding and Ladders
- IS: 3812 - Indian Standard Specification for Fly Ash for Use as Admixture for Concrete
- IS: 4014 - Code of practice for steel tubular scaffolding.
- IS: 4031 - Indian Standard Specification for Method of Tests for Hydraulic Cement
- IS: 4082 - Indian Standard Specification for Recommendation on Stacking and Storage of Construction Materials at site
- IS: 4090 - Indian Standard Specification for Design of Reinforced Concrete Arches
- IS: 4634 - Indian Standard Specification for Method of Testing Performance of Batch-type Concrete Mixes
- IS: 4656 - Indian Standard Specification for Form Vibrators for Concrete
- IS: 4925 - Indian Standard Specification for Concrete Batching and Mixing Plant
- IS: 4926 - Indian Standard Specification for Ready Mixed Concrete



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 75 of 361

- IS: 4990 - Indian Standard Specification for Plywood for Concrete Shuttering work
- IS: 4991 - Indian Standard Specification for Blast Resistant Design of structure for Explosion above ground
- IS: 4995 - Indian Standard Specification for Design of Reinforced Part-I & II Reinforced Concrete Bins for the Storage of Granular and Powdery Materials
- IS: 4998 - Indian Standard Specification for Design of Reinforced Concrete Chimneys.
- IS: 5256 - Code of practice for sealing joints in concrete lining on canals.
- IS: 5512 - Indian Standard Specification for Flow Table for use in Tests of Cement and Pozzolanic materials
- IS: 5513 - Indian Standard Specification for vacate Apparatus.
- IS: 5515 - Indian Standard Specification for Compaction Factor Apparatus.
- IS: 5525 - Recommendation for detailing of reinforcement in reinforced concrete works.
- IS: 5624 - Indian Standard Specification for foundation bolts.
- IS: 5751 - Indian Standard Specification for Precast Concrete Coping Blocks.
- IS: 5816 - Indian Standard Specification for Method of Test for Splitting Tensile strength of Concrete Cylinders.
- IS: 5891 - Indian Standard Specification for Hand operated Concrete Mixers.
- IS: 5892 - Indian Standard Specification for transit mixer and agitators.
- IS: 6452 - Indian Standard Specification for High Alumina Cement for Structural Use
- IS: 6909 - Indian Standard Specification for Super sulphated Cement
- IS: 6923 - Indian Standard Specification for Method of Test for Performance of Screed Board Concrete Vibrators.
- IS: 6925 - Indian Standard Specification for Method of Test for



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 76 of 361`

Determination of Water Soluble Chloride in Concrete Admixtures.

- IS: 7242 - Indian Standard Specification for Concrete Spreaders.
- IS: 7246 - Indian Standard Specification for Table Vibrators for Consolidating Concrete.
- IS: 7251 - Indian Standard Specification for Concrete Finishers.
- IS: 7293 - Safety code for working with construction machinery.
- IS: 7320 - Indian Standard Specification for Concrete Slump Test Apparatus.
- IS: 7861 - Indian Standard Specification for Recommended Practice Part-I&II for Extreme Weather Concreting.
- IS: 7969 - Safety Code for Storage and Handling of Building Materials.
- IS: 8041 - Indian Standard Specification for Rapid Hardening Portland cement.
- IS: 8112 - Indian Standard Specification for high strength Ordinary Portland Cement.
- IS: 8142 - Indian Standard Specification for Determining Setting time of concrete by Penetration Resistance.
- IS: 8989 - Safety Code for Erection of Concrete Framed Structures.
- IS: 9012 - Recommended method for shotcreting.
- IS: 9013 - Indian Standard Specification for Method of Making, Curing, and determining compressive Strength of Accelerated-cured Concrete Test Specimens.
- IS: 9077 - Code of Practice for Corrosion Protection of Steel Reinforcement in RB and RCC Construction.
- IS: 9103 - Indian Standard Specification for Admixtures for Concrete.
- IS: 10262 - Recommended Guidelines for Concrete Mix Design.
- IS: 13311 - Non-destructive testing of concrete.
- SP: 34 - Handbook of concrete, reinforcement and detailing.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 77 of 361`



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 78 of 361`

SECTION - D

SUB-SECTION – D3

CARPENTRY AND JOINERY

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 79 of 361`

2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA
4.00.00	I.S. CODES
5.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 80 of 361

CARPENTRY AND JOINERY

1.00.00 SCOPE

This section covers supply, fitting and fixing of timber frames to doors and windows with M S holdfasts, flush doors, windows, shutters, partitions, wall panelling, pelmets, shelves, furniture, etc. as shown in drawings, including a prime coat of approved paint, varnish, or fixing of decorative plastic laminate where called for. This shall also include the supply and fixing of all hardware and fixtures shown in drawing or specified.

2.00.00 INSTALLATION

2.00.01 Materials

a) Timber

Unless otherwise specified, all timber shall be best quality well seasoned CP teakwood free from large or loose knots, cracks or any other defects. All timber shall be treated with approved wood preservative before use, unless specified otherwise. The rough timber shall be approved by the Engineer before incorporating in the works and starting the carpenter's work.

b) Plywood

Plywood shall be of commercial quality or with decorative surface veneer. Unless specifically permitted otherwise, the adhesive used in plywood shall be phenol formaldehyde synthetic resin of BWP grade conforming to IS: 848.

c) Decorative Laminated Plastic Sheets

The colour, pattern, finish and texture shall be approved by the Engineer. The bulk supply shall be procured in full sheet sizes which will ensure the least number of joints in one surface.

d) Flush Doors

Flush doors shall be solid core doors with commercial or decorative faces and hardwood edges conforming to IS: 2202 (Part-1). The core for solid core doors shall be of block board or wood particle board. Manufacturer's literature and test certificates shall be submitted for the approval of the Engineer. The Contractor shall give a guarantee that the adhesive used is BWP grade phenol formaldehyde synthetic resin conforming to IS: 848. The thickness shall be as specified.

e) Panel Doors



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 81 of 361

Panel door shall be of teakwood shutter frame, unless otherwise noted and panels with teakwood/commercial ply/teakwood particle board. Other considerations shall be as mentioned in item (d) above.

f) Windows, Ventilators

Windows and ventilators shall be made of teakwood shutter frame, unless specified otherwise and glazing of specified thickness shall be fixed with wooden beadings.

g) Fixtures

Fixtures for doors, windows, furniture etc. shall be as shown on drawing or specified.

2.02.00 Workmanship

2.02.01 General

The work shall be done by skilled carpenters as per details shown on drawing or instructed by the Engineer.

Framing timber and other work shall be close - fitting with proper wood joinery, accurately set to required lines or levels and rigidly secured in place. The surface of frames etc., which will come in contact with masonry after fixing, shall be given two coats of approved paint before fixing. Mastic caulking shall be done after fixing external door and window frames. Special care shall be taken to match the grain of timber or plywood, which will be subsequently polished. Screwing or nailing will not be permitted to the edge of plywood and particle board. The edge of all plywood, blackboard and particle board shall be finished with teakwood lipping unless otherwise shown on drawings.

Fixing to frames and partitions shall generally be with 40 mm x 6 mm x 300 mm long M S holdfasts bifurcated at end and grouted with 1:2:4 cement concrete. The gap between masonry and external door and window frame shall be caulked with polysulphide mastic. M.S. grills or guard bars shall be provided to windows where called for in the drawings.

2.02.02 Finish

All carpentry work after finishing shall be sand papered smooth. A prime coat paint shall be given after inspection of the Engineer to all surfaces other than those, which shall be subsequently polished or covered with laminated plastic sheet.

2.02.03 Surface Treatment



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 82 of 361`

When shown on drawings or called for, decorative ply or laminated plastic sheets shall be bonded under pressure to the surface to be finished. The adhesive used shall be of brand and brought to site in sealed containers. The rate of application and the length of time for which the pressure is to be applied shall be as per the manufacturer's instructions. The edge of sheets shall be protected by teak lipping or bevelled as shown on drawings.

3.00.00 ACCEPTANCE CRITERIA

3.00.01 Door and Window Frames

All frames shall be square and flat at the time of delivery and shall be checked for dimensions and corner angles. After fixing they shall be on a fine vertical plane. All external door and window frames shall be caulked with mastic.

3.02.00 Door and Window Shutters

All doors and window shutters shall be of proper size, shape, and design and free of warp. When fixed to frames, these shall operate smoothly without jamming and all latching or locking devices shall engage properly without undue pressure.

3.03.00 Partitions, Paneling, Pelmet, Furniture, etc.

3.03.01 General

These shall conform to drawings in all details. No unsightly nail marks etc. shall be permitted. Plywood grains shall be matched to give a uniform and pleasing appearance.

3.03.02 Partition

Shall be checked for rigidity of fixing, plumb and horizontal as well as vertical alignment.

3.03.03 Pelmet

Shall be checked for rigidity of fixing and adequate clearance of fixture.

3.03.04 Cupboard Shutters

Shall operate smoothly without jamming and locks, bolts and double ball catches shall engage securely. Single ball catches shall not be used.

3.03.05 Drawers



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 83 of 361

Shall operate smoothly and have backstops to prevent them from being pushed too far. Locks shall engage securely.

3.03.06 Loose Furniture

When placed on a level surface, tables tops etc. shall be horizontal and the pieces stand stably on legs or supports.

4.00.00 IS CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 848 - Synthetic resin adhesives for plywood (Phenolic and Aminoplastic)

IS: 1003 - Timber panelled and glazed shutters.

IS: 2191 - Wooden flush door shutter (Cellular and hollow core type).

IS: 2202 - Wooden flush door shutters (solid core type).

IS: 4021 - Timber door, window, and ventilator frames.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall include of all activities mentioned in “Schedule of Item” for completion of the work. No separate payment shall be made for fixing, caulking, application of primer coat, polishing, providing of butt hinges, holdfasts, sliding/tower bolts, door stoppers, door closers and other fittings and fixtures.

5.02.00 Measurement

Measurement shall be done in Sqm for doors, windows, ventilators, shutters, partitions etc.

Measurement for wooden frame shall be in CuM.

Pelmets shall be measured in RM.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 84 of 361`



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 85 of 361`

SECTION – D

SUB-SECTION – D4

**ROOF AND UNDERGROUND STRUCTURES WATER PROOFING, INSULATION
AND ALLIED WORKS**



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 86 of 361`

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA AND GUARANTEE
4.00.00	I.S. CODES AND STANDARDS
5.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 87 of 361

**ROOF AND UNDERGROUND WATER PROOFING,
INSULATION AND ALLIED WORKS**

1.00.00 SCOPE

This section covers furnishing, installation, repairing, finishing, curing, testing, protection, maintenance till handing over of roof and underground water-proofing, insulation and allied works for buildings and at locations covered under the scope of this package.

2.00.00 INSTALLATION

2.01.00 Grading Underbed

The surface to receive the underbed shall be roughened and thoroughly cleaned with wire brush and water. Oil patches if any shall be removed with detergent. The surface shall be soaked with water and all excess water removed just before laying of the underbed.

The underbed shall not be laid under direct hot sun and shall be kept in shade immediately after laying so as to avoid quick loss of water from the mix and separation from the roof surface. The underbed shall be cured under water for at least 7 days.

The underbed shall be laid to provide an ultimate run off gradient not less than 1 in 120 and as directed by the Engineer. Upto an average thickness of 25mm the underbed shall usually be composed of cement and sand plaster. For higher thickness the underbed shall be made with cement concrete. The underbed shall be finished to receive the waterproofing treatment direct or insulation as the case may be.

2.01.01 Plaster

The grading plaster shall be average 25 mm thick maximum. It shall consist of cement and coarse sand in the ratio 1:4 nominal by volume. The sand and cement shall be thoroughly mixed dry and then water added. Each batch of mix shall be consumed before the initial set starts.

The plaster shall be fully compacted to the desired grade in continuous operation. The surface shall be even and reasonably smooth.

2.01.02 Concrete

The concrete shall be used where the subgrade is more than average 25 mm thick. It shall consist of cement concrete 1:2:4 nominal mix by volume with 12 mm down stone chips and coarse sand. The aggregate shall be mixed dry and minimum quantity of water shall be added to make the mix workable.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 88 of 361

The mix shall be laid to proper grade, fully consolidated and surface shall be smooth and even.

2.02.00 Insulation

The Tendered shall along with the tender send specifications of insulating materials he proposes to use and the proposed method of laying. Before bulk supply, the contractor shall send samples of insulating material to the Engineer, and after approval of the samples, the Contractor shall procure and transport the bulk material to the site. Whenever asked by the Engineer, the Contractor shall furnish test certificates from testing laboratory on the insulating and other properties of the materials.

After laying the insulation the surface shall be made ready as required to receive the waterproofing treatment. If any plastering is used it shall be not leaner than 1:4 cement sand by volume and not thinner than 12 mm and it shall be cured for seven days.

2.02.01 Foam Concrete

This shall be of lightweight foam concrete of average 50 mm thickness or as specified or as shown on drawings. This may be laid in situ in suitable panels or precast blocks. The insulating properties shall be such that the thermal conductivity shall not exceed 0.125 Kcl/sq.m. h degree C. Before starting the laying of foam concrete samples shall be prepared at site and got tested for approval of the Engineer.

The foam concrete laid shall be sufficiently strong to make the usual workload and standard loads expected on the roof. Any damaged portion shall be removed and replaced forthwith. Approval of the Engineer shall be taken before laying the waterproofing over the insulation.

While laying the foam concrete, samples from each batch of the mix shall be kept for test if so desired by the Engineer.

2.02.02 Expanded Polystyrene Blocks

The expanded polystyrene block Insulation shall be fire retardant quality and shall have a maximum thermal conductivity of 0.026 Kcl m/sq.m h °C. It must be strong enough to withstand without any deformation under the workload and standard loads expected on the roof.

The Contractor shall lay the expanded polystyrene block as per manufacturer's approved specification. Only specifically experienced workers shall be used for this work. If the Engineer is not satisfied about the efficiency of the workers the Contractor shall secure manufacturers supervision at no extra cost to the Owner.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 89 of 361

2.03.00

Fillets

Fillets at Junction of roofs and vertical walls shall be provided with the same insulating material as provided for the main roof insulation. The fillets shall be 150 mm x 150 mm in size unless otherwise shown on drawings or instructed by the Engineer.

Where there is no insulation over roof slab, fillets shall be cast-in-situ cement concrete (1:2:4) nominal mix volume.

2.04.00

Waterproofing

Waterproofing treatment shall be laid by a specialist firm with long experience in the particular trade.

2.04.01

Water proofing with bitumen felt

The waterproofing treatment for roofs with bitumen felts shall be done following relevant IS: 1346. Bitumen felt shall conform to IS: 1322 and Bitumen primer to IS: 3384.

The bonding materials shall consist of blown type conforming to IS: 702 or residual bitumen to IS: 73 or a mixture of the two to withstand local conditions of prevailing temperature or gradient of roof surface. The Contractor shall convince the Engineer that the bonding material proposed to be used is suitable for the particular job.

The Contractor shall state the source from where he proposed to procure the materials. Samples of the self-finished felt shall be submitted in advance to the Engineer along with test certificates for his review. Test certificates for the bonding materials shall also be submitted and samples, if desired by the Engineer, shall be provided for confirmatory tests. Samples shall be submitted if instructed by the Engineer.

Minimum overlaps of 100 and 75 mm shall be given at the end and sides of strips of felt and properly bonded with bitumen. Joints in successive layers of felt shall be staggered.

Normal treatment with one layer of felt, heavy treatment with two layers of felt or Extra Heavy treatment with three layers of felt shall be indicated. Brief details of the various treatments shall be as follows:

a) Normal Treatment - Five courses

1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.

2) Hot applied bitumen at the rate of 1.2 kg/sq.m. (min.)



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 90 of 361

- 3) Hessian base self finished felt, type 3, grade 1.
- 4) Hot applied bitumen at the rate of 1.2 kg/sq.m. (min.)
- 5) 20 mm thick pressed precast concrete tiles with 15 mm, thick 1:4 cement-sand mortar underbed.

b) Heavy Treatment - Seven Courses

With Hessian base felt

- 1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.
- 2) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)
- 3) Hessian base self-finished felt, type 3, grade 1.
- 4) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)
- 5) Hessian base self-finished felt, type 3, grade I.
- 6) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)
- 7) 20 mm thick pressed precast concrete tiles with 15 mm thick 1:4 cement: sand mortar underbed.

or

With fiber base felt

- 1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.
- 2) Not applied bitumen at the rate of 1.2 kg/sq.m (Min.)
- 3) Fiber base self-finished felt, type 2, grade 2.
- 4) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)
- 5) Fiber base self-finished felt, type 2, grade 2.
- 6) Hot applied bitumen at the rate of 1.2 kg/sq.m (Min.)
- 7) 20 mm thick pressed precast concrete tiles with 15 mm thick 1:4 cement: sand mortar underbed.

c) Extra Heavy Treatment – Nine courses

With fiber based felt



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 91 of 361

- 1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.
- 2) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)
- 3) Fiber-base self-finished felt type 2, grade 1.
- 4) Hot applied bitumen at the rate of 1.2 kg/sq.m (min.)
- 5) Fibre base self-finished felt type 2, grade 1.
- 6) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)
- 7) Fibre base self-finished felt type 2, grade 1.
- 8) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)
- 9) 20 mm thick pressed precast concrete tiles with 15 mm thick 1:4 cement: sand mortar underbed.

or

With Hessian base felt

- 1) Primer coat conforming to IS:3384 applied at the rate 0.27lits/sqm min.
- 2) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)
- 3) Hessian base self-finished felt, type 3, grade 1.
- 4) Hot applied bitumen at the rate of 1.2 kg/sqm. (min.)
- 5) Hessian base self-finished felt, type 3, grade 1.
- 6) Hot applied bitumen at the rate of 1.2 kg/sqm. min.
- 7) Hessian base self-finished felt, type 3, grade 1.
- 8) Hot applied bitumen at the rate of 1.2 kg/sqm. min.
- 9) 20 mm thick pressed precast concrete tiles with 15 thick 1:4 cement: sand mortar underbed.

However, in special cases, more courses, or a combination of fibre base and hessian base felts may be asked for.

The surface to receive the waterproofing treatment must be cleaned and dried



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 92 of 361

satisfactorily and the Engineer's approval taken before starting the work. If any existing waterproofing treatment is being augmented the existing top course shall be completely removed and all damaged felts or other defects repaired.

The Engineer may instruct the Contractor to lay part of the stipulated courses at the first instant to be followed later on with the balance courses. This interim finish shall be done with a course of hot applied bitumen. While doing the balance again hot bitumen shall be applied to start with after repair of all damages to the already laid course.

After completion the surface shall be cleaned taking care that felt cuttings etc. do not find their way into rainwater down comers.

2.05.02

Elastomeric Membrane

a) Material

The material shall consist of high solid content Polyurethane based cold liquid applied coatings as per ASTM C836 & C898 comprising of urethane pre-polymers extended with flexible material, which cure by reaction with atmospheric moisture to give a continuous film which is rubbery and elastic or any other equivalent material permitted as per ASTM and approved by the Engineer. The material shall consist of high solid coating designed to give a high-build film. The material shall not be diluted. The coating shall have physical feature like high viscosity, 90% solids, high resistance to impact, abrasion and cracking, superior tensile strength, application limit of 70°C minimum, 300% elongation and forming a perfectly smooth permanently flexible seamless membrane which should have good adhesion to roof substrates (RCC, tiles, brick, and metals), having a minimum life of 10 years. It should also be resistant to acid (mild concentrated), alkalies and have a very low water absorption rate (0.5%) max. at ambient temp. after 7 days.

The pack shall not be older than 9 months after the date of manufacture and packing.

b) Primer coat

It shall consists of polyurethane (P.U.) or any other equivalent material. Primer coat shall be a special blend of moisture curing urethane pre-polymers in solvent. A single coat of this primer shall be applied by brush over the prepared bed as an adhesion coat of an application rate of minimum 6 sq.m per litre.

The primer shall be allowed to dry for minimum of 2hrs. time before the successive finishing coats of P.U. liquid membrane are applied.

c) Finishing coats :



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 93 of 361

The finishing coats shall consist of two successive liquid coatings of high solids content urethane pre-polymers or equivalent material to form an elastomeric membrane. The overall dry film thickness shall be 1.5mm subject to minimum 500 gm per sq.m per coat application rate.

Each coat shall be allowed to dry for minimum 12 hours before applying the next coat. The surface should be dry and smooth before application.

The coating shall be continued up the parapets/walls for a minimum of 150mm over the finished roof surface. It shall be continued into rain water pipes by atleast 100mm.

The final coat of P.U. liquid when tacky shall be sprinkled with the sand.

For edges, expansion joints and any vulnerable points a layer of polyscrim cloth /fabric to be embedded between 2 finishing coats.

d) Surface Finish :

Areas of roof treatment which are vulnerable to accidental damage shall be provided with wearing course consist of minimum 20 mm thick PCC of Grade M15 (using 12.5mm size aggregate) cast in panel of maximum size of 1.20m x 1.20m and reinforced with 0.56mm diameter galvanised chicken wire mesh and sealing of joints using sealant or elastomeric compound.

When the roof surface is subjected to foot traffic or used as a working area, a cement mortar (1:4) shall be applied over the top most layer of roofing treatment. Over this, a layer of chequered cement concrete flooring tiles conforming to IS:13801 and shall be provided in place of stone grit and cement painted. The tiles shall be laid as per IS:1443.

2.04.03 Waterproofing By Epoxy Resin Based Application

Exposed surfaces of cement concrete, lime concrete or brickwork to be treated for waterproofing by the resin-based application shall be thoroughly cleaned and the epoxy resin based material to be applied as directed by the manufacturer. The material shall not have any adverse effect on the surface on which it is applied and must stick to it uniformly to make a strong durable bond. It shall not be affected by short duration fire, sun exposure, and light duty traffic. The application shall be resistant to growth of fungus and proof against saltpetre action. If desired by the Engineer, a sample shall be prepared in advance and tested for waterproofness for 48 hours under 300 mm depth of standing water. The Contractor shall arrange the demonstration by providing free the materials and labour for the application as free of cost to Owner. This item shall carry a guarantee as specified.

2.04.04 Flashing



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 94 of 361

Unless otherwise stated flashing shall be done in the same way as the waterproofing except that the last layer shall be finished with two coats of bituminous primer. The flashing shall be extended up the vertical surfaces as shown on drawing. The flashing shall end in grooves in vertical walls. The grooves shall be at least 65 mm deep and caulked with waterproof mastic cement. The minimum overlap with horizontal roofing felt shall be 100 mm.

Where specified or directed by the Engineer, metal flashing shall be provided. The materials shall be 18 Gage or 22 G G.I. sheets, as specified or as directed by the Engineer.

2.05.00

WATER-PROOFING OF UNDERGROUND STRUCTURES

Basements, ducts, pits, tunnels etc below the ground water table and in contact with soil are covered under this. Bonding material shall be blown bitumen of 65/25 grade conforming to IS: 702.

Waterproofing shall be provided on the outside of walls and top of floors and shall be carried 150mm above ground level. The number of layers of bitumen felt to be used for walls and floor unless otherwise shown in the drawing shall be:

- a) For depths up to 5m below ground level 2 layers
- b) For depths beyond 5m below ground level 3 layers

2.05.01

Method of laying the bitumen felts and workmanship shall be as per IS: 1609 and IS: 3067. Water proofing work shall be taken in hand only when the sub-soil water level is at its lowest; the site shall be kept dry by adequate arrangements for pumping out water till the work has been completed.

For this purpose drains shall be formed along the edges of the excavation but beyond the building line, with suitable collecting sumps.

In case of large excavation areas where it is necessary to dewater under the floor, additional land drains shall be formed across the excavation, to adequately drain the area.

Adequate arrangement shall be made to protect the sides of excavation from slipping while the work is in progress.

The base concrete or mud-mat shall be rendered smooth by a 20mm thick sand-cement plaster (6:1). Any sharp edges/corners, over which the waterproofing course is to be laid, shall be eased out by means of cement.

The surface must be dry before the next operation is carried out.

Water proofing/damp proofing treatment:



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 95 of 361

A) Heavy Treatment (Two layers of felt)

- i) Primer (For vertical faces only), as per I.S. 3384.
- ii) Hot applied blown bitumen at the rate of 1.2 Kg/m²
- iii) Hessian base, bitumen felt type 3 grades 2
- iv) Hot applied blown bitumen @ 1.2 Kg/m²
- v) Hessian base, bitumen felt type 3 grade 2
- vi) Hot applied blown bitumen @ 1.2 Kg/m²

B) Extra Heavy treatment (Three layers of felt)

- i) Primer (for vertical faces only) as per I.S. 3384
- ii) Hot applied bitumen at the rate of 1.2 Kg/m²
- iii) Hessian base bitumen felt type 3 grades 2
- iv) Hot applied bitumen at the rate 1.2 Kg/m²
- v) Hessian base bitumen felt type 3 grades 2
- vi) Hot applied bitumen at the rate of 1.2 Kg/m²
- vii) Hessian base bitumen felt type 3 grades 2
- viii) Hot applied bitumen at the rate of 1.2 Kg/m²

The surface must be dry before the next operation is carried out at each stage said above.

The laying of felt over the bitumen so applied, shall always commence on the floor, and shall be carried over to the walls only after treatment of the floor is complete. The minimum over lapping at sides and ends of strips shall be 10cm. Point for subsequent layers completely sealed by blow lamp.

A protective flooring of either brick flat in cement mortar (1:3) or 6cm thick cement concrete (M 15) or a coat of cement plaster (1:3) 4 cm thick shall be constructed over the bitumen layers to prevent damage to the latter during subsequent construction of the structural floor.

The walls shall be treated in a similar way; the bitumen felts joining at the base with the projecting felt laid over the mud-mat. The wall surface shall be made smooth where necessary with a coat of cement plaster (1:3), the felts laid



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 96 of 361`

as for the floor, ensuring that the surface to be treated is dry and then a protective brick wall, 12.5 cm nominal thickness shall be built in cement mortar (1:3) over the projecting mud-mat, the space between the wall and felt being grouted with cement.

3.00.00 ACCEPTANCE CRITERIA AND GUARANTEE

The surface level shall be such as to allow quick draining of rains without leaving any pool anywhere. The finishing course shall be fully secured and shall have an even density. There shall not be any bubble formation or crushed or squeezed insulation or underbed.

The contractor shall give a guarantee in writing for all works executed under this specification supplemented by a separate and unilateral guarantee from the specified agency for the roof waterproofing treatment work. The guarantee shall be for materials and workmanship for 5 years in case of normal treatment, 10 years for heavy treatment and 20 years for extra heavy treatment. The mode of execution of the guarantee shall be acceptable to the Owner.

4.00.00 I.S. CODES AND STANDARDS

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

- a) IS: 73 - Paving Bitumen
- b) IS: 702 - Industrial Bitumen
- c) IS: 1203 - Methods of testing tar and bitumen
- d) IS: 1322 - Bitumen felts for waterproofing and damp proofing.
- e) IS: 1346 - Code of practice for waterproofing of roofs with bitumen felts.
- f) IS: 3384 - Bitumen primer for use in waterproofing and damp proofing.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall be for complete work, including the cost of all materials and labour, as detailed in the specification unless any portion is specifically excluded in the "Schedule of Items".



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 97 of 361`

No extra shall be paid for finishing around opening, sleeves, pipes, ducts, inserts, etc.

No separate payments shall be made for cleaning of surface, treating of cracks and surface preparation.

5.02.00

Measurement

The finished work shall be measured in Sqm of actual surface area for the purpose of payment.

No deduction shall be made and no extra shall be paid for openings upto 0.4 sqm.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 98 of 361`

SECTION - D

SUB-SECTION – D5

**METAL DOORS, WINDOWS, VENTILATORS,
LOUVERS ETC.**

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 99 of 361`

4.00.00 INFORMATION TO BE SUBMITTED

5.00.00 I.S. CODES

6.00.00 RATES AND MEASUREMENTS

ATTACHMENT

ANNEXURE – A SCHEDULE OF FIXTURES



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 100 of 361

METAL DOORS, WINDOWS, VENTILATORS, LOUVERS ETC.

1.00.00 SCOPE

This section covers supplying and/or erecting and installing of all metal doors, windows, ventilators, louvers, glazed partitions, etc. The scope of work shall also include the assembly and erection of all doors, windows, louvers, glazed partitions, etc. Supplying and/or fixing of all door and window accessories and hardware are also included in the scope.

2.00.00 INSTALLATION

2.01.00 Materials

Steel sections used for fabrication of doors, windows etc. shall be standard rolled steel sections specified in IS: 1038 and IS: 1361 or as specified.

Steel sheets for frames, shutters, louver blades etc. shall be of gauge mentioned in drawings and schedules.

Aluminium sections for fabricating doors, windows, partitions etc. shall be extruded sections conforming to IS:733 or IS:1285 or as manufactured by Indian Aluminium Company Limited or approved equivalent. Aluminium door, windows and ventilator shall be fabricated as per IS:1948 and IS:1949. The alloy used shall conform to IS Designation HE 9-WP of IS: 733.

Hardware and fixtures shall be as specified and the best quality from approved manufacturers shall only be used. The tenderer shall specifically state the particular manufacturer's materials he proposes to use. Improper alignment or faulty operation due to inadequate strength of hardware or fixture shall entirely be the Contractor's responsibility.

All hardware and fixtures shall be able to withstand repeated use. Door closures shall conform to IS: 3564 and shall be suitable for doors weighing 61-80 Kg. unless otherwise stated. Each closer shall be guaranteed against manufacturing defect for one year and any defect found within this period shall be rectified or shall be replaced free of charge. Concealed door closers shall be either floor mounted or transom mounted, suitable for installation with metal doors. It shall conform to the performance Requirements and endurance test stated in IS: 3564 - Appendix-A. The Contractor shall submit samples of each type of hardware to the Engineer. The approved samples shall be retained by the Engineer for comparison of bulk supply. The samples shall be returned to the Contractor towards end for incorporation in the job. The mastic for caulking shall be of best quality from a manufacturer approved by, the Engineer. In general, mastic for fixing of metals frames shall be as per IS: 1081 or as approved by the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 101 of 361

2.02.00 Fabrication

2.02.01 Steel Doors, Windows, Ventilators, louvers etc.

a) Door Frames

Frames shall be fabricated from 16 gage(G) sheets. They shall, be mortised, reinforced, drilled, and tapped for hinge lock and bolt strikes. Where necessary, frames shall be reinforced for door closers. Welded construction with mitered Corners shall be used. Rubber door silencers shall be furnished for the striking jamb. Loose "T" masonry anchors shall be provided. Frames shall finish flush with floor and adjustable floor anchors shall be installed. Frames shall be brought to site with floor ties/weather bars installed in, place.

b) Double Plate Flush Door Shutters

Door shutters shall be 45 mm thick, completely flush design and shall comprise of the outer sheets or 18 G steel sheets, rigidly connected and reinforced inside with continuous vertical 20 G stiffeners, spot welded in position at not more than 150 mm on centres.

Both edges of doors shall be joined and reinforced full height by steel channels placed immediately inside and welded to the door faces. Top and bottom of doors shall be reinforced horizontally as shown on drawing by steel channels running full width of door. Doors shall not have more than 2.5 mm clearance at jambs and heads, shall have proper level on lock stiles and rails to operate without binding, and shall be reinforced at corners to prevent sagging or twisting. Pairs or double doors shall have meeting-stile edges bevelled or rebated. Where shown on drawing, or called for in the schedule of items, the doors shall be sound deadened by filling the inside voids with mineral wool or other suitable approved materials.

Doors shall be mortised, reinforced, drilled, and tapped in shop for hinges, locks, and bolts. They shall also be reinforced for closers, push-plates, and other surface hardware where necessary. Any drilling and tapping required for surface hardware shall be done at site. Where shown drawing, provision shall be made for fixing glazing, vision panels, louvers etc. glazing mouldings shall be of 18 G steel or extruded aluminium sections and suitable for fixing 6 mm. glass. Louvers blades shall be V or Z shaped and made out of 16 G sheets.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 102 of 361

c) Single Sheet Door Shutters

Single sheet doors shall be made from best quality 18 G mild steel sheets, and shall present a flush surface on the outside. The inside shall be stiffened with semi tubular edge and central stiffening rail, which shall convey the lock and other fixture. The frames shall be made from best quality, 16 G mild steel sheets.

Wherever required, provisions for fixing glass panes, louvers etc. shall be made.

The manufacturing shall be done as specified in 2.02.01 (b) "Double Plate Flush Door Shutters."

d) Sliding Door

Sliding doors shall be either double plate or single plate Construction made out of 18 gauge steel sheets with adequate stiffeners. The contractor shall specify the weight of the door in his shop and submit the manufacturer's catalogue of the sliding gear he proposes to use. Where called for the Contractor shall make provision for openings to the door for monorail beams. Doors shall close positively to exclude rainwater from seeping in. When called for, sliding doors shall withstand specified wind loads without buckling or jamming. The door shall slide freely under all ambient conditions.

e) Door Threshold

Door threshold shall be provided. Doors without threshold shall have bottom tie of approved type.

f) Steel Windows, Sashes, and Ventilators etc.

These shall conform in all respects to IS: 1038 and IS: 1361 latest editions. The details as called for in the above codes shall be applicable for coupling mullions, transoms, weather bars, and pivot arrangements for ventilators, etc. or as called for. All welds shall be dressed flush on all exposed and contact surfaces. Where composite unit openings are required the individual window units shall be joined together with requisite transoms and mullions. All windows shall be outside glazed, fixed with putty or metal glazing beads as specified. Where aluminium glazing beads are specified, they shall be extruded aluminium channel 9.5 mm x 9.5 mm x 1.6 mm (Indal Section No. 2209) unless otherwise shown on drawings. Aluminium beads shall be given one coat of zinc chromate primer before fixing to windows.

2.02.02

Aluminium Door, Windows, and Frames



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 103 of 361

Extruded sections shall have a minimum 3 mm wall thickness. All sections shall be approved by the Engineer before fabrication is taken up. Doors frames, mullions, transom etc. shall be anodized in a bath of sulphuric acid to provide a clear coating of minimum 15 micron thickness. The anodized materials shall then be sealed by immersing in boiling water for 15 minutes. A protective transparent Coating shall be applied to the sections before shipment from the factory.

All work shall be fitted and shop assembled to a first class job, and ready for erection. Shop joints shall be made to hair lines and then welded or braced by such method as will produce an uniform colour throughout the work. Work on the above, other than described, shall be carefully fitted and assembled with neat joints with concealed fasteners. Wherever possible, joints shall be made in concealed locations and on edges of doors. Field connections of all work may be made with concealed screws or other approved type of fasteners. Glazing beads shall be snap fit type without visible screws and shall be of sizes to accommodate 6 mm thick glazing. All work shall be adequately braced and reinforced as necessary for strength and rigidity.

2.03.00 Shop Coat or Paint

The shop Paint for steel doors, windows etc. shall be best lead or zinc chromate primer paint from, approved manufacturer. All surfaces shall be thoroughly cleaned of rust, grease, loose mill scales etc. and given one coat of shop paint. Portions like mullions, transoms etc. that will be inaccessible after assembly of units shall be given an extra coat of paint before assembly.

Where called for, all steel doors, windows, etc. shall be hot dip galvanized to give a coating weight of 1½ - 2 oz. per sqft. One coat zinc chromate primer coat shall then be applied as shop paint.

Portions of aluminium frame, which come in contact with masonry construction shall be (before shipment from workshop) protected with a heavy coat of alkali resistant paint. Aluminium coming in contact with other incompatible metals shall be coated with zinc chromate primer.

2.04.00 Handling & Storage of Fabricated Material

All metal doors, windows, etc. shall be packed and crated properly before dispatch, to ensure that there will be no damage to the fabricated materials. Loading into wagons and trucks shall be done with all care to ensure safe arrival of materials at site in undamaged condition.

When taking delivery of items supplied by Owner, the Contractor shall satisfy himself that the items supplied are up to the specified standard. Any defect detected shall promptly be brought to the notice of the Engineer.

All metal doors, windows etc. shall be stored under cover in a way to prevent



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 104 of 361

damage or distortion. Special care shall be taken to prevent staining of aluminium products by rust, mortar etc.

2.05.00 Assembly & Erection at Site

In general, the fixing of steel doors, windows, ventilators, louvers, etc. shall conform to IS: 1081. The Contractor shall assemble and install all steel doors, windows, sashes, fixed metal louvers, etc. including transoms and mullions for composite units in respective places, keening proper "Lines and levels", and in approved workmanlike manner, to give trouble free and leak-proof installations. Installation shall be done according to instructions of the manufacturer, and/or as approved by the Engineer. If required by the Engineer, the installation shall have to be carried out under the supervision of the manufacturer's staff. The Contractor shall take all precaution against damage of the components during installation. Necessary holes, chases, etc. required for fixing shall be made by the Contractor and made good again as per original, after installation, without any extra charge.

After installation of steel doors, windows, etc. all abrasions to shop-coat of paint shall be retouched and made good the same quality of paint used in shop coat.

All coupling mullions, transoms, frames, etc. in contact with adjacent steel and other members, shall be well bedded in mastic. The Contractor shall bring to the site the cement in original sealed containers of manufacturer and shall apply it as per the instruction. For all frames supplied by either the owner or the Contractor, mastic shall be supplied by the Contractor and caulking done properly as per drawings, specifications and as per instructions of the Engineer.

Door shutters, partitions hardware fixtures etc. shall be fixed only after major equipments have been installed in rooms.

Wherever required, nylon cords of approved quality shall be supplied along with pivoted sashes and shall be of adequate length to terminate one metres from the floor. Loose ends of cords shall end in metal or plastic pull as approved by the Engineer.

2.06.0 Fire proof Door

Fire proof doors shall be provided at all fire exit points as specified and also to restrict the spread of fire within buildings whether from internal fire or from external fire. The construction details of door shall conform to the requirements stipulated in IS:3614(Part-1). Doors shall comply with the testing requirement mentioned in IS:3614 (Part-2). The doors shall be approved by Tariff Advisory Committee and shall have minimum 2 hrs. fire rating.

Metal covered (on both sides) Doors having insulating core filled up with



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 105 of 361

mineral wool shall be used at all fire exit points and shall open out side.

All necessary accessories and hardware shall also be supplied along with doors. Fire proof door shall be provided with zinc silicate primer (minimum DFT 75 micron) after blast cleaning the surface to near white metal surface and shall be finished painted with epoxy based painting.

3.00.00 ACCEPTANCE CRITERIA

3.01.00 For fabricated Items

- a) Overall dimensions shall be within ± 1.5 mm of the size shown on drawings.
- b) Mullions, transoms etc. shall be in one length and permissible deviations from straightness shall be limited to ± 1.5 mm from the axis of the member.
- c) Door and window shutters shall operate without jamming. The clearance at head and jamb for door shutters shall not exceed 1.5 mm for double leaf doors; the gap at the meeting stiles shall not be more than 1.5 mm.
- d) Door leaves shall be undercut where shown on drawings.
- e) Doors, windows, frames, etc. shall be on a true planes, free from warp or buckle.
- f) All welds shall be dressed flush on exposed and contact surfaces.
- g) Correctness of location and smoothness of operations of all shop installed hardware and fixtures
- h) Provision for hardware and fixtures to be installed at site.
- i) Glazing beads shall be cut with mitered corners.
- j) Glazing clips, fixing devices etc. shall be supplied in adequate numbers.
- k) Shop coats shall be properly applied.
- l) Exposed aluminum surfaces shall be free from scratches, stains, and discoloration. Anodized surfaces shall present a uniform and pleasing look.

3.02.00 For installed Items

- a) Installations shall be at correct location, elevation and in general, on a true vertical plane.
- b) Fixing details shall be strictly as shown on drawings.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 106 of 361

- c) Assembly of composite units shall be strictly, as per drawings with mastic caulking of transoms and mullions, gaskets, weather strips etc. complete.
- d) All frames on external walls shall be mastic caulked to prevent leakage through joint between frames and masonry.
- e) All openable section shall operate smoothly without jamming.
- f) Locks, fasteners etc. shall be engage positively. Key shall, be non-interchangeable.
- g) Cutting to concrete or masonry shall be made good and all abrasions to shop paint shall be touched up with paint of same quality as shop paint.
- h) Aluminium doors, windows, etc. shall be free from scratches stain or discoloration.

4.00.00 INFORMATION TO BE SUBMITTED

4.01.00 With Tender

- a) Names of manufacturers for Doors, windows etc.
- b) Manufacturer's catalogue for all hardware and fixtures proposed to be used.

4.02.00 After Award

- a) Before starting fabrication of all metal doors, windows, etc. the Contractor shall submit detailed fabrication drawings to the Engineer for approval. The fabrication shall be started only after approval of drawings.
- b) He shall submit a programme of work to be done for the approval of the Engineer.
- c) Before bulk supply, he shall submit for the approval of the Engineer samples of all bought out items and samples of each type of fabricated items. The samples shall be retained by the Engineer for comparison of bulk supply and returned to the Contractor towards the end for final incorporation in the job.

5.00.00 IS CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 107 of 361

standard practice, as may be specified by the Engineer, shall be followed.

Specification for Wrought Aluminium and Aluminium Alloy bars, rods and sections (for general engineering purpose)	-	IS: 733
Specification for Wrought Aluminium and Aluminium Alloy, extruded round tube, hollow section (for general engineering purpose)	-	IS: 1285
Steel doors, windows, and ventilators	-	IS: 1038
Steel windows for industrial, building	-	IS: 1361
Aluminium doors windows, and ventilators	-	IS: 1948
Aluminium windows for industrial buildings	-	IS: 1949
Steel doorframes	-	IS: 4351
Code of practice for fixing and glazing of Metal (steel and aluminium) doors, windows and Ventilators.	-	IS: 1081
Specification for Fire-check Doors – Part 1: Plate, Metal covered and Rolling type	-	IS: 3614
Hot Rolled Steel Sections for Doors, Windows and Ventilators – Specification	-	IS: 7452

6.00.00 RATES AND MEASUREMENT

6.01.00 Rates

Rates shall be applicable of all elevation. Rates shall include preparation of working drawings (if required), supply of material, fixtures, gaskets, erection of unit, caulking and jamming of frames, including cutting/drilling/welding, grouting, grinding, making good of the structure for installing the unit etc. complete as per “Schedule of Items”.

Rates shall also include cost of surface preparation, application of primer, enamel painting or anodizing as applicable.

Rate for fire proof door is inclusive of providing insulation core, primer, shop painting (epoxy based), all hardware as specified in Schedule of items.

6.02.00 Measurement



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 108 of 361

Supply and installation of doors, windows, and ventilators shall be measured in Sqm in net outer to outer (excluding frame) area of doors, windows, and ventilators of each type used as described in "Schedule of Items". Frame for steel or aluminium shall be measured in Kgs. Wooden frames shall be measured in Cum. Measurement for aluminium partition shall be from net outer to outer area of frames i.e., frames are part of partition.

Measurement for fire proof door shall be in SqM in net area outer to outer of the door.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 109 of 361

ANNEXURE-A

SCHEDULE OF FIXTURES

A. TIMBER DOORS

1. For single leaf panel/flush doors
 - i) 100 mm brass butt hinges with screws - 3 Nos.
 - ii) 150 mm brass tower bolts with screws - 1 No.
 - iii) 100 mm x 225 mm clear plastic push
Plate with counter sunk brass screws - 1 No.
 - iv) 30 mm brass ring pull handle with
Plates and screws - 1 No.
 - v) 150 mm brass coat hook with screws - 1 No.
 - vi) Heavy duty, cylinder locks on active leaf - for flush door. For door-
closure, see "Door Schedule".

B. ALUMINIUM DOORS

1. For double leaf door
 - i) Concealed hanging arrangement for door leaves.
 - ii) Concealed two points bolt encasing simultaneously at head and threshold
on inactive leaf, operable from inside.
 - iii) Heavy duty, cylinder lock on active leaf.
 - iv) Pull handle of approved design on both leaves.
 - v) Doors stops for both leaves.
 - vi) Overhead door closure for both leaves.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 110 of 361

ANNEXURE-A

C. STEEL DOORS AND WINDOWS

1. Doors

a) Double leaf doors

- i) 100 mm butt hinges - 3 Nos. on each leaf.
- ii) 300 mm aluminum tower bolt - 2 Nos. (top and bottom)
On inside of inactive
Leaf. 1. No. (Top only)
On inside active leaf.
- iii) 200 mm anodized aluminum pull handle - 1 No. of each leaf.
- iv) Door stop of approved design - 1 No. of each leaf.

NOTE: For locks, door closure and threshold, see "Door Schedule".

b) Single leaf doors

- i) 100 mm butt hinges - 3 Nos.
- ii) 300 mm aluminum tower bolt - 2 Nos. top & bottom of Inside
face
- iii) 200mm anodised aluminum Pull handle - 1 No.
- iv) Door stop of approved design - 1 No.

NOTE: For locks, door closures and threshold, see "Door Schedule".

2. Windows, Ventilators, etc.

a) Side Hung Windows

- i) Hinges - As per standard Practice of the
Manufacturer, but minimum two
hinges Per leaf.
- ii) 12" peg stays - 1 No. per leaf

ANNEXURE-A



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 111 of 361

iii) 2 point handles - 1 No. per leaf

b) Top Hung Ventilators (Projecting Out)

i) Hinges - As per standard Practice of the
Manufacturer, but minimum two
hinges Per leaf.

ii) Adjustable sliding fabrication
assemblies - 2 Nos. per leaf.

iii) 2 point handles - 1 No. per leaf.

c) Bottom Hung Ventilators (Projecting in)

i) Hinges - As per standard Practice of the
Manufacturer, but minimum two
hinges Per leaf.

ii) Concealed side arms for
opening adjustment. - 2 Nos. per leaf.

iii) Spring Catch - 1 No. per leaf.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 112 of 361

ANNEXURE-A

D. ALUMINIUM WINDOW, VENTILATORS, ETC.

(As per I.S-1948 latest editions)

a) Side Hung Windows

- | | |
|----------------------|--|
| i) Hinges | - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf. |
| ii) 300 mm peg stays | - 1 No per leaf |
| iii) 2 point handles | - 1 No per leaf |

b) Top Hung Ventilators (Projecting out)

- | | |
|---|--|
| i) Hinges | - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf. |
| ii) Adjustable sliding fabrication assemblies | - 2 Nos. per leaf |
| iii) 2 Point handles | - 1 No. per leaf |

c) Bottom Hung Ventilation&(Projecting In)

- | | |
|--|--|
| i) Hinges | - As per standard Practice of the Manufacturer, but minimum two hinges Per leaf. |
| ii) Concealed side arms for opening adjustment | - 2 Nos. per leaf |
| iii) Spring Catch | - 1 No. per leaf |



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 113 of 361

SECTION - D

SUB-SECTION – D6

GLASS AND GLAZING

C O N T E N T



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 114 of 361

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA
4.00.00	I.S. CODES
5.00.00	RATES



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 115 of 361

GLASS AND GLAZING

1.00.00 SCOPE

This section covers supplying and fixing of all glass and glazing including all clips, putty, mastic cement etc. wherever required as per specifications.

2.00.00 INSTALLATION

2.01.00 General

The Contractor shall supply and install all glass and glazing as required for various doors, windows, sashes, ventilators and fixed louvers, miscellaneous glazing and partitions, from approved manufacturer like Hindustan Pilkinton or equivalent, having uniform refractive index and free from flaws, specks, and bubbles. The glass shall be brought to site in the original packing from the manufacturer and cut to size at site.

Materials

- a) Glare reducing or heat absorbing glass shall be "Calorex" of Hindustan Pilkinton or approved equivalent and special care shall be taken to grind smooth and round off the edges before fixing.
- b) Clear glass shall be flat draw sheet glass and shall be at least 4 mm thick. Sheet glass for doors shall be minimum 5.5 mm thick.
- c) Wired glass shall be thick- rolled glass with centrally embedded 42g wire mesh of Georgian type. This may be of clear or coloured glass, as required.
- d) Obscure glasses shall have a cast surface in one side.
- e) Coloured and figured glass shall be as per approved sample.
- f) In general, the putty shall conform to IS: 400 and be of best quality from approved manufacturer. It shall be brought to site in the manufacturer's original packing.
- g) Neoprene gaskets with snap-fit glazing beads shall be fixed as per manufacturer's instructions and shall sit snugly against glass to give a leak proof installation.

2.03.00 Glazing, Setting, and Finish

All glazing clips, bolts, nuts, putty, mastic cement etc. as required shall be supplied by the Contractor.

All glass shall be thoroughly cleaned before putting in position. Each glass



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 116 of 361

pane shall be held in place by special glazing clips of approved type. As specified in relevant I.S. Codes, four glazing chips shall be provided per glass pane, except for large panes where six or more clips shall be used as per engineer's instructions. All holes that may be necessary for holding the clips glazing heads and all other attachments shall be drilled by, the Contractor.

Glass panes shall be set without springing, and shall be bedded in putty and back puttied, except where mouldings or gasket are specified, putty, mastic cement etc. shall be smoothly finished to the even line and figured glass shall be set with smooth side out.

Where owner will supply glass, the Contractor shall cut it to size and fix them in the same as specified above.

The Contractor shall supply necessary glazing clips, putty, mastic cement etc.

After completion of glazing, the Contractor shall remove all dirt stains, excess putty etc. clean glass panes and leave the work in perfectly acceptable condition. All broken cracked or damaged glass shall be replaced by new ones at the contractor's own cost.

3.00.00

ACCEPTANCE CRITERIA

- a) All installation shall be free from cracked, broken, or damaged glass. Edges of large panes of thicker glass and heat absorbing glass shall be inspected carefully for chipped, cracked, or underground edges.
- b) Glazing shall be carefully done to avoid direct contact with metal frames.
- c) All glass shall be embedded in mastic or fixed by neoprene gaskets to give a leak proof installation.
- d) At completion, the panes shall be free from dirt, stains, excess putty etc. to the complete satisfaction of the Engineer.

4.00.00

I.S. CODES

Following are some of the important I.S.Codes relevant to this Section:

IS: 3548 - Code of practice for glazing in building.

IS: 1081 - Code of practice' for fixing and glazing metal doors, windows ventilators.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 117 of 361

5.00.00

RATES

Rates of glass and glazing are included in respective items for supply and installation of window, ventilator, and partitions. No separate payment shall be made for glazing clips, mastic cement, putty, screws; rails, etc. nor for drilling holes in frames for inserting glazing clips.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 118 of 361

SECTION - D

SUB-SECTION – D7

ROLLING STEEL SHUTTERS AND GRILLS

C O N T E N T



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 119 of 361

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA & GUARANTEE
4.00.00	I.S. CODES
5.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 120 of 361

ROLLING STEEL SHUTTERS AND GRILLS

1.00.00 SCOPE

This Section covers the design and supply of materials, fabrication, delivery and erection of Rolling Shutters/Grills with motor drive and/or manual operation including all accessories as hereinafter specified.

2.00.00 INSTALLATION

2.01.00 Components

- a) Slats for rolling shutters shall be made from tested bright cold rolled, annealed M.S. strips, not less than 0.9 mm thick for shutters upto 4.5 M wide and not less than 1.25 mm thick for shutters having width more than 4.5 M, wide and above, machine rolled at 75 mm rolling centers, interlocking with each other. The profile will be such as to prevent excessive deflection under specified wind load.
- b) Rolling grills shall be constructed out of 6mm rods at 35 mm on centers running horizontally flexible connected with vertical links spaced not more than 200 centers. Alternatively, rolling grills shall be made from perforated slats of approved design reinforced with 6mm dia rods.
- c) End locks shall be heavy type M.C.I./C.I. and shall be provided at each end of alternate slats unless specified otherwise.
- d) Bottom bars shall be finished with two angles not less than 6 mm thick for external shutters. When shown on drawings, a flexible weather strip shall be applied to make tight contact with the floor.
- e) Guides shall be of such depth as to retain the shutter under a wind pressure of 100 Kg/Sq.m.
- f) Shafts shall be of steel pipe of sufficient size to carry the tensional load with a maximum deflection of 1/360th of span. Grease packed ball bearings or bushings shall be provided for smooth trouble free operation.
- g) Hoods shall be formed of not less than 20 gauge steel, suitable reinforced to prevent sag.
- h) Locks shall be slide bolt and hasp, or cylinder lock operable from one or both sides. Provision securing hand chain with pad-lock, provision for removable handle for hand cranks etc. shall be made as prescribed by the Engineer.
- i) Power unit shall be suitable for 3 phase, 50 cycles, 400-volt A.C. power supply and be either floor or wall mounted unit. The motor shall be of



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 121 of 361

sufficient capacity, to move the shutter in either direction at a speed of 0.3 metres per second. In addition to the gear motor each standard power unit shall include a magnetic brake, a reversing starter with built-in overload protection, a geared limit switch and one push button station located inside the building unless otherwise stated in drawing.

It is desirable that the bottom bar of motor operated doors shall be provided with a sensitive edge, electrically connected to stop the travel of the door on meeting an obstruction.

- j) Operating chains shall be of tested quality, heavily galvanized and with all ends rounded to assure smooth operation and hand protection.
- k) Reduction gears shall be high strength grey cast iron, machine moulded from machine out patterns.

2.02.00 Manually Operated Shutters/Grills

Manually operated shutters shall be easily operable by one person. The speed of operation shall be about 1.3 metres per second. In general, manually operated shutters shall be push pull type for opening up to 9 Sq. metre in area. Larger shutters shall, be either chain and gear operated or crank and gear operated. The crank handle shall be removable. All shutters shall be lockable from one or both sides as desired by the Engineer.

2.03.00 Power operated Shutters/Grills

These shall be operable from a push button station conveniently located beside the door. One emergency hand chain/crank operation shall also be provided for use in case of failure of the electric system. Where called for, externally mounted shutters shall be operated by control mechanism located inside the building.

2.04.00 Shop Coat

Shutters shall be painted with one coat of red lead or zinc chromate primer. Where specified, doors shall be galvanized and subsequently painted one coat of zinc chromate for adhesion of field coat.

2.05.00 Erection

Door shall be installed by the manufacturer or his authorized representative and all work shall be as per manufacturer's instructions. Any drilling or cutting to concrete, masonry etc. shall be made good after erection of shutters and all abrasion to shop coat shall be touched up. All electrical work shall be in strict accordance with the latest Indian Electricity Rules.

3.00.00 ACCEPTANCE CRITERIA AND GUARANTEE



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 122 of 361

3.01.00 Shop Inspection

After completing the manufacture of the different components of the rolling shutter, an arrangement for shop inspection by the Engineer shall be made to check the conformity with approved shop drawings.

3.02.00 Field Inspection

After installing the shutters, the Contractor shall test the performance of the shutter in the presence of the Engineer. The doors shall be smoothly operable under all ambient conditions. All control and locking devices shall give fault free performance.

3.03.00 Guarantee

The Contractor shall give one year's guarantee for the successful operation of the shutters. This shall be supported by a separate and unilateral guarantee from the manufacturer of the shutters.

4.00.00 I.S. CODE

IS: 6248 - Metal rolling shutters and rolling grills.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates for rolling shutters and grill shall include the cost of the locks, guide channels, cost of drive as specified. In case of electrically operated rolling shutters, the rate shall also include the mounting of controls, wire and wiring from the nearest junction box, conduit and other electrical connections and cost of electric motor.

5.02.00 Measurement

Supply and installation of rolling shutter and grill shall be measured in Sqm in net outer to outer (including frame) area of each type used as described in "Schedule of Items".



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 123 of 361`

SECTION - D

SUB-SECTION – D8

MISCELLANEOUS METAL

C O N T E N T



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 124 of 361

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA
4.00.00	IS CODES
5.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 125 of 361

MISCELLANEOUS METAL

1.00.00 SCOPE

This section covers supply, fabrication and erection of miscellaneous metal items of light nature in gates, balcony and stair hand rails, structural works, ladders, hangers, masonry anchors, anchor bolts, fasteners, chain link fencing, barbed wire fencing etc. as specified or shown on drawing or as instructed by the Engineer. The above items shall be of fabricated or cast of mild steel, aluminium, brass, cast iron, M.S. & galvanized M.S. sheets, aluminium sheets, expanded metal, wire mesh as shown on drawings or specified.

2.00.00 INSTALLATION

2.01.00 Fabrication/casting

2.01.01 General

All work shall be done according to approved shop drawings. All workmanship shall be equal to the best practice in modern structural or foundry shop.

2.01.02 Shop Connections

- a) All shop connections shall be riveted or welded except when noted otherwise on drawings.
- b) Welding of steel shall be done in accordance with IS: 816.
- c) Welding of aluminium shall be done accordance with IS: 2812, "Arc welding of Aluminium and Alloys." Special care shall be taken to grind smooth all welded surface that shall remain exposed to view. Welds shall be electrically continuous if so required by the Engineer.

2.01.03 Shop Coat

Before leaving the shop, all metal work shall be thoroughly cleaned by effective means of all loose mill scale, rust and foreign matter. Except where encased in concrete, all steelwork shall be given one coat of approved metal protective paint, applied by brush thoroughly and evenly, well worked into joints and other open spaces. All paint shall be applied to dry surfaces. When specified steel work shall be galvanised or painted with a coat of zinc chromate primer. Aluminium surfaces, which shall come in contact with masonry, shall be given one coat of bituminous paint.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 126 of 361

2.02.00 Erection

2.02.01 Bracing

The Contractor shall provide all necessary temporary guys and braces to ensure alignment and stability of the members and to take care of all loads to which the structure may be subjected, including erection of equipment and operation of the same.

2.02.02 Temporary Bolting-Up

As erection proceeds the Contractor shall plum up and level all members and shall securely bolt up to take care of all dead load, wind load and erection stresses. Wherever erection equipment or other loads are carried by members during erection, proper provision shall be made to take care of the stresses resulting from the same.

2.02.03 Turned Bolt

For field connections where bolting is specified, holes for the turned bolts may be reamed in the field, if required. All drilling or reaming for turned bolts shall be done after the parts to be connected are assembled.

2.02.04 Welding

Where specified on drawings, welding shall be done in accordance with IS: 816 for steel and IS: 2812 for Aluminium & Alloys.

2.02.05 Cutting and Fitting

No cutting of sections, flanges, webs of angles shall be done without the approval of the Engineer. Where indicated on the drawings holes, cuttings, etc. shall be provided as required for installation, to the work by the other Contractors. No additional holes or cuttings, than those shown on drawings, shall be made without the approval of the Engineer.

2.02.06 Drifting

Correction minor misfits and a reasonable amount of reaming and cutting of excess stock from rivets may be permitted. For this, light drifting may be allowed to draw holes together. Twist drills shall be used to enlarge as necessary to make connections, reaming that weakness the members or make it impossible to fill the holes properly or to adjust accurately after reaming shall not be allowed.

Any error in shop work which prevents the proper assembling and fitting of parts by moderate use of drift pins or a moderate amount of reaming and slight chipping and cutting shall immediately be called to the attention of the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 127 of 361

Engineer-and approval of the method of correction obtained. The use of cutting torches to enlarge or alter rivet holes shall not be permitted.

2.02.07 Spot Painting

All field rivets and bolts and also any serious abrasion to shop paint shall be spot painted with the same materials and used for the shop paint or equivalent.

2.02.08 Good

All cutting to concrete or masonry shall be made good to the satisfaction of the Engineer.

2.02.09 Grouting

All bearing plates, loose, lintels and beams, etc. shall be set to proper grade and level by the Contractor and the Engineer's approval obtained before proceeding with the grouting. Grouting shall be done in 1:1½:3 concrete with 6 mm down stone chips or as specified in schedule of items.

2.02.10 Anchor Fasteners

The anchor fasteners shall be of two type viz. light duty for carrying tensile load upto 0.5MT per fasteners and heavy duty for carrying tensile load of 0.5MT to 5.0MT per fasteners. These anchor fasteners shall be fixed into concrete. The Contractor shall submit the Manufacture's literature showing the average pull out and average shear value for anchor of various sizes. Anchors shall be fixed in position strictly as per the manufacturers instructions and as approved by the Engineer.

Heavy Duty Anchor Fasteners

The safe tensile load carrying capacity of the anchors shall be arrived by providing the minimum factor of capacity of 2.5 for the characteristic load of the anchor. Minimum size of anchor shall be M8 (8mm). All anchors shall be from the approved manufacturers like HILTI or equivalent.

- a) Anchor fasteners shall be supplied and fixed in position by the contractor. Anchor fasteners can be of mechanical bonding or chemical bonding.
- b) Capacity of the anchor shall be established after considering the effect of concrete grade, embedment depth, concrete thickness, anchor spacing and edge distance from the concrete edge.
- c) The selection for the particular type of bonding for the anchors shall be made after considering the concrete grade, available embedment depth, load to be transferred, space available for installing anchors.
- d) The mechanical bonding anchor are torque controlled anchors made from carbon steel of grade 8.8 as per IS:1367 part 3. Anchors in bolt as well as nut version are acceptable. The bolt version anchors consists of bolt washer, sleeves, plastic section, expansion sleeves and a cone. Nuts



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 128 of 361

version anchor consists of nuts, threaded rod, washer, sleeves, plastic section, expansion sleeves and a cone. All steel component of anchor shall be electro galvanised to minimum 5 micron coating thickness. The plastic section shall be of polyacetal Derlin 100 or equivalent.

- e) Chemical bonding anchor shall consist of foil capsule and threaded rod. The foil capsule shall contain the resin and hardener. The threaded rod shall have chiselled tip. The behaviour of anchors under fire shall conform the heating curves as per ISO:834. Anchors of size M8 to M24 shall conform to grade 5.8 and anchors of size M27 to M39 shall conform to grade 8.8 as per IS:1367 part 3. All steel components of the anchors shall be electro-galvanised to minimum 5 micron thickness.

Light Duty Anchors

This anchor shall comprise of stud, nut, washers, expansion sleeve. The one end of the stud shall have thread and the other end shall have cold formed conical head. All steel components of the anchors shall be electro-galvanised to minimum 5 micron thickness. The expansion sleeve shall preferably be of stainless steel of SS316. The anchors shall conform to minimum grade 5.8 as per IS:1367 part 3.

2.02.11 Pipe Joints

MS pipes or GI pipes shall be joined by threaded sockets or by welding. Cast iron pipes shall be socket and spigot joined and caulked with hemp and molten head.

2.03.0 FENCING

2.03.01 Chain Link Fencing

The material requirement shall conform to IS: 2721 latest edition. The chain link fencing shall be woven from 3.15mm dia. wire with mesh size of 50mm. The mesh wire shall not vary from specified dia. by more than ± 0.05 mm. all steel wire shall be hot dipped galvanised wire. The dia shall be measured over the galvanised coating. The line wire shall be 4.0mm dia. mild steel. The stirrup wire for securing the line wire to the intermediate post (RCC/structural steel) shall be 2.5 mm diameter mild steel. The tying wire for securing the chain link fencing to the line wire shall be 1.6mm diameter mild steel. Hair pin chain staples for fastening down the bottom of galvanised chain line fencing to the concrete sill shall be 3.15mm wire. The ends shall be bent outwards for securing anchorage.

Cleat for eye bolts shall be of uniform size and shall consist of mild steel angle of 75 x 50 x 8 mm. The eye bolts strainer shall consist of bolt with welded eye sufficiently threaded and fitted with a nut and washer. Two-way eye bolt strainer shall have suitable ring nuts fitted after the wires have been strained on one side. Stretcher bar shall consist of mild steel flats 25 x 4.75 mm. They



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 129 of 361

shall be secured to the cleats by steel bolts.

The chain link fencing shall be strained between each pair of straining posts and secured to each straining posts by means of a stretcher bar. One of top line wire shall be threaded through appropriate adjacent row of mesh, care being taken that no meshes in the row are bypassed by the line wire except where deviation is necessary at the straining posts. The second top line wire shall be strained in front of the fencing. The fencing shall be attached to the top and bottom line wire by wire ties spaced at 150mm apart and to the other middle line wire by wire ties spaced at 450mm apart.

The bottom of fencing shall be treated as follows:

Continuous concrete sill 125mm wide x 225mm high for full length between posts shall be cast with the top 25mm above GL and 25mm below the chain link fencing. Hair pin staples shall be threaded through the bottom row of mesh at 750mm c/c and set in the sill to a depth of 150mm.

2.03.02

Barbed Wire Fencing

The barbed wire shall conform to IS:278 latest edition. The barbed wire shall be galvanised and galvanising shall conform to the requirement laid down for 'light-coated wire' of IS:4826 and it shall be smooth and relatively free of lumps etc. Wire with excessive roughness blisters, salammoniac spots shall be rejected. The barbed wire shall be made from two line wire and two point wire of 2.5 mm thickness each. The barbs shall have four point and shall be formed by twisting two point wires, each two turns, tightly around both or one line wire (Type A - around both line wire, Type B - around one line wire) making altogether four complete turns. The barbs shall be so finished that four points are set and located or locked as far as possible at right angle to each other. The barbs shall have a length of not less than 13mm and not more than 18mm. The distance between two barbs shall be 75 ± 12 mm.

Straining posts shall be provided at all ends and corners of fences or at changes in direction or acute variation in level and at intervals not exceeding 66 M on straight lengths of fence. Intermediate posts shall be spaced at regular intervals not exceeding 3.0m. Struts shall be fitted to all straining posts behind the chain link fabric in the direction of line of fence. There shall be four evenly spaced row of line wire in all. The top line wire shall be doubled, making five line wire in all. The bottom wire shall be closed to the ground. Each line wire shall be strained tightly by means of eyebolts strainers or winders at each straining points. Each line wire shall be secured to each intermediate post by a wire stirrup passed through a hold in the post and secured to the line wire by three complete turns on each sides of the post. The barbed wire shall be fitted with one dropper at the centre of each bay, secured to the wire so that they could not be bunched together. Droppers for barbed wire shall be of mild steel of not less than 25 x 4.75 mm thick with 38 x 4.85 mm half round staples for fastening the barbed wire to them. Bracing for the rows of barbed wire shall be approved by the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 130 of 361

3.00.00 ACCEPTANCE CRITERIA

- a) All items shall be correct shape, size, weight etc. shown on drawings and schedule of items.
- b) For installed items, the tolerances shall be as follows
 - i) Permissible deviation from, straightness – 1 in 1000.
 - ii) Seats, stiffener connections etc. shall be as per approved drawings and shall not interfere with architectural clearances.
- c) All castings shall be free from blowholes, cracks, and other blemishes.
- d) All MS wire fencing shall be in true vertical plain, and shall not bulge.

4.00.00 IS CODES

- IS:278 Specification for Galvanised Steel Barbed wire for fencing.
- IS:816 Code of practice for use of Metal Arc welding for general construction in mild steel.
- IS:1367 Industrial Fasteners – Threaded steel fasteners - Technical supply condition.
- IS:2721 Specification for Galvanised Steel Chain Link fence fabric.
- IS:2812 Arc welding of Aluminum and Alloy

5.00.00 RATES AND MEASUREMENTS

5.01.0 Rates

Rates shall include supply, fabrication and installation for misc. metals works as required for completion of works like gates, fencing, handrails, ladders, hangers, anchors etc., unless otherwise specified in Schedule of Items.
Rate for fencing shall also include excavation, concreting and supply, erection & fabrication of post (post made of either structural steel or reinforced cement concrete), unless any specific item is excluded.

5.02.0 Measurements

Measurement for MS gates shall be in MT.

Measurement for galvanised MS wire fencing shall be in Sqm.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 131 of 361`

Measurement for Anchors shall be in nos. for the type as specified in schedule of items.

Measurement of other misc. metals shall be done in MT unless otherwise specified in schedule of items.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 132 of 361

SECTION - D

SUB-SECTION – D9

MASONRY AND ALLIED WORKS

C O N T E N T

CLAUSE NO.	DESCRIPTION
-------------------	--------------------



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 133 of 361

1.00.00	SCOPE
2.00.00	MATERIALS
3.00.00	INSTALLATION
4.00.00	I.S. CODES
5.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 134 of 361

MASONRY AND ALLIED WORKS

1.00.00 SCOPE

This section covers furnishing, installation including handling, transporting, batching, mixing, laying scaffolding, centering, shuttering, finishing, curing, protection, maintenance and repair of common building materials till handing over of masonry and allied works for use in structures and locations covered under the scope of this package.

2.00.00 MATERIALS

a) Brick (Fly Ash Cement Bricks with min 75kg/sq cm strength)

Bricks for general masonry work shall be of class designation 7.5 of nominal dimensions as per Indian standard specification, well burnt, of uniform size, shape and colour, free from cracks, flaws or modules of free lime and emit clear ringing sound when struck. Fractured surface shall show uniform texture free from grits, lumps holes etc. Water absorption after 24 hours immersion shall not exceed 20% by weight for bricks. Dimensional tolerance shall not exceed 8% of the size shown in drawings for bricks. All bricks shall have rectangular faces and sharp straight edges. The bricks shall show no efflorescence after soaking in water and drying in shade.

Each brick shall have the manufacturer's identification marks clearly marked on the frog. Representative samples shall be submitted and approved samples shall be retained by the Engineer for further comparisons and reference. Any brick not found up to the specification shall be removed immediately from site at the Contractor's own cost.

Bricks shall not be dumped at site. They shall be stacked in regular tiers, even as they are unloaded; to minimize breakage and defacement of bricks. Bricks selected for different situation of use in the work shall be stacked separately.

b) Stone

All stones shall be obtained from approved quarries, hard, tough, durable compact grained, uniform in texture and colour and free from decay, flaws, veins, cracks and sand holes. The surface of a freshly broken stone shall be bright, clean, and sharp and shall show uniformity of texture, without loose grains and free from any dull, chalky, or earthly appearance. Stone showing mottled colours shall not be used for face work. A stone shall not absorb more than 5 per cent of its weight of water after 24 hours immersion. The type of stone shall be as specified on drawings and/or



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 135 of 361

instructed by the Engineer. Samples shall be submitted by the Contractor and approved samples shall be retained by the Engineer for comparison of bulk supply.

c) Cement

Cement used shall be Ordinarily Portland Cement or Portland Slag Cement or Portland Pozzolana Cement conforming to IS Codes and shall be fresh when delivered. In special cases, Rapid Hardening Portland Cement, Low Heat Cement etc. may be permitted or directed to be used by the Engineer. The Contractor shall submit the manufacturer's certificate for each consignment of cement procured to the Engineer. If at any time, the Engineer feels that the cement being used by the Contractor is not up to specification, he may stop the work and send the samples of the cement to a testing laboratory for standard tests and all expenses incurred thus shall be borne by the Contractor. The Contractor shall also have no claim for this type of suspension of work.

The cement shall be stored above the ground level in perfectly dry and watertight sheds. The bags shall be stacked in a manner so as to facilitate removal or first in first out basis. Any material considered defective by the Engineer shall not be used by the Contractor and shall be removed from the site immediately.

d) Coarse Aggregate

Coarse aggregates shall be as per IS: 383 latest editions, consisting of hard, strong and durable pieces of crushed stone and shall be free from organic or clay coatings and other impurities like disintegrated stones, soft flaky particles etc. and any other material liable to affect the strength, durability or appearance of concrete.

Aggregates other than crushed stone conforming to the provisions of specification may be used if permitted by the Engineer.

Washing of aggregates by approved means shall be carried out, if desired by the Engineer.

Grading of coarse aggregates shall generally conform to IS: 383 and shall be such as to produce a dense concrete or the specified proportions and strength and of consistence that will work readily into position without segregation.

Aggregates shall be stored on brick soling or an equivalent platform so that they do not come in contact with dirt, clay, grass, or any other injurious substances at any stage.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 136 of 361

Aggregate of different size shall be kept in separate stacks. If so desired by the Engineer aggregate from different sources shall be stacked separately with proper care to prevent intermixing.

e) Sand

Sand shall be hard, durable, clean, and free from adherent coatings or organic matter and shall not contain clay balls or pellets. The sand shall be free from impurities such as iron pyrites, alkalis, salts, coal, mica, shale or other laminated materials in such forms or quantities as to affect adversely the hardening, strength, durability or appearance of mortar, plaster or concrete or to cause corrosion to any metal in contact with such mortar, plaster or concrete. All sand shall be properly graded and shall be as per relevant IS Code. Sand for concrete shall conform to IS: 383.

f) Water

Water shall be clean, fresh and free from organic matters, acids or soluble salts and other deleterious substances which may cause corrosion, discoloration, efflorescence etc.

g) Reinforcement

Reinforcement steel shall be clean and free from loose mill scales, dust, loose rust, oil and grease or other coatings, which may impair proper bond. Structural steel shall conform to IS: 2062. Mild steel and medium tensile steel bars and hard-drawn steel wire for concrete reinforcement shall conform to IS: 432. Cold twisted steel bars shall conform to IS: 1786. Hand drawn steel wire fabric shall conform to IS: 1566. Hexagonal wire netting shall conform to IS: 3150. All steel bars including and above 10 mm diameter shall be of tested quality. All wire netting shall be galvanized.

Reinforcement bars shall be stored off the ground and under cover if so desired by the Engineer. If necessary, a coat of cement wash shall be given to the bars to guard against rusting.

3.00.00 INSTALLATION

3:01.00 Soling

3.01.01 Brick Soling

The ground shall be dressed, consolidated by ramming, or by light rolling and a 12 mm thick cushion of sand laid. On the sand cushion the bricks shall be laid with fine joints and placed firmly in position by hammering with wooden mallet. The surface shall be free from undulations. The 'frog' side shall be on



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 137 of 361

the underside. The joints shall be broken the in all direction and bricks cut as required. The pattern of laying and number of layers shall be as per Schedule of item. Orientation shall be as desired by the Engineer. After laying of each layer of bricks sand shall be spread over and worked into the joints to pack the bricks tight.

3.01.02 Stone Soling

The stones for soling shall be selected on the basis of thickness of soling specified in the Schedule of Items. The larger stones shall be laid and the gaps filled by smaller stones. The interstices shall then be firmly packed with sand by flooding with water.

3.02.00 Brick-on-Edge

Excavation shall be done close to the brick dimensions and in perfect alignment. Bricks shall be firmly placed by hammering with wooden mallets and sides and joints packed firmly with earth so that the edging is not disturbed easily. Alignment and level shall be acceptable to the Engineer.

3.03.00 Masonry

3.03.01 General

All masonry work shall be true to lines and levels as shown on drawings. All masonry shall be tightly built against structural members and bonded with dowels, inserts etc. as shown on drawings.

3.03.02 Cement Mortar

Cement mortar shall be prepared with materials specified in clause 2.00.00. Sand for masonry mortar shall conform to IS: 2116. Cement and sand in the specified proportion shall be mixed dry thoroughly and minimum water added to attain required workability.

Surplus mortar droppings from masonry, if received on surface free from dirt may be mixed with fresh mortar if permitted by the Engineer who may direct addition of additional cement without any extra payment. No mortar, which has stood for more than half an hour, shall be used.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 138 of 361

3.03.03

Brick Masonry

Bricks shall be soaked by submergence in clean water for at least two hours in approved vats before use. Bricks shall be laid in English bond unless specified otherwise. Broken bricks shall not be used. Cut bricks shall be used if necessary to complete bond or as closers. Bricks shall be laid with frogs upwards over full mortar beds. Bricks shall be pressed into mortar and tapped into final position so as to embed fully in mortar. Inside faces shall be buttered with mortar before the next bricks is placed and pressed against it. Thus all joints between bricks shall be fully filled with mortar.

Mortar joints shall be kept uniformly 10 mm thick. All joints on face shall be raked to minimum 10 mm depth using raking tool while the mortar is still green to provide bond for plaster or pointing.

Where plaster or pointing is not provided, the joints shall be struck flush and finished immediately. Brickworks two bricks thick or more shall have both faces in true plane. Brickwork of lesser thickness shall have one selected face in true plane.

3.03.04

Exposed Brickwork

Brickwork in superstructures, which is not covered by plaster, shall be as shown on drawing and executed by specially skilled mason. Courses shall be truly horizontal and vertical joints truly vertical. Wooden straight edges with brick course graduations and position of window sills and lintels shall be used to control uniformity of brick courses. Masons must check workmanship frequently with plumb, spirit level, rule, and string. All brickwork shall be cleaned at the end of days work. If face bricks are specified, the brickwork shall be in composite bricks, with face bricks on the exposed face and balance in routine bricks, but maintaining the bond fully. Where face bricks are not specified, bricks for the exposed face shall be specially selected from routine bricks. All exposed brickwork on completion of work shall be rubbed down, washed clean, and pointed as specified. Where face bricks are used carborandum stone shall be used for rubbing down.

3.03.05

Reinforced Brickworks

Reinforcements shall be as specified. All reinforcements shall be thoroughly cleaned and fully embedded in mortar. Where M.S. bars are used as reinforcement, these shall be lapped with dowels if left in R.C. columns or welded to steel stanchions.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 139 of 361

3.03.06 Stone Masonry

Stones shall be thoroughly soaked before laying. Stones shall be laid on their natural quarry beds. Individual stones shall be fitted with mallet and properly wedged to reduce thickness of mortar joints. Thickness of joint shall be not less than 8 mm and not greater than 25 mm. At least two stones shall run the full width of the wall for every square meter of surface area.

3.03.07 Exposed Stone work

Stonework, which is to be kept exposed, shall be as shown on approved drawing. It shall be executed by specially skilled mason. Stones used for exposed face shall be specially selected. All exposed stone faces shall be kept clean and free from mortar and pointed up neatly as the work proceeds in a manner called for in the drawings or instructions. A sample wall, 10 Sq.M. area shall be built and approved by the Engineer and all works shall match with this sample.

3.03.08 Composite Masonry

Where stonework facing with brick masonry backing is specified the bond between them shall be achieved by bond stones of dimensions and frequency as desired by the Engineer.

3.03.09 Expansion & Separation Joints

Location of joints shall strictly be as shown on drawings or as instructed by the Engineer. Expansion joints shall be as shown on drawings and specified. Expansion joint filler boards and sealing strips shall have minimum transverse joints. Transverse joints shall meet the approval of the Engineer.

Separation joints shall be with standard waterproof paper or with alkathene sheets about 1 mm in thickness. Length and sealing of laps shall be to the satisfaction of the Engineer.

3.03.10 Mouldings, Cornices, Drip Course

These shall be made as shown in drawings. Bricks or stone shall be cut and dressed as required. If no subsequent finish is envisaged, these shall be rubbed to correct profile with Carborundum stone.

3.03.11 Curing

Masonry shall be cured by keeping it wet for seven days from the date of laying. In dry weather at the end of days work top surface of masonry shall be kept wet by ponding.

3.03.12 Embedding of fixtures



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 140 of 361

All fixtures shall generally be embedded in mortar and masonry units shall be cut as required.

3.03.13 Encasing of Structural Steel

This shall be done by building masonry work round flanges, webs etc., and filling the gap between steel and masonry by minimum 12 mm thick mortar. Encased members shall be wrapped with chicken wire mesh when shown on drawings or instructed by the Engineer. The minimum lap in chicken wire mesh shall be 50 mm.

3.04.00 Damp Proof Course (DPC)

Unless otherwise specified Damp-proof course shall be 40 mm thick 'artificial stone' in proportion 1:1½:3 cement sand stone-chips (10 mm down) with admixture of a waterproofing compound as approved by the Engineer. The percentage of admixture shall be as per manufacturer's specifications but not less than 2% by weight of cement. The top surface shall be double chequered and cured by ponding for seven days.

3.05.00 Damp Proof Membrane

Damp proof treatment using fibre or hessian base bitumen felt shall be 6, 8 or 10 course treatment as specified in IS: 1609. The number of courses shall be as shown as drawings or as specified. Sequence of work shall be as directed by the Engineer. Extreme care shall be taken to prevent damage to felt during and after laying. The Contractor shall be obliged, at his own expense, to rectify any leakage appearing within 5 years of installation by removing and renewing the coats at the point of leakage.

Where shown on drawing, damp proof membrane with one layer bitumen paper or one layer alkathene sheet shall be laid with minimum 150 mm lap under slabs on grade.

3.05.00 Plinth Protection

Plinth of buildings shall be protected with brick-on-edge paving of minimum 750mm width unless otherwise shown on the drawings. The treatment shall consist of laying bricks in cement mortar 1:6 (1 cement: 6 sand) over a 75mm thick bed of dry graded brick aggregate, 40mm nominal size, grouted with sand. The top shall be finished with 1:2 cement mortar pointing (1 cement: 2 sand). Plinth protection shall be laid with a minimum outward slope of 1 in 50. The brick aggregate shall be well graded, broken from well burnt or slightly overburnt and dense brickbats. It shall be homogeneous in texture, roughly cubical in shape, clean and free from dirt or any other foreign matter.

The ground shall first be prepared to the required slope around the building. The high portions of the ground should be cut down; hollows and depressions



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 141 of 361

filled up to the required level from the excavated earth and rammed so as to give uniform outward slope. The bed shall be watered and rammed with heavy iron square rammers. Surplus earth, if any, shall be disposed off beyond a lead of 50m or as directed by the Engineer.

Over this, 75mm thick bed of aggregate of 40mm nominal size, shall be laid with a minimum outward slope of 1 in 50. Aggregates shall be carefully laid and packed, bigger sized being placed at the bottom. The brick aggregates shall be consolidated dry with heavy iron rammers.

The aggregates shall then be grouted evenly with sand at the rate of 0.6 cubic metre per square metre area, adequately watered to ensure filling of voids by sand and again rammed with heavy iron rammers. The finished surface shall give uniform appearance. After the subgrade has been compacted thoroughly, brick flooring with bricks of specified strength in cement mortar 1:6 (1 cement: 6 sand) shall be laid.

The bricks shall be laid on edge in Diagonal/Herring Bone Bond or other pattern as specified or as directed by the Engineer. Bricks shall be laid on 12mm thick mortar bed and each brick shall be properly bedded and set home by gentle tapping with handle of trowel or wooden mallet. Its inside face shall be buttered with mortar before the next brick is laid and pressed against it. On completion of the portion of flooring, the vertical joints shall be fully filled from the top with mortar. The surface shall present a true plain surface with the required slope.

The pointing shall be done in cement mortar 1:2 (1 cement: 2 sand). The mortar shall be pressed into the joints and shall be finished off flush and level with the edges of the bricks so as to give a smooth appearance. The edges shall be neatly trimmed with a trowel and a straight edge. The mortar shall not spread over surface of the masonry.

Brick flooring & pointing shall be kept wet for a minimum period of seven days. These shall be protected from rain by suitable covering when the mortar is green.

4.00.00

I.S. CODES

Some of the important relevant codes for this section are:

IS: 1127: Recommendations for dimensions and workmanship of natural building stones for masonry work.

IS: 1597: Code of Practice for Construction of stone Masonry.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 142 of 361

IS: 1609: Code of Practice for laying Damp proof treatment using bitumen felts.

IS: 2212: Code of Practice for Brickwork.

IS: 2250: Code of Practice for preparation and use of masonry Mortar.

IS: 5134: Bitumen Impregnated Paper & Board.

5.00.00 RATES AND MEASUREMENTS

5.01.00 Rates

Unit rate for masonry work shall include the following:

- a) Raking out joints for plastering or pointing or finishing the joint flush as the work proceeds.
- b) Preparing top sand sides of existing wall for joining old with new work.
- c) Providing, dismantling and removing the scaffolding.

Unit rate for DPC shall be inclusive of formwork and bitumen painting.

5.02.00 Measurement

Brickwork in wall of half brick thickness shall be measured separately in Sqm stating the wall thickness and more than half brick thickness shall be measured by volume. Plaster thickness shall not be considered for computation of volume.

Masonry work in sub structure and super structure shall be measured separately, unless otherwise specified in the Schedule of items.

No deductions shall be made and no extra payment shall be made for following:

- a) Opening upto 0.1 Sqm each in area. In calculating the area of the opening lintels or sills shall be included along with the size of the opening.
- b) Drainage holes and recesses for cement blocks to embed holdfasts for doors, windows etc.
- c) Pipe and fixtures upto 300mm dia. and nothing extra shall be paid for the mortar used for fixing.

Reinforcement in masonry work shall be paid separately under respective items.

Damp proof course shall be measured in Sqm. No deduction shall be made and no extra shall be paid for opening upto 0.1 Sqm in area.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 143 of 361

Plinth protection shall be measured under respective item of works executed required for completion of the work as specified.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 144 of 361

SECTION - D

SUB-SECTION – D10

FINISH TO MASONRY AND CONCRETE

C O N T E N T

CLAUSE NO.	DESCRIPTION
-------------------	--------------------

1.00.00	SCOPE
---------	-------



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 145 of 361`

2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA
4.00.00	I.S. CODE
5.00.0	<u>RATES AND MEASUREMENTS</u>



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 146 of 361

FINISH TO MASONRY AND CONCRETE

1.00.00 SCOPE

This Section covers finishing, installation, repairing, finishing, curing, testing, protection, maintenance till handing over of finishing items for masonry and concrete. This shall also include the work to be done to make the surface suitable for receiving the finishing treatment.

Before commencing finishing items the Contractor shall obtain the approval of the Engineer regarding the scheduling of work to minimize damage by other trades. He shall also undertake normal precaution to prevent damage or disfiguration to work of other trades or other installation.

2.00.01 INSTALLATION

2.01.00 Preparation of Surface

All joints in masonry walls shall be raked out to a depth of at least 10 mm with a hooked tool made for the purpose while the mortar is still green. Walls shall be rushed down with stiff wire brush to remove all loose dust from joints and thoroughly, washed with water. All laitance shall be removed from concrete to be plastered.

For all types of flooring, skirting and dado work, the base cement concrete slab or masonry surface shall be roughened by chipping and cleaned of all dirt, grease or loose particles by hard brush and water. The surface shall be thoroughly moist to prevent absorption of water from the base course. Any excess of water shall be mopped up.

At any point, the level of base shall be lower than the theoretical finished floor level by the thickness of floor finish. Any chipping or filling to be done to bring the base in the required level shall be brought to the notice of the Engineer and his approval shall be taken regarding the method and extent of rectification work required.

Prior to commencement of actual finishing work, the approval of the Engineer shall be taken as to the acceptability of the base.

2.02.00 PLASTERING

2.02.01 Mortar

Mortar for plastering shall be as specified.

For sand cement plaster, sand and cement in the specified proportion shall be mixed dry, on a watertight platform and minimum water added to achieve



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 147 of 361

working consistency. The sand for plaster shall conform to IS: 1542.

No plaster, which has stood for more than half an hour, shall be used; plaster that shows tendency to become dry before this time shall have water added to it.

2.02.02 Application of Plaster

Plaster, when more than 12 mm thick, shall be applied in two coats a base coat followed by the finishing coat. Thickness of the base coat shall be sufficient to fill up all unevenness in the surface; no single coat, however, shall exceed 12 mm in thickness. The lower coat shall be thicker than the upper coat; the overall thickness of the coats shall not be less than the minimum thickness shown on the drawings. The undercoat shall be allowed to dry and shrink before applying the second coat of plaster. The undercoat shall be scratched or roughened before it is fully hardened to form a mechanical key. The method of application shall be 'thrown on' rather than 'applied by trowel'.

To ensure even thickness and true surface, patches of plaster about 100 mm to 150 mm square or wooden screed 75 mm wide and of the thickness of the plaster, shall be fixed vertically about 2000 mm to 3000 mm apart, to act as gauges. The finished wall surface shall be true to plumb, and the Contractor shall, without any extra cost to the Owner, make up any irregularity in the brickwork with plaster.

All vertical edges of brick pillars, doorjambs etc. shall be chamfered or rounded off as directed by the Engineer. All drips, grooves, mouldings and cornices as shown on drawing or instructed by the Engineer shall be done with special care to maintain true lines, levels and profiles. After the plastering work is completed, all debris shall be removed and the area left clean. Any plastering that is damaged shall be repaired and left in good condition at the completion of the job.

2.02.03 Finish

Generally, the standard finish shall be used unless otherwise Shown on drawing or directed by the engineer. Wherever any special treatment to the plastered surface is indicated, the work shall be done exactly as shown on the drawings, to the entire satisfaction of the engineer regarding the texture, color and finish.

a) Standard Finish

Wherever punning is indicated, the interior plaster shall be finished rough; otherwise the interior plaster shall generally be finished to a smooth surface. The exterior surface shall generally be finished with a wooden float.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 148 of 361

b) Neat Cement Finish

Immediately after achieving a true plastered surface with the help of a wooden straight edge, the entire area shall be uniformly treated with a paste of neat cement at the rate of one (1) kg. per Sq.M. and rubbed smooth with a trowel.

c) Coloured Plaster Finish

This shall be done in the same way as specified in Clause 2.02.02 but using Coloured cement in place of ordinary cement. When coloured plastering is specified in more than one coat, the topcoat only shall be made with coloured cement.

Coloured cement shall be either ready mixed material or may be obtained by mixing pigments and cement at site, as approved by the Engineer. The pigments to be mixed with cement shall conform to Appendix-A of IS: 2114 latest editions.

Samples of colouring material shall be submitted to the engineer for approval and material procured, shall conform in all respects to the approved samples, which shall remain with the Engineer. All coloured cement and/or pigments shall be stored in an approved manner in order to prevent deteriorations.

d) Pebble-dash Finish

Mortar of required thickness consisting of 1 part cement and 4 parts sand by volume shall be applied in the usual manner as described under plastering Clause 2.02.02. While the mortar is still plastic small pebbles or crushed stone of size generally from 10mm to 20mm as approved by the Engineer shall be thrown on the plastered surface. The aggregate shall be lightly tapped into the mortar with a wood float or the flat end of oil a trowel, in order to ensure satisfactory bond between the dashing and the mortar.

e) Rough-cast Finish

A wet plastic mix of 3 parts coloured cement 6 parts sand and 4 parts aggregate by volume (gravel or crushed stone of size from 6 mm to 12 as approved by the Engineer) shall be thrown on to the wall by means of a plaster's trowel and left in the rough condition.

f) Scraped Finish

Ordinary plaster as described under Clause 2.02.02 after being leveled and allowed to stiffen for a few hours, shall be scraped with a steel straight edge to remove the surface skin. The pattern shall be as approved by the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 149 of 361

Engineer.

g) Textured Finish

Mortar consisting of 1 part cement and 3 parts sand by volume shall be applied in a manner as specified under "Plastering" Clause 2.2.2 Ornamental treatments in the form of horizontal or vertical rib texture fan texture etc. shall be applied by means of suitable tools to the freshly applied plastered surface, as approved by the Engineer.

h) Sand Faced Plaster

The plaster shall be applied in 2 coats. The first coat or the scratch coat should be approximately 14mm and shall be continuously carried out without break to the full length of wall or natural breaking points such as doors, windows, etc. The scratch coat shall be dashed on the prepared surface with heavy pressure, brought to true and even surface and then lightly roughened by cross scratch lines, to provide bond for the finishing coat. The mortar proportion for this scratch coat shall be as specified in the respective item or work. The scratch coat shall be cured for at least 7 days & then allowed to dry. The second coat shall be 6mm thick and it shall not be applied until at least 10 days have elapsed after the application of scratch coat. Before application of the second coat, the scratch coat shall be evenly damped. This coat shall be applied from top to bottom in one operation & without joints; finish shall be straight, true, & even. The mortar of this coat shall be as specified under the respective item of work. White sand for finish shall be used for the second coat & for finishing work. Sand for finish shall be of even coarse size & shall be dashed on the surface & sponged.

2.02.04 Curing

All plastered surfaces after laying shall be watered, for a minimum period of seven days, by an approved method, and shall be protected from excessive heat and sunlight by suitable approved means. Moistening shall commence, as soon as the plaster has hardened sufficiently and not susceptible to damage. Each individual coat of plaster shall be kept damp continuously, for at least two days, and then dried thoroughly, before applying the next coat.

2.03.00 Pointing to masonry

All Joints of brickwork shall be raked out to a depth of 10 mm with a hooked tool made for the purpose while the mortar is still green. The brickwork shall then be brushed down with a stiff wire brush, so as to remove all loose dust from the joints and thoroughly washed with water. Mortar consisting of 1 part cement and 3 parts clean, sharp, well graded sand by volume shall be pressed carefully into the joints and finishes with suitably tools to shape as shown on the drawings. Any surplus mortar shall be scalped off the wall face leaving



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 150 of 361

the surface clean.

The pointed surface shall be kept wet for at least three days for curing.

2.04.00 Plaster with Metal Lath

The supports, hangers, brackets, cleats etc. shall be as shown on drawings and/or as approved by the Engineer. These shall have a coat of prime paint before and another coat of approved paint after erection.

The metal lath shall be expanded metal, with 12 mm x 38 mm mesh, 16 thick and 3 mm wide strands. Side laps shall be minimum 12 mm and end laps 25 mm minimum. The plastering shall be minimum 20 mm thick measured from the back of lath and applied in two-layers. The mortar for plastering shall consist of 1 part cement and 4 parts sand by volume mixed as specified in plastering, Clause 2.02.01. The application, finish etc. shall be as specified under relevant clause above. Where called for a 2 mm Plaster of Paris punting shall be applied over plaster as a finishing coat to give perfectly smooth and even finish.

2.05.00 Lime Punning

For plastered surfaces, where an even smooth surface is specified, lime punning with 5 parts of shell lime properly slaked, strained and aged, mixed with 1 part clean, washed, sieved, fine sand by volume shall be done. The thickness of lime punning shall be not less than 2 mm and more than 3 mm. The plastered surface shall be saturated with water before application of the lime punning. The punning shall be applied by skilled workman and given a smooth and even finish free from undulations, cracks etc. and to the satisfaction of the Engineer.

2.06.00 Plaster of Paris Punning

Plastered surfaces, where specified shall be finished with Plaster-of-Paris punning. The material shall be from approved manufacturers and approved by the Engineer. The thickness of the punning shall be 2 mm and shall be applied by skilled workmen. The finish shall be smooth, even and free from undulation, cracks etc.

Before bulk work is taken in hand, a sample of punning shall be done on roughly 10 Sq.M. areas and approval of the Engineer taken. The work shall then be taken in hand as per approved sample.

2.07.00 Stone Facing

Stone facing where specified shall be done as shown on design drawings and approved shop drawings. The stone shall be as specified on drawings. Samples of stone shall be submitted to the Engineer for approval and then bulk



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 151 of 361

purchase made. The Contractor shall submit three copies of shop drawings for the Engineer's approval before commencing the work.

The thickness of facing stone shall be not less than 25 mm unless otherwise specified on drawings.

The stone slabs shall be cut and finished to sizes as per pattern shown on drawings.

They shall be fastened to wall with suitable non-corrodible anchorage as approved by the Engineer. Where mild steel clamps, stays etc. are used for anchorage, they shall be galvanized (weight of zinc coating shall not be less than 700 gms per square meter of surface) to prevent rust stains developing on the finished surface. There shall be at least 12 mm gap between the stone and masonry, which shall be filled up and packed by a mortar of 1 part cement and 3 parts of sand by volume. After the mortar is set and cured for at least four days, the exposed surface shall be rubbed and polished as approved by the Engineer.

The completed surface shall be neat, or uniform texture and acceptable to the Engineer.

Where pointing is specified on drawings it shall be done by mortar as specified on drawings.

3.00.00 ACCEPTANCE CRITERIA

Finish to masonry and concrete shall fully comply with the Specifications, approved samples and instructions of the Engineer with respect to lines, levels, thickness, colour, texture, pattern and any other special criteria as mentioned in the body of the specification or as shown on drawings.

4.00.00 I.S. CODE

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 1661: Code practice for cement and cement-lime plaster finish on wall & ceilings.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 152 of 361

IS: 4101: code of practice for external facings and veneers.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall also include providing, dismantling and removing of scaffolding, surface preparation, curing and all type of surface, shapes/ profiles and at all elevations.

5.02.00 Measurement

All plastering shall be measured net (on surface area on which it is applied) in Sqm. Plaster work shall be classified according to the type used and shall be measured separately. Plaster on ceiling and walls shall be measured separately. Soffits of stairs shall measured as plastering on ceiling.

No deduction shall be made for opening not exceeding 0.5 Sqm and for ends of beams, joints, etc. also no payment shall be made for reveals, jams, soffits, sills of these openings.

50% deduction shall be made for opening exceeding 0.5 Sqm but not exceeding 3.0 Sqm each and no addition shall be made for reveals, jams, soffits, sills etc.

In case of opening exceeding 3.0 Sqm each, deduction shall be made for opening but jams, soffits, and reveals shall be measured and paid for.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 153 of 361

SECTION - D

SUB-SECTION – D11

PAINTING, WHITEWASHING, POLISHING



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 154 of 361`

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA AND TESTING
4.00.00	I.S. CODES AND STANDARDS
5.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 155 of 361

PAINTING, WHITE WASHING, POLISHING, ETC.

1.00.00 SCOPE

This section covers painting, white washing, varnishing, polishing etc. of both interior and exterior surfaces of wood work, masonry, concrete plastering, plaster of paris, false ceiling, structural and other miscellaneous steel items, rain water down comer, floor and roof drains, soil, waste and service water pipes, and other ferrous and non-ferrous metal items.

Copper, bronze, chromium plate, Nickel, stainless steel and aluminium shall generally not be painted or finished except if otherwise specified.

Before commencing painting, the Contractor shall obtain the approval of the Engineer in writing regarding the schedule of work to minimize damage; disfiguration or staining to work of other trades or other installations.

2.00.00 Installation

2.00.01 Materials

Materials shall be highest grade products or well-known approved manufacture and shall be delivered to the site in original sealed containers, bearing brand name, manufacturer's name and colour shade, with labels intact and seals unbroken. All materials shall be subject to inspection, analysis and approved by the Engineer. It is desired that materials of one manufacturer only shall be used as far as possible and paint of one shade is obtained from the same manufacturing batch. Each and every supply of primer, finish paint etc. shall be accompanied by manufacturer's test certificate. All paint shall be subject to analysis from random samples taken at site from painters bucket, if so desired by the Engineer.

All prime coats shall be compatible to the material of the surface to be finished as well as to the finished coats to be applied.

All unspecified materials such as snellac, turpentine or linseed oil shall be of the highest quality available and shall conform to the latest IS standards. All such materials shall be made by reputable recognized manufacturers and shall be approved by the Engineer.

All colours shall be as per painting schedule and tinting and matching shall be done to the satisfaction of the Engineer. In such cases, where samples are required, they shall be executed in advance with the specified materials for the approval of the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 156 of 361

a) White Wash/Colour Wash

Shall be done from pure shell lime or fat lime, or a mixture of both as instructed by the engineer, and shall conform to IS: 712 latest editions. Samples of lime shall be submitted to the Engineer for approval, and lime as per approved sample shall be brought to site in unslaked condition. After slaking, it shall be allowed to remain in a tank for two days and then stirred up with a pole, until it attains the consistency of thin cream. 100 grams of gum to 6 liters of white wash water and a little of indigo or synthetic ultramarine blue shall be added to the lime. Mineral colour not affected by lime shall be added to white wash to get the required tint/shade approved by the Engineer.

b) Dry distemper

Shall be made from suitable pigments, extenders, lime proof tinters, water-soluble binders etc. and shall conform to IS: 427. The distemper shall be diluted with prescribed thinner in a manner recommended by the manufacturer. Only sufficient quantity of distemper required for a day's work shall be prepared.

c) Oil Bound Washable Distemper

Shall be of oil emulsion type containing suitable preservatives and shall conform to IS: 428. The distemper shall be diluted with prescribed thinner in a manner recommended by the manufacturer. Only sufficient quantity of distemper required for a day's work shall be prepared.

d) Waterproof Cement Paint

Shall be made from best quality white cement and lime resistant colours with accelerators, waterproofing agents and fungicides. The paint shall conform to IS: 5410.

e) Acrylic Emulsion Paint

Shall be water-based acrylic copolymer emulsion with rutile titanium dioxide and other selected pigments and fungicide conforming to IS: 5411 (Part-1). It shall exhibit excellent adhesion to plaster and cement surface and shall resist deterioration by alkali salts. The paint film shall allow the moisture in wall to escape without peeling or blistering. The paint, after it is dried, shall be able to withstand washing with mild soap and water without any deterioration in colour, or without showing flaking, blistering, or peeling.

f) Synthetic Enamel Paint



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 157 of 361

Shall be made from synthetic resins and drying oil with rutile titanium dioxide and other selected pigments to give a smooth, hard, durable and glossy finish to all exterior and resist interior surfaces. White and pastel shades shall not yellowing and darkening with aging. The paint shall conform to IS: 2932 and IS: 2933.

g) Aluminium Paint

Shall be in two pack containers and shall resist weathering. The paint shall conform to IS: 2339.

h) Varnishing

Shall be best quality alkyd varnish suitable for brushing over the tint of paint or light natural wood and shall not darken or yellow with age.

i) French Polish

Shall be made from best quality shellac, denatured spirit and other suitable alcohol soluble ingredients and made by a well known approved manufacturer. The material shall conform to IS: 348.

French polish shall not be used on bare wood it shall only be used as finishing coat on wood after the woods pretreated with a liquid wood filler conforming to IS: 345 is applied and rubbed out.

j) Bitumen paint (black bituminous anti-corrosive paint)

Bitumen based anti-corrosive paint conforming to IS: 158 shall be used.

2.00.02 Storage

The Contractor shall arrange for safe and proper storage of all materials and tools. The storage space if allotted within the building shall be adequately protected from damage, disfigurement, & stains. Paint shall be kept covered at all times and mixing shall be done in suitable containers. All necessary precautions shall be taken by the contractor to prevent fire.

2.01.00 Preparation of surface

Before starting the work the Contractor shall obtain the approval of the Engineer regarding the soundness & readiness of the surface to be painted on.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 158 of 361

2.01.02 Wood

All surfaces shall be free from, dirt and loose or peeling paints. The surface shall be rubbed down smooth. All nails & screws shall be sunk below the surface and filled with putty after applying an under coat. Small knots that do not justify cutting and sap streaks shall be covered with minimum 2 coats of pure shellace coating applied thinly & extended 25 mm beyond the area. All large, loose, or resinous knots shall be removed and filled with sound wood. All work shall be done as per IS: 2338.

2.01.02 Masonry, Concrete, and Plastered Surface

Surface shall be free from all oil, grease, efflorescence, mildew, loose paint, or other foreign and loose materials. Masonry cracks shall be cleaned out and patch filled with mortar similar to the original surface and uniformly textured. Where this type of resurfacing may lead to the finishing paint being different in shade from, the original surfaces, the resurfaces area shall be treated with minimum one coat of cement primer, which should be continued to the surrounding area for a distance of minimum 100 mm.

Surface with **Mildew or Efflorescence** shall be treated as below:

All mildewed surfaces shall be treated with an approved fungicide such as ammoniacal wash consisting of 7g of copper carbonate dissolved in 80ml liquor ammonia and diluted to water, or 2.5 percent magnesium silicofluoride solution and allowed to dry thoroughly before paint is applied.

2.01.03 Metal

The surface preparation shall be done in accordance with IS:1477(Part-1) 'Code of practice for painting of ferrous metals in building' and as directed by Engineer. All metal surfaces shall be absolutely clean, dry, and free from rust, scales, weld slag, flux deposit, wax, grease, dried soap films, foreign matters like cement mortar etc and free from existing loose red oxide zinc chromate primer and should be removed by means of wire brushes, hand scrappers, sand paper, emery cloth, emery papers, or by mechanical power tools etc. or as directed by Engineer. For exposed chemical resistant paints, surfaces shall be blast cleaned to near white metal. All galvanized iron surfaces shall be pretreated with a compatible primer according to the manufacturer's direction. Any abrasion in shop coat shall be touched up with the same quality of paint as the original coat. The actual painting work should be commenced only after obtaining clearance from the Engineer regarding proper cleaning of the surface.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 159 of 361

2.02.00 Application

2.02.01 General

The method of application shall be as recommended by the manufacturer. In case of selection of special shades and colour (not available in standard shades) the Contractor shall mix different shades and prepare test panels of minimum size 1 meter square as per instruction of the Engineer and obtain his approval prior of application of finishing paints.

Proper tools and implements shall be used. Scaffoldings used shall be independent of the surface to be painted to avoid shade differences of the freshly repaired anchor notes.

Painting shall be done by skilled labours in a workmanlike manner. All materials shall be evenly applied so as to free of sags, runs, crawls, or other defects. All coats shall be of proper consistency. In case of application by brush, no brush marks shall be visible. The brushes shall be clean and in good condition before application of paint.

All priming undercoat for painting shall be applied by brush only, and rollers spray equipments etc. shall not be used.

No work shall be done under conditions that are unsuitable production of good results. No painting shall be done when plastering is in progress or is drying. Application of paint, which seals the surfaces to moisture shall only be done after the moisture on and below the surface has dried out.

All coats shall be thoroughly dry before succeeding coat is applied. Coats of painting as specified are intended to cover surfaces perfectly. In case the surface is not covered property by applying the specified number of coats, further coats shall be applied by the Contractor when so desired by the Engineer.

All primers and undercoats shall be tinted to approximate the colour of the finishing coats. Finished coats shall be of exact colour and shade as per approved samples and all finish shall be uniform in colour and texture. All parts of mouldings and ornaments shall be left clean and true to finish.

Painting on ferrous metal surface shall, be done as per IS: 1477 (Part I & 2). The total dry thickness of film should not be less than 120 Micron.

2.02.02 White Washing

The surface where white washing is to be applied shall be cleared of all loose materials and dirt. All holes and irregularities of the surface shall be filled up with lime putty and shall be allowed to dry up before white washing.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 160 of 361

One coat of whitewash shall consist of one stroke from top downwards, another from bottom upwards over the first stroke and another from left to right before the previous one dries up. Second coat shall be applied and in case the Engineer feels that one or more coats are required the Contractor shall do so without any extra cost to the Owner. No brush marks shall show on the finished surface.

2.02.03 Dry Distemper

New plastered surface shall be allowed to dry for at least two months. New lime or lime cement plastered surface shall be washed with a solution of 1 part Vinegar to 12 parts water or 1:50 sulphuric acid solution and for 24 hours after which the wall shall be thoroughly washed with clean water. For cement-plastered surface, the surface shall be washed with solution of 100 gms. of zinc sulphate to 1 litre of water and allowed to dry.

Dry distemping shall be done as per manufacturers instruction. In applying the distempers the brush, should first be applied horizontally and immediately crossed off perpendicularly. Brushing shall not be continued too long, otherwise brush marks may result.

2.02.04 Oil bound washable distemper

The distemper shall be applied after surface is primed with an alkali resistant primer, and followed by minimum two coats of oil bound washable distemper all as per manufacturer's instruction.

2.02.05 Waterproof Cement Paint

Surface to be coated with cement paint shall be washed and brushed down. As soon as the moisture has disappeared, the surface shall be given one coat of paint. Care shall be taken so that the paint does not dry out too rapidly. After 4 to 6 hours, the water shall be sprinkled over the surface to assist curing and prevent cracking. After the first coat has dried (24 to 48 hours) the second coat shall be applied in a similar manner. The finished surface shall be kept moist by occasional sprinkling with water for seven days after painting.

2.02.06 Acrylic Emulsion Paint

Paint shall be applied after providing one coat of cement primer solvent of approved quality and primer shall be conform to IS: 109. Lime gauged cement plastered surfaces shall not be painted for at least one month after plastering. A sample patch shall be painted to check alkali reaction if so desired by the Engineer. Painting shall be done strictly as per manufacturer's specification.

2.02.07 Synthetic Enamel Paint

Shall be applied on properly primed surface. Subsequential coat shall not be applied till the previous coat is dry. The previous shall be lightly sand papered



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 161 of 361

for better adhesion of subsequent coats.

2.02.08

Aluminium Paint

The paint, supplied in two pack containers shall be mixed and applied strictly as per manufacturer's direction. When more than one coat of paint is required or indicated, the next coat shall only be applied after the previous coat become hard dry.

2.02.09

Clear Synthetic Varnish

The Varnish shall be applied on wood surface after (a) filling, (b) staining & (c) sealing operations are carried out. The application of a combination of filler and stain shall not be permitted.

For the finishing coats of varnish, the surface shall be allowed to dry and be rubbed down lightly, wiped off and allowed to dry. Careful attention to cleanliness is required for varnishing. All dust and dirt shall be removed from the surface as well as from the neighbourhood. Damp atmosphere and draughts shall be avoided, and exposure to extreme heat or cold & dampness shall not be allowed.

The varnish shall be applied liberally with a brush and spread evenly over a portion of the surface with light strokes to avoid frothing. It shall be allowed to flow on white the next section is being laid on excess varnish shall then be scrapped off the brush and the first section be crossed, recrossed and then laid off lightly. The varnish once it has begun to set shall not be retouched. In case of any mistake in application, the varnish shall be removed and the work started afresh.

The varnish shall be minimum of two coats, with the first coat being a flatting varnish. This shall be allowed to dry hard and be flatted down, before applying the next coat. Sufficient time must be allowed between coats to get a hard dry surface before next coat is applied. All work shall be as per relevant IS Code.

2.02.10

French polish

All unevenness of the surface shall be rubbed down to smoothness with sand paper and the surface shall well dusted. The pores in the shall be filled up with a paste of whitening in water or methylated spirit with a suitable pigment like burnt siemme or umber.

After application of the filler paste, the French polish shall be applied with a pad of woollen cloth covered by a fine cloth. The pad shall be moistened with polish and rubbed hard on the surface in a series of overlapping circles so that the polish is sparingly but uniformly applied over the entire area to give an even surface. A trace of linseed oil may be used on the pad for ease of application. The surface shall be allowed to dry before further coats are



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 162 of 361

applied in the same manner. To finish off, the pad shall be covered with a fresh piece of clean fine cloth, slightly dampened with methylated spirit, and rubbed lightly and quickly with circular motions to leave the finished surface with a uniform texture and high gloss.

2.02.11 Chemical Resistant Paint

For chemical resistant paints, epoxy, chlorinated rubber, or vinyl butryl paint system shall be used. Manufacturer's recommendation shall be followed regarding the paint system, exposed to moderately to severe corrosive condition and subject to acid/alkali spillage & fumes, shall be followed.

2.03.00 Protection

Furniture and other movable objects, equipment, fittings and accessories shall be moved, protected and replaced upon completion of work. All stationary equipment shall be well covered so that no paint can fall on them. Work finished by other agencies shall be well protected. All protections shall be done as per instructions of the Engineer.

2.04.00 Cleaning up

In addition to provisions in general conditions the Contractor shall, upon completion of painting etc. remove all marks and make good surfaces, where paint has been splashed or splattered, including all equipment, fixtures, glass, furniture, fittings etc. to the satisfaction of the Engineer.

3.00.00 ACCEPTANCE CRITERIA AND TESTING

- a) All painted surfaces shall be uniform and pleasing in appearance.
- b) All varnished surfaces shall be of uniform texture and high glossy finish.
- c) The colour, texture etc. shall match exactly with those of approved samples.
- d) All stains, splashes, and splatters of paints and varnishes shall be removed from surrounding surfaces.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 163 of 361

Testing

- a) As, each part of the work is under progress, i.e. preparation of surface, providing primer, providing different coats of finishing paints, it shall be passed by the Engineer. Variation from the drawings or specification or standard etc. shall not be accepted. The Contractor shall ascertain from the Engineer as to which parts will be inspected and passed from time to time. The Contractor shall provide all necessary arrangement for inspection of the painting work during its different working phase. The Contractor shall provide necessary scaffolding, approach for inspection of the above as per direction and satisfaction of the Engineer. All the necessary cost for scaffolding, approach, platform, lighting arrangement testing and inspection shall be borne by the Contractor. Such inspection and testing will not, however, exonerate the Contractor from his responsibilities for proper workmanship, material etc.
- b) The Contractor shall carry out all sampling and necessary testing in accordance with the relevant Indian Standards and shall conduct such tests as called for by the Engineer. Where no specific testing procedure is mentioned in the relevant codes, the tests shall be carried out as per the prevalent accepted Engineering practice as per the direction of the Engineer. Tests shall be done in a laboratory, approved by the Engineer, and cost of testing shall be borne by the contractor.
- c) Material/workmanship unsuitable for acceptance shall be removed and replaced by the Contractor. The work shall be redone as per Specification of the contract and direction of the Engineer without extra cost to owner.

4.00.00

I.S. CODE

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS: 348 Specification for French polish

IS: 427 Specification for Distemper, dry colour as required.

IS: 428 Specification for Distemper oil emulsion, colour as required.

IS: 1477 Code of Practice for painting of ferrous metal
(I & II) in buildings.

IS: 2338 Code of Practice for finishing of wood and
(I & II) wood based materials.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 164 of 361

IS: 2339 Specification for Aluminium, Paints for general purposes in dual containers.

IS: 2395 Code of Practice for painting concrete, masonry, and Plaster surface.

IS: 2932 Specification for enamel, exterior type-1.

IS: 5410 Specification for cement paint, colour as required.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall be unit rates for complete items described in the “Schedule of Items”.

Rate shall include cleaning, preparation of surface, supply and application of primer, painting and providing all protection and scaffolding required at site.

5.02.00 Measurements

Painting over the concrete/masonry/wooden surface shall be measured net (on the surface area on which it is applied) in Sqm.

No deduction shall be made for opening not exceeding 0.5 Sqm and ends of beams, joints, etc. also no payment shall be made for reveals, jams, soffits, sill of these openings.

50% deduction shall be made for opening exceeding 0.5 Sqm but not exceeding 3.0 Sqm each and no addition shall be made for reveals, jams, soffits, sills etc.

In case of opening exceeding 3.0 Sqm each, deduction shall be made for opening but jams, soffits, and reveals shall be measured and paid for.

Corrugated surfaces shall be measured flat and measured area shall be increased by 15%.

Painting of structural steel works shall be measured in M.T. unless specified otherwise.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 165 of 361

SECTION - D

SUB-SECTION – D12

FLOOR FINISH AND ALLIED WORKS

C O N T E N T



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 166 of 361

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	ACCEPTANCE CRITERIA
4.00.00	I.S. CODES
5.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 167 of 361

FLOOR FINISH AND ALLIED WORKS

1.00.0

SCOPE

This section covers furnishing, installation, finishing, curing, testing, protection, maintenance till handing over various types of floor finishes, and allied items of work as listed below

a) In Situ Finishes

- i) Integral finish to concrete base
- ii) Terrazzo finish
- iii) Granolithic finishes
- iv) Patent Stone
- v) Metallic Hardener like "Ironte"/Hardonate Finish
- vi) Mastic Asphalt finishes
- vii) Chemical Resistant finish

b) Tiled Finishes

- i) Terrazzo tile
- ii) Chequered tile
- iii) Glazed tile
- iv) Tesse rae (Mosaic etc.)
- v) Chemical Resistant
- vi) Rubber, Vinyl etc.
- vii) Stone Slab including Kota Stone.

1.01.00 Base

The base to receive the finish is covered under other relevant specifications.

1.01.01 Sequence

Commencement, scheduling and sequence of the finishing works shall be planned in detail and must be specifically approved by the Engineer in view the activities of other agencies working in that area. However, the Contractor for the finishing items shall remain fully responsible for all normal precautions and vigilance to prevent any damages whatsoever till handing over.

2.00.00 INSTALLATION



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 168 of 361

2.00.01 Special Materials

Basic materials are covered elsewhere under the Specification. In general, all such materials shall be as per relevant Codes where available. In all cases these materials shall be of the best quality available indigenously unless specified otherwise.

The materials for finishing items must be procured from well-reputed specialized manufacturers and on the basis of approval of samples by the Engineer. The materials shall be ordered, procured and stored well in advance to avoid compulsion to use substandard items to maintain in the construction schedule.

2.00.02 Workmanship

Only workers specially experienced in particular items of finishing work shall be engaged, where such workers are not readily available, with the Engineer's permission, experienced supervisors recommended by the manufacturer shall be engaged. In particular cases where the Engineer so desires the Contractor shall get the finishing items installed by the manufacturer.

2.00.03 Preparation of the Base Surface

The surface to be treated shall be thoroughly examined by the Contractor. Any rectification necessary shall be brought to the notice of the Engineer and his approval shall be taken regarding method and extent of such rectification work.

For all types of flooring, skirting, dado and similar locations, the base to receive the finish shall be adequately roughened by chipping, raking out joints and cleaning thoroughly all dirt, grease etc. with water and hard brush and detergent if required, unless otherwise directed by the manufacturer of any special finishing materials or specifically indicated in this specification.

To prevent of water from the finishing treatment the base shall be thoroughly soaked with water and all excess water mopped up.

The surface shall be bone dry where adhesives are used for fixing the finishes.

Prior to commencement of actual finishing work the approval of the Engineer shall be taken as per the acceptability of the surface.

2.01.00 In Situ Finishes

2.01.01 Integral Finish To Concrete Base

While the surface of the concrete laid as per specification for 'Cement Concrete' has been fully compacted and levelled but the concrete is still 'green' thick slurry, made with neat cement shall be applied evenly and worked in with iron floats. When the slurry starts to set it shall be pressed with iron floats to have a firm compact smooth surface without trowel mark or undulations. This finish shall be as thin as possible by using 2.2 kg. of cement per Sq.M. of area.

The surface shall be kept in shade for 24 hours and then cured for at least 7 days continuously by flooding with water. The surface shall not be subjected to any load or abrasion till 21 days after lying.

As desired by the Engineer the surface, while still 'green' shall be indented by pressing strings, the marking shall be of even depth, in straight lines and the panels shall be of uniform and symmetrical patterns.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 169 of 361

2.01.02 Terrazzo Finish in Situ

It shall consist of an underbed and a topping laid over an already laid and matured concrete base.

a) Thickness

Unless otherwise specified the total thickness of the 'finish shall be minimum 40 mm for horizontal and 25 mm for vertical surface of which the topping shall be not less than 10 mm. While the topping shall be of uniform thickness the underbed may vary in thickness to provide necessary slopes. The vertical surface shall project out 6 mm from the adjacent plaster or other finish. Necessary cutting into the surface receiving the finish shall be done to attain the specified thickness. All junctions of vertical with horizontal shall be rounded neatly to uniform radius of 25 mm.

b) Mix

i) Underbed

The underbed for floors and similar horizontal surfaces shall consist of a mix of 1 parts cement, 1½ parts sand and 3 parts stone chips by volume. For vertical surfaces the mix shall consist of 1 part cement to 3 parts sand by volume. The sand shall be coarse. The stone chips shall be 10 mm down well graded. Only sufficient water to be added to give a workable consistency.

ii) Topping

The mix for the topping shall be composed of cement, colour Pigment, marble dust and marble chips. Proportions of the ingredients shall be such as to produce the terrazzo of colour texture and pattern approved by the Engineer. The cement shall be white or gray or a mixture of the two to which pigment shall be added to achieve the desired colour. To 3 parts of this mixture 1 part marble powder by volume shall be added and thoroughly mixed dry. To 1 part of this mix 1 to 1½ parts of marble chips by volume shall be added and thoroughly mixed dry again.

The pigment must be stable and nonfading. It must be very finely ground. The marble powder shall be from White marble and shall be finer than IS Sieve No.: 30. The size of marble chips shall be between 1 mm to 20 mm. Sufficient quantity to cover each visible area shall be prepared in one lot to ensure uniform colour. Water to make it just workable shall be added to a quantity that can be used up immediately before it starts to set.

c) Laying

The underbed shall be laid in panels. The panels shall not be more than 5 Sq.M. in area of which no side shall be more than 2.5 M. long. For exposed locations the maximum area of a panel shall be 2.0 Sq.M. The panel shall be laid in alternate bays or chequered board pattern. No panel shall be cast in contact with another already laid until the latter has contracted to the full extent.

Dividing strips made of aluminium or glass shall be used for forming the panels. The strips shall exactly match the total depth of underbeds plus topping.

After laying, the underbed shall be levelled compacted and brought to proper grade with a screed or float. The topping shall be laid after about 24 hours while the underbed is still somewhat "green" but firm enough to receive the topping. A slurry of the mixture of



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 170 of 361

cement and pigment already made shall be spread evenly and brushed in just before laying the topping. The topping shall be rolled for horizontal areas and thrown and pressed for vertical areas to extract all superfluous cement and water and to achieve a compact dense mass fully bonded with the underbed. The surface of the topping shall be trowelled over, pressed and brought to a smooth dense surface showing a minimum 75% area covered by marble chips in a even pattern of distribution.

d) Curing

The surface shall be left for curing for about 12 to 18 hours and then cured by allowing water to stand on the surface or by covering with wet sack for four days.

e) Grinding and Polish

When the surface has sufficiently hardened it shall be watered and ground evenly with rapid cutting coarse grade (no.80) grit blocks, till the marble chips are exposed and the surface is smooth. Then the surface shall be thoroughly washed and cleaned. A grout with already prepared mixture of cement and pigment shall be applied to fill up all pinholes. The surface shall be cured for 7 days by keeping it moist and then ground with fine grit blocks (no.: 120). It shall again be cleaned with water, the slurry applied again to fill up any pinholes that might have appeared and allowed to be cured again for 5 days. Finally, the surface is ground a third time with very fine grit blocks (no.: 320) to get smooth surface without any pinhole. A suitable machine shall do the grinding. Where grinding machine can not be used hand grinding may be allowed when the first rubbing shall be with carborundum stone of coarse grade (no.:60), second rubbing with medium grade (no.: 80) and final rubbing and polishing with fine grade (no.: 120). The surface shall be cleaned with water, dried, and covered with soil free, clean sawdust if directed by the Engineer. The final polishing shall be postponed till before handing over if desired by the Engineer. Just before handing over the surface shall be dusted with oxalic acid at the rate of 0.33 gm. per. Sq.M., water sprinkled on to it and finished by buffing with felt or hessian bobs. The floor shall be cleaned with soft moist rag and dried. However, all excess wax polish to be wiped off and the surface to be left glossy, but not slippery.

2.01.03 Granolithic Finish

Granolithic finish shall either be laid monolithically over base concrete or separately over hardened base concrete.

a) Thickness

The finish shall be average 20 mm and minimum 12 mm thick, unless specified otherwise.

b) Mix

The mix shall consist of 1 part cement: 1 part coarse sand 2 parts coarse aggregate by volume. The coarse aggregate shall be very hard like granite and well graded between 6 mm and 12 mm. Minimum quantity of water to get workability shall be added.

c) Laying of Monolithic Topping

The concrete base shall be laid as per specification "Cement Concrete" and levelled upto the required grade. The form shall remain sufficiently protruding to take the finish.

Within about 3 hours of laying the base while it is still fully -green- the topping shall be laid evenly to proper thickness and grade. If considered necessary the surface of the base shall roughened by wire brushing. Unless manual operation is permitted by the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 171 of 361

Engineer, mechanical vibrators of suitable design shall be used to press the topping firmly and work vigorously and quickly secure full bond with concrete base.

The laitance brought to the surface during compression shall be removed carefully without disturbing the stone chips. The surface shall then be lightly trowelled to remove all marks. When sufficiently set, hand trowelling shall be done to secure a smooth surface without disturbing the stone chips.

For large areas the laying shall be in panels of maximum 25 Sq.M. area. The panels shall be laid in chequered board pattern.

d) Laying of Topping Separately on Hardened Base

The base concrete shall be prepared as stated in clause 2.00.03 and a slurry of neat cement applied just prior to laying the granolithic concrete mix (1:1:2). The method of compaction etc. shall be same as for monolithic topping.

e) Curing

Immediately after laying, the finish shall be protected against rapid drying. As soon as the surface has hardened sufficiently, it shall be kept continuously moist for at least 10 days by means of wet gunny bags or ponding of water on the surface. The floor shall not be exposed to heavy traffic during this period.

f) Grinding

If grinding is specified, it shall start only after the finish has fully set. Clause 2.01.02 (e) shall be followed. However, the Engineer shall decide upon the ultimate polish required.

g) Finishing

Where specified, sodium silicate or magnesium or zinc silico fluoride treatment shall be done. The number of coats to be applied shall be as per approved drawings or as instructed. The concentration and method of application of the solutions shall be as specified in IS: 5491.

2.01.04 Patent Stone

It shall consist of an underbed and a topping laid on an already laid and matured concrete base.

a) Thickness

The patent stone finish shall have thickness as stipulated under clause 2.01.02 (a) except that the topping shall be 12 mm thick.

b) Mix

i) Underbed

The mix shall be as stipulated under clause 2.01.02 (b).

ii) Topping

The mix for the topping shall consist of 1 part cement and 2 part stone aggregate 6mm nominal size by volume.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 172 of 361

c) Laying

The Patent Stone finish including the underbed shall be laid in alternate bays or in Chequered board pattern. No panel shall be cast in contact with another already laid till the contraction of the latter has already taken place.

The maximum area of each panel shall be 3 Sq.M. of which no side shall be more than 2 M. long.

A cement grout shall be applied and worked into the surface to receive the finish; the underbed then laid, compacted, and leveled to proper grade with a screed or float. The topping shall be applied evenly on the underbed while it is not fully set but firm enough and rolled and pressed to get full bond. The topping shall be trowelled to a dense finish to the satisfaction of the Engineer. All trowel marks shall be mopped out with a soft cloth to give a clean smooth surface.

After the surface is sufficiently set, the finished floor shall be kept moist for 7 days for curing. If desired the finish shall be polished as directed by the Engineer.

2.01.05 Metallic Hardener Like 'Ironite'/'Hardonate' Finish

This will consist of a topping (incorporating iron particles) to bond with concrete base while the latter is 'green'.

a) Thickness

Unless otherwise specified the metallic hardener finish shall be of 12 mm depth.

b) Material

The hardening compound shall be uniformly graded iron particles free from non-ferrous metal impurities, oil, grease, sand soluble alkaline compounds or other injurious materials when desired by the engineer, actual samples shall be tested.

c) Mix

Proportion of the metallic hardener shall be as specified or as indicated by the manufacturer. However, in absence of any such direction 1 part metallic hardener shall be mixed dry, with 4 parts cement, by weight. To this mixture 6 mm nominal size stone chips shall be added in proportion of 1 part cement (mixed with hardener) to 2 parts of stone chips by volume and uniformly mixed. Minimum quantity of water shall be added to make it workable.

d) Laying

The concrete floor shall be laid as per specification 'Cement Concrete' and levelled upto required grade. The forms, if any, shall remain sufficiently projecting to make the finish. The surface shall be roughened by wire brash as soon as possible.

The finish shall be laid while the concrete underbed is still very 'green' within about 3 hours of laying of the latter. The finish shall be of uniform thickness and even dense surface without trowel marks, pin holes etc. This topping layer shall be pressed firmly and worked vigorously and quickly to secure full bond with the concrete base. Just when the initial set starts the surface shall be finished smoothened with steel trowel.

The finished floor shall be cured for 7 days by keeping it wet.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 173 of 361

2.01.06 Mastic Asphalt Finish

This is a one-layer treatment on concrete or brick base.

a) Thickness

The thickness shall be as specified in the drawing.

b) Materials

Bitumen shall be industrial Bitumen of the grade 90/15 and 75/15 conforming to IS: 702.

Mineral filler shall be dry stone dust passing through 75 micron IS Sieve.

Fine aggregate shall be crushed and graded natural limestone or other hard work.

Coarse aggregate shall be crushed siliceous stone or other approved aggregate 6 mm stone chips shall be used for finish upto 20 mm thick & 10 mm chips for thicker finish.

c) Composition

Bitumen mastic shall conform IS: 1195 and shall be either brought to site in blocks weighing about 25 Kg or prepared at site. If brought in blocks, these shall be remelted in mechanically agitated mastic cookers and coarse aggregate, preferably preheated fed in successive portions until the complete change is thoroughly, incorporated. At no stage during the remelting and mixing process, shall the temperature exceed 205°C.

d) Laying

The hot mastic shall be laid on dry base surface cleaned thoroughly by wire brushing and sweeping. The mastic shall be leveled and when cooled to some extent shall be finished with a wooden float with addition of small quantity of fine sand if required. No load shall be allowed till the finish has cooled to normal temperature.

The mastic shall be laid in suitable panels of about 1.5 Sq.M. in area each formed by formers. Succeeding panels shall be laid overlapping the finish panel so as to melt its edges and form a continuous finish without joint.

2.01.07 Chemical Resistant in Situ Finish

Chemical resistant in situ finish shall be as epoxy resin with suitable filler material over a primer. The minimum thickness shall be 6 mm. About its performance the Engineer shall have to be fully satisfied by test results and examination of similar treatment already in existence. The contractor shall get it done by a specialized Manufacturer and get guarantee of performance from the organization and pass it on to the Owner in addition to his own guarantee.

2.02.00 Tiled Finish

These shall include finish tiles, stone slabs, and similar manufactured or natural items over already laid and matured base of concrete or masonry by means of an underbed or an adhesive layer.

2.02.01 Terrazzo Tile Finish

The finish will consist of manufacture terrazzo and an underbed.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 174 of 361

a) Thickness

The total thickness including the underbed shall be minimum 40 mm for floors 30 mm for walls unless otherwise specified.

The skirting, dado and similar vertical surfaces shall project out 6 mm uniformly from the adjacent plaster or other wall finishes. The necessary cutting into the surface receiving the tiled finish, to accommodate the specified thickness shall be done.

b) Tiles: Terrazzo

The tiles shall, unless specifically permitted in special cases be machine made under quality control in a shop. The tile shall be pressed hydraulically to a minimum of 140 Kg. per Sq.cm.

Each tile shall bear on its back permanent and legible trademark of the manufacturer. All angles of the tiles shall be right angles all arises sharp and true, colour and texture of the wearing face uniform throughout. Maximum tolerance allowance length and breadth shall be ± 1 mm and the thickness ± 3 mm. Face of the tile shall be plane, free from pinholes and other blemishes.

The tiles shall be composed of a backing and topping. The topping shall be of uniform thickness not less than 10 mm.

The total thickness including the topping shall be as specified but not less than 20 mm in any case.

The backing shall be composed of 1 part ordinary gray cement and 3 parts of stone chips by weight mixed with water.

The topping shall be as specified under clause 2.01.02 (b).

The tile shall be cured at the shop for at least 14 days before delivery to the site. First grinding shall be given to the tiles at the shop before delivery. Tiles shall be packed properly to prevent damage during transit and storage. The tiles must be carefully stored to prevent staining by damp, rust, oil, and grease or other chemicals.

Tiles made in each batch shall be kept and used separately so that colour of each area of the floor may remain uniform.

The manufacturer shall supply along with the tiles the grout mix containing cement and pigment in exact proportions as used in topping of the tiles. The containers for the grout mix shall be suitably marked to relate it to the particular type and batch of tiles.

c) Mix: Underbed

The underbed for floor and similar horizontal surfaces shall be 1 part lime putty: 1 part surkhi: 2 parts coarse sand by weight mixed with sufficient water to form a stiff workable mass. For skirting and dado and all vertical surfaces it shall be about 12 mm thick and composed of 1 part cement and 3 parts coarse sand by weight.

d) Laying

The underbed mortar shall be evenly spread and brought to proper grade and consolidated to a smooth surface. The surface shall be roughened for better bond. Before the underbed had time to set and while it is still fairly moist but firm, cement shall be hand dusted over it or a cement slurry applied and the tiles shall immediately be placed upon and firmly



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 175 of 361

pressed by wooden mallet on to the underbed until it achieves the desired level. The tiles shall be kept soaked for about 10 minutes just before laying. The joints between tiles shall be as close as possible and not more than 1.5 mm wide.

Special care shall be taken to check the level of the surface and the lines of the joints frequently so that they are perfect.

When tiles are required to be cut to match the dimensions these shall be sawn and edges rubbed smooth. The location of cut tiles shall be planned in advance and approval of the Engineer taken.

At the junction of horizontal surface with vertical surface the tiles on the former shall enter at least 12 mm under the latter.

After fixing, the floor shall be kept moist and allowed to mature undisturbed for 7 days. Heavy traffic shall not be allowed.

If desired dividing strips as specified under Clause 2.01.02(c) may be used for dividing the work into suitable panels.

e) Grinding and Polishing

Procedure shall be same as Clause 2.01.02(e). Grinding shall not commence earlier than 14 days after laying of tiles.

2.02.02 Chequered Tile Finish

The finish shall consist of manufactured gray or coloured cement tiles or terrazzo tiles with chequered face and an underbed laid over concrete or brick surface.

a) Thickness

Thickness shall be same as in clause 2.02.01 (a).

b) Tiles: Chequered

The tiles shall have chequers not less than 2.5 cm. c/c and not more than 5 cm. c/c. Depth of grooves shall be not less than 5 mm. The grooves shall be uniform and straight.

The tiles shall conform to clause 2.02.01 (b) except that these may have the topping in terrazzo or plain gray cement or colour pigment added to cement.

c) Under-bed

As per clause 2.02.01 (c).

d) Laying

As per clause 2.02.01 (d).

e) Grinding and Polishing

As per clause 2.02.01 (e) except that the tiles shall be ground and polished by hand and after laying taking special care in polishing the grooves properly and uniformly.

2.02.03 Glazed Tiles Finish



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 176 of 361

This finish shall be composed of glazed earthenware tiles with an underbed laid over a concrete or masonry base.

a) Thickness

The total thickness shall be between 20mm and 25mm including the underbed.

The tile finish on vertical surface shall project out 6 mm uniformly from the adjacent plaster or other wall finishes. The necessary cutting into the surface receiving the finish, to accommodate the specified thickness shall be done.

b) Tiles: Glazed

The tiles shall be of earthenware, covered with glaze white or coloured, plain or with designs, of 150 mm x 150 mm nominal sizes and 5.5 mm to 6 mm on thick unless otherwise specified. The tolerance shall be ± 1.5 mm for length and breadth and ± 0.5 mm for thickness specials like internal and external angles; beads, covers, cornices, corner pieces etc. shall match. The top surface of the tiles shall be glazed with a gloss or matt, unfading stable finish as desired by the Engineer. The tiles shall be flat and true to shape. The colour shall be uniform and fractured section shall be fine grained in textures, dense and homogeneous. The tiles shall be strong and free from flaws like cracks, craze, specks, crawlings, etc. and other imperfections. The edge and the underside of the tiles shall be completely free from glaze and the underside shall have ribs or indentations for better anchorage with the fixing mortar.

The coloured tiles, when supplied, shall preferably come from one batch to avoid difference in colour.

c) Mix: Underbed

The mix for the underbed shall consist of 1 part cement and 3 parts coarse sand by weight mixed with sufficient water or any other mix if specified.

d) Laying

Same as clause 2.02.01 (d).

e) Finishing

The joints shall be cleaned and flush pointed with white cement and cured for 7 days by keeping it wet. The surface shall be cleaned with soap or suitable detergent, washed fully, and wiped with soft cloth to prevent scratching before handing over.

2.02.04 Tesserae Finish (Mosaic etc.)

This finish consists of manufactured vitreous, glass, ceramic or similar hard small pieces set in an underbed over a concrete or masonry surface, already laid.

a) Thickness

The total thickness including the underbed shall be between 16 mm & 25 mm.

b) Tesserae Finish

These shall usually be 6 mm thick small piece of ceramic vitreous china, tinted glass, or similar hard wearing, strong, and durable material in desired shapes and sizes and patterns.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 177 of 361

The supply shall come in the desired pattern in full or sections conveniently for handling, stuck to pieces of strong thick paper on the surface to be exposed. The gum used for this purpose must be water soluble and non-staining. The sections shall be properly marked to avoid mistakes and master drawing shall be available at the site for guidance.

- c) Mix: Underbed
Same as clause 2.02.03 (c)
- d) Laying

The specification for laying if given by the manufacturer of the item shall be followed provided it is approved by the Engineer. Otherwise clause 2.02.03 (d) shall generally be followed. However, instead of gray cement the slurry shall be made with white cement to fix the panels. The paper-mounted patterns in sections shall be carefully placed and pressed in position true to lines and levels. Earliest possible the paper shall be peeled off and surface examined and cleaned, joints flush pointed with white cement and cured for 7 days by keeping it wet.

2.02.05 Chemical Resistant Tiled Finish

This shall include all varieties of special tiles used for specific chemical resistance function and an underbed over already laid concrete or masonry.

- a) Tiles

The chemical resistant tiles shall be of the best indigenous Manufacture unless otherwise specified and shall be resistant to the chemical (both acid and alkali). The tiles shall have straight edges, uniform thickness, plain surface, uniform nonfading colour, and textures.

Usually the chemical resistant tiles shall not absorb water more than 2% by weight. The tiles shall have at least compression strength of 700 Kg/cm². The surface shall be abrasion resistant and durable.

- b) Laying

The mortar used for setting or for underbed these tiles shall be durable, strong and chemical resistant epoxy mortar. The grout, which shall be to the full depth of tile, shall have equal chemical resistant properties. Joints shall be pointed if so desired. The setting and fixing shall be according to the manufacturer's specification approved by the Engineer.

2.02.06 Rubber, Vinyl, or Vinyl Asbestos Tiles Finish

This shall include various types of tiles manufactured from rubber, vinyl etc. set with an adhesive on concrete or masonry base. An underbed may be required to secure desirable surface and grade.

- a) Thickness

The thickness of the tiles shall be as incorporated in drawing.

- b) Tiles

Unless otherwise desired the tiles shall be squares of approved dimensions. The tolerance in dimensions shall be ± 1.5 mm.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 178 of 361

The face of the tiles shall be free from porosity, blisters, cracks, embedded foreign matters or either physical defects which affect appearance or serviceability. All edges shall be cut true and square. The colour shall be nonfading and uniform in appearance, insoluble in water and resistant to alkalies, cleaning agents and usual floor polishes.

Each tile shall be marked on the back legibly and indelibly with manufacturer's trademark, the thickness, sizes, batch number, and date of manufacturer.

Tiles shall be delivered securely packed and stored in clean, dry well ventilated place at a temperature near about to that the tiles shall be called upon to stand ultimately.

Adhesive to be used for sticking the tiles shall be approved by the tile manufacturer. The adhesive shall have a short drying time and long life in addition to toughness.

c) Mix: Underbed

The underbed where required to make up the specified thickness or to give the required grade or to get the right type of surface shall be composed of 1 part like putty:1 part cement: 3 parts coarse sand mixed with just sufficient water to make it workable.

d) Laying

The tiles shall be kept in the room to be tiled for at least 24 hours to bring them to the same temperature as the room. For air-conditioned space, the air-conditioning shall be completed before tiling is taken up.

The surface to receive this finish shall be firm even textured but not too smooth, without undulations and other deficiencies. If an underbed is laid the same shall be cured for at least 7 days by keeping it moist and then fully dried.

The surface shall be thoroughly cleaned. All loose dust particles shall be removed. Oil and grease if any shall be completely cleaned by use of detergent.

The adhesive shall be applied to fully dry surface in desired thickness uniformly. The adhesive shall also be applied to the backs and edges of the tiles and allowed to surface dry. The tiles shall be placed neatly on the surface exactly to the approved pattern and set with a suitable tool. If the edges tend to curl, weights are to be used to keep the edges down. Special care shall be taken to avoid formation of air pockets under the tiles. The joints shall be very fine. Any adhesive squeezed out through the joints shall be removed immediately.

e) Finishing

If any adhesive mark is there on the surface a soft cloth soaked in solvent shall be used to wipe it off. The surface shall be cleaned with soft soap, dried, and polished with an approved type of polish just before handing over.

2.02.07 Stone Slab Finish: Marble, Stone, and Similar Fine Grained Stone including Kota stone

a) Thickness

The underbed shall be minimum 12 mm and average 20 mm thick. The slabs will be 20 mm thick.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 179 of 361

b) Stone Slab

The stone slabs shall be made from selected stock, which is hard, sound, homogeneous and dense in texture and free from flaws. Angles and edges shall be true, square, and free from chipping and surface shall be plane. The slabs shall preferably be machine cut to the required dimensions. Tolerance of ± 5 mm in dimensions and ± 2 mm in thickness will be allowed. Unless specified the slabs shall be minimum 300 mm x 300 mm.

The stone slabs shall come from specific regions and in specified quality with top surface fine chisel dressed. All sides shall also be fine chisel dressed to the full depth to allow finest possible joints.

The slabs shall be delivered to the site well protected against damages and stored in dry place under cover.

c) Mix: Underbed
Same as clause 2.02.01 (c).

d) Laying

The sides and top surface of the slabs shall be machine rubbed or table rubbed with coarse sand stone and washed before laying.

The underbed mortar shall be evenly spread and brought to proper level on the area under each slab. The slab shall be laid over the underbed, pressed, and tapped down with wooden mallet to the proper level. The slab shall then be lifted and the underbed corrected as necessary and allowed to stiffen a little. Next, thick cement slurry shall be spread over the surface. The edges of the slab shall be buttered with slurry of cement, gray / white / mixed with pigment matching the colour of the stone slabs. The slab shall be gently laid and tapped with wooden mallet to bed properly to a very fine joint and to the required level. All surplus cement slurry shall be removed and the surface mopped clean with wet soft cloth. The laid finish shall be cured for 7 days by keeping it wet.

e) Polishing, Finishing

Fine chiselling shall be done to remove the slight undulations that usually exist at the joints. The polishing and finishing shall be done as specified under clause 2.02.01 (e). However, the joints shall be so fine in the case of stone slabs that grouting shall not be called for.

2.02.08 Stone Slab Finish: Sand Stone and Similar Coarse Grained Stone Finish

Generally clause 2.02.07 shall be followed except that the workmanship and finish shall not be fine as which are explained hereunder.

The slabs shall be rough chiselled or fine chiselled as specified. Tolerance may be allowed upto ± 6 mm for rough finish, but no sharp unevenness and shall be allowed. For fine chiselling the unevenness shall be limited to ± 2 mm. The sides shall be chisel dressed at least to half slab depth so that the maximum deviation from straight line shall be within 25 mm. Beyond this depth the edge may be slightly splayed.

The joint thickness shall be kept limited to 5 mm in case of rough finish and 3 mm in case of fine finish unless wider joints are specified. The joints shall be grouted with white or coloured cement. If fine joints in the flooring are specified, the edges of slabs shall be cut in such a way that it shall form an inverted 'Y'.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 180 of 361

3.00.00

ACCEPTANCE CRITERIA

The finish shall be checked specially for:

- a) Level, Slope, Plumb as the case may be
- b) Pattern and Symmetry
- c) Alignment of joints, dividing strip etc.
- d) Colour, texture
- e) Surface finish
- f) Thickness of joints
- g) Details at edges, junctions etc.
- h) Performance
- i) Precautions specified for durability

4.00.00 I.S. CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

- IS: 777 : Glazed earthenware tiles
- IS: 1196 : Code of practice for laying bitumen mastic flooring.
- IS: 1197 : Code of practice for laying of rubber floors
- IS: 1237 : Cement concrete flooring tiles
- IS: 1443 : Code of practice for laying and finishing of cement concrete flooring tiles.
- IS: 2114 : Code of practice for laying in situ terrazzo floor.
- IS: 3461 : PVC asbestos floor tiles
- IS: 4860 : Specification for acid resistant bricks
- IS: 5518 : Code of practice for laying of flexible PVC Sheet and tile flooring.
- IS: 5491 : Code of practice for laying in situ granolithic floor topping.

5.00.00 RATES AND MEASUREMENT

5.01.00 Rates

Rates shall be for the complete work (including dividing strips, ironite, metals, tiles etc. if any) as per the schedule of items. Rates shall be applicable for application on horizontal and vertical surfaces at all elevations and for all types of work including stairs tread and riser,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 181 of 361

laying in desired pattern and panels, cost of specials (if any) rounding of corners, mouldings etc.

Rates shall be including provision of side shuttering (if required) for casting of floor in alternate panels and or without dividing strips.

5.02.00 Measurement

The finished surface shall be measured in Sqm for area unless otherwise specified. Deduction shall not be made for opening or embedded articles having area not exceeding 0.1 Sqm.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 182 of 361

SECTION - D

SUB-SECTION – D13

SHEET WORK IN ROOF AND SIDING

C O N T E N T

CLAUSE NO.	DESCRIPTION
-------------------	--------------------

1.00.0	SCOPE
--------	-------

2.00.00	INSTALLATION
---------	--------------



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 183 of 361`

- 3.00.00 ACCEPTANCE CRITERIA
- 4.00.00 I.S. CODES
- 5.00.00 RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 184 of 361

SHEET WORK IN ROOF AND SIDING

1.00.00 SCOPE

This section covers supply, cutting & fabrication and erection of corrugated/plain asbestos, corrugated galvanized iron, aluminum, permanently colour coated troughed zinc-aluminium alloy coated M.S. sheet or other sheet for covering to roof and sides at various elevations as specified.

2.00.00 INSTALLATION

2.01.00 Storage of Materials

All materials shall be stored by the Contractor in proper way to prevent all damage.

2.02.00 Workmanship

The workmanship shall be according to best construction practice to give a watertight finish to the satisfaction of the Engineer. Fixing of gutters and down pipes shall be according to IS: 2527.

2.02.01 Asbestos Sheeting

Asbestos sheets of profiles as specified shall be fixed with minimum 150 mm end lap and side laps as per manufacturer's specification. Hook bolts or J-bolts shall be 8 mm dia. at 305 mm centres. Six (6) mm dia. galvanized iron seam bolt and nut with G.I. flat washers and bitumen washers shall be used for stitching ridge cappings, corner pieces, ventilators, north light curves etc.

2.02.02 C.G.I. Sheeting and Aluminium Sheeting

Side laps shall be 2 corrugations for roof and one corrugation for side sheeting. End laps shall be minimum 150 mm for roof and 100 mm for side sheeting. In ridges and hips where plain sheets are used, the end laps shall be minimum 100 mm. Holes in C.G.I. sheets shall preferably be made on the ground. The sheets should be placed on purlins/trestles and holes punched in the ridge of the corrugation from the outside inward for obtaining proper seating of limpet washers. Sheets shall be secured to sheet framing by 8 mm dia. galvanised iron hooks or J-bolts and maximum spacing of the bolts shall be 305 mm. The length of the hook or J-bolts shall be to suit the sections of the bearers. Sheets shall also be bolted at the ends at every third corrugation with 6 mm dia. galvanized iron seam bolts and G.I. flat washers and bituminous washers.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 185 of 361

2.02.03 Fibre Glass Reinforced Plastic Sheeting

This shall be of thickness and profile as specified. Colour and light transmittance shall be as mentioned. Where used in conjunction with C.G.I. or asbestos sheeting, the end and side laps and fixing device shall be same as used for general sheeting. Where used in lieu of glass, the fixing shall be by means of timber or metal glazing beads. In all cases, the installation shall be completely watertight and able to withstand the designed wind-pressure.

2.02.04 PERMANENT COLOUR COATED SANDWICHED INSULATED METAL CLADDING SYSTEM

- i. Troughed zinc-aluminium alloy coated (both sides) M.S. sheet having 0.6mm minimum thickness (or high tensile steel sheet having minimum yield strength of 350 Mpa of 0.5mm minimum thickness) shall be used on external face (outer face) of cladding system. Weight of coating shall not be less than 150 gm/sq.m. The outer side (exposed face) shall be permanently colour coated with Polyfluro Vinyl Coating (PVF₂) of Dry Film Thickness (DFT) 20 microns (minimum) over primer. Inner side of external sheet shall be provided with suitable pre-coating of minimum 7 microns.
- ii. Galvanised M.S. sheets of minimum 0.6mm thickness shall be used as inner liner (internal face) of cladding system. The exposed face shall be permanently colour coated with silicon modified polyester paint of DFT 20 microns (minimum) over primer. Inner face of external sheet shall be provided with suitable pre-coating of minimum 7 microns. The rate of galvanization shall not be less than 275 gm/sqm.
- iii. The permanent colour coated sheet shall meet the general requirements of IS:14246 and shall conform to class 3 for the durability.
- iv. Inner sheet shall be fixed directly to side runners and Z spacers made out of at least 2 mm thick galvanized steel sheet of grade 375 as per IS:277. Inner sheet shall be fixed at the rate not more than 1.50M centre to centre to hold the insulation and external sheeting. The fasteners shall be of high quality corrosion resistant grade of self tapping / self drilling type provided with suitable cap.
- v. The insulation shall be of bonded mineral wool of minimum thickness 50mm conforming to IS:8183, having a density of 32 Kg/cu.m. for glass wool & 48 Kg/cu.m. for rock wool.

2.02.05 PERMANENT COLOUR COATED (NON-INSULATED) METAL CLADDING SYSTEM

- i. Troughed zinc-aluminium alloy coated not less than 150 gm/sq.m M.S. sheets having 0.6 mm minimum thickness (or High tensile steel sheet having minimum yield strength of 350 Mpa of 0.5mm minimum thickness) shall be



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 186 of 361

used for the cladding system. The outer side (exposed face) shall be permanently colour coated with PVF₂ paint of minimum DFT 20 microns over primer and the inner side (internal face) shall be coated with same paint of minimum DFT 12 microns over primer. These shall be fixed directly to runners. The sheets shall meet the general requirement of IS:14246 and shall conform to class 3 for the durability.

ii. **FLASHING, CAPS, TRIM CLOSURES ETC.**

All flashings, trim closures caps etc. required for the metal cladding system shall be made out of plain sheets having same material and coating specification as mentioned above for the outer face of the sandwiched metal cladding.

3.00.00 ACCEPTANCE CRITERIA

The installations shall present a neat appearance and shall be checked for water tightness. The following shall be checked:

- a) Side and end laps
- b) Absence of cracks, holes or damages in sheet
- c) Spacing of bolts
- d) Provision of double washers (G.I. and asbestos or bituminous washers)
- e) Proper installation of flashing.

4.00.00 I.S. CODE

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

- IS: 3007 : Code of practice for laying of asbestos cement sheets.
- IS: 2527 : Code of practice for fixing rainwater gutters and down pipes for roof drainage.
- IS: 1626 : Specification for asbestos cement building pipes, gutters and fittings.
- IS: 277 : Specification for galvanized steel sheets (plain and corrugated).

5.00.00 RATES AND MEASUREMENT



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 187 of 361

5.01.00 Rates

Rates shall be unit rate for complete item described in “Schedule of Items” and shall include all wastage.

5.02.00 Measurement

Sheeting work in roof & sides shall be measured in Sq.M. for net area of the work done. Profiled sheeting shall be measured flat and not girthed. Opening less than 0.40 Sqm shall not be deducted. No extra shall be paid for extra labour in cutting and for wastage etc. No payment shall be made for laps in sheeting works.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 188 of 361

SECTION - D

SUB-SECTION – D14

SUSPENDED CEILING

C O N T E N T



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 189 of 361`

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	INSTALLATION
3.00.00	SAMPLES
4.00.00	SHOP DRAWINGS
5.00.00	ACCEPTANCE CRITERIA
6.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 190 of 361

SUSPENDED CEILING

1.00.00 SCOPE

This section covers supply and installation of suspended ceiling together with the suspension system as shown on drawing or specified in schedule of item with all materials, labour and equipments. The work shall also include providing of openings in the ceiling for lighting, air-conditioning diffusers etc. as shown on drawings or as instructed by the Engineer.

2.00.00 INSTALLATION

2.01.00 Suspension System

2.01.01 General

Suspension system shall consist of the grid supporting the ceiling panels, intermediate runner supports for the grid if any and hangers, wall angles etc. required to suspend the grid or the runners from structural works, slabs and beams.

All members of the suspension system shall be of sufficient strength and rigidity to carry, the ceiling boards or sheets in a true and level plane without exceeding a deflection of 1/360th of their span. All joints in ceiling panels shall run straight and cross joint shall be at perfect right angles. Angle moulds where shown on drawings shall be securely fixed to walls. All drillings of structural concrete and installation of suitable anchoring device for installation including welding of the suspension system shall be included in the rate. All M.S. sections used for supports etc. shall be given one coat of synthetic enamel paint over a coat of red lead primer.

2.01.02 Metal Grid Suspension System

Aluminium grid ceiling system shall be "Bead lock" as manufactured by W A Beard shell and Co. Pvt. Ltd. or Ajit India Limited or approved equal. Steel grid ceiling system shall be 'Jolly Snap Grid' as manufactured by Jolly Board Limited or approved equal.

Steel tees as intermediate members and steel channels, as end pieces will be assembled in the form of grid. Size of tees and channels shall be as required.

The cross-tees shall intersect main tee runners in pattern shown on drawing and positively locked together with intersection members. All perimeter areas shall have tee runners fixed to vertical wall surfaces and end channels shall be fixed to runners leaving return air space between vertical wall and channels, unless otherwise shown on drawings. Angle cleats or other suitable fixing device shall be fixed to the structural beams above for fixing of hangers. Main runners shall be hung by M.S. flats, angles, rods or 12G or heavier galvanized



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 191 of 361

tie wire hangers at maximum 1.2 metre centres. Extra hangers shall be provided at light fixtures that are supported from the ceiling system. The spacing of main and cross runners shall be as shown on drawings. Turnbuckles shall be provided in M.S. rods for adjustment in levels.

2.02.00 Ceiling Panels

2.02.01 Material

Ceiling panels shall be best quality material in thickness and properties called for in the "Schedule of items". The Contractor shall submit test certificates to the Engineer for approval before bulk supply. The ceiling panels may be of following type:

- a) Plaster of Paris board (decorative)
- b) Expanded polystyrene insulation board with plastic fascia.
- c) Fibre Insulation board.
 - d) Bonded wooden particle board (Plain and decorative)
 - e) Glass fibre reinforced polystyrene sheets.
 - f) Flat asbestos sheets (with plastic fascia).

2.02.02 Installation of Ceiling Panels

Installation of Ceiling panels shall be strictly as per manufacturer's instruction.

For concealed grid system, tiles shall be fixed to the supporting grid in manner shown on drawing or as specified by the manufacturer. Where V joints in tiles are called for in drawings, these shall be in true lines. Where flush surface is required, the joints shall be filled with approved filler material and finished to give a neat uniform surface. Special care shall be taken to neatly finish the ceiling at junctions with walls, light fixtures, diffusers etc.

2.02.03 Aluminium Lineal Ceiling System

Aluminium lineal ceiling system shall be "Luxalon 84C " or approved equal and the installation shall be strictly as per manufacturer's instruction/specification subject to approval of the Engineer.

Aluminium lineal ceiling shall comprise of plain panels, 84 mm wide and 12.5 mm deep with a 23.9 mm recessed flange, roll formed out of 0.5 mm thick aluminium alloy panels stove enamelled on both sides, fixed on roll-formed carriers made of enamelled 0.95 mm thick aluminium, 32 mm wide and 39 mm deep with prongs to hold panels in the module of 100mm, at maximum



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 192 of 361

spacing 1.2 M centre to centre. The carriers shall be suspended from roof by 4 mm dia galvanised steel wire hangers with special height adjustment clips made out of spring steel at maximum spacing of 1.2 M c/c. Hangers shall be fixed to roof by 'J' hooks and nylon inserts. 25 mm thick resin bonded mineral wool (spintex 300 or equivalent) insulation bound in polythene shall be laid on top of panels. Lineal ceiling shall be fixed in pattern as per detailed drawings.

3.00.00

SAMPLES

Samples of Ceiling panels and metal suspension system components as noted below shall be submitted for Engineer's approval:

Panels : 3 samples approximately 300 mm square/long each

Suspension System : 3 samples of short length : each of main and secondary system

4.00.00

SHOP DRAWINGS

Shop drawings shall be submitted for approval as required and approval shall be obtained prior to delivery of suspended ceiling components. Shop drawings shall be co-coordinated with all related work and shall show the following information:

- a) A reflected ceiling plan of areas indicated to receive the ceiling showing electrical and mechanical features.
- b) Typical Intermediate framing for support where required.
- c) Hanger fastening details.
- d) Panels - unit support at ceiling penetrations.
- e) Details of splicing method for main and cross runners.
- f) A table indicating load bearing capacity of main and cross runner
- g) A note stating that the suspension system member furnished will not deflect more than 1/360 of the span under the indicated loading.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 193 of 361

5.00.00 ACCEPTANCE CRITERIA

Finished ceiling shall be at the correct plane and present a pleasing and uniform appearance, free from, sags, warps, disfigured, or damaged board. Cutouts for light fixtures, diffusers etc. shall be of exact dimensions and in exact locations.

6.00.00 RATES AND MEASUREMENT

6.01.00 Rates

Rates shall be for the complete item called for in the "Schedule of Items". No extra payment will be made for alignment and adjustment of lighting fixtures, air-conditioning diffusers, access panels etc. The rate shall include all cutting and wastage from standard size sheets, runners/carries etc.

6.02.00 Measurement

Actual area of work shall be measured in Sqm correct to second place of decimal. However, no deduction will be made for opening upto 0.25 Sqm. each in area.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 194 of 361

SECTION - D

SUB-SECTION – D15

WATER SUPPLY, DRAINAGE AND SANITATION



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 195 of 361

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	MATERIAL
3.00.00	INSTALLATION
4.00.00	TESTING AND ACCEPTANCE CRITERIA
5.00.00	I.S. CODES
6.00.00	RATE AND MEASUREMENT



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 196 of 361

WATER SUPPLY, DRAINAGE AND SANITATION

1.00.00 SCOPE

This section covers supply of all materials labour and incidentals required for supply, laying and installation of under/over ground pipes for water supply, drainage and sanitation with all fittings, fixtures and jointing, construction of ancillary works like manholes, drop connections, gully chambers, septic tank, soak pits, surface drain etc.

The supply and installation of water supply/sanitation fixtures and accessories like water closets, urinals, wash basins, sinks, mirrors, shelves, towel rail, soap container etc. with all fittings, fixtures, water supply/sanitation pipes and water storage tanks etc.

2.00.00 MATERIAL

All materials, fittings, fixtures, and appliances shall be of the best quality conforming to relevant Indian Standard and shall be procured from approved manufacturers. Unless specifically allowed by the Engineer, the Contractor shall submit samples of fittings and fixtures, which will be retained by him for comparison when bulk supplies are received at the site. Ultimate choice of type, model, and manufacturer lies completely with the Engineer.

It shall be the responsibility of the Contractor to procure the materials selected by the Engineer. Hence orders are to be placed with the manufacturers in time, so that the materials are available at the site well ahead of their requirement.

The materials brought to the site, shall be stored in a separate secured enclosure away from the building materials. Pipe threads, sockets, and similar items shall be specially protected till final installation. Brass and other expansive items shall be kept under lock and key. Fragile items shall be checked thoroughly when received at the site and items found damaged shall not be retained at the site.

2.01.01 Pipes and Pipe Fittings

For water supply, galvanised mild steel pipe of medium grade conforming to IS: 1239 shall be used. The galvanising shall not be less than 400gm/sqm of pipe surface area. Galvanising shall be smooth and shall be subjected to testing as per IS: 2633 for uniformity of coating. The zinc coating shall be free from defects.

For Roof drainage and building sanitation works following type of pipe are covered in this Section:

a) Cast Iron pipe



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 197 of 361

- b) Steel pipe (lined, coated with bituminous composition, out coated with cement concrete or mortar or galvanized)
- c) Concrete pipe
- d) Asbestos cement pipe
- e) PVC pipe
- f) Stoneware pipe
- g) Vitrified pipe
- h) Lead pipe (not to be used for portable water)

2.02.01

Fixtures

All material, fittings, fixtures, appliances, accessories shall be of approved quality and shall be procured from reputed brands like Hindustan/Pasriware/Cera or equivalent or as approved by Engineer. The bidder shall procure the fixtures from the above named reputed manufacturers and shall mention in his bid the type & make of the fixtures he intends to use.

All items brought to the site must bear the manufacturer's identification mark. Procurements shall be made well in advance and should get inspected & approved immediately by the Engineer. All fixtures shall be adequately protected, covered, and plugged till handing over.

All fittings, gratings, fasteners, unless specified otherwise, shall be chromium plated. The chromium plating shall be of grade-2 (10micron thickness) confirming to IS: 4827. Powder coating shall be of approved colour and shall have minimum thickness (DFT) of 20micron. Stainless steel accessories shall be of grade SS-304 and from reputed manufacturer (like Salem Steel) and shall be polished bright finish.

Unless specified in the contract the fixtures shall be as specified hereinafter.

Water closet

a) European type

It shall consist of European type glazed vitreous china basin (confirming to IS: 2556, part-II), with siphon open front solid plastic seat and plastic cover, low level glazed stoneware flushing cistern with valve less fittings, supply connections and necessary fittings. All fittings shall be chromium plated. Colour of basin, cistern, seat and cover shall be as approved by the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 198 of 361

b) Squatting type

It shall consist of Orissa pattern glazed vitreous china squatting pan with integral foot rests (confirming to IS:2556, part-III) and high level cast iron flushing cistern with valve less fittings, supply connections and necessary fittings. All fittings shall be chromium plated. The flushing cistern shall be painted as specified by the Engineer.

Urinals

It shall consist of wall type glazed vitreous china urinals (conforming to IS:2556), cast iron automatic flushing cistern complete with supply connections, flush pipe, lead pipes, gratings, traps and all other necessary fittings. Frequency of automatic flushing shall be approximately once every five minutes. For every four urinals (maximum) located together may be served by one cistern of adequately capacity. All fittings shall be chromium plated.

Wash Basin

It shall be made of glazed vitreous china conforming to IS:2556, part-IV. The basin shall be flat back, wall hung by painted cast-iron brackets and complete with hot and cold CP brass faucets with nylon washers, PVC connection pipe with CP brass nuts, CP brass chain with rubber plug, 32mm dia. Chromium plated brass waste of standard pattern, 32mm dia. CP brass trap union complete with necessary fittings.

Sink

It shall be made of glazed vitreous china conforming to IS:2556, part-V. It shall be wall hung by painted cast iron brackets and complete with one CP brass faucet with nylon washers, PVC connection pipe with CP brass nuts, CP brass chain with rubber plug, 40mm dia. chromium plated brass waste of standard pattern, 40mm dia. CP brass trap union complete with necessary fittings.

Bathroom mirror

It shall be made of the best quality 6 mm thick glass and produced by a reputed mirror manufacturer. It shall be wall mounted with adjustable revolving brackets. The brackets, screws, and other fittings shall be chromium plated.

Glass shelves

Class shelves shall consist of 6 mm thick clear glass with guardrails and shall be wall mounted with brackets. All brackets, guardrails, and screws shall be



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 199 of 361

chromium plated.

Towel rail

Towel rails shall be 20 mm dia chromium plated MS pipes wall mounted with steel brackets. The brackets, screws etc. shall also be chromium plated.

Soap holder

It shall be made of chromium plated strong members. The holders shall be wall mounted with chromium-plated screws.

Liquid Soap Dispenser

It shall be round and easily revolving with removable threaded nozzle. The body, bracket for wall mounting and screws shall be chromium plated.

Toilet roll holder

It shall be made of glazed vitreous china with suitable cover cum cutter. Wall mounting screw shall be chromium plated.

Valve, cocks, Taps

All valves, stop cocks, taps etc. shall conform to relevant Indian standard specification and shall be of best quality from approved manufacturers. These shall be suitable for normal working pressures. Nominal size and material shall be as required / specified.

2.03.00 Water Storage Tank

Water storage tank shall be PVC of approved brand and make (Syntex or equivalent). Reservoirs made of concrete masonry or fabricated steel shall be covered by respective work specifications.

3.00.00 INSTALLATION

3.01.00 General

Basic layouts may be available in the drawings provided, the details might have to be supplemented by the Contractor and get the approval of the Engineer before installation. Special attention shall be given to economise the layout. Symmetry of layout is very important. Fittings meant for operation shall be located and oriented to allow easy reach and operation. Maintenance, repairs, and replacements of pipes, fittings, and fixtures must be conveniently possible. All pipe lines, locations of fittings and fixtures, etc. shall be as per drawings or as directed by the Engineer. Correctness of lines, plumb, orientation, symmetry, and levels shall be strictly ensured. All items shall be



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 200 of 361

fully secured against movement in any direction and so located as to allow easy maintenance.

All pipelines, fittings, and fixtures shall be installed leak proof. When the works under scope of this specification linked up with works executed by others, the connections shall be such as to prevent any splashing or spilling or emission of foul odour and gases.

3.02.00 Portable water supply Pipe Lines

3.02.01 Laying

In addition to fulfilling the functional requirements all pipelines shall be laid true to line, plumb and level and shall run on the surface of the walls, ceiling or in chases. Any deviation shall need approval of the Engineer. Meticulous care shall be taken to avoid chances of airlock and water hammer.

Pipes shall be laid on continuous unyielding surface or on reliable supports at least one near each joint and spacing as directed by the Engineer. The support must be strong, neat and shall have provisions for securing the pipes in every direction and easy maintenance. All pipes used for water supply should be thoroughly and efficiently disinfected before taken in to use.

3.02.02 Back Flow

The layout of pipe work shall be such that there is no possibility of back flow towards the source of supply from any cistern or appliances, whether by siphonage or otherwise. All pipe works shall be so laid or fixed and maintained as to be and to remain completely watertight, thereby avoiding waste of water, damage of property and the risk of contamination of the water conveyed.

3.02.03 Contamination

There shall be no cross connection whatsoever between a pipe/fitting for conveying or containing wholesome water and a pipe/fitting for containing impure water or water liable to contamination or of uncertain quality of water which has been used for any other purpose. No piping shall be laid or fixed so as to pass into or through any sewer, scour outlet or drain or any manhole connected therewith.

3.02.04 Underground Piping

Underground piping shall be laid at such a depth that it is not likely to be damaged by traffic and other loads and frost, where applicable. The size and depth of the trench shall be as approved by the Engineer. Back filling shall be done with selected fine earth, unless otherwise permitted, in 150 mm layers and carefully consolidated. Special care shall be taken while filling in the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 201 of 361

vicinity of the pipe to avoid damage. Before backfilling, the laid pipe shall be fully tested and approved.

Where the pipe rests on rock it may be bedded on a layer of fine selected material or concrete to avoid local point support. The trench shall be so treated by gradient and filling in the area that it does not act as a drainage channel.

3.02.05 Concealed Piping

Where desired by the Engineer or shown on the drawings the pipes shall be concealed in masonry or concrete of the structure. The Contractor may co-ordinate with the building Contractor for leaving the chases, openings, and conduits as necessary. However, the Contractor will rectify if required the chases, openings, and conduits, supplement and make good after laying and testing of the concealed pipelines.

3.02.06 Jointing of Pipes

All G.I. pipes shall be properly thread/weld jointed and made completely water tight and durable. Burr from the joints shall be removed after screwing. Union joints shall be provided for all required location to facilitate maintenance.

3.02.07 Painting

Where required, underground G.I. pipes shall be given 2 coats of bituminous paint on the outside after laying. When painting is to be done above ground G.I. pipes shall be given one coat of red lead or zinc chromate primer and top coats shall be minimum 2 coats of best quality paint as specified.

3.03.00 RAINWATER DOWN COMERS

3.03.01 Pipes

Rainwater down comers shall be standard Cast Iron or Heavy duty PVC/GI. In case where specifically desired, M.S. pipes may also be used. M.S. pipes shall be painted outside with two coats of anticorrosive paints under a coat of primer.

Rainwater down comers shall run along and be secured to walls, columns etc. Where desired by the Engineer these may have to be installed in chases cut in the structure. All pipes shall be well secured and supported by adequately strong brackets. The brackets may be wrought iron clevis type, split ring type, or perforated strap iron type as approved by the Engineer. For vertical runs each pipe shall hang freely on its brackets fixed just below the socket. Suitable spacer blocks shall be provided against the vertical surface to which the pipe is fixed.

All bends and junctions shall be supplied with watertight cleanouts.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 202 of 361

Roof and floor drains and yard gullies shall be installed, if required, by cutting into the structure and grouted with 1:2:4 cement concrete. All gutters shall be provided with removable gratings.

All horizontal pipes shall have a minimum fall of 1 in 100.

3.03.02 Khurras

The khurras shall be constructed before the work in parapet wall is taken up and it shall be 45x45 cm in size, unless otherwise specified and shall be formed of cement concrete of M-20 grade.

3.03.03 Gutters

The gutters shall be made of G.I. or A.C and procured from reputed specialised manufacturers. Each section shall be sufficiently rigid, edges and corners straight and the slopes perfectly uniform. G.I. gutters shall have the edges strengthened by suitable means.

Unless noted otherwise the gutters shall have a minimum fall of 1 in 120. Adequate number of string supports shall be provided so that there is no sagging even when the gutter is full. Each joint must have a support. Unless otherwise specified the supports shall be fabricated M.S. brackets. All junctions shall be thoroughly watertight. The joints may be made by riveting, bolting or soldering. All joints between successive lengths of gutters shall have an overlap of at least 5 cm. The drop in the overlap shall always be in the direction of the fall of the gutter. Ends of gutters shall be closed watertight. Junction with rainwater down comers shall be made fully watertight and secured.

3.04.00 SOIL AND DRAINAGE PIPES

3.04.01 Gradients

If not specified the minimum gradients of soil and drainage pipeline shall be as follows:

100 mm nominal dia	:	1 in 35
150 mm nominal dia	:	1 in 65
230 mm nominal dia	:	1 in 120
300 mm nominal dia	:	1 in 200

3.04.02 Relation with water supply pipelines

Unless specifically cleared by the Engineer, under no circumstances shall drainage and sewer pipes be allowed to come close to water supply pipelines.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 203 of 361

3.04.03 Laying

Each separate pipe shall be individually set for line and for level. Where lengths of sewer or drain pipes are laid in trench, properly painted sight rails shall be fixed across the trench at a height, equal to length of the boning rod to be used, above the required invert level of the drain or sewer at the point where the sight is fixed. More sight rails shall be required at manholes, change of gradient and intermediate positions if the distance for sighting is more than 50 ft. apart. The excavation shall be boned in at least once in every 6 ft. The foot of the boning rod shall be set on a block of wood of the exact, thickness of the wall of the pipe. Each pipe shall be separately and accurately boned between sight rails.

3.03.04 Support and Protection of Pipelines

All pipes shall be laid with sockets leading uphill. Preferably the pipe shall rest on solid and even foundations for the full length of the barrel. However, the pipe manufacturer's instruction as approved by the Engineer shall be followed in the matter of support and jointing.

To achieve full and continuous support, concrete for bedding and packing is the best. Where pipes are not bedded on concrete, the floor shall be left slightly high and carefully placed so that the pipe barrels rest on undisturbed ground. If anywhere the excavation has been carried too low packing shall be done in concrete. Where laid on rock or very hard ground which cannot be easily excavated to a smooth surface, the pipes shall be laid on a cradle of fine concrete floor of gravel and crushed stone over laid with concrete or on a well consolidated gravel and crushed stone bed as desired by the Engineer. PVC or similar pipes shall be laid directly on stable soil and packed with selected soil.

The minimum support and protection for glazed stoneware pipes shall be as follows:

- a) When cover is less than 2 metre below ground level and where pipes are unavoidably exposed above ground surface, the pipes shall be completely encased or surrounded with concrete.
- b) Where pipes are laid on soft soil with the maximum water table laying at the invert of the pipe, the sewer shall be bedded on concrete.
- c) Where the pipes have to be laid on soft soil with the maximum water table rising above the invert of the pipe, but below the top of the barrel, the pipe sewer shall be haunched.
- d) Where maximum water table is likely to rise above the top of the barrel or wherever the pipe is laid on soft soil the pipe sewers shall be completely encased or surrounded with concrete.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 204 of 361

Vitrified clay pipes shall be laid on a bed of 150 mm thick cement concrete (1:3:6) nominal mix by volume.

Cast iron pipes and concrete pipes may be supported on suitable concrete or brick support, where specified. The supports shall be unyielding and strong enough. At least one support shall be located close to ends. Spacing of intermediate supports shall be as decided by the Engineer. Pipes shall be secured to the supports by approved means.

Anchoring of pipes where necessary shall be achieved by suitable concrete encasing designed for the expected thrust.

3.03.05 Entry into structures

For entry of the pipe lines into any building or structure suitable conduits under the structure or sleeves shall be used. The conduits and sleeves shall be such as to allow easy repairs and replacement of the pipes. When openings or chases are required to be made in the structure for entry of pipelines, locations and sizes shall be marked and checked by the Engineer. After laying of the pipeline the openings and chases shall be mended.

3.03.06 Ducts

Where solid, waste and ventilating pipes are accommodated in ducts, access to cleaning areas shall be provided. Connection to drain shall be through a gully with sealed cover to guard against ingress of sewer gas, vermin, or backflow.

3.03.07 Traps and Ventilating Pipes

Pipes are carrying off the waste from water closets and waste water and overflow water from baths, wash basins, sinks to drains shall be trapped immediately beneath such fixtures. Traps shall have minimum water seal of 50 mm and shall be ventilated whenever such ventilation is necessary to maintain water seal of the trap. Ventilating pipes shall be carried up vertically from the drain to a height of at least 600 mm above the outer covering of the roof of the building or as shown on drawings. All vertical ventilating, anti-siphonage and similar pipe shall be covered on top with a cowl. The cowl shall be made of C. I. unless desired otherwise by the Engineer.

3.03.08 Manhole & Inspection Chambers

At every change of alignment, gradient or diameter there shall be a manhole or inspection chamber. The maximum distance between manholes shall be 30 meter unless specially permitted otherwise. However, for truck route (for pipes above 900 mm dia.) this distance can be increased to 45 M. The distance between manhole or inspection chamber and gully chamber shall not exceed 6 metres unless desired otherwise provision of IS: 4111 (Part-1) shall be followed for construction of a manhole. Manhole shall be constructed so as to



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 205 of 361

be watertight under test. The change in alignment shall be carried out in such a manner as to provide no lodgement for any splashing in case of accidental flashing of the chamber. The channel or drain at the bottom of chamber shall be plastered with 1:2 cement, sand mortar and finished smooth to the grade. The channels and drains shall be shaped and laid to provide smooth flow.

Unless otherwise specified, 560 mm dia. circular cast iron manhole cover with frame, heavy-duty, conforming to IS: 1726 shall be provided. The covers shall be close fittings so as to prevent gases from coming out.

3.03.09 Cutting of Pipes

Manufacturer's instructions shall be followed for cutting of pipes where necessary. Suitable and approved tools shall be used for the cutting so as to leave surface clean and square to the axis of the pipe.

3.03.10 Jointing

Jointing of pipes shall be so planned as to avoid completely any movement or strain to the joints already made. If any joint is suspected to be damaged it shall be opened out and redone.

All joints between pipes, pipes and fittings and manholes shall be gas-tight when above ground and watertight when underground. Method of jointing shall be as per instructions of the pipe and fittings manufacturer and as approved by the Engineer. However, in the absence of any instruction available from the manufacturer the methods as detailed hereunder shall be used.

a) Cast Iron Pipes

Socket and spigot pipes shall be jointed by the cast lead joints. The spigot shall be centred in the socket of the pipe by tightly caulking in sufficient turns of tarred gasket or hemp yarn to have unfilled half the depth of socket. When the gasket or hemp yarn has been caulked tightly a jointing shall be placed round the barrel and tightened against the face of the socket to prevent airlock. Molten lead shall then be poured in to fill the remainder of the socket and caulked with suitable tools right round the joint to make up for shrinkage of the molten metal on cooling and shall be finished 3 mm behind the socket face.

Joints in cast iron pipes with special jointing arrangements like 'Tyton' Joints etc. shall follow the instructions of the manufactures.

In special cases if flanged joints are accepted by the Engineer the joints shall be made leak proof by inserting approved type of rubber gaskets. The bolts shall be secured in stages to avoid uneven strain.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 206 of 361

b) Concrete Pipes

Jointing of concrete pipes shall be generally of rigid type. Unless otherwise stated collar type joint shall be provided. IS: 783 shall be followed for general guidance.

The two adjoining pipes shall be butted against each other and adjoined in correct position. The collar shall then be slipped over the joint, covering equally both the pipes. The angular space shall be filled with stiff mixture of cement mortar 1:2 (1 cement : 2 sand) which shall be rammed with caulking tool. After a day's work, any extraneous material shall be removed from the inside of the pipe and the newly made joint shall be cured for 7 days.

c) Glazed Stoneware Pipes

Tarred gasket or hemp yarn soaked in thick cement slurry shall first be placed round the spigot of each pipe and the spigot shall then be placed into the socket of the pipe previously laid. The pipe shall then be adjusted and fixed in the correct position and the gasket caulked tightly so as not to fill more than 1/4 of the total depth of the socket. The remainder of the socket shall be filled with a stiff mixture of cement mortar 1:1 (1 cement : 1 sand). A fillet shall be formed round the joint with a trowel, forming an angle of 45 deg. with the barrel of the pipe. The newly made joints shall be protected, until set and shall be cured by covering with damp cloth or other suitable materials.

d) Vitrified clay pipes

The vitrified clay pipe shall be made from refractory clay mixed with crushed pottery and stone and burnt at a high temperature. These shall be hard, compact, and glazed to make them acid resistant and impervious, and shall be obtained from approved manufacturer.

Special care shall be taken in handling these pipes. The pipes shall not be jointed until the earth has been partly refilled over the portion of the pipe between the joint holes. Before laying the second pipe, the socket of the first pipe laid shall be thinly painted all round on the inside with cement slurry (1 part of cement and 2 parts of clean, sharp sand). A ring of rope yarn (closely twisted hemp or jute) dipped in neat cement paste or tar or bitumen, shall be inserted in the socket of pipe and driven home with caulking tools. The rope shall fully encircle the spigot with a slight overlap and shall not occupy more than one-fourth of the total depth of the socket. Where the spigot end of the pipe is made for receiving the gasket, it shall be wrapped with two or three turns of tarred spun, as close to the end as possible, before inserting into the socket. The joint shall then be completely filled with cement mortar (1:1), which shall have very little water. A fillet shall be formed round the joint with trowel, forming an



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 207 of 361

angle of 45 degrees with the outside pipe. Special care shall be taken so that any excess mortar etc. left inside the pipe joints is neatly cleaned off immediately after each joint is made. A semi-circular wooden scrapper or a rubber disc to which a long handle is fixed could be used for this purpose.

e) Lead Pipes

The joints in lead pipes shall be made as wiped solder joint. The minimum and the maximum length of the wiped solder joints shall be 8 cm. and 9 cm. respectively. The solders shall generally consist of two parts of lead and one part of tin.

f) Polyethylene Pipes

The joints shall be thermo welded or bolted as per manufacturer's instructions.

g) Jointing Cast Iron Pipes with Stoneware Pipes

Where any cast iron drain pipe, ventilating pipe or trap is connected with a stoneware or semi-vitrified waste pipe, the beaded spigot end of such cast iron drain pipe, waste or ventilating pipe or trap shall be inserted into a socket of such stoneware pipe and the joint made with mortar consisting of one part of cement and one part of clean sand after placing a ratted gasket or hemp yarn soaked in neat cement slurry round the joint and inserted in it by means of a caulking tool.

h) Jointing Stoneware with Cast Iron Pipes

Where any water closet pan or earthware trap connected to such a pan is to be jointed with a cast iron soil pipe, the joint between the stoneware spigot and the cast iron socket shall always be of a flexible nature. Such joint shall be made with a mixture of bitumen and chopped asbestos fibre.

3.04.11 Trenches and other excavations

Width of the trench at the bottom shall be such as to provide 200 mm clearance on either side of the pipe for facility of laying and jointing.

Excavated material shall be stacked sufficiently away from the edge of the trench and the side of the spoil bank shall not be allowed to endanger the stability of the excavation. Spoil may be carted away and used for filling the trench behind the work.

Turf, top soil or other surface material shall be set aside, turf being carefully rolled and stacked for use in reinstatement.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 208 of 361

All excavation shall be properly timbered, where necessary.

Efficient arrangements for dewatering during excavation and keeping it dry till backfilling shall be made to the satisfaction of the Engineer. Sumps for dewatering shall be located away from the pipe layout.

Where the excavation proceeds through roads necessary permissions shall be secured by the Contractors from the appropriate authorities.

Special care shall be taken not to damage underground services, cables etc. These when exposed shall be kept adequately supported till the trench is backfilled.

The backfilling shall be done only after the pipeline has been tested and approved by the Engineer. Special care shall be taken under and sides of the pipe during hand packing with selected material. At least 300 mm over the pipe shall also be filled with soft earth or sand. Consolidation shall be done in 150 mm layers. The surface water shall be prevented from getting into the filled up trench. Traffic shall not be inconvenienced by heaping up unduly the backfilling material to compensate future settlement. All future settlements shall be made good regularly to minimize inconvenience of traffic where applicable.

3.04.12 Protection

Open end of each pipe shall be protected during installation by suitable covers or plugs so that the ends, threads, sockets, or spigot are not damaged and no foreign material can find its way into the pipeline. Fittings and fixtures liable to be misused or stolen during the construction phase shall be fitted only before testing and handing over.

3.05.00 Water Storage Tanks

Overhead/loft type water storage tank shall be made of PVC. These tanks shall be provided for each toilet block and placed on the roof/loft of the building. Tank shall be installed with proper supports and anchorage for applicable wind and seismic condition. Installation of tank shall be carried out according to the recommendation of IS: 12701. These tanks shall rest preferable on flat surface so as to distribute the load evenly. The tank shall be leakproof and water tight.

The outlet pipe shall be 50 mm above the bottom of the tank and provided preferably with strainers. The wash out or draining pipe shall be connected at the lowest point and flush with bottom of tank.

Tank shall be provided with all fittings for inlet, outlet, overflow pipes and ball valves.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 209 of 361

3.06.00 SEPTIC TANK AND EFFLUENT DISPOSAL

3.06.01 Septic tank

Septic tank shall consist of the tank itself with inlet and outlets there from complete with all necessary earthwork and backfilling. The details of septic tank shall be as shown on drawings. This item shall also include ventilating pipe of at least 100 mm dia whose top shall be provided with a suitable mosquito proof wiremesh and cowl. Ventilating pipe shall extend to a height of about 2 meter when the septic tank is at least 15 meter away from the nearest building and to a height of 2 meter above the top of building when it is located closer than 15 meter. Ventilating pipes can be connected to the normal soil ventilating system of the building where allowed.

3.06.02 Effluent Disposal

The effluent from the septic tank shall be disposed by allowing it into an open channel or a body of water if the concerned authority approves or into a soak pit for absorption by soil or shall be allowed to be absorbed by soil through open jointed SW pipes laid in a trench filled with broken bricks.

3.06.03 Soak pit

The soak pit shall be complete. It shall consist of a 900 mm dia pit 1000 mm in depth below the invert level of the inlet pipe. The pit shall be lined with stone; brick or concrete blocks set in cement mortar (1:6) and filled with brickbats. Inlet pipe shall be taken down to a depth of 900 mm from the top as an anti-mosquito measure.

3.06.04 Open jointed SW Pipe/dispersion trenches

Minimum dia of the SW pipes shall be 150 mm nominal. The trench for laying the pipes shall be a minimum 600 x 600 mm. The joints of the pipes shall be left unsealed. The entire length of the pipe within the trench shall be buried in a 250 mm layer gravel or crushed stone of uniform size. On top of gravel/crushed stone layer is a 150 mm bed of well-graded coarse aggregate. Ordinary soil is used for filling the top of trench.

3.06.05 Commissioning septic tank

After the septic tank has been proved watertight and the sewage system is checked the tank shall be filled with water to its outlet level before the sewage is let into the tank. It shall be seeded with well digested sludge obtained from septic tank or sludge digestion tank. In the absence of digested sludge a small quantity of decaying organic matter such as digested cow-dung may be introduced.

3.07.00 Related Works



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 210 of 361

All works, like earthwork, masonry, concrete, steelwork, cutting holes, chases, repairs and rectification associated directly with installation of water supply and sanitation systems shall come under scope of the Contractor unless specifically excluded. These works are not detailed out in this Section.

3.08.00 Regulation

The work which is required to be carried out under this section, shall be executed by a licensed Plumber only (engaged by the Contractor) and he shall obtain all necessary sanctions, permissions, certificates etc., from Municipal and/or other Local Authorities and shall abide by all the rules of such Authorities.

4.00.00 TESTING AND ACCEPTANCE CRITERIA

4.01.00 Inspection Before installation

All pipes, fittings, and appliance shall be inspected, before delivery at the site to see whether they conform to accepted standards. The pipes and fittings shall be inspected on site before laying and shall be sounded to disclose cracks. Any defective items shall be clearly marked as rejected and forthwith removed from the site.

4.02.00 Testing of Water Supply pipe line

4.02.01 Testing of Mains After Laying

After laying and jointing, the main shall be slowly and carefully charged with water, so that all air is expelled from the main by providing a 25 mm inlet with a stop-cock, allowed to stand full of water for a few days if time permits, and then tested under pressure. The test pressure shall be 5 Kg/sq.cm or double the maximum working pressure, whichever is greater. The pressure shall be applied by means of a manually operated test pump, or in the case of long mains or mains of a large diameter, by a power driven test pump, provided that the pump is not left unattached. In either case due precaution shall be taken to ensure that the required test pressure is not exceeded. Pressure gauges shall be accurate and shall preferably have been recalibrated before the test. The pump having been stopped, the test pressure shall maintain itself without measurable less for at least five minutes. The end of the main shall be closed by fitting a watertight expanding plug and the plug shall be secured by struts to resist the end thrust of the water pressure in the mains.

4.02.02 Testing of Service Pipes and Fittings

The service pipes shall be slowly and carefully charged with water allowing all air to escape avoiding all shock or water hammer. The service pipe shall then be inspected under working conditions of pressure and flow. When all draw-off taps are closed, the service pipes shall be absolutely watertight. All piping, fittings, and appliances shall be checked for satisfactory support and



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 211 of 361

protection from damage, corrosion, and frost.

4.03.00 Testing of Drain and Sewerage Pipelines

All soil pipes, waste pipes, ventilating pipes and all other pipes, when above ground, shall be gas tight. All sewers and drainpipes laid below ground shall be tested water tight. The method of actual tests shall be decided by the Engineer. All test data shall be recorded and submitted to the Engineer for review and instruction. The Engineer's discretion regarding tolerance shall be final.

General guidance for the tests are given below:



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 212 of 361

a) Smoke test

All soil pipes, waste pipes and vent pipes and all other pipes when above ground shall be approved gastight by a smoke test conducted under a pressure of 25 mm of water and maintained for 15 minutes after all trap seals have been filled with water. The smoke is produced by burning oily waste or tarpaper or similar material in the combustion chamber of a smoke machine. Chemical smokes shall not be used.

b) Water test

The pipes shall be subjected to a test pressure of at least 1.5 m head of water at the highest point of the section under tests. The tolerance figure of two litres per centimetre of diameter per kilometre may be allowed during a period of 10 (ten) minutes. The test shall be carried out by suitably plugging the low end of the drain and the ends of connections, if any, and filling the system, with water. A knuckle bend shall be temporarily jointed in at the top end and a sufficient length of the vertical pipe jointed to it so as to provide the required test head or the top end may be plugged with a connection to a hose ending in a funnel which could be raised or lowered till the required head is obtained and fixed suitably for observation.

Subsidence of test water may be due to one or more of the following cases:

- a) Absorption by pipes and joints
- b) Sweating of pipes or joints
- c) Leakage at joints or from defective pipes
- d) Trapped air.

Allowance shall be made for (a) by adding water until absorption has ceased and after which the test proper should commence. Any leakage and the defective part of the work shall be cut out and made good.

c) For straightness

- i) By inserting at the high end of the sewer or drain a smooth ball of a diameter 13 mm less than the pipe bore. In the absence of obstruction, such as yarn or mortar projecting through the joints, the ball will roll down the invert of the pipe and emerge at the lower end; and
- ii) By means of a mirror at one end of the line and lamp at the other. If the pipeline is straight, the full circle of light may be observed. The mirror will also indicate obstruction in the barrel if the pipeline is not straight.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 213 of 361

4.04.00 Fittings and Fixtures etc.

All fittings and fixtures shall be connected by water tight joints. No dripping of water shall be acceptable.

4.05.00 Testing Septic Tank

The septic tank shall be tested for water tightness. It shall be filled up with water and allowed to soak for 24 hours. Then, it shall be topped up and allowed to stand again for 24 hours and loss of level recorded. The fall shall not be more than 15 mm in 24 hrs.

5.00.00 I.S. CODES

Important relevant IS Codes for this specification are listed below:

Latest editions shall always be consulted.

- | | | |
|--------------------------|---|---|
| IS: 404 | : | Lead pipes. |
| IS: 407 | : | Brass tubes for general purposes. |
| IS: 458 | : | Concrete pipes (with or without reinforcement) |
| IS: 783 | : | Code of Practice for laying of concrete pipes. |
| IS: 1172 | : | Code of basic requirements for water supply, drainage and sanitation. |
| IS: 1200
(Pt.XVI) | : | Laying of water and sewer lines, including appurtenant items. |
| IS: 1230 | : | Cast iron rain water pipes and fittings. |
| IS: 1239
(Pt.I & III) | : | Specification for Mild Steel Tubes and Mild Steel Tubulars and other wrought steel pipe fittings (10 mm to 15 mm nominal diameter). |
| IS: 1536 | : | Specification for centrifugally cast (Spun) iron pressure pipes for water gas and sewage. |
| IS: 1537 | : | Specification for vertically cast iron pressure pipes for water, gas and sewage. |
| IS: 1592 | : | Asbestos cement pressure pipes, |
| IS: 1626 | : | Asbestos cement pressure pipes, gutters and fittings (Spigot and Socket types). |



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 214 of 361

- IS: 2065 : Code of Practice for Water Supply in buildings.
- IS: 2501 : Copper tubes for general engineering purposes.
- IS: 2556 : Specification for vitreous sanitary appliances (vitreous china) Part – I - General requirement
- IS: 2633 : Method of testing, uniformity of coating on zinc coated articles.
- IS: 3076 : Low density polyethylene pipes for portable water supplies.
- IS: 3486 : Specification for Cast iron spigot and socket drain pipes (80 mm to 250 mm nominal diameter).
- IS: 3589 : Specification for Electrically welded steel pipe for water, gas and sewage (200 mm to 2000 mm nominal diameter).
- IS: 4827 : Specification for electro plated coatings of nickel and chromium on copper and copper alloy.
- IS: 4964 : High-density polyethylene pipes for portable water supplies.
- IS: 12701 : Rotational moulded polyethylene water storage tanks

6.00.00 RATE AND MEASUREMENT

6.01.00 RATE

6.01.01 G.I. Pipes For Water Supply

Rate shall include providing and fixing of the pipes including all specials and fittings, such as tees, bands, elbows, clamps, drain heads, cleanouts etc. with cutting, making chases and jointing of pipes, making good the walls.

6.01.02 Rainwater Down-comers

Rate shall include providing and fixing of the pipes including all specials and fittings, such as tees, bands, elbows, clamps, drain heads, cleanouts etc. The rate also include cost of jointing and making good the opening in structure.

6.01.03 Sanitary Fixtures



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 215 of 361

Rate shall include providing and fixing of sanitary appliances & fixtures and at all elevation, including all accessories and fittings, connections pipes, waste trap and pipes all complete as per description of "Schedule of Items". Rate shall also include the jointing of waste & traps to drain pipes.

6.01.04 Drainage and Sewer Pipes

Rate shall be inclusive of providing, laying and jointing of pipes as specified. Rate also include cost of lead joints or other joint as specified, cost for painting and cutting and making good walls, floors etc.

6.01.05 Floor and Gully Traps

Rate of traps is inclusive of all excavation, filling, repair, making good of opening in floor and walls, grating, painting etc. complete as described in "Schedule of Items".

6.01.06 Manholes, Septic Tank, Soak Pit and Cover

Rate of manholes, septic tank, soak pit shall be paid under respective items of work executed like brick work, plastering, concrete, reinforcement steel etc. provided for completion of the structure as per drawing and specifications. Manhole cover shall be paid separately as per description of item.

6.01.07 Water Storage Tank

The rate for water storage tank is inclusive of supply and installation of tank with all fittings, inlets, outlets, valves etc. complete.

6.02.00 Measurements

6.02.01 Pipe for Water Supply and Drainage

For G.I. Pipe of water supply line, rainwater down comers, drainage and sewer pipe, the measurements shall be in running metres and shall be taken along centre line of pipe or specials.

The pipe shall be measured separately according to dia. and class of pipe.

Fixtures like bibcock, stopcocks, valves etc. shall be measured in numbers.

6.02.02 Sanitary Appliances & Fixtures and Allied Works

All sanitary appliances & fixtures like sink, washbasin, WC, shall be measured in numbers for the complete work as described in schedule of items.

Floor and gully traps shall be measured in numbers unless otherwise specified.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 216 of 361`

Water storage tank shall be measured in numbers for the capacity as specified in "Schedule of Items".

The item of work executed for completion of manholes, septic tank & soak pit shall be measured in respective items of work like brick work, RCC, plastering etc. CI cover shall be measured in numbers as specified in "Schedule of Items".



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 217 of 361`

SECTION - D

SUB-SECTION – D16

ROADS AND DRAINAGE



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 218 of 361

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	CODES AND STANDARDS
3.00.0	EXECUTION
4.00.00	TESTING AND ACCEPTANCE CRITERIA



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 219 of 361

Road And Drainage

1.00.00 Scope

The scope include all works required for the construction of road including construction of embankment, sub-base course, base course, tack coat, bituminous macadam, wearing course, liquid seal coat, shoulder and all incidental items of work specified or not shown but reasonably implied or necessary for the completion of the work etc.

The scope also include all works required for the construction of drainage including construction of road side drains, RCC culverts, pipe culverts, drainage pipes, manholes and all other incidental items necessary for the completion of the work etc.

1.01.00 Works To Be Provided By The Contractor

The works to be provided by the contractor unless specified otherwise shall include but not be limited to the following.

- a) Construction of roads including providing all materials, labour, supervision, services, equipments, tools and plants, transportation etc all required for the completion of the work.
- b) Submission of detailed scheme of all operations required for executing the work (e.g. material handling, placement, services, approaches etc) to the engineer for approval.
- c) Carrying out tests whenever required by the engineer to assess the quality of work and submission of the test results to the engineer after completion of the same etc.

1.02.00 Work To Be Provided By Others

No work under this specification will be provided for by any agency other than the contractor unless specifically mentioned elsewhere in the contract.

1.03.00 Conformity With Designs

The contractor shall carryout the work as per the construction drawings, specification and as directed by the engineer.

1.04.00 Materials To Be Used

All materials required for the work shall be the best commercial variety and as approved by the engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 220 of 361

2.00.00

Codes and Standards

All works under this specification shall conform to the latest revision and/or replacement of the following or any other IRC/IS Codes and Standard Practices unless specified otherwise.

- a) Specification for road and bridge works of Ministry of Shipping & Transport (Road Wing) Published by the IRC
- b) IRC: 19 - Standard specification and code of practice for Water bound Macadam
- c) IRC :SP 11 - Hand Book of Quality Control for Construction of Roads and Runways
- d) IS:456 - Indian Standard Code of Practice for Plain and Reinforced Concrete.
- e) IS:2212 - Code of Practice for Brick work
- f) IS: 783 - Code of Practice for Laying of Concrete Pipes
- g) IS: 1201 - Methods of testing tar and bituminous materials to 1220
- h) IS: 73 - Specification for paving bitumen
- i) IS: 215 - Specification for Road tar
- j) IS: 216 - Coal tar pitch
- k) IS: 217 - Specification for cut-back bitumen
- l) IS: 454 - Specification for cut-back bitumen from waxy crude
- m) IS: 1834 - Specification for hot applied sealing compound for joint in concrete
- n) IS: 1838 - Specification for performed fillers for expansion joints in concrete, non extruding and resilient type
Part I Bitumen impregnated fibre
Part II CNSL Aldehyde resin and coconut pith
- o) IS : 334 - Glossary of terms relating to bitumen and tar
- p) IS: 1077 - Common burnt clay building bricks.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 221 of 361

q) IS : 3117 - Specification for bitumen emulsion roads (anionic type).

r) Other specifications mentioned elsewhere in this specification.

In case any particular aspect of work is not covered specifically by the specification/Indian Standard Code of practices, any other standard practice as may be specified by the engineer shall be followed.

2.01.00

Quality Control

The Contractor shall establish and maintain quality control for all materials, procedures, workmanship and equipments used. All works shall conform to the lines, grades, cross sections and dimensions shown on the drawings, specification and as directed by the engineer. Permitted tolerances for road works are described hereinafter.

a) Horizontal Alignment

Horizontal alignment shall be reckoned with respect to the centre line of the carriageway as shown on the drawings. The edges of the carriageway as constructed shall be correct within a tolerance of ± 25 mm therefrom. The corresponding tolerance for edges of the roadway and lower layers of the pavement shall be ± 40 mm.

b) Longitudinal Profile

The finished levels of the sub-grade and different pavement courses as constructed shall not vary from those calculated with reference to the longitudinal and cross-profile of the road shown on the drawings or as directed by the engineer and shall not exceed the tolerances as mentioned below.

Sub-grade ± 25 mm

Sub-base ± 20 mm

Base course ± 15 mm

Wearing course ± 10 mm

Tolerance in wearing course shall not be permitted in conjunction with the positive tolerance on base course if the thickness of the wearing course is thereby reduced by more than 6 mm.

c) Surface Regularity of Sub-grade and Pavement Courses

The surface regularity of the completed sub-base, base course and wearing surfaces in the longitudinal and transverse directions shall be within the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 222 of 361

tolerances indicated in Table - I. The longitudinal profile shall be checked with a 3m long straight edge at the middle of each traffic lane along a line parallel to the centre of the road. The transverse profile shall be checked with a set of three camber boards at intervals of 10m.

TABLE –I

PERMITTED TOLERANCE OF SURFACE REGULARITY FOR PAVEMENT COURSES

Sl. No.	Type of Construction	Longitudinal profile with 3m straight edge					Cross Profile
		Maximum permissible Undulation (mm)	Maximum number of undulations permitted in any 300m length with undulation exceeding (mm)				Maximum permissible variation from specified profile under camber template (mm)
			18	12	10	6	
1	2	3	4	5	6	7	8
1.	Earthen sub-grade	25	30	-	-	-	15
2.	Granular sub-base	15	-	30	-	-	12
3.	Water Bound Macadam with oversize metal (40-90 mm size)	15	-	30	-	-	12
4.	Water Bound Macadam with normal size metal (20-50 mm and 40-63 mm size), Bituminous Penetration Macadam	12	-	-	30	-	8
5.	Surface dressing** (two coat) over WBM (20-50 mm or 40-63 mm size metal), Bituminous penetration macadam	12	-	-	20	-	8
6.	Open graded premix carpet, mix seal Surfacing	10	-	-	-	30	6
7.	Bituminous macadam	10	-	-	-	20***	6
8.	Semi-dense carpet	10	-	-	-	20***	6
9.	Asphaltic Concrete	8	-	-	-	10***	4

Notes:

1. ** For surface dressing in all other cases, the standards of surface evenness will be the same as those for the surface receiving the surface dressing.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 223 of 361

2. *** These are for machine laid surfaces. If laid manually due to unavoidable reasons, tolerance upto 50 percent above these values in this column may be permitted at the discretion of the Engineer. However this relaxation does not apply to the values of maximum undulation for longitudinal and cross profiles mentioned in columns 3 and 8 on the table.

3. Surface evenness requirements in respect of both the longitudinal and cross profiles should be simultaneously satisfied.

3.00.00 Execution

3.01.00 Setting Out

Within 15 days of the award of contract, the contractor shall prepare and submit to the Engineer, detailed drawings/schemes of embankment filling and excavation works as proposed to be executed by him showing the dimensions as per construction drawings and specification adding his proposals of drainage and dewatering of pits, watering and compacting the embankment fill etc. On receiving the approval from the Engineer with modifications and corrections if any, the contractor shall set out the work from the control points furnished by the Engineer and fix permanent points and markers for ease of future checking. These permanent points and markers will be checked by the Engineer and certified by him after which the contractor shall proceed with the work. It should be noted that this checking by the Engineer prior to the start of the work will in no way absolve the contractor of his responsibility of carrying out the work to true lines and levels as per the approved drawings. If any errors are noticed in the Contractor's work at any stage, the same shall be rectified by the contractor at his own risk and cost. Profiles of the embankment made by Bamboo, earth or other convenient materials and strings shall be set up at suitable intervals for the guidance of the workmen.

3.02.00 Clearing and Grubbing etc

Before commencement of earthwork, the surface area of ground to be occupied shall be cleared of all fences, trees, logs, stumps, bush, vegetation, rubbish, slush etc. Cutting of trees shall include trees having girth of any size and removing roots upto a depth of 600mm below ground level or 300mm below formation level whichever is deeper. After the removal of roots of trees, the pot holes formed shall be filled with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the Engineer. The trees shall be cut into suitable pieces as instructed by the Engineer. Before earthwork is started, all the spoils and unserviceable materials and rubbish shall be burnt or removed from the site to the approved disposal areas as may be specified. Useful materials, saleable timbers, firewood, etc shall be the property of the Owner and shall be stacked properly at the worksite in a manner as directed by the Engineer.

3.03.00 Filling in Embankment



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 224 of 361

3.03.01

General

The material used for constructing the embankment shall be earth, moorum, gravel or a mixture of the above or any other material approved by the Engineer. The material shall be free from lumps & clods, boulders and rock pieces, roots and vegetation, harmful salts and chemicals, organic materials, loose silts, fine sands and expansive clays in order to provide a stable embankment. The filling and compaction operation should be such that the best available materials are saved for the top portion and will result in an acceptable and uniform gradation of material and provide impermeability and stability to the embankment when compacted. The size of the coarse material in the mixture of earth shall ordinarily not exceed 75mm. However, the Engineer may at his discretion permit the use of material coarser than the specified if he is satisfied that the same will not present any difficulty as regard to the placement and compaction of the fill material are concerned. Ordinarily, only the materials satisfying the density requirements as given below in Table-II shall be employed for embankment construction.

Table - II

Density Requirements of Embankment Materials

Sl. No.	Type of Work	Maximum laboratory dry density when tested as per IS: 2720 (Part - VII)
1.	Embankment upto 3m height	Not less than 1.44 gm/cc
2.	Embankment exceeding 3m height and embankment of any height subject to long period of inundation	Not less than 1.52 gm/cc
3.	Top 0.5m of the embankment below sub-base and shoulders (where earth shoulders are specified)	Not less than 1.65 gm/cc

Expansive clays exhibiting marked swell and shrinkage properties shall not be used for embankment construction.

The material for embankment construction shall be obtained from approved sources with preference given to the materials available from nearby road excavation or any other excavation under the same contract.

3.03.02

Setting Out



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 225 of 361

After the site clearance, the work shall be set out true to lines, curves, slopes, grades and sections as shown on the approved drawings or as directed by the Engineer. The contractor shall provide all labour, survey instruments and materials such as strings, pegs, nails, bamboo, stones, lime, mortar, concrete etc required in connection with the setting out of the works and establishment of the bench marks. The limits of the embankment shall be marked by fixing batter pegs on both sides at regular intervals as guides before commencing the earthwork. To ensure the safety, the pegs should normally be fixed about 500mm away from the actual limits of the fill and to be painted in a distinct colour. The centreline of the embankment shall be pegged at regular intervals of 25/30m and at all skew/curves. The actual profile of the embankment shall be made at every third centreline peg with bamboo posts and strings. Preferably prototype profiles developed with wooden planks need to be fixed at every 200m and at the intersection points at curves. The profile shall be about 3m long.

3.03.03 Stripping and Storing top soil

The construction of the earthen embankment by filling shall conform to the dimensions, slopes and other details shown in the approved drawings. Before commencement of the embankment construction, the surface area of ground to be occupied after clearing and grubbing shall be stripped off to a minimum depth of 150mm or more as directed by the Engineer in order to remove all perishable material and any soil which may become unstable on saturation or may interfere with the development or proper bonding between the foundation and embankment. It is not necessary to remove all the soil containing fine hair like roots but only the rather heavy mats are to be removed. In localities where most of the available embankment fill materials are not conducive to plant growth or when so directed by the Engineer, the top soil shall be stripped to specified depths not exceeding 150mm.

3.03.04 Compacting Original Ground

In all cases, the original ground after stripping shall be compacted by rolling with a minimum of six passes of 8-10 tonne roller and as directed by the Engineer. Where the height of the proposed embankment is less than 0.5m and the original ground does not already have a relative compaction of at least 95 percent, the same shall be loosened upto a depth of 0.5m and filled in layers not exceeding 250mm in loose thickness and each layer shall be watered and compacted to 100% maximum dry density of the fill material determined in accordance with IS:2720, Part-VII. However, before relaying and compacting the loosened material, the surface below this level shall be suitably compacted as directed by the Engineer with a minimum of six passes of a 8 - 10 tonne roller.

Where so directed by the Engineer, any unsuitable material occurring in the embankment foundation shall be removed and replaced with approved materials



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 226 of 361

suitably compacted. Embankment work shall not proceed until the foundation soil of the embankment is inspected by the Engineer and approved.

3.03.05 Filling

The embankment material shall be spread uniformly over the entire width of the embankment in layers not exceeding 250mm in loose thickness. Successive layers of embankment shall not be placed until the layer under construction has been thoroughly compacted to the requirements set down hereunder. Moisture content of the fill material shall be checked at the source of supply and if found less than that specified for compaction, the same shall be made good either at the source or after spreading the soil in loose thickness for compaction. In the latter case water shall be sprinkled directly from a hose line or from a truck mounted water tank and flooding shall not be permitted under any circumstances. After adding required amount of water, the soil shall be processed by means of harrows, rotary mixers or by any other approved methods until the layer is uniformly wet.

If the material delivered to the road bed is too wet, it shall be dried by aeration and exposure to the sun till the moisture content is acceptable for compaction. Should circumstances arise where owing to wet weather, the moisture content cannot be reduced to the required amount by the above procedure, the work on compaction shall be suspended.

Moisture content of each layer shall be checked in accordance with IS:2720, Part-II and unless otherwise specified shall be so maintained making due allowance for evaporation losses that during compaction, the moisture content shall be in the range of 1 percent above to 2 percent below the optimum moisture content as determined in accordance with IS:2720, Part-VII.

Clods or hard lumps of earth shall be broken to have a maximum size of 150mm when being placed in the lower layers of the embankment and a maximum size of 60mm when being placed in the top 0.5m portion of the embankment below sub-base.

Hauling equipment shall be dispersed uniformly over the entire surface of the previously constructed layer to minimise rutting or uneven compaction.

Where the embankment is to be constructed across a low swampy ground that will not support the weight of trucks or other hauling equipments, the lower part of the fill shall be constructed by dumping successive loads in a uniformly distributed layer to a thickness not greater than that necessary to support the hauling equipment while placing subsequent layers.

3.03.06 Compaction



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 227 of 361

Compaction equipment approved by the Engineer shall only be employed for construction. If directed by the Engineer, the Contractor shall demonstrate the efficiency of the plant he intends to use by carrying out compaction trials.

Each layer shall be thoroughly compacted to the density as specified in Table-III. Subsequent layers shall be placed only after the finished layer has been tested and accepted by the Engineer.

Table - III

Compaction Requirements For Embankment

Sl. No.	Type of work/material	Field dry density as a percentage of maximum laboratory dry density as per IS : 2720, Part-VII
1.	Top 0.5m portion of embankment below sub-base and shoulders	Not less than 100
2.	Other portions of embankment	Not less than 95

When density measurement reveal any soft area in the embankment, further compaction shall be carried out as directed by the Engineer. If in spite of that the specified compaction is not achieved, the material in the soft area shall be removed and replaced with approved material, compacted to the density requirements and satisfaction of the Engineer.

3.03.07 Drainage

The surface of the embankment at all times during construction shall be maintained at such a cross fall as will shed water and prevent ponding.

3.03.08 Finishing Operations

Finishing operations shall include the work of shaping and dressing the shoulders, road bed and side slopes to conform the alignment, levels, cross sections and dimensions as shown on the drawings or as directed by the Engineer. Both the upper and lower ends of the side slopes shall be rounded off to improve appearance and merge the embankment with the adjacent terrain.

3.04.00 Turfing With Sods

3.04.01 General

This work shall consist of furnishing and laying of live sod of perennial turf forming grass on embankment slopes, shoulders or other locations as shown



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 228 of 361

on the drawings or as directed by the Engineer. Unless otherwise specified the work shall be taken up following the construction of embankment provided the season is favourable for establishment of the sod.

3.04.02 Materials

The sod shall consist of dense, well rooted growth of permanent and desirable grasses, indigenous to the locality where it is to be used and shall be practically free from weeds or other undesirable matter. At the time the sod is cut, the grass shall have a length of approximately 50mm and the sod shall be free from any debris.

Thickness of the sod shall be as uniform as possible with some 50 to 80mm of soil covering the grass roots depending on the nature of the sod so that practically all the dense root system of the grass are retained in the sod strip. The sods shall be cut in rectangular strips of uniform width not less than 250mm x 300mm in size but not so large so that it is convenient to handle and transport without damage. During wet weather the sod shall be allowed to dry sufficiently to prevent rearing during handling and during dry weather it shall be watered before lifting to ensure its vitality and prevent dropping of soil during handling.

3.04.03 Placing The Sods

The area to be sodded shall be previously constructed to the required slope and cross section. Soil on the area shall be loosened, freed from all stones larger than 50mm size, sticks, stumps and any other undesirable foreign matter etc and brought to a reasonably granular texture to a depth not less than 25mm for receiving the sod. Following soil preparation, fertilizer and ground limestone when specified shall be spread uniformly. After spreading, the materials shall be incorporated in the soil by discing or other means. The prepared sod bed shall be moistened if not already sufficiently moist and the sod shall be placed thereon within approximately 24 hours after the same has been cut. Each sod strip shall be laid in close contact with each other and shall be lightly tamped with suitable wooden or metal tampers so as to eliminate air pockets and to press it into the underlying soil. At points where water may flow over the sod, the upper edges of the sod strips shall be turned into the soil below the adjacent area and a layer of earth shall be placed over it followed by thorough compaction.

3.04.04 Staking the Sods

Where the side slope is 2 to 1 or steeper and the distance along the slope is more than 2m, the sods shall be staked with pegs or nails spaced approximately 500 to 1000mm along the longitudinal axis of the sod strips. Stakes shall be driven approximately plumb through the sods and to be almost flushed with them.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 229 of 361

3.04.05 Top Dressing

After the sods have been laid in position, the surface shall be cleaned of loose sod, excess soil and other foreign materials. Thereafter a thin layer of top soil shall be scattered over the top dressed surface and the area shall be thoroughly moistened by sprinkling water.

3.04.06 Watering and Maintenance

The turfing so laid shall be well watered and protected until final acceptance. Watering shall be done in such a way that no erosion or damage to the sodded areas/embankment occur. The Contractor shall erect necessary warning signs and barriers, repair or replace the sods which are failing to show uniform growth of grass or damaged by his operation and shall maintain the sod at his own cost until final acceptance.

3.05.00 Shoulder Construction

3.05.01 Description

This work shall consist of constructing shoulder on either side of the pavement in accordance with the requirements of this specification and in conformity with the lines, grades and cross sections shown on the approved drawings and as directed by the Engineer.

3.05.02 Materials

Shoulder shall be made of selected earth or granular material as specified conforming to relevant IRC standards.

3.05.03 Construction Operations

Except in the case of bituminous pavements, the shoulders shall be constructed in advance to the laying of pavement courses. The compacted thickness of each layer of shoulder shall correspond to the compacted layer of pavement course to be laid adjacent to it. After compaction, the inside edges of shoulders shall be trimmed vertical and the area enclosed between the shoulders shall be cleaned of all spilled material before proceeding with the construction of the pavement layer.

In the case of bituminous pavements, shoulder shall be constructed only after the pavement courses have been laid and compacted.

Regardless of the method of laying, all shoulder construction material shall be placed directly on the shoulder. Any spilled material dragged on to the pavement surface shall be immediately removed without any damage to the pavement and the area so affected shall be thoroughly cleaned. During all



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 230 of 361

stages of shoulder construction, the required crossfall shall be maintained to drain off surface water.

3.06.00 Kerb

3.06.01 Material

Kerb if required for the construction of footpath shall consist of precast concrete blocks with concrete grade of M-20. The blocks shall be of 100mm thick and of suitable length. The depth of blocks unless otherwise mentioned elsewhere shall be 375mm considering 225mm height of footpath above the road level.

3.06.02 Laying

The kerb shall be laid by cutting trenches of 150mm deep. The width of the trench shall be minimum and just sufficient to insert the kerbs. The inside faces of the kerbs shall be in plumb and the gap between the block shall not be more than 10mm. The gap shall be filled with cement mortar as specified.

The kerbs shall be thoroughly packed with a mixture of stone chips (50%) and moorum (50%) at the outside face. The laying and packing shall be done in a proper workmanlike manner acceptable to the Engineer.

3.07.00 Sub-base (Granular Sub-base)

3.07.01 Description

This work shall consist of laying and compacting well graded material on the prepared sub-grade in accordance with the specification. The material shall be laid in one or more layers as shown on the drawings and shall conform to the lines, grades and cross sections shown on the drawings and as directed by the Engineer.

3.07.02 Materials

The materials to be used for the work shall be natural sand, moorum, gravel, crushed stone, crushed slag, crushed concrete, brick metal, laterite, kankar etc or combinations thereof depending upon the grading required. The mixed materials shall be free from organic or other deleterious constituents and conform to one of the three grading given in Table - IV below.

Table - IV

Grading for Granular Sub-base Material



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 231 of 361

Sieve designation	Percent by weight passing the sieve		
	Grading 1		
80 mm	100	100	100
63 mm	90 - 100	90 - 100	90 - 100
4.75 mm	35 - 70	40 - 90	50 - 100
75 micron	0 - 20	0 - 25	0 - 30
Minimum CBR value for the fraction of material passing 20 mm sieve.	30 %	25%	20%

Note : The materials passing 425micron sieve for all the three gradings when tested according to IS : 2720, Part V shall have liquid limit and plasticity index not more than 25 percent and 6 percent respectively.

3.07.03 Physical Requirements

The fraction of materials passing 20 mm sieve shall give a CBR value as specified in Table – IV when tested in accordance with IS : 2720, Part XVI after preparing the samples at maximum dry density and optimum moisture content corresponding to IS : 2720, Part VII and soaking the same in water for 4 days.

3.07.04 Spreading and Compacting

Immediately prior to laying of sub-base, the sub-grade already finished shall be prepared by removing all vegetations and other extraneous matter, lightly sprinkled with water if necessary and rolled with one pass of 8 - 10 tonne smooth wheeled roller.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 232 of 361

The sub-base material shall be spread on the sub-grade with the help of a drag spreader, motor grader or other approved means. The thickness of loose layers shall be so regulated that the maximum thickness of each layer after compaction shall not exceed 150mm.

Moisture content of the loose material shall be checked in accordance with IS : 2720, Part II and shall be suitably adjusted by sprinkling additional water from a hose line, truck mounted water tank or other approved means so that at the time of compaction it shall be from 1 percent above to 2 percent below the optimum moisture content. While adding water, due allowance shall be made for evaporation losses. After water has been added, the material shall be processed by mechanical or other approved means if so directed by the Engineer until the layer is uniformly wet.

Immediately thereafter, rolling shall be done with 8 to 10 tonne smooth wheeled rollers or with any other approved plant. Rolling shall commence from the edges and progress towards the centre longitudinally except that on super elevated portions it shall progress from the lower to the upper edge parallel to the centre line of the pavement. Each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass. During rolling, the grade and camber shall be checked and any high spots or depressions which become apparent shall be corrected by removing or adding fresh material.

Rolling shall be continued till the density achieved is at least 100% of the maximum dry density of the material determined as per IS : 2720, Part VII. The surface of any layer of material on completion of compaction shall be well closed free from movement under compaction plant and from compaction planes, ridges, cracks or loose material. All loose, segregated or otherwise defective areas shall be made good to the full thickness of layer and recompacted.

3.08.00 Water Bound Macadam Sub-base/Base Course

3.08.01 Description

Water bound macadam shall consist of clean crushed aggregates mechanically interlocked by rolling and bonded together with screenings, binding material wherever necessary and water laid on the prepared sub-grade or sub-base as the case may be and finished in accordance with the specification and in conformity with the lines, grades and cross-sections shown on the approved drawings.

3.08.02 Materials

a) Coarse Aggregates - General Requirements



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 233 of 361

Coarse aggregates shall be either crushed or broken stone. The aggregates shall conform to the physical requirements set forth in Table - V.

Table - V
Physical Requirements of Coarse Aggregates for water Bound Macadam

Sl.No.	Type of Construction	Test	Test method	Requirements
1.	Sub-base	Los Angeles Abrasion Value * or Aggregate Impact Value	IS : 2386 (Part IV) IS : 2386 (Part IV) or IS : 5640**	50 percent maximum 40 percent maximum
2.	Base	a) Loss Angeles Abrasion value* or Aggregate Impact Value b) Flakiness Index ***	IS : 2386 (Part IV) IS : 2386 (Part IV) or IS : 5640 ** IS : 2386 (Part I)	50 percent maximum 40 percent maximum 15 percent maximum

* Aggregates may satisfy requirements of either of the two tests.

** Aggregates like brick metal, kankar and laterite which get softened in presence of water shall be tested for impact value under conditions in accordance with IS : 5640.

*** The requirements of Flakiness Index shall be enforced only in case of crushed or broken stone and crushed slag.

b) Crushed or Broken Stone

Crushed or broken stone shall be hard, durable and free from excess flat, elongated, soft and disintegrated particles, dirt and other objectionable matters.

c) Grading Requirements of Coarse Aggregates



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 234 of 361

The coarse aggregates shall conform to one of the gradings given in Table – VI. However the use of Grading No.1 shall be restricted to sub-base courses only.

**Table - VI
Grading Requirements of Coarse Aggregates**

Grading No.	Size range	Sieve designation	Percent by weight passing the sieve
1.	90mm to 40 mm	100 mm	100
		80 mm	65 - 85
		63 mm	25 - 60
		40 mm	0 - 15
		20 mm	0 - 5
2.	63 mm to 40 mm	80 mm	100
		63 mm	90 - 100
		50 mm	35 - 70
		40 mm	0 - 15
		20 mm	0 - 5
3.	50 mm to 20 mm	63 mm	100
		50 mm	95 - 100
		40 mm	35 - 70
		20 mm	0 - 10
		10 mm	0 - 5

d) Screenings

Screenings to fill voids in the coarse aggregate shall generally consist of the same material as the coarse aggregates. However, where permitted, predominantly non-plastic material such as moorum or gravel (other than rounded river borne material) may be used for this purpose provided liquid limit and plasticity index of such material is below 20 and 6 respectively and fraction passing 75 micron sieve does not exceed 10 percent.

As far as possible, screenings shall conform to the grading set forth in Table-VII. Screenings of Type A in Table-VII shall be used with coarse aggregates of Grading No.1 in Table-VI. Screenings of Type-A or B shall be used with coarse aggregates of Grading No.2. Type-B screenings shall be used with coarse aggregates of Grading No. 3.

**Table - VII
Gradings For Screenings**



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 235 of 361

Grading classification	Size of screenings	Sieve designation	Percent by weight passing the sieve
A	12.5 mm	12.5 mm 10.0 mm 4.75 mm 150 micron	100 90 - 100 10 - 30 0 - 8
B	10 mm	10 mm 4.75 mm 150 micron	100 85 - 100 10 - 30

e) Binding Material

Binding material to be used for water bound macadam construction shall comprise of a suitable material approved by the Engineer having plasticity index value of less than 6 as determined in accordance with IS : 2720, Part V. Application of binding material may not be necessary when the screenings used are of crushable type such as moorum or gravel.

3.08.03 Construction Operations

- a) The sub-grade/sub-base to receive the water bound macadam coarse shall be prepared to the specified grade and camber and made free of dust and other extraneous material. Any ruts or soft yielding places shall be corrected in an approved manner and rolled until firm. Where water bound macadam is to be laid over an existing black topped surface, 50mm x 50mm furrows shall be cut at an angle of 45 degrees to the centre line of the road at 1m intervals in the latter before laying the coarse aggregates.

b) Inverted Choke

If water bound macadam is to be laid directly over the sub-grade without any other intervening pavement course, a 25mm course of screenings (Grading B) shall be spread on the prepared sub-grade before application of the coarse aggregates is taken up.

c) Spreading Coarse Aggregates

The coarse aggregates shall be spread uniformly over the prepared surface in such quantities that the thickness of each compacted layer is limited to 100mm for Grading No.1 and 75 - 100mm for Grading No. 2 and 3.

The spreading shall be done from stockpiles along the side of the roadway or directly from the vehicles. In no case shall the aggregate be dumped in heaps directly on the surface prepared to receive the aggregate nor shall hauling over permitted.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 236 of 361

The surface of the aggregates spread shall be carefully checked with templates and all high or low spots remedied by removing or adding aggregate as may be required. No segregation of large or fine particles shall be allowed and the coarse aggregate as spread shall be of uniform gradation with no pockets of fine material.

The coarse aggregate shall not normally be spread more than 3 days in advance of the subsequent construction operations.

d) Rolling

Immediately following the spreading of the coarse aggregates, rolling shall be started with three wheeled power rollers of 8 to 10 tonne capacity or tandem or Vibratory rollers of approved type. The weight of the roller shall depend upon the type of the aggregate and be indicated by the Engineer.

Except on super elevated portions where the rolling shall proceed from inner edge to the outer, rolling shall begin from the edges gradually progressing towards the centre. First the edge/edges shall be compacted with roller running forward and backward. The roller shall then move inwards parallel to the centre line of the road. Each pass of the roller shall uniformly overlap not less than one half the width of the track made in the preceding pass.

Rolling shall continue until the aggregates are thoroughly keyed and the creeping of aggregates ahead of the roller is no longer visible. During rolling slight sprinkling of water may be done if necessary. Rolling shall not be done when the sub-grade is soft or yielding or when it causes a wavelike motion in the sub-grade or sub-base course.

The rolled surface shall be checked transversely and longitudinally with templates and any irregularities found shall be corrected by loosening the surface, adding or removing necessary amount of aggregates and rerolled until the entire surface conform to the desired camber and grade. In no case shall the use of screenings be permitted to make up the depressions.

e) Application of Screenings

After the coarse aggregate has been rolled, screenings to completely fill the interstices shall be applied gradually over the surface. These shall not be damp or wet at the time of application. Dry rolling shall be done while the screenings are being spread so that vibrations of the roller cause them to settle into the voids of the coarse aggregates. The screenings shall not be dumped in piles but be spread uniformly in successive thin layers either by the spreading motion of hand shovels or by mechanical spreader or directly from trucks. Trucks operating for spreading the screenings shall be so driven as not to disturb the coarse aggregates.

The screenings shall be applied at a slow and uniform rate (in three or more applications) so as to ensure filling of all voids. This shall be accompanied by dry rolling and brooming with mechanical brooms or hand brooms or with both. In no



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 237 of 361

case shall the screenings be applied so fast and thick as to form cakes or ridges on the surface in such a manner as would prevent filling of voids or prevent the direct bearing of the roller on the coarse aggregate. These operations shall continue until no more screenings can be forced into the voids in the coarse aggregates.

The spreading, rolling and brooming of screenings shall be carried out in only such lengths of the road which could be completed within one day's operation.

f) Sprinkling and Grouting

After the screenings have been applied, the surface shall be copiously sprinkled with water, swept and rolled. Hand brooms shall be used to seep the wet screenings into the voids and to distribute them evenly. The sprinkling, sweeping and rolling operations shall be continued with additional screenings applied as necessary until the coarse aggregate has been thoroughly keyed, well-bonded and firmly set to its full depth and a grout has been formed of screenings. Care shall be taken to see that the base or sub-grade does not get damaged due to the addition of excess quantity of water during construction.

g) Application of Binding Material

After the application of screenings, the binding material where it is required to be used shall be applied successively in two or more thin layers at a slow and uniform rate. After each application the surface shall be copiously sprinkled with water and the resulting slurry shall be swept in with hand brooms or mechanical brooms to fill the voids properly and rolled during which water shall be applied to the wheels of the rollers if necessary to wash down the binding material sticking to them. These operations shall continue until the resulting slurry after filling the voids form a wave ahead of the wheels of the moving roller.

h) Setting and Drying

After the final compaction of water bound macadam course, the road shall be allowed to dry overnight. Next morning hungry spots shall be filled with screenings or binding material as directed, lightly sprinkled with water if necessary and rolled. No traffic shall be allowed on the road until the macadam has set. The Engineer shall have the discretion to stop hauling traffic from using the complete water bound macadam course if in his opinion it would cause excessive damage to the surface.

3.09.00 Tack Coat

3.09.01 Description

The work shall consist of application of a single coat of low viscosity liquid bituminous material to an existing road surface preparatory to another bituminous construction.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 238 of 361

3.09.02 Materials

The binder used for tack coat shall be bitumen of a suitable grade as approved by the Engineer and conforming to IS-73, IS-217 or IS-454 as applicable or any other approved cutback.

3.09.03 Construction Operations

a) Preparation of Base

The surface on which the tack coat is to be applied shall be thoroughly swept and scraped clean of dust and any other extraneous materials before the application of the binder.

b) Application of Binder

Binder shall be heated to the temperature appropriate to the grade of bitumen used and approved by the Engineer and sprayed on the base at the rate specified below. The rate of spread in terms of straight run bitumen shall be 5 kg per 10 square metre area for an untreated water bound macadam surface. The binder shall be supplied uniformly with the aid of sprayers.

The tack coat shall be applied just ahead of the oncoming bituminous construction.

3.10.00 Bituminous Macadam Binder Course

3.10.01 Description

This work shall consist of construction in a single course of 50mm/75mm thickness of compacted crushed aggregates premixed with a bituminous binder laid immediately after mixing on a base prepared previously in accordance with the specification and in conformity with the lines, grades and cross sections shown on the approved drawings.

3.10.02 Materials

a) Binder

The Binder shall be straight run bitumen of a suitable grade as directed by the Engineer complying with IS : 73.

b) Aggregates

The aggregates shall consist of crushed stone, crushed gravel (shingle) or other stones. They shall be clean, strong, durable, fairly cubical



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 239 of 361

shape and free of disintegrated pieces, organic and other deleterious matter and adherent coats. The aggregates shall preferably be hydrophobic and of low porosity.

The aggregates shall satisfy the physical requirements set forth in Table - VIII.

Table - VIII

Physical Requirements of Aggregates For Bituminous Macadam

Sl. No.	Test	Test method	Requirements
1.	Los Angeles Abrasion Value *	IS : 2386 (Part IV)	35 percent maximum
2.	Aggregate Impact Value *	IS : 2386 (Part IV)	30 percent maximum
3.	Flakiness Index	IS : 2386 (Part I)	35 percent maximum
4.	Stripping Value	IS : 6241 (Part IV)	25 percent maximum
5.	Water Absorption	IS : 2386 (Part III)	2 percent maximum

*Aggregates may satisfy requirements of either of the two tests.

The Aggregates for bituminous macadam for different thickness shall conform to the grading A or B given in Table IX or X.

Table-IX

Aggregates Grading For 75mm Compacted Thickness Of Bituminous Macadam

Sieve Designation	Percent by weight passing the sieve	
	Grading A	Grading B
63 mm	100	
50 mm	90 - 100	
40 mm	35 - 65	100
25 mm	20 - 40	70 - 100
20 mm	-	50 - 80



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 240 of 361

12.5 mm	5 - 20	-
4.75 mm	-	10 - 30
2.36 mm	-	5 - 20
75 micron	0 - 5	0 - 4

Table-X

Aggregates Grading For 50mm Compacted Thickness Of Bituminous Macadam

Sieve Designation	Percent by weight passing the sieve	
	Grading A	Grading B
50 mm	100	
40 mm	90 - 100	
25 mm	50 - 80	100
20 mm	-	70 - 100
12.5 mm	10 - 30	-
10 mm	-	35 - 60
4.75 mm	-	15 - 35
2.36 mm	-	5 - 20
75 micron	0 - 5	0 - 4

c) Proportioning of Materials

The binder content for premixing shall be 3.5 and 4.0 percent by weight of the total mix for aggregate grading- A and B respectively unless directed otherwise by the Engineer.

The quantity of aggregates to be used shall be sufficient to yield the specified thickness after compaction.

d) Variation in Proportioning of Materials

The Contractor shall have the responsibility for ensuring proper proportioning of materials and producing a uniform mix. Variation in binder content upto ± 0.3 percent by weight of total mix shall however be permissible for individual specimens taken for quality control tests.

3.10.03 Construction Operations

a) Weather and Seasonal Limitations

Bituminous macadam shall not be laid during rainy weather or when the base course is damp or wet.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 241 of 361

b) Preparation of Base

The base on which the bituminous macadam is to be laid shall be prepared, shaped and conditioned to the specified lines, grade and cross sections as shown on drawings and as directed by the Engineer. The surface shall be thoroughly swept and scraped clean and free from dust and foreign matter.

c) Tack Coat

A tack coat shall be applied over the base.

d) Preparation and Transport of Mix

Hot mix plant of adequate capacity shall be used for preparing the mix. The temperature of binder at the time of mixing shall be in the range 150 Deg. - 165 Deg. C and to that of aggregates shall be in the range 125 Deg. - 150 Deg. C provided the temperature difference between the binder and the aggregate at no time exceeds 25 Deg. C. Mixing shall be thorough to ensure that a homogenous mixture is obtained in which all particles of the aggregates are coated uniformly. The mixture shall be transported from the mixing plant to the point of use in a suitable vehicle. The vehicle employed for transport shall be clean and be covered over in transit if so directed by the Engineer.

e) Spreading

After mixing, the mix shall be spread immediately by means of a self propelled mechanical paver with suitable screeds capable of spreading, tamping and finishing the mix to the specified lines, grade and cross sections. However in restricted locations and in narrow widths where the available plants cannot operate in the opinion of the Engineer may permit manual laying of the mix.

The temperature of mix at the time of laying shall be in the range 110 Deg. - 135 Deg. C.

In multilayer construction, the longitudinal joint in one layer shall offset that into the layer below by about 150mm. However, the joint in the topmost layer shall be at the centre line of the pavement.

Longitudinal joints and edges shall be constructed true to the delineating lines parallel to the centre line of the road. All joints shall be cut vertical to the full thickness of the previously laid mix and the surface painted with hot bitumen before placing fresh material.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 242 of 361

f) Rolling

After spreading of mix, rolling shall be done with 8 to 10 tonne power rollers or other approved plant. Rolling should start as soon as possible after the material has been spread. Rolling shall be done with care to avoid any undulation in the pavement surface.

Rolling on the longitudinal joint shall be done immediately after the paving operation. After this, the rolling shall commence at the edges and progress towards the centre longitudinally except on superelevated portions where it shall progress from the lower to the upper edge parallel to the centre line of the pavement.

The initial or breakdown rolling shall be done as soon as it is possible to roll the mixture without cracking the surface and no mix pick up on the roller wheels. The second or intermediate rolling shall follow the break down rolling as closely as possible and be done while the paving mix is still at a temperature that will result in maximum density. The final rolling shall be done while the material is still workable enough for removal of roller marks.

When the roller has passed over the whole area once, any high spots or depressions which become apparent shall be corrected by removing or adding fresh materials. The rolling shall then be continued till the entire surface has been rolled to compaction and there is no crushing of aggregates and till all the roller marks are eliminated. Each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass. The roller wheels shall be kept damp if necessary to avoid the bituminous material from sticking to the wheels and being picked up. In no case shall fuel/lubricating oil be used for this purpose.

Rolling operation shall be completed in every respect before the temperature of the mix fall below 80 Deg. C.

Rollers shall not stand on the newly laid material as it may lead to undue deformation. The edges along and transverse of the bituminous macadam laid and compacted earlier shall be cut to their full depth so as to expose fresh surface which shall be painted with a thin surface coat of appropriate binder before the new mix is placed against it.

The bituminous macadam shall be provided with a final surfacing without any delay. If there is to be any delay the course shall be covered by seal coat before allowing any traffic over it.

3.11.00 Open Graded Premix Carpet

3.11.01 Description



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 243 of 361

This work shall consist of laying and compacting open graded carpet of specified thickness in a single course of suitable small sized aggregates premixed with bituminous binder on a previously prepared base to form wearing course in accordance with the specification.

3.11.02 Materials

a) Binder

The binder shall be bitumen of a suitable grade, as approved by the Engineer and satisfying the requirements of IS: 73, 217, 454 or any other approved cutback as applicable.

b) Aggregates

The aggregates shall consist of angular fragments of clean, hard, tough and durable rock of uniform quality throughout. They shall be obtained by crushing rock, gravel or river shingle and be free of elongated and flaky pieces, soft and disintegrated materials, vegetable and any other deleterious matter etc. They shall preferably be hydrophobic type.

The aggregates shall satisfy the quality requirements set forth in Table VIII except that the Flakiness Index shall be limited to a maximum of 30.

c) Proportioning of Materials

The materials shall be proportioned in the ratio of its thickness based upon quantities given in Table XI.

Table - XI

**Quantity of Materials Required For 10 Sq. M of Road Surface For
20mm Thick Open Graded Premix Carpet**

Aggregates for Carpet

i)	Stone Chippings - 12mm size ; passing 20 mm sieve and retained on 10 mm sieve	0.18 Cu.m
ii)	Stone Chippings - 10 mm size; passing 12.5 mm sieve and retained on 6.3 mm sieve	0.09 Cu.m
Total		0.27 Cu.m

Binder for premixing (quantities in terms of straight run bitumen)

i)	For 0.18 Cu.m of 12 mm size stone	9.5 Kg
----	-----------------------------------	--------



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 244 of 361

Chippings at 52 Kg per Cu.m

ii) For 0.09 Cu. M of 10mm size stone
Chippings at 56 Kg per Cu.m 5.1 Kg

Total 14.6 Kg

3.11.03 Construction Operation

a) Weather and Seasonal Limitations

Open graded premix carpet shall not be laid during rainy weather or when the base course is damp or wet or when the atmospheric temperature in shade is 16 Deg. C or below.

b) Preparation of Base

The underlying base on which the bituminous carpet is to be laid shall be prepared, shaped and conditioned to the specified lines, grade and cross section in accordance with the drawing, specification and as directed by the Engineer. The surface shall be well cleaned by removing caked earth and other foreign matters with wire brushes, sweeping with brooms and finally dusting with sacks as necessary.

c) Tack Coat

A tack coat complying with clause 3.09.00 shall be applied over the base preparatory to laying of the carpet. However application of tack coat shall not be necessary when the laying of carpet follows soon after laying the bituminous course.

d) Preparation of Premix

Mixers of approved type shall be employed for mixing the aggregates with the bituminous binder.

The binder shall be heated to the temperature appropriate to the grade of bitumen approved by the Engineer in boilers of suitable design avoiding local overheating and ensuring a continuous supply.

The aggregates shall be dry and suitably heated to a temperature as directed by the Engineer before these are placed in the mixer. After about 15 seconds of dry mixing, the heated binder shall be distributed over the aggregates at the rate specified.

The mixing of binder with chipping shall be continued until the chippings are thoroughly coated with the binder. The mix shall be immediately transported from the mixer to the point of use in suitable vehicles or wheel barrows. The vehicles employed for transport shall be clean and be covered over in transit if so directed.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 245 of 361

e) Spreading and Rolling

The premixed material shall be spread on the road surface with rakes to the required thickness and camber or distributed evenly with the help of a drag spreader without any undue loss of time. The camber shall be checked by means of camber boards and inequalities evened out. As soon as sufficient length of bituminous material has been laid rolling shall be commenced with 6 to 8 tonne power rollers preferably with smooth wheel tandem type or with any other approved plant. Rolling shall begin at the edges and progress toward the centre longitudinally except on the superelevated portions where it shall progress from the lower to upper edge parallel to the centre line of the pavement.

When the roller has passed over the whole area once, any high spots or depressions which become apparent shall be corrected by removing or adding premixed materials. Rolling shall then be continued until the entire surface has been rolled to compaction and all the roller marks have been eliminated. In each pass of the roller, preceding track shall be overlapped uniformly by at least 1/3 width. The roller wheels shall be kept damp to prevent the premix from adhering to the wheels and being picked up. In no case shall fuel/lubricating oil be used for this purpose. Rollers shall not stand on newly laid material as it may lead to undue deformations.

The edges along and transverse of the carpet laid and compacted earlier shall be cut to their full depth so as to expose fresh surface which shall be painted with a thin surface coat of approved binder before the new mix is placed against it.

f) Seal Coat

A seal coat conforming to clause 3.12.00 shall be applied to the surface immediately after laying the carpet. No traffic shall be allowed on the road till the seal coat has been placed.

3.12.00 Seal Coat

3.12.01 Description

This work shall consist of application of a seal coat as specified for sealing the voids in the bituminous surface laid to the specified levels, grade and camber.

Type A : Liquid seal coat comprising of an application of a layer of bituminous binder followed by a cover of stone chippings.

Type B : Premixed seal coat comprising of a thin application of fine aggregate premixed with bituminous binder.

3.12.02 Materials

a) Binder



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 246 of 361

The binder shall be bitumen of suitable grade as directed by the Engineer and conforming to the requirements of IS : 73, 217 or 454 as applicable or any other approved cutback.

The quantity of binder to be adopted in terms of straight run bitumen shall be 9.8 Kg and 6.8 Kg per 10 square metre area for Type A and Type B seal coat respectively.

b) Stone Chippings for Type A Seal Coat

The stone chippings shall consist of angular fragments of clean, hard, tough and durable rock of uniform quality throughout. They shall be free of elongated or flaky pieces, soft or disintegrated stone, vegetable or other deleterious matters etc. Stone chippings shall be of 6mm size defined as 100 percent passing through 10mm sieve and retained on 2.36mm sieve. The quantity used for spreading shall be 0.09 cu.m per 10 sq.m area. The chippings shall satisfy the quality requirements spelled out in Table- VIII except that the upper limit for flakiness Index shall be 30.

c) Fine Aggregate for Type B Seal Coat

The fine aggregate shall be sand or fine grit and shall consist of clean, hard, durable, uncoated dry particles and shall be free from dust, soft or flaky material, organic matter or other deleterious substances. The aggregate shall pass 1.7 mm sieve and be retained on 180 micron sieve. The quantity used for premixing shall be 0.06 cubic metre per 10 square metre area.

3.12.03 Construction Operations

a) Preparation of Base

The seal coat shall be applied immediately after laying the bituminous course which is required to be sealed. Before application of seal coat, the surface shall be cleaned free of any dust or other extraneous matters.

b) Construction of Type- A Seal Coat

The binder shall be heated in boilers of suitable design to the temperature appropriate to the grade of bitumen approved by the Engineer and sprayed on the dry surface in a uniform manner preferably with the help of mechanical sprayers. Excessive deposits of binder caused by stopping or starting of the sprayer or through leakage or due to any other reason shall be suitably corrected before the stone chippings are spread.

Immediately after the application of binder, stone chippings in a dry and clean state shall be spread uniformly on the surface preferably by means of a mechanical grittier or otherwise manually so as to cover the surface completely. If necessary the surface shall be broomed to ensure uniform spread of chippings.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 247 of 361

Immediately after the application of the cover material, the entire surface shall be rolled with a 8 - 10 tonne smooth wheeled roller. Rolling shall commence at the edges and progress towards the centre except in superelevated portions where it shall proceed from the inner edge to the outer. Each pass of the roller shall uniformly overlap not less than one third of the track made in the preceding pass. While rolling is in progress additional chippings shall be spread by hand in whatever quantities required to make up the irregularities. Rolling shall continue until all aggregate particles are firmly bedded in the binder and present a uniform closed surface.

c) Construction of Type-B Seal Coat

Mixers of approved type shall be employed for mixing the aggregates with the bituminous binder.

The binder shall be heated in boilers of suitable design to the temperature appropriate to the grade of bitumen approved by the Engineer. Also the aggregates shall be dry and suitably heated to a temperature as directed by the Engineer before the same are placed in the mixer. Mixing of binder with aggregates to the specified proportions shall be continued till the latter is thoroughly coated with the former.

The mix shall be immediately transported from the mixing plant to the point of use and spread uniformly on the bituminous surface to be sealed.

As soon as sufficient length has been covered with the premixed material, the surface shall be rolled with 6 - 8 tonne smooth wheeled power rollers. Rolling shall be continued till the premixed material completely seals the voids in the bituminous course and a smooth uniform surface is obtained.

3.12.04 Opening to Traffic

In case of Type-B Seal coat, traffic may be allowed soon after the final rolling when the premixed materials are cooled down to the surrounding temperature. However in case of Type- A seal coat, the traffic shall not be permitted until the following day.

3.13.00 Repair of Existing Water Bound Macadam Surfaces

Pot holes or patches and ruts in the water bound macadam base or surface course which is to be surface treated shall be repaired by removing all loose materials by cutting in rectangular patches and replacing with suitable materials. The repair shall be done as under.

Pot holes, patches and ruts shall be drained of water and cut to regular shape with vertical sides and then be filled either with i) Coarse aggregate and screenings conforming to the specification for water bound macadam and compacted with rollers or other approved rammer etc or ii) premixed material



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 248 of 361

conforming to the specification for open graded premix carpet and compacted with rollers or other approved means after painting the sides and bottom of the holes with a thin application of bitumen or a combination of both as directed by the Engineer.

3.14.00 Road Side Drains

3.14.01 Drains

The road side drains shall be made in sizes and slopes as shown on approved drawings. The sides and bottom shall be neatly dressed after excavation. Proper connections shall be made to the culverts outside the plant area as per drawings and instructions of the Engineer.

The excavated spoils other than that required for backfilling shall be transported and filled in low areas within the plant area or in embankments as instructed by the Engineer. The lining for the drains shall be as per drawing. Lining of drains may be of bricks or cement concrete blocks of M15 grade concrete as shown on approved drawing or as directed by the Engineer. If shown on approved drawing, drains may be of R.C.C. construction with necessary slopes.

3.15.00 Culverts

Excavation in trenches for foundation of culverts and wing walls shall be done with side slopes as per the drawings and instructions of the Engineer after clearing the site etc. As per the specification of earthwork, backfilling in layers with watering and compaction shall be done after the construction of foundations. The construction of culverts shall be done true to the lines and levels as shown on the drawings. The specification for Masonry and/or Plain and Reinforced Cement concrete shall be followed as applicable.

3.16.00 Pipe Culverts and Drainage Pipes

3.16.01 Materials

The drainage pipes shall be made of R.C.C and shall be either class NP-2 or NP-3 as shown on the approved drawings.

Pipe culverts shall be made of reinforced concrete pipe and shall be of class NP4 or of RDSO class for railway as shown in the drawing. All pipes shall meet the requirements of IS : 458 and shall be procured from approved manufacturers with collars as per manufacturer's specification. The tenderer shall specifically mention the particular manufacturer's product he proposes to use.

Cement shall be ordinary Portland Cement as per IS : 269.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 249 of 361

Aggregates shall be as per IS : 383. Maximum size shall not exceed one third the thickness of the pipe or 20 mm whichever is smaller.

Fine aggregates for concrete shall be as per IS : 383.

3.16.02 Laying of Pipes

Laying of concrete pipes shall correspond to IS : 783 and as per the specification given below.

- a) The foundation bed for pipe shall be excavated true to lines and grades shown on the drawings and as directed by the Engineer. When trenching is involved, its width on either side of the pipe shall not be less than 150mm and not more than one third the diameter of pipe unless otherwise instructed/permitted by the Engineer. The sides of the trench shall be as nearly vertical as possible. Side slope, shoring, bailing out water etc as required shall be done by the Contractor.

Side slips if there be any shall be removed by the Contractor. After laying of the pipes are completed, backfilling of the trenches shall be done as per the specification of earth work to the satisfaction of the Engineer. The surplus spoils shall be transported and filled in low areas within the plant area as instructed by the Engineer.

When bedrock or boulder stratum is encountered during excavation, the excavation shall be taken down to at least 200mm below the bottom of the pipe with prior permission of the Engineer and all rock/boulders in the area shall be removed and space filled with approved earth free from stone or fragmented materials, shaped to the requirements and thoroughly compacted to provide adequate support for the pipe.

Filling of trench shall be carried out simultaneously on both sides of the pipe in such a manner that unequal pressures do not occur and shall be done as per the specification of earth work.

When two or more pipes are to be laid adjacent to each other, they shall be separated by a distance equal to at least half the diameter of the pipe subject to a minimum of 450 mm.

Laying of pipes shall start from the outlet and proceed towards inlet.

All pipes and fittings shall be gradually lowered into the trench or placed on the supports by approved means taking due care not to damage them. Under no circumstances the pipes shall be dropped into the trench or on supports from the height.

- b) Pipe bedding shall be first class projection bedding for positive projecting pipes as per IS : 783 having a projection ratio not greater than 0.70. The pipe shall be carefully laid on bedding made up of fine granular materials in an earth foundation; the bedding shall be carefully shaped to fit the lower part of the pipe exterior for at least ten percent of its overall height and in which the fill material is thoroughly compacted in



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 250 of 361

layers not exceeding 150mm in depth around the pipe for the remainder of the pipe laid in trench.

When indicated on the drawings or directed by the Engineer, the pipe shall be bedded on a cradle constructed of concrete having a mix not leaner than M15. The shape and dimension of the cradle shall be as indicated on the drawing or as directed by the Engineer. The pipe shall be laid on the concrete bedding before the concrete is set.

- c) The drop walls shall be made with first class brickwork in 1:4 cement mortar.
- d) The pipe culverts shall be made with proper care with respect to the invert of the pipe, gradient if any etc as specified on drawings and as instructed by the Engineer.
- e) Where R.C.C pipes are encased in concrete at road crossings or at other places the pipes need be suitably supported avoiding reinforcements of concrete blocks, joints properly done before concreting is taken up. Concreting of total height of block may be done in a single operation or may be done upto some height for pipes to be properly laid in position and the balance height of the block shall be concreted subsequently.
- f) The R.C.C. pipes shall be joined with cement mortar. Cement mortar shall consist of 1 part cement and 2 part of clean sand with only enough water for workability. Procedure of jointing shall be as per IS : 783.

3.16.03 Relation With Water Supply Pipeline

Unless specifically cleared by the Engineer, under no circumstances shall the drainage pipes be allowed to come close to water supply pipelines.

3.17.00 Manholes and Inspection Chambers

The maximum distance between the manholes shall be 30m unless specifically permitted otherwise. In addition, at every change of alignment, gradient or diameter there shall be a manhole or inspection chamber. The distance between the manhole or inspection chamber and gully chamber shall not exceed 6 meters unless permitted otherwise. Manhole shall be constructed so as to be water tight under test. The channel or drain at the bottom of chamber shall be plastered with 1:2 cement sand mortar and finished smooth to the grade. The channels and drains shall be shaped and laid to provide smooth flow.

Connection to existing pipelines shall be through a manhole.

Manholes shall be provided with standard covers usually of C.I. or as directed by the Engineer. The cover shall be closely fitted so as to prevent gases from coming out.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 251 of 361

4.00.00 Testing And Acceptance Criteria

All testing as mentioned in the specification and as mentioned in Clause No. 900 of the "Specification for Roads and Bridge Works, 1983" published by IRC on behalf of Ministry of Shipping and Transport (Roads Wing) shall be carried out by the Contractor as per the direction of the Engineer.

SECTION - D

SUB-SECTION – D17

FABRICATION OF STRUCTURAL STEEL WORK



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 252 of 361`



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 253 of 361

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.0	SCOPE
2.00.00	GENERAL
3.00.00	WORKMANSHIP
4.00.00	INSPECTION, TESTING, ACCEPTANCE <u>CRITERIA AND DELIVERY</u>
5.00.00	INFORMATION TO BE SUBMITTED
6.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 254 of 361

FABRICATION OF STRUCTURAL STEEL WORK

1.00.00 SCOPE

This specification covers supply, fabrication, testing, painting and delivery to site of structural steelwork including supply of all consumable stores and rivets, bolts, nuts, washers, electrodes and other materials required for fabrication and field connections of all structural steelwork covered under the scope of the contract.

2.00.00 GENERAL

2.01.00 Work to be provided for by the Contractor

The work to be provided for by the Contractor, unless otherwise specified elsewhere in the contract, shall include, but not be limited to the following

- a) Preparation of complete detailed fabrication drawings and erection marking drawings required for all the structures covered under the scope of the contract based on the approved design drawings. As decided by the Engineer, some or all of these detailed drawings will have to be submitted for approval.
- b) To submit revised design with calculations and detailed fabrication drawings in case any substitution of the designed sections are to be made.
- c) To submit design calculations for joints and connections developed by the contractor along with detailed fabrication drawings.
- d) Furnish all materials, labour, tools and plant and all consumables required for fabrication and supply, all necessary rivets, bolts, nuts, washers, tie rods and welding electrodes for field connections,
- e) Furnish shop painting of all fabricated steelwork as per requirements of this Specification.
- f) Suitably mark, bundle, and pack for transport all fabricated materials.
- g) Prepare and furnish detailed Bill of Materials, Drawing Office Dispatch lists, Rivet and Bolt List and any other list of bought out items required in connection with the fabrication and erection of the structural steelwork.
- h) Insure, load and transport all fabricated steelwork field connection materials to site.
- i) Maintain a fully equipped workshop at site for fabrication, modification and repairs of steelwork at site as may be required to complete the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 255 of 361

works in accordance with the Contract.

j) Specific technical requirements are given in Section –C of this document. In case of any contradiction between Section –D and Section –C , requirements as given in Section –C shall prevail.

2.02.00 Work by others

No work under this specification will be provided for by any agency other than the contractor, unless specifically mentioned otherwise elsewhere in the contract.

2.03.00 Codes and standards

All work under this specification shall, unless otherwise specified in the contract, conform to the requirements of the latest revision and/or replacements of the following or any other relevant Indian Standard specifications and codes of practice. In case any particular aspect of the work is not specifically covered by any Indian Standard specification, any other standard practice, as may be specified by the Engineer shall be followed:

- IS : 226 - Structural steel (Standard Quality)
- IS : 800 - Code of Practice for general construction in steel.
- IS : 806 - Code of practice for use of steel tubes in general building construction.
- IS : 808 - Rolled steel beams, channels, and angle sections
- IS : 813 - Scheme of symbols for welding
- IS : 814 - Covered electrodes for metal arc welding of structural steel
- IS : 815 - Classification and coding of covered electrodes for metal arc welding of structural steels.
- IS : 816 - Code of practice for use of metal arc welding for general construction in mild steel
- IS : 817 - Code of practice for training and testing metal arc welders
- IS : 818 - Code of practice for safety and health requirements in electric and gas welding and cutting operations
- IS : 822 - Code of practice for inspection of welds
- IS : 919 - Recommendations for limits and fits for Engineering
- IS : 961 - Structural Steel (High Tensile)
- IS : 1148 - Rivet bars for structural purposes



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 256 of 361

- IS : 1149 - High tensile rivet bars for structural purposes
- IS : 1161 - Steel Tubes for structural purposes
- IS : 1200 - Method of measurement of steelwork and ironwork (Part 8)
- IS : 1239 - Mild Steel Tubes
- IS : 1363 - Black hexagon bolts, nuts and lock nuts (dia. 6 to 30 mm) and black hexagon screws (dia 6 to 24 mm)
- IS : 1364 - Precision and semi-precision hexagon bolts, screws, nuts and locknuts (dia, range 6 to 39 mm)
- IS : 1367 - Technical supply conditions for threaded fasteners
- IS : 1442 - Covered electrodes for the metal arc welding of high tensile structural steel
- IS : 1608 - Method for tensile testing of steel products other than sheet strip, wire and tube
- IS : 1730 - Dimensions for steel plate, sheet, and strip for structural and general engineering purposes.
- IS : 1731 - Dimensions for steel flats for structural and general engineering purposes
- IS : 1852 - Rolling and cutting tolerances for hot-rolled steel products
- IS : 1977 - Structural steel (ordinary quality) St-42-0
- IS : 2062 - Steel for General Structural Purposes
- IS : 2074 - Ready mixed paint, red oxide Zinc chromate priming
- IS : 2595 - Code of Practice for Radiographic Testing
- IS : 2629 - Recommended practice for Hot-Dip Galvanizing of Iron and Steel
- IS : 2633 - Method for testing uniformity of coating on Zinc Coated Articles
- IS : 3757 - High strength structural bolts
- IS : 4759 - Specifications for Hot-Dip Zinc Coatings on Structural Steel and other allied products
- IS : 7205 - Safety Code for Erection of Structural Steelwork



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 257 of 361

IS : 7215 - Tolerances for fabrication of steel structures

IS : 7280 - Bare wire electrodes for submerged arc welding of structural steels.

IS : 9595 - Recommendations for metal arc welding of carbon and carbon manganese steels.

2.04.00 Conformity with Designs

The contractor shall design all connections, supply and fabricate all steelwork and furnish all connection materials in accordance with the approved drawings and/or as instructed by the Engineer keeping in view the maximum Utilization of the available sizes and sections of steel materials. The methods of painting, marking, packing and delivery of all fabricated materials shall be in accordance with the provisions of the contract and/or as approved by the Engineer. Provision of all relevant Indian Standard Specifications and Codes of Practice shall be followed unless otherwise specified in the contract.

2.05.00 Materials to be used

2.05.01 General

All steel materials required for the work will be supplied by the contractor unless otherwise specified elsewhere in the contract. The materials shall be free from all imperfections, mill scales, slag intrusions, laminations, fittings, rusts etc. that may impair their strength, durability, and appearance. All materials shall be of tested quality only unless otherwise permitted by the Engineer and/or Consultant. If desired by the Engineer, Test Certificates in respect of each consignment shall be submitted in triplicate. Whenever the materials are required to be used from unidentified stocks, if permitted by the Engineer, a random sample shall be tested at an approved laboratory from each lot of 50 tones or less of any particular section.

The arc welding electrodes shall be of approved reputed manufacture and conforming to the relevant Indian Standard Codes of Practice and Specifications and shall be of heavily coated type and the thickness of the coating shall be uniform and concentric. With each container of electrodes, the manufacturer shall furnish instructions giving recommended voltage and amperage (Polarity in case of D.C. supply) for which the electrodes are suitable.

2.05.02 Steel

All steel materials to be used in construction within the purview of this specification shall comply with any of the following Indian Standard



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 258 of 361

Specifications as may be applicable:

- a) IS : 2062 - Steel for general structural purposes
- b) IS : 961 - Structural steel High Tensile
- c) IS : 1977 - Structural steel (Ordinary quality) St-42-0

In case of imported steel materials being used, these shall conform to specifications equivalent to any of the above as may be applicable.

2.05.03 Rivet Steel

All rivet steel used in construction within the purview of this Specification shall comply with one of the following Indian Standard Specifications as may be applicable:

- a) IS : 1148 - Rivet Bars for structural purpose
- b) IS : 1149 - High tensile rivet bars for structural purposes. Where high tensile steel is specified for rivets, steps shall be taken to ensure that the rivets are so manufactured that they can be driven and heads formed satisfactorily without the physical properties of steel being impaired.

2.05.04 Electrodes

All electrodes to be used under the Contract shall be of approved reputed manufacture and shall comply with any of the following Indian Standard Specifications as may be applicable

- a) IS : 814 - Covered electrodes for metal arc welding of structural steel
- b) IS : 815 - Classification and coding of covered electrodes for metal arc welding of mild steel and low alloy high tensile steel
- c) IS : 1442 - Covered electrodes for the metal arc welding of high tensile structural steel
- d) IS : 7280 - Bare wire electrodes for submerged arc welding of structural steels

2.05.05 Bolts and Nuts

All bolts and nuts shall conform to the requirements of Indian Standard Specification IS: 1367 - Technical Supply Conditions for Threaded Fasteners.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 259 of 361

Materials for Bolts and nuts under the purview of this contract shall comply with any of the following Indian Standard Specifications as may be applicable.

a) Mild Steel

All mild steel for bolts and nuts when tested in accordance with the following Indian Standard Specification shall have a tensile strength of not less than 44 Kg/mm² and a minimum elongation of 23 per cent on a gauge length of 5.6 $\sqrt{A}$, where "A" is the cross sectional area of the test specimen

- i) IS: 1367: Technical supply conditions for threaded fasteners
- ii) IS: 1608: Method for tensile testing of steel products other than sheet, strip, wire and tube

b) High Tensile Steel

The material used for the manufacture of high tensile steel bolts and nuts shall have the mechanical properties appropriate to the particular class of steel as set out in IS: 1367 or as approved by the Engineer.

2.05.06 Washers

Washers shall be made of steel conforming to any of the following Indian Standard Specifications as may be applicable under the provisions of the Contract:

- a) IS : 2062 - Steel for general structural purposes
- b) IS : 961 - Structural Steel (High Tensile Quality)
- c) IS : 1977 - Structural steel (Ordinary Quality) St-42-0
- d) IS : 6649 - Hardened washers

2.05.07 Paints

Paints to be used for shop coat of fabricated steel under the purview of this contract shall conform to the Indian Standard Specification IS: 2074 - Ready mixed Paint, Red oxide Zinc Chromate Priming.

2.06.00 Coal Bin

- 2.06.01** Shape of bins shall be circular, polygonal, square, or rectangular in plan. Bottom hopper portion may have be conical-cum-hyperbolic or any other profile shape as shown in the drawing. Bin shall be termed as bunkers or silos



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 260 of 361

according to their shape and plane of rupture of coal.

2.06.02 For general requirements, fabrication and construction details IS: 9178 (Pt.I & 11) shall be followed as general guidance. The bins shall be fabricated and erected in segments.

2.06.03 The Coal bins shall be made of mild steel plates joined together with full strength butt weld and provided with stiffeners at regular interval. Stiffeners shall be provided on the external face and it may be welded with external face.

2.06.04 Bending of plates and rolled sections to the required shape for fabrication shall be done by plate bending machine or cold bending process Without resorting to heating, hammering, angle smithy and black smithy process.

2.06.05 Poking hole (manual or pneumatic) and striking plate shall be provided to facilitate coal flow. Poking holes shall have circular MS pipe and cover cap as detailed in the drawing.

2.07.00 New Erection Marks

2.07.01 Additional structures involving new erection marks may be required to be added at any stage of work.

2.07.02 All such new erection marks shall be detailed and included in marking schemes and fabrication carded out thereafter.

2.07.03 All such new erection marks shall be considered under item of original fabrication work. As a result of additional structures becoming necessary if the work is delayed beyond the time schedule stipulated, the Engineer shall give suitable extension of time provided he is satisfied about the reasonableness of the delay involved. However, no claim for extra payments or revision of rates due to delay shall be entertained.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 261 of 361

2.08.00 ELECTRO FORGED STEEL GRATINGS

- 2.08.01** Factory made fabricated electro forged gratings unit with steel conforming to IS: 2062 shall be supplied, fabricated, transported, erected and aligned in floorings, platforms, drain and trench covers, walkways, passages, staircases with edge binding strips and anti skid nosing in treads etc.
- 2.08.02** All grating units shall be rectangular in pattern and electro forged. The size and the spacing of the bearing bars and cross bars shall be as detailed in fabrication drawings. The contractor shall submit the grating design for different spans and load intensities along with fabrication drawings. The depth of the grating unit shall be 40 mm, unless specified otherwise.
- 2.08.03** The gratings shall be made up in panel units designed to coincide with the span of the structural steel framing or openings as indicated in the design/scope drawings. Maximum possible standardization of the grating panel sizes shall be tried and designed.
- 2.08.04** The grating unit shall be accurately fabricated and finished, free from wraps, twists, or any defects that would impair their strength, serviceability, and appearance.
- 2.08.05** Grating work shall include cut outs and clearance opening for all columns, pipes, ducts, conduits or any other installation penetrating through the grating work. Such cut outs and clearances shall be treated as specified in subsequent clauses.
- 2.08.06** The gratings shall be notched, trimmed and neatly finished around flanges and webs of the columns, moment connections, cap plates, and such other components of the steel structures encountered during the placement of the gratings. In all such cases, the trimming shall be done to follow the profile of the components encountered. After trimming, the binding strip shall be provided on the grating to suit the profile so obtained.
- 2.08.07** Opening in gratings for pipes or ducts that are 150mm in size or diameter or larger shall be provided with steel bar toe plates of not less than 5mm thickness and appropriate width, set flush with the bottom of the bearing bars.
- 2.08.08** Penetrations in gratings that are more than 50mm but less than 150mm in size or diameter shall be welded with plates of size shown in the detailed drawings set flush with the bottom of the grating panel.
- 2.08.09** Unless otherwise indicated on the drawings, grating units at all penetrations shall be made up in split section, accurately fitted and neatly finished to provide for proper assembly and erection at the job site.
- 2.08.10** Grating units shall be provided with all necessary clips, bolts, nuts and lock washers required for proper assembly and rigid installation and fastening to



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 262 of 361

abutting units supporting structural steel framing members.

2.08.11 The gratings shall be of reputed make and manufacturer, as approved by Engineer. The unit rate quoted by him for this item shall be inclusive of transport of gratings to the project site, all taxes, duties etc. He shall also provide all facilities and access to the Engineer or his representative to carry out inspection during all stages of manufacturing of gratings.

2.08.12 Maximum deviation in linear dimension from the approved dimension shall not exceed 12mm.

2.08.13 All fabricated grating section and accessories shall be blast cleaned to near white metal surface (Sa 2½) followed by either of the following two:

(a) Two coats of red lead primer and two coats of black enamel finish paint.

(b) Hot dipped galvanization at 610 gm/sq.m.

in the shop prior to erection at site, as the approved drawing.

2.08.14 Prior to finishing all surfaces shall be cleaned, free from rust, mill scale, grease, oil, or any other foreign matter by blast cleaning. BS: 4232 shall be followed for blast cleaning.

2.08.15 Primer can be applied by spray guns or by brushes, however the finish paint shall necessarily be applied by means of spray guns. The applied coatings shall be uniform, free from voids and streaks; drilled or punched holes shall be touched up prior to erection or assembly.

2.09.00 GALVANIZATION OF GRATINGS

2.09.01 Purity of Zinc to be used-for galvanizing shall be 99.5% as per IS: 2 15

2.09.02 After the shop work is complete, the structural material shall be punched with erection mark and be hot double dip galvanized. Before galvanizing the steel section shall be thoroughly blast cleaned to near white metal surface (Sa 2½).

2.09.03 The weight of the zinc coating shall be at least 610 gm/m² - unless noted otherwise.

2.09.04 The galvanized surface shall consist of a continuous and uniformly thick coating of zinc, firmly adhering to the surface of steel. The finished surface shall be cleaned and smooth and shall be free from defects like discoloured patches, bare spots, unevenness of coating, spelter that is loosely attached to the steel, blistered surface, flaking or peeling off etc. The presence of any of these defects noticed on visual or microscopic inspection shall render the material liable to rejection.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 263 of 361

2.09.05 There shall be no flaking or loosening when struck squarely with a chisel faced hammer. The galvanized steel member shall withstand minimum four one minute dips in copper sulphate solution as per IS: 2633.

2.09.06 When the steel section is removed from the galvanizing kettle, excess spelter shall be removed by 'bumping'. The processes known as 'wiping' or 'scrapping' shall not be used for this purpose.

2.09.07 Defects in certain members indicating presence of impurities in the galvanizing bath in quantities larger than that permitted by the specifications or lack of quality control in any manner in the galvanizing plant, shall render the entire, production in the relevant shift liable to rejection.

2.09.08 All structural steel shall be treated with sodium dichromate or an approved equivalent solution after galvanizing; so as to prevent white storage stains.

2.09.09 If the galvanizing of any member is damaged, the Engineer shall be shown of the extent of damage, if so directed the galvanizing may have to be redone in the similar manner as stated above at no extra cost to the Owner.

2.10.00 STAINLESS STEEL HOPPERS

2.10.01 Material

Stainless steel hopper of grade SS 4 15M as manufactured by SAIL or equivalent shall be provided in the lower portion of bunker hopper. SS 4 15M having the following chemical composition shall be used.

Material	%	Remarks
Carbon	10.03%	Max.
Silicon	1.60%	Max.
Manganese	0.80% to 1.50%	
Phosphorous	0.03%	Max.
Sulphur	0.03%	Max.
Chromium	10.80% to 12.50%	
Nickel	1.50%	Max.
Titanium	0.75%	Max.
Nitrogen	0.03%	Max.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 264 of 361

The mechanical properties shall be as follows:

Description	Value	Remarks
Hardness Rock Well B Scale	90	Max.
Tensile Strength	450 MPa	Min.
Yield Strength	300 MPa	Min.
Elongation	25%	Min.

2.10.02 Fabrication

The fabrication, erection, alignment and welding shall be carried out as per the accepted practice and in accordance with relevant I.S. and international specification as well as stipulations contained herein. Fabrication drawings shall be prepared by the contractor on the basis of the design / scope drawings furnished by Engineer. The fabrication and erection works shall be done as per the approved fabrication drawings.

2.10.03 Fabrication Drawings

- Fabrication drawing shall give the cutting plan for each hopper plate. Such, cutting plan shall be based on the size of the Stainless Steel plate available at store. In order to reduce the wastage and ensure the maximum utilization of stainless steel plate, the cutting plan shall take in the consideration of the reverse curvature and place the various elements of hopper plate in opposite fashion to reduce the end wastage. Similarly the hopper plate element having different radii shall be placed one inside the other, to optimize the stainless steel plate use. Such optimization may also required adjustment in the size of the each element of hopper plate and also additional weld joints.
- The bill of material of hopper plate shall indicate the inner surface area of the hopper, weight of the hopper based on the inner surface area, weight of each of the cut plate of hopper fabrication, weight of cut and scrap pieces generated. Contractor shall return to the Owner's store all unutilized (surplus) stainless steel plates and all waste and cut pieces generated. Non return of any part of the surplus/waste steel pieces to the Owner's store will call for the penal recovery at three (03) times the maximum procurement rate for the weight of stainless steel pieces not returned to the store.
- In case the contractor does the cutting of the stainless steel without approved cutting plan then all the wastage (i.e. the difference between the weight of stainless steel plate cuts and the actual finished weight considered for the measurement for payment) shall be subjected to the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 265 of 361

penal recovery at the rate mentioned above.

2.10.04 Cuffing

Cutting may be affected by shearing, or by using plasma. The cut edges of all plates shall be perfectly straight and uniform through out. Cutting shall be done as per the cutting plan shown in the fabrication drawing. Should the Engineer find it necessary, the edges shall be ground smooth afterwards by contractor within the unit rates quoted by him. All the edge s shall be ground smooth before they are welded.

2.10.05 Jointing

Welding shall join stainless steel. All weld joints (along the inclined plane) shall be staggered. Any common welding process can weld stainless steel viz. MIG, metal arc or plasma using the covered compatible electrodes as per IS: 5206 or by inert gas arc welding as per IS: 2811. Shielding gas shall be Argon + Hydrogen mixture or Argon + Oxygen mixture. However, Argon + Oxygen mixture shall be preferred. Carbon-di-oxide mixture shall be avoided. 308L and 315L electrodes/fillers shall be used for the welding of Stainless Steel to Stainless Steel and Stainless Steel to Mild Steel respectively. However, the welding process and the type of the electrodes to be used for welding shall be as per welding procedure, as approved by the Engineer. On the basis of the welding procedure, the Contractor shall conduct qualification test.

2.10.06 Bending

The stainless steel plates shall be subjected to cold forming and bending in order to get the desired shape and profile.

2.10.07 Welding sequence

The type of electrodes, welding sequence, preheat and interpass temperature and post weld heat treatment shall be as approved by the Engineer.

2.10.08 Acceptance Criteria of Fabricated Structures

The acceptance of the fabricated structure work shall depend upon correct dimensions and alignment, absence of distortion in the structure, satisfactory results from the inspection and testing of the welded structure joints and the test specimens, general workmanship being good meeting the tolerance requirements given in IS: 7215.

2.11.00 BEARINGS

2.11.01 PTFE (Poly tetra fluorethylene) slide bearing

a) General

The bearings shall consist of upper and lower units. The upper unit shall include a sole plate with mirror finish stainless steel facing bonded to the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 266 of 361

bottom surface of the sole plate. The lower unit shall consist of a relevant laminated elastomers pad surfaced with PTFE. A rigid confining medium substructure bonds the PTFE to the pad. When the upper and lower units are mated the stainless steel slides on the PTFE surface with an extremely low coefficient of friction. These bearings shall be designed as per the performance requirements. The bearing shall be of reputed make and manufacturer as approved by Engineer, for required vertical loads, as per the construction drawings and for a maximum displacement of ± 50 mm.

b) Material

PTFE bearing shall be sliding against highly polished stainless steel and the coefficient of friction between them shall be less than 0.06 at 55 kg/cm². In order to prevent cold flow in the PTFE surface it shall be rigidly bonded by a special high temperature resistant adhesive to the stainless steel sub-strata. The stainless steel surface, which slides against the PTFE, is mirror polished. The stainless steel shall be bonded to the top plate by special high strength adhesive. The thickness of the stainless steel shall be between 1.0 to 1.5mm.

The resilient bearing pad shall consist of multiple layers of lightweight fabric impregnated with a high quality elastomer compound vulcanized into slabs of uniform standard thickness as per the requirement. This shall withstand vertical (compressive) load not less than 500 kg/cm² and shear loads upto 40 kg/cm².

c) Installation

The seating area for PTFE bearing shall be prepared accurately level and furnished with a thin layer of epoxy resin mortar. The bearing will be placed on this layer while it is still workable and the bearing is levelled. The bearing should not be displaced as the beam is lowered into position. When the mortar and adhesive are fully set and the beam slightly above the top of the bearing. The upper surface of the bearing shall then be coated with sufficient thickness of epoxy resin mortar so that when the beam is lowered on to the temporary supports it comes into full contact with the mortar and some is squeezed out. The surplus shall be troweled off and after the mortar is fully set the temporary supports removed.

2.12.00 Storage of material

2.12.01 General

All materials shall be so stored as to prevent deterioration and to ensure the preservation of their quality and fitness for the work. Any material, which has deteriorated or has been damaged, shall be removed from the contractor's yard immediately, failing which, the Engineer shall be at liberty to get the material removed and the cost incurred thereof shall be realised from the Contractor.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 267 of 361

The Contractor shall maintain upto date accounts in respect of receipt, use, and balance of all sizes and sections of steel and other materials. In case the fabrication is carried out in contractor's fabrication shop outside the plant site where other fabrication works are also carried out, all materials meant for use in this contract shall be stacked separately with easily identifiable marks.

2.12.02 Steel

The steel to be used in fabrication and the resulting cut-pieces shall be stored in separate stacks off the ground section wise and lengthwise so that they can be easily inspected, measured, and accounted for at any time. If required by the Engineer, the materials may have to be stored under cover and suitably painted for protection against weather.

2.12.03 Electrodes

The electrodes for electric arc welding shall be stored in properly designed racks, separating different types of electrodes in distinctly marked compartments. The electrodes shall be kept in a dry and warm condition if necessary by resorting to heating.

2.12.04 Bolts, Nuts and Washers

Bolts, nuts and washers and other fastening materials shall be stored on racks off the ground with a coating of suitable protective oil. These shall be stored in separate gunny bags or compartments according to diameter, length, and quality.

2.12.05 Paints

Paints shall be stored under cover in air tight containers. Paints supplied in sealed containers shall be used up as soon as possible once the container is opened.

2.13.00 Quality Control

The Contractor shall establish and maintain quality control procedures for different items of work and materials to the extent he deems necessary to ensure that all work is performed in accordance with this specification. In addition to the Contractor's quality control procedures, materials and workmanship at all times shall be subjected to inspection by the Engineer or Engineer's representative. As far as possible, all inspection by the Engineer or Engineer's representative shall be made at the Contractor's fabrication shop whether located at Site or elsewhere. The Contractor shall co-operate with the Engineer or Engineer's representative in permitting access for inspection to all places where work is being done and in providing free of cost all necessary help in respect of tools and plants, instrument, labour and materials required to carry out the inspection. The inspection shall be so scheduled as to provide



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 268 of 361

the minimum interruption to the work of the Contractor.

Materials or workmanship not in reasonable conformance with the provisions of this Specification may be rejected at any time during the progress of the work.

The quality control procedure shall cover but not be limited to the following items of work

- a) Steel: Quality manufacturer's test certificates, test reports of representative samples of materials from unidentified stocks if permitted to be used.
- b) Rivets, Bolts, Nuts & Washers : Manufacturer's certificate, dimension checks, material testing.
- c) Electrodes : Manufacturer's certificate, thickness and quality of flux coating.
- d) Welders : Qualifying Tests
- e) Welding sets : Performance Tests
- f) Welds : Inspection, X-ray, Ultrasonic tests
- g) Paints : Manufacturer's certificate, physical inspection reports
- h) Galvanizing : Tests in accordance with IS 2633 - Method for testing uniformity of coating on Zinc Coated Articles and IS : 4759 - Specification for Hot-Dip Zinc coatings on Structural Steel and other allied products.

2.14.00 Standard dimensions, forms and weights

The dimensions, forms, weights and tolerances of all rolled shapes rivets, bolts, nuts, studs, washers etc. and other members used in the fabrication of any structure shall, wherever applicable, conform to the requirements of the latest relevant Indian Standards, wherever they exist, or, in the absence of Indian Standards, to other equivalent standards.

2.15.00 Fabrication Drawings

The contractor shall within thirty (30) days after the award of the Contract submit to the Engineer the Schedule of Fabrication and erection of structural Steelworks, for approval. Within one week after receipt of approval on design of any steel structure (part or full) based on the approved design. As decided



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 269 of 361

by the Engineer, six (6) copies each of some or all of the detailed fabrication drawings will have to be submitted for approval.

The sequence of preparation of fabrication drawings shall match with the approved fabrication and erection schedule. The above-mentioned approval for fabrication drawings will be accorded only towards the general conformity with the design requirements as well as specifications. The approval of drawing however shall not relieve the contractor of his sole responsibility in carrying out the work correctly and fulfilling the complete requirements of contract documents.

The fabrication drawings shall include but not limited to the following:

- a) Assembly drawings giving exact sizes of the sections to be used and identification marks of the various sections.
- b) Dimensional drawings of base plates, foundation bolts location etc.
- c) Comparison sheets to show that the proposed alternative section, if any, is as strong as the original sections shown on the Design Drawings.
- d) Complete Bill of Materials and detailed drawings of all sections as also their billing weights.
- e) Any other drawings or calculations that may be required for the clarification of the works or substituted parts thereof.

These drawings shall give all the necessary information for the fabrication, erection, and painting of the steelwork in accordance with the provisions of this Specification. Fabrication drawings shall be made in accordance with the best modern practice and with due regard to sequence, speed and economy in fabrication and erection. Fabrication drawings shall give complete information necessary for fabrication of the various components of the steelwork, including the location, type, size, and extent of welds. These shall also clearly distinguish between shop and field rivets, bolts, and welds and specify the class of bolts and nuts. The drawings shall be drawn to a scale large enough to convey all the necessary information adequately. Notes on the fabrication drawings shall indicate those joints or groups of joints in which it is particularly important that the welding sequence and technique of welding shall be carefully controlled to minimize the locked up stresses and distortion. Welding symbols used shall be in accordance with the requirements of the Indian Standard Specification. IS: 813 - Scheme of symbols for Welding, and shall be consistent throughout. Weld lengths called for on the drawings shall mean the net effective length.

The Contractor shall be responsible for and shall carry out at his cost any alterations of the work due to any discrepancies, errors or omissions on the drawings or other particulars supplied by him, whether such drawings or other



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 270 of 361

particulars have been duly approved or not in accordance with the Contract.

3.00.00 WORKMANSHIP

3.01.00 Fabrication

3.01.01 General

All workmanship shall be equal to the best practice in modern structural shops, and shall conform to the provisions of the Indian Standard IS: 800 - Code of Practice for general construction in steel and other relevant Indian Standards or equivalent.

3.01.02 Straightening Material

Rolled materials before being laid off or worked, must be clean, free from sharp kinks, bends or twists and straight within the tolerances allowed by the Indian Standard Specification on IS: 1552 - Specification for rolling and cutting tolerance for hot-rolled steel products. If straightening is necessary, it may be done by mechanical means or by the application of a limited amount of localized heat. The temperature of heated areas, as measured by approved methods, shall not exceed 600°C.

3.01.03 Cutting

Shearing, cropping, or sawing shall affect cutting. Use of a mechanically controlled gas-cutting torch may be permitted for mild steel only. Gas cutting of high tensile steel may also be permitted provided special care is taken to leave sufficient metal to be removed by machining, so that all metal that has been hardened by flame is removed. Gas cutting without a mechanically controlled torch may be permitted if special care is taken and done under expert hand, subject to the approval of the Engineer.

To determine the effective size of members cut by gas, 3 mm shall be deducted from each cut edge. Gas cut edges, which will be subjected to substantial stress or which are to have weld metal deposited on them, shall be reasonably free from gouges, occasional notches or gouges not more than 4 mm deep will be permitted. Gouges greater than 4 mm that remain from cutting shall be removed by grinding. All re-entrant corners shall be shaped notch free to a radius of at least 12 mm. Shearing, cropping and gas cutting shall be clean, reasonably square and free from any distortion.

3.01.04 Planning of edges

Planning or finishing of sheared or cropped edges of plates or shapes or of edges gas-cut with a mechanically controlled torch shall not be required, unless specifically required by design and called for on the drawings, included in a stipulation for edge preparation for welding or as may be required after



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 271 of 361

the inspection of the cut surface. Surface cut with hand-flame shall generally be ground, unless specifically instructed otherwise by the Engineer.

3.01.05 Clearances

The erection clearance for cleated ends of members connecting steel to steel shall preferably be not greater than 2 mm at each end. The erection clearance at ends of beams web shall be not more than 3 mm at each end, but where for practical reasons greater clearance is necessary, suitably designed cheatings shall be provided.

3.02.00 Riveted and bolted construction

3.02.01 Holes

Holes through more than one thickness of material for members, such as compound stanchions and girder flanges, shall be drilled after the members are assembled and tightly clamped or bolted together. Punching may be permitted before assembly, if the thickness of the material is not greater than the nominal diameter of rivet or bolt plus 3 mm subject to a maximum thickness of 16 mm provided that the holes are punched 3 mm less in diameter than the required size and reamed after assembly to the full diameter.

Holes for rivets or black bolts shall be not more than 1.5 mm or 2.0 mm (depending on whether the diameter of the rivet or bolt is less or more than or equal to 25 mm) larger in diameter than the nominal diameter of the rivet or black bolt passing through them.

Holes for turned and fitted bolts shall be drilled to a diameter equal to the nominal diameter of the shank or barrel subject to a tolerance grade of BS as specified in IS: 919. Parts to be connected shall be firmly held together by tacking welds or clamps and the holes drilled through all the thicknesses in one operation and subsequently reamed to size. Holes not drilled through all thickness in one operation shall be drilled to a smaller size and reamed out after assembly.

Holes for rivets or bolts shall not be formed by gas cutting process.

3.02.02 Assembly

All parts of riveted members shall be well pinned or bolted and rigidly held together while riveting. Drifting to enlarge unmatching holes shall not generally be permitted. In case drifting is permitted to a slight extent during assembly, it shall not distort the metal or enlarge the holes. Holes that must be enlarged to admit the rivets or bolts shall be reamed. Poor matching of holes shall be cause for rejection. The component parts shall be so assembled that they are neither twisted nor otherwise damaged, and shall be so prepared that the specified cambers, if any, are maintained.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 272 of 361

Rivets shall ordinarily be hot driven, in which case their finished heads shall be approximately hemispherical in shape and shall be of uniform size throughout the work for rivets of the same size full, neatly finished and concentric with the holes. Rivets shall be heated uniformly to a temperature not exceeding 1125°C they shall not be driven after their temperature has fallen below 540°C.

Rivets shall be driven by power riveters, of either compression or manually operated type, employing pneumatic, hydraulic or electric power. Hand driven rivets shall not be allowed unless in exceptional cases specifically approved by the Engineer. After driving, rivets shall be tight, shall completely fill the holes and their heads shall be in full contact with the surface. In case of countersunk rivets, the countersinking shall be fully filled by the rivet, any proudness of the countersunk head being dressed off flush, if required.

Riveted members shall have all parts firmly drawn and held together before and during riveting and special care shall be taken in this respect for all single riveted connections. For multiple riveted connections, a service bolt shall be provided in every third or fourth hole.

All loose, burnt, or otherwise defective rivets shall be cut out and replaced and special care shall be taken to inspect all single riveted connections. Special care shall also be taken in heating and driving long rivets. The Contractor shall prove the quality of riveting by cutting some rivets chosen at random by the Engineer. No extra payment will be made to the Contractor for such cutting and replacing. Riveting work, for any particular section or group, will be considered satisfactory when at least 90% of the corresponding cut rivets is found to be sound. If the ratio is below 75%, all the rivets in the particular section or group shall be cut, removed and replaced and tested again at the Contractor's expense. For cases between 75% and 90% the engineer shall have the option to instruct cutting and replacing any number of further rivets at the Contractor's cost as he deems necessary.

Bolted construction shall be permitted only in case of field connections if called for on the Drawings and is subjected to the limitation of particular connections as may be specified. In special cases, however, shop bolt connections may be allowed if shown on drawing or directed by the Engineer.

Washers shall be tapered or otherwise suitably shaped, where necessary, to give the heads and nuts of bolts a satisfactory bearing. The threaded portion of each bolt shall project through the nut at least one thread. In all cases the bolt shall be provided with a washer of sufficient thickness under the nut to avoid any threaded portion of the bolt being within the thickness of the parts bolted together. In addition to the normal washer one spring washer or lock nut shall be provided for each bolt for connections subjected to vibrating forces or otherwise as may be specified on the Drawings.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 273 of 361

3.03.00 Welded Construction

3.03.01 General

Welding shall be in accordance with relevant Indian Standards and as supplemented in the Specification. Welding shall be done by experienced and good welders who have been qualified by tests in accordance with IS: 817.

3.03.02 Preparation of material

Surface to be welded shall be free from loose scale, slag, rust, grease, paint, and any other foreign material except that mill scale, which withstands vigorous wire brushing, may remain. Joint surfaces shall be free from fins and tears. Preparation of edges by gas cutting shall, wherever practicable, be done by a mechanically guided torch.

3.03.03 Assembling

Parts to be fillet welded shall be brought in, as close contact as practicable and in no event shall be separated by more than 4 mm. If the separation is 1.5 mm or greater, the size of the fillet welds shall be increased by the amount of the separation. The fit of joints at contact surfaces, which are not completely sealed by, welds, shall be close enough to exclude water after painting. Abutting parts to be butt-welded shall be carefully aligned. Misalignments greater than 3 mm shall be corrected and in making the correction the parts shall not be drawn into a sharper slope than two degrees (2°).

The work shall be positioned for flat welding whenever practicable.

3.03.04 Welding Sequence

In assembling and joining parts of a structure or of built-up members, the procedure and sequence of welding shall be such as will avoid needless distortion and minimize shrinkage stresses in the closing welds of a rigid assembly, such closing welds shall be made in compression elements.

In the fabrication of cover-plated beams and built-up members, all shop splices in each component part shall be made before such component part is welded to other parts of the member. Long girders or girder sections may be made by shop splicing not more than three sub-sections, each made in accordance with this paragraph.

When required by the Engineer, welded assemblies shall be stress relieved by heat-treating in accordance with the provisions of the relevant Indian Standard or any other Standard approved by the Engineer.

3.03.05 Welding technique



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 274 of 361

Submerged-Arc-Welding/ process employing semi-automatic welding (GMAW/SAW) shall be used for welding longitudinal fillet welds (connecting flange with web) and longitudinal butt joints for fabrication of columns, framing beams and crane girders, unless manual arc welding is specifically approved by the Engineer. Necessary jigs and fixtures and rotation of structures shall be so arranged that vertically down-hand position of welding become possible. 'Open-Arc-Welding' process employing coated electrodes shall be employed for fabrication of other welded connections and field welding.

All complete penetration groove welds made by manual welding, except when produced with the aid of backing material not more than 8 mm thick with root opening not less than one-half the thickness of the thinner part joined, shall have the root of the initial layer gouged out on the back side before welding is started from that side, and shall be so welded as to secure sound metal and complete fusion throughout the entire cross-section. Groove welds made with the use of the backing of the same material, as the base metal shall have the weld metal thoroughly fused with the backing material. Backing strips need not be removed. If required, they may be removed by gouging or gas cutting after welding is completed, provided no injury is done to the base metal and weld metal and the weld metal surface is left flush or slightly convex with full throat thickness.

Groove welds shall be terminated at the ends of a joint in a manner that will ensure their soundness. Where possible, this should be done by use of extension bars or run-off plates. Extension bars or run-off plates need not be removed upon completion of the weld unless otherwise specified elsewhere in the contract.

3.03.06 Temperature

No welding shall normally be done on parent material at a temperature below (-) 5°C. However, if welding is to undertaken at low temperature, adequate precautions as recommended in relevant Indian Standard shall be taken. When the parent material is less than 40 mm thick and the temperature is between (-) 5°C and 0°C, the surface around the joint to a distance of 100 mm or 4 times the thickness of the material, whichever is greater, shall be preheated till it is hand warm. When the parent material is more than 40 mm thick, the temperature of the area mentioned above shall be in no case be less than 20°C. All requirements regarding preheating of the parent material shall be in accordance with the relevant Indian Standard.

3.03.07 Peening

Where required, intermediate layers of multiple-layer welds may be peened with light blows from a power hammer, using a round-nose tool, peening shall be done after the weld has cooled to a temperature warm to the hand. Care shall be exercised to prevent scaling or flaking of weld and base metal from over peening.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 275 of 361

3.03.08 Equipment

These shall be capable of producing proper current so that the operator may produce satisfactory welds. The welding machine shall be of a type and capacity as recommended by the manufacturers of electrodes or as may be approved by the engineer.

3.04.00 Finish

Column splices and butt joints of compression members depending on contact for stress transmission shall be accurately machined and close-butt over the whole section with a clearance not exceeding 0.1 mm locally at any place. In column caps and bases, the ends of shafts together with the attached gussets, angles, channels etc; after welding/riveting together, should be accurately machined so that the parts connected butt over the entire surfaces of contact. Care should be taken that those connecting angles of channels are fixed with such accuracy that they are not reduced in thickness by machining by more than 1.0 mm.

3.05.00 Slab bases and caps

Bases and caps fabricated out of steel slabs, except when cut material with true surface, shall be accurately machined over the bearing surface and shall be in effective contact with the end of the stanchion. A bearing face, which is to be grouted direct to a foundation, need not be machined if such face is true and parallel to the upper face.

To facilitate grouting, holes shall be provided, where necessary, in stanchion bases for the escape of air.

3. 12.00 Lacing bars

The ends of lacing bars shall be neat and free from burns.

3. 13.00 Separators

Rolled section or built-up steel separators or diaphragms shall be required for all double beams except where encased in concrete, in which case, pipe separators shall be used.

3.14.00 Bearing Plates

Provision shall be made for all necessary steel bearing plates to take up reaction of beams and columns and the required stiffeners and gussets whether or not specified in Drawings.

3.15.00 Floor Grating



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 276 of 361

All grating units shall be rectangular in pattern and of pressure locked assembly. The size and spacing of bearing bars and cross bars shall be as approved in detailed drawings. Alternatively diamond pattern grating if approved may be used.

The grating shall be made in panel units designed to span as indicated in structural steel framing drawing or as directed by the Engineer.

The grating units shall be finished free from warps, twists, or any other defects. Grating work shall include cutouts and clearance openings for all columns, pipes, ducts, conduits etc. The gratings shall be notched, trimmed, and neatly finished around components of the steel structures encountered. Binding strip shall be provided on the grating to suit the profile. Openings in gratings shall be provided with steel bar toe plates of not less than 5 mm thickness and 100 mm width.

Unless otherwise indicated on drawings, all penetrations of grating units shall be made up in split section, accurately fitted, and neatly finished. Grating units shall be provided with all necessary clips, bolts, lock washers etc. for proper assembly and installation on supporting steel members. Maximum deviation in linear dimension shall not exceed 12 mm.

3.10.00 Chequered Plates

Minimum thickness of chequered plate floorings, covers etc. shall be 6 mm O/P. Chequered plate shall be accurately cut to the required sizes and shapes and the cut edges properly ground. Stiffeners shall be provided wherever required from design consideration.

3.11.00 Architectural Clearances

Bearing plates and stiffener connections shall not be permitted to encroach on the designed architectural clearances.

3.11.00 Shop connections

- a) All shop connections shall be otherwise riveted or welded as specified on the Drawings.
- b) Heads of rivets on surfaces carrying brick walls shall be flattened to 10 mm thick projection.
- c) Certain connections, specified to be shop connections, may be changed to field connections if desired by the Engineer for convenience of erection and the contractor will have to make the desired changes at no extra cost to the exchequer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 277 of 361

3.13.00 Castings

Steel castings shall be annealed.

3.14.00 Shop erection

The steelwork shall be temporarily shop-erected complete or as directed by the Engineer so that accuracy of fit may be checked before dispatch. The parts shall be shop-erected with a sufficient number of parallel drifts to bring and keep the parts in place. In case of parts drilled or punched using steel jigs to make all similar parts interchangeable, the steelwork shall be shop erected in such a way as will facilitate the check of interchange ability.

3.15.00 Shop painting

3.15.01 General

Unless otherwise specified, steelwork, which will be concealed by interior building finish, need not be painted; steelwork to be encased in concrete shall not be painted. Unless specifically exempted, all other steelwork shall be given one coat of shop paint, applied thoroughly and evenly to dry surfaces which have been cleaned, in accordance with the following paragraph, by brush, spray, roller coating, flow-coating or dipping as may be approved by the Engineer.

After inspection and approval and before leaving the shop, all steelwork specified to be painted shall be cleaned by hand-wire brushing or by other methods of loose mill scale, loose rust, weld slag or flux deposit, dirt and other foreign matter. Oil and grease deposits shall be removed by the solvent. Steelwork specified to have no shop paint shall, after fabrication, be cleaned of oil or grease by solvent cleaners and be cleaned of dirt and other foreign material by trough sweeping with a fibre brush.

3.15.02 Inaccessible parts

Surfaces not in contact, but inaccessible after assembly, shall receive two coats of shop paint, Positively of different colours to prove application of two coats before assembly. This does not apply to the interior of sealed hollow sections.

3.15.03 Contact surfaces

Contact surface shall be cleaned in accordance with sub-clause 3.13.1 before assembly.

3.15.04 Finished surfaces

Machine finished surfaces shall be protected against corrosion by a rust



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 278 of 361

inhibiting coating that can be easily removed prior to erection or which has characteristics that make removal unnecessary prior to erection.

3.15.05 Surfaces adjacent to field welds

Unless otherwise provided for, surfaces within 50 of any field weld location shall be free of materials that would prevent proper welding or produce objectionable fumes while welding is being done.

3.16.00 Galvanizing

3.16.01 General

Structural steelwork for switchyard or other structures as may be specified in the contract shall be hot dip galvanized in accordance with the American Society for Testing and Materials Specification ASTM-A 123 or IS: 2629 - Recommended practice for Hot-Dip Galvanizing of Iron and steel. Where the steel structures are required to be galvanized the field connection materials like bolts, nuts and washers shall also be galvanized.

3.16.02 Surface Preparation

All members to be galvanized shall be cleaned, by the process of pickling of rust, loose scale, oil, grease, slag and spatter of welded areas and other foreign substances prior to galvanizing. Pickling shall be carried out by immersing the steel in an acid bath containing either sulphuric or hydrochloric acid at a suitable concentration and temperature. The concentration of the acid and the temperature of the bath can be varied, provided that the pickling time is adjusted accordingly.

The pickling process shall be completed by thoroughly rinsing with water, which should preferably be warm, so as to remove the residual acid.

3.16.03 Procedure

Galvanizing shall be carried out by hot dip process in a proper and uniformly heated bath. It shall meet all the requirements when tested in accordance with IS: 2633 - Method for testing uniformity of coating on Zinc Coated Articles and IS: 4759 - Specification for Hot-dip zinc coatings on Structural Steel & other allied products.

After finishing the threads of bolts, galvanizing shall be applied over the entire surface uniformly. The threads of bolts shall not be machined after galvanizing and shall not be clogged with zinc. The threads of nuts may be tapped after galvanizing but care shall be taken to use oil in the threads of nuts during erection.

The surface preparation for galvanizing and the process of galvanizing itself,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 279 of 361

shall not adversely affect the mechanical properties of the materials to be galvanized. Where members are of such lengths as to prevent complete dipping in one operation, great care shall be taken to prevent warping.

Materials on which galvanizing has been damaged shall be acid stripped and re-galvanized unless otherwise directed, but if any member becomes damaged after leaving been dipped twice, it shall be rejected. Special care shall be taken not to injure the skin on galvanized surfaces during transport, handling, and erection. Damages, if occur, shall be made good in accordance or as directed by the Engineer.

4.00.00 INSPECTION, TESTING, ACCEPTANCE CRITERIA AND DELIVERY

4.01.00 Inspection

Unless specified otherwise, inspection to all, work shall be made by the or Engineer's representative at the place of manufacture prior to delivery. The Engineer or his representative shall have free access at all reasonable times to those parts of the manufacturer's works which are concerned with the fabrication of the steelwork under this Contract and he shall be afforded all reasonable facilities for satisfying himself that the fabrication is being done in accordance with the provisions of this Specification.

The Contractor shall provide free of charge, such labour, materials, electricity, fuel, water, stores, tools and plant, apparatus and instruments as may be required by the Engineer to carry out inspection and/or tests in accordance with the Contract. The Contractor shall guarantee compliance with the provisions of this Specification.

4.02.00 Testing and Acceptance Criteria

4.02.01 General

The Contractor shall carry out sampling and testing in accordance with the relevant Indian Standards and as supplemented herein for the following items at his own Cost. The Contractor shall get the specimens tested in a laboratory approved by the Engineer and submit to the Engineer the test results in triplicate within 3 (three) days after completion of the test.

4.02.02 Steel

All steel supplied by, the Contractor shall conform, to the relevant Indian Standards. Except otherwise mentioned in the contract, only tested quality steel having mill test reports shall be used. In case unidentified steel materials are permitted to be used by the Engineer, random samples of materials will be taken from each unidentified lot of 50 M.T or less of any particular section for tests to conform to relevant Indian Standards. Cost of all tests shall be born by the contractor.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 280 of 361

All material shall be free from all imperfections, mill scales, slag intrusions, laminations, fittings, rusts etc. that may impair their strength, durability, and appearance.

4.02.02 Welding

- a) The weld surface shall be cleaned with steel wire brush to remove spatter metal, slag etc. and 100% of welds shall be inspected visually for size, length of weldment and external defects. Weld gauges shall be used for checking weld sizes. The surface shall be clean with regular beads and free from slags, cracks, blow-holes etc.
- b) Non-destructive examination shall be carried out to determine soundness of weldments as follows:
 - i) 10% at random on fillet-joints.
 - ii) 100% on all butt-joints.
- c) Should the ND tests indicate defects like improper root penetration, extensive blowholes, slag intrusion etc., such welds shall be back gauged, joints prepared again and rewelded. All defects shall be rectified by the Contractor at no extra costs.
- d) All electrodes shall be procured from approved reputed manufacturers with test certificates. The correct grade and size of electrode, which has not deteriorated in storage, shall be used. The inspection and testing of welding shall be performed in accordance with the provisions of the relevant Indian Standards or other equivalents. For every 50 tones of welded fabrication, the Engineer may ask for 1(one) test-destructive or non-destructive including X -ray, ultrasonic test or similar, the cost of which shall be borne by the Contractor.

4.02.04 Rivets, bolts, nuts and washers

All rivets, bolts, nuts, and washers shall be procured from M/s. Guest Keen William Ltd. or equivalent and shall confirm to the relevant Indian Standards. If desired by the Engineer, representative samples of these materials may have to be tested in an approved laboratory and in accordance with the procedures described in relevant Indian Standards. Cost of all such testing shall have to be borne by the Contractor. In addition to testing the rivets by hammer, 2% (two per cent) of the rivets done shall have to be cut off by chisels to ascertain the fit, quality of material and workmanship. The removal of the cut rivets and re-installing new rivets shall be done by the Contractor at his own cost.

4.02.05 Shop painting



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 281 of 361

4.02.12 Galvanizing
All paints and primers shall be of standard quality and procured from approved manufacturers and shall conform to the provisions of the relevant Indian Standards.

All galvanizing shall be uniform and of standard quality when tested in accordance with IS: 2633 - Method for testing uniformity of coating on Zinc Coated Articles and IS: 4759 - specification for Hot-Dip Zinc Coatings on Structural Steel & other allied products.

4.03.00 Tolerance

The tolerances on the dimensions of individual rolled steel components shall be as specified in IS: 1852 - specification for rolling and Cutting Tolerances for Hot-rolled Steel Products. The tolerances on straightness, length etc. of various fabricated components (such as beams and girders, columns, crane gantry girder etc.) of the steel structures shall be as specified in IS: 721 - Tolerances for Fabrication of Steel Structures.

4.04.00 Acceptance

Should any structure or part of a structure be found not to comply with any of the provisions of this specification, the same shall be liable to rejection. No Structure or part of the structure once rejected, shall be offered again for test, except in cases where the Engineer considers the defects rectifiable. The Engineer may, at his discretion, check some of the tests at an appropriate laboratory at the contractors cost.

When all tests to be performed in the Contractor's shop under the terms of this contract have been successfully carried out, the steelwork will be accepted forthwith and the Engineer will issue acceptance certificate, upon receipt of which, the items will be shop painted, packed and dispatched. No item to be delivered unless an acceptance certificate for the same has been issued. The satisfactory completion of these tests or the issue of the certificates shall not bind the Owner to accept the work, should it, on further tests before or after erection, be found not in compliance with the Contract.

4.05.00 Delivery of materials

4.05.01 General

The Contractor will deliver the fabricated structural steel materials to site with all necessary field connection materials in such sequence as will permit the most efficient and economical performance of the erection work. The Owner may prescribe or control the sequence of delivery of materials, at his own discretion.

4.05.02 Marking



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 282 of 361

Each separate piece of fabricated steelwork shall be distinctly marked on all surfaces before delivery in accordance with the markings shown on approved erection drawings and shall bear such other marks as will further facilitate identification and erection.

4.05.03 Shipping

Shipping shall be strictly in accordance with the sequence stipulated in the agreed Programme. Contractor shall dispatch the materials to the worksite securely protecting and packing the materials to avoid loss or damage during transport by rail, road or water. All parts shall be adequately braced to prevent damage in transit.

Each bundle, bale or package delivered under this contract shall be marked on as many sides as possible and such distinct marking (all previous irrelevant markings being carefully obliterated) shall show the following:

- a) Name and address of the consignee
- b) Name and address of the consignor
- c) Gross weight of the package in tonnes and its dimensions
- d) Identification marks and/or number of the package
- e) Custom registration number, if required

All markings shall be carried out with such materials as would ensure quick drying and indelibility.

Each component or part or piece of material when shipped, shall be indelibly marked and/or tagged with reference to assembly drawings and corresponding piece numbers.

Each packing case shall contain in duplicate in English a packing list pasted on to the inside of the cover in a water-proof envelope, quoting especially -

- a) Name of the Contractor
- b) Number and date of the Contract
- c) Name of the office placing the contract
- d) Nomenclature of stores
- e) A schedule of parts or pieces, giving the parts or piece number with reference to assembly drawings and the quantity of each.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 283 of 361

The shipping dimensions of each packing shall not exceed the maximum dimensions permissible for transport over the Indian Railways/Roads.

After delivery of the materials at site, all packing materials shall automatically become the property of the Owner.

Notwithstanding anything stated hereinbefore, any loss or damage resulting from inadequate packing shall be made good by the Contractor at no additional cost to the Owner. When facilities exist, all shipments shall be covered by approved Insurance Policy for transit at the cost of the Contractor.

The contractor shall ship the complete materials or part on board a vessel belonging to an agency approved by the Owner or on rail and/or road transport as directed. The Contractor shall take all reasonable steps to ensure correct appraisal of freight rates, weights and volumes and in no case will the Owner be liable to pay any warehouse, wharfage, demurrage and other charges.

If, however, the Owner has to make payment of any of the above-mentioned charges, the amount paid will be deducted from the bills of the Contractor.

Necessary advise regarding the shipment with relevant details shall reach the Engineer at least a week in advance.

5.00.00 INFORMATION TO BE SUBMITTED

5.01.00 With Tender

The following information is required to be submitted with the Tender:

a) Progress Schedule

The Contractor shall quote in his Tender a detailed schedule of progress of work and total time of completion, itemizing the time required for each of the following aspects of work.

- i) Preparation and approval of fabrication drawing
- ii) Procurement of Materials
- iii) Fabrication and shipping of all anchor bolts
- iv) Fabrication and shipping of main steelwork.
- v) Fabrication and shipping of steelwork for bunkers, tanks and/or silos as applicable.
- vi) Fabrication and shipping of all other remaining steelwork including miscellaneous steelwork.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 284 of 361

vii) Final date of completion of all shipments.

b) Shop

Location of the Tenderer's fabrication workshop giving details of equipment, manpower, the total capacity, and the capacity that will be available exclusively for this contract shall be submitted.

5.02.00 After Award

After award of the Contract the successful Tenderer is to submit the following:

- a) Complete fabrication drawings, material lists, cutting lists, rive and bolt lists, field welding schedules based on the approved design drawings prepared by him in accordance with the approved schedule.
- b) Monthly Progress Report with necessary photographs in six (6) copies to reach the Engineer on or before the 7th day o. each month, giving the up-to-date status of preparation of detailed shop drawings, bill of materials, procurement of materials, actual fabrication done, shipping and all other relevant information.
- c) Detailed monthly material reconciliation statements relevant to the Work done and reported in the Progress Report, giving the stock at hand of raw steel, work in progress, finished materials.
- d) Results of any test as and when conducted and as require by the engineer.
- e) Manufacturer's mill test report in respect of steel materials, rivets, bolts, nuts, and electrodes as may be applicable.

6.00.00 RATES AND MEASUREMENT

6.01.00 Rates

6.01.01 The items of work in the Schedule of items describe the work in brief. The various items of the Schedule of items shall be read in conjunction with these specifications including amendments and additions, general conditions of contract, special conditions of contracts, and other tender documents, if any. For each item of Schedule of Items, the bidder's rates shall include the activities covered in the description of the item as well as all necessary operations described in the Specifications.

6.01.02 The bidder's rates shall include cost of all minor details which are obviously and fairly intended and which may not have been included in the description in these documents but are essential for the satisfactory completion of the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 285 of 361

work. Rates shall also include for taking all safety measures.

- 6.01.03** The bidder's -rates for all items of schedule of items shall include complete cost towards plant, equipment, erection and dismantling of scaffolding, men, materials and consumables, skilled and unskilled labour, levies, taxes, royalties, duties, transport, storage, repair/rectification/maintenance until handing over, contingencies, overhead and all incidental items not specifically mentioned but reasonably implied and necessary to complete the work.
- 6.01.04** No claims shall be entertained, if the details shown on the 'Released for Construction' drawings differ from those shown on the bid/tender drawings.
- 6.01.05** Rates shall be inclusive of all leads and lifts/elevation.
- 6.01.06** The bidder's rates for Structural Steel shall include for fabrication and erection, transportation to site, preparation checking collecting and distributing of the fabrication drawings and design calculations, erection scheme, alignment, welding, including preheating and post heating, testing of welders, inspection of welds, visual inspection, non destructive and special testing, rectification and correction of defective welding works, production test plate, inspection and testing, erection scheme, protection against damage in transit, stability of structures, etc. The rates shall also be inclusive of providing and installing temporary structures, transport of Owner issue material from store, return of surplus/waste steel materials including cut pieces/waste steel, provision of additional butt/weld joint to reduce the wastage and all other general, special, such requirements as may be required, for the successful completion of the work.
- 6.01.07** The bidder's rates for foundation bolts assembly shall include fabrication erection, installation, and alignment of complete bolt assembly with nuts, locknuts, anchor plates, stiffener plates, protective tape, etc. This shall also include the cost of materials not issued by the Owner.
- 6.01.08** The bidders rates for application of inorganic primer shall include surface preparation to near white metal surface by blast cleaning, abrasives, touch up painting, suitable enclosure to avoid contamination and the necessary statutory approval from the factory inspector/pollution control board etc. regarding the method of blast cleaning and abrasives used, and getting approval of the specialized agency supplying the zinc silicate primer.
- 6.01.09** The bidder's rates for application of finish painting system shall include surface preparation, application of intermediate (under) coat, finish coat and final finish coat, and getting approval of the specialized agency supplying the finish paint.
- 6.01.10** The bidder's rates for electro-forged gratings (if specified) shall include supply, fabrication, transportation to the site, erection and alignment of factory made electro-forged gratings, all taxes, duties thereon etc. The rates shall also include preparation of grating design for different spans and load intensifies,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 286 of 361

preparation of design and fabrication drawings, edge preparation, blast cleaning followed by finish paint.

- 6.01.11** The bidder's rates for galvanization of factory made electro-forged gratings (if specified) shall include the application of hot dipped galvanization as finish over the fabricated gratings and the treatment to be given for prevention of white storage stains, as per the technical Aspiration.
- 6.01.12** The bidder's rates for permanent mild steel bolts, nuts and washers shall include the supply and fixing of such bolts, nuts and washers in position, for various types of Structural Steel works, as per the technical specification.
- 6.01.13** The bidder's rates for high strength structural bolts, nuts and washers shall include the supply and fixing of such bolts, nuts and washers in position, for various types, of Structural Steel works, as per the technical specification.
- 6.01.14** The bidder's rates for dismantling, additions to, alterations in and/or modifications shall be inclusive of all operations such as lowering of material, carriage etc., as mentioned in the technical specification. Unutilised steel pieces cut/removed shall be returned to the project stores free of charge. Non-return of unblazed steel pieces to the Owner's store would be considered as wastage and recovery would be affected as per the provision of contract for structural steel consumption. This shall not include the weight of temporarily dismantled/supported members, connected member.
- 6.01.15** The bidder's rates for re-erection of erection marks after additions to, alterations in and/or modifications shall be inclusive of all operations mentioned in technical specification for the calculated weight of the rectified/modified erection mark rejected at site. This shall not include the weight of temporarily dismantled/supported members, connected member. All the operations mentioned above for restoring such members shall be carried out at no extra cost. The work of erection of any erection mark which has not been dismantled but have been modified/rectified before erection shall not be paid under this item but shall be paid under relevant item of fabrication and erection of steel work of Schedule of items for the modified weight.
- 6.01.16** The bidder's rates for PTFE shall include design, supply, transportation of the complete assembly with guides and dust protection cover and installation of bearings in position drilling, bolting, erecting aligning etc. along with any taxes, duties thereon etc.
- 6.01.17** The bidder's rates for Stainless Steel hopper (if specified) shall include fabrication and erection, transportation to site, preparation checking collecting and distributing of the fabrication drawings and design calculations, all other operations mentioned in the technical specification. The rates shall also include for erection scheme, alignment, making cutting plan, cutting, jointing, bending, rolling, grinding, drilling, bolting, assembly, edge preparation, welding including pre-heating, post-heating, testing of welders, inspection of



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 287 of 361

welds, inspection and testing, protection against damage in transit, stability of structures, installation of temporary structures etc. The rates shall also be inclusive of providing and installing temporary structures, transport of Owner issue material from store, return of surplus / waste steel materials including cut pieces/waste steel, provision of additional butt / weld joint to reduce the wastage and all other general, special, such requirements as may be required, for the successful completion of the work.

6.01.18 The bidders rates for preformed flexible open ended bellow strap of neoprene (if specified) shall include supply and transportation, installation in position, drilling, bolting, aligning etc. complete along with any taxes, duties thereon etc.

6.01.19 The bidder's rates for Stainless Steel Hand Rail (if specified) shall include complete Hand Rail including, stainless steel beading, stainless steel cleats, stainless steel fasteners, neoprene gaskets, preparation of shop drawing but excluding the cost of glazing. The Owner for this item of work shall supply no material.

6.02.00 MODE OF MEASUREMENT

6.02.01 The measurement for the item of foundation bolts assembly including that of nuts; locknuts shall be based on the calculated weight of steel installed in Metric Tonne, corrected to second place of decimal. The weight of the foundation bolt shall be calculated in the same way as that done for the item of fabrication, erection, alignment of structural steel. The weight of the nut / locknut shall be taken as per actual weight supplied by the contractor and accepted by the Engineer.

6.02.02 The measurement for the item of fabrication, erection, alignment, welding, etc. of structural steel work shall be based on the approved weight of steel nearest to a Kg, by applying the unit weight as adopted at the time of issue of structural steel on the measurements worked out as given below.

6.02.03 For ISMB, ISMC, ISA, flats, round bars, square bars and pipes, length shall be taken as per distance between planes normal to the axis of the member passing through the extreme points of the section.

6.02.04 Gussets plates in trusses, and bracings, brackets plates, stiffeners, and skew cuts if any in plates for butt welds the area shall be assumed as the minimum circumscribed rectangle.

6.02.05 For bunker wall plates the minimum-circumscribing rectangle of the individual plate/pieces out of which these wall plates are assembled by butt-welding, shall be measured. Care shall be taken to ensure maximum utilization of cut-pieces generated by providing extra butt joints (for which no extra payment shall be made).



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 288 of 361

- 6.02.06** For all other plates, where the area of any notch/skew cut in the plate is less than 0.2 sq.m. the area of the plate shall be assumed as that of the minimum circumscribing rectangle for the purpose of measurement and calculation of area for the purpose of payment. However, if the area of any notch/skew cuts in a plate is more than 0.2 sq.m. the actual profile of the plate shall be considered for the purpose of payment.
- 6.02.07** No deduction shall be made for the hole in the members, if the area of individual hole is less than 0.2 sq.m. The weight shall be calculated by deducting the area of holes, if area of individual hole is more than 0.2 sq.m.
- 6.02.08** All cut-pieces and scrap generated due to cutting of holes, skew-cuts of plates, gussets, brackets, stiffeners, etc. shall be stacked separately and handed over to the project stores without being considered for material accounting as the circumscribing rectangle has been considered for payment.
- 6.02.09** The splice plate shown in the fabrication drawing or approved by the Engineer shall only be measured for payment.
- 6.02.10** The weight of permanent bolts, washers and nuts and welds shall not be included in the weights of the members. No extra payment shall be made for welding/bolting.
- 6.02.11** The bolts and nuts required for erection purpose shall not be paid for and may be taken away by the Contractor after final welding for members. Erection boltholes left after removal of erection bolts shall be suitably plugged with welds.
- 6.02.12** The measurement for the item of application of inorganic primer including blast cleaning of steel surfaces shall be based on the weight on which the zinc silicate primer is applied, after blast cleaning in Metric Tonne, corrected to third place of decimal. The weight shall be the weight as approved, for erection mark/element of the mark painted, for payment of the item of fabrication and erection of structural steel works.
- 6.02.13** The measurement for the item of application of finish primer system shall be based on the weight on which the epoxy based finish primer is applied in Metric Tonne, corrected to third place of decimal. The weight shall be the weight as approved, for erection mark/element of the mark painted, for payment of the item of fabrication and erection of structural steel works.
- 6.02.14** The measurement for the item of gratings shall be based on the actual weight in Kgs, corrected to second place of decimal, as supplied by the Contractor, and accepted by the Engineer. Nothing extra shall be payable for making cutouts, notches, openings of any profile, trimming profiles etc. in the grating units.
- 6.02.15** The measurement for the item of hot dipped galvanization of gratings shall be



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 289 of 361

based on the actual weight in Kgs, corrected to second place of decimal of gratings galvanized by the Contractor and accepted by the Engineer.

6.02.16 The measurement for the item of permanent bolts with nuts and washers shall be based on the actual weight in Kgs, corrected to second place of decimal, as supplied by the Contractor and accepted by the Engineer, and as per the approved bolts and nuts schedules.

6.02.17 The measurement for the item of High Strength Structural bolts with nuts and washers shall be based on the actual weight in Kgs, corrected to second place of decimal, as supplied by the Contractor and accepted by the Engineer, and as per the approved bolts and nuts schedules.

6.02.18 The measurement for the item of the work of dismantling, additions, alterations, reerection etc. shall be as given below

6.02.19 For dismantling, the unmodified weight of the actually dismantled erection marks shall only be measured.

6.02.20 For the work of addition to, alteration in and / or modification of 'erection marks' either in erected position or in the fabrication yard, measurement of weight for payment purpose shall be calculated as the arithmetic sum of weight of steel cut and removed from the erection mark, weight of steel reutilised out of such cut and removed pieces and weight of additional new steel pieces added to the erection mark.

6.02.21 For re-erection the weight of the modified erection mark shall only be measured.

6.02.22 The weight shall be measured nearest to kg. and shall be arrived in a manner similar to the measurement for the item of fabrication, erection, alignment and welding of structural steel.

6.02.23 The measurement for the item of PTFE bearings shall be based on the actual weight in MT, corrected to third place of decimal, supplied by the contractor and as accepted by the Engineer and as per the approved bearing schedule, for the total vertical load carrying capacity, for all bearings.

6.02.24 The measurement for the item of stainless steel hopper shall be based on the actual finished weight of hopper weight in Kgs, corrected to second place of decimal. The hopper weight shall be arrived by multiplying of the inner surface area of the hopper with the unit weight of the hopper plate.

6.02.25 The measurement for the item of flexible open-ended bellows straps of neoprene shall be based in running meter, corrected to second place of decimal. Bellow Straps shall be supplied as per the requirement of the approved drawings. The measurement shall be done for the inner circumference of the bunker on which neoprene has been fixed and for the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 290 of 361

length supplied by the Contractor and as accepted by the Engineer.

6.02.26

The measurement for the item of Stainless Steel Hand Railing shall be based in Kgs corrected to second place of decimal. The weight shall also include the weight of Stainless Steel fasteners, Stainless Steel beading, Stainless Steel cleats etc. The weight shall be the finished weight of Hand Rail, as accepted by the Engineer.

SECTION - D

SUB-SECTION – D18



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 291 of 361

ERECTION OF STRUCTURAL STEELWORK

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	GENERAL
3.00.00	WORKMANSHIP
4.00.00	TESTING AND ACCEPTANCE CRITERIA
5.00.00	INFORMATION TO BE SUBMITTED



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 292 of 361

ERECTION OF STRUCTURAL STEELWORK

1.00.00 SCOPE

This specification covers the erection of structural steelwork including receiving and taking delivery of fabricated structural steel materials arriving at site, installing the same in position, painting and grouting the stanchion bases all complete as per Drawings, this Specification and other provision of the Contract.

2.00.00 GENERAL

2.01.00 Work to be provided for by the Contractor, unless otherwise specified in the Contract, shall include but not be limited to the following:

- a) The Contractor shall provide all construction and transport equipment, tools, tackle, consumables, materials, labour, and supervision required for erection of the structural steelwork.
- b) Receiving, unloading, checking, and moving to storage yard at Site including prompt attendance to all insurance matters as necessary for all fabricated steel materials arriving at Site. The Contractor shall pay all demurrage and/or wharfage charges etc. on account of default on his part.
- c) Transportation of all fabricated structural steel materials from Site storage yard, handling, rigging, assembling, riveting, bolting, welding and satisfactory installation of all fabricated structural steel materials in proper location according to approved erection drawings and/or as directed by the Engineer. If necessary suitable temporary approach roads to be built for transportation of fabricated steel structures.
- d) Checking center lines, levels of all foundation blocks including checking line, level, position and plumb of all bolts and pockets. Any defect observed in the foundation shall be rectified with Engineer's approval. The Contractor shall fully satisfy himself regarding the correctness of the foundations before installing the fabricated steel structures on the foundation blocks.
- e) Aligning, plumbing, levelling, riveting, bolting, welding and securely fixing the fabricated steel structures including floor gratings, chequered plates etc. in accordance with the Drawings or as directed by the Engineer.
- f) Painting of the erected steel structures.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 293 of 361

g) All minor modifications of the fabricated steel structures as directed by the Engineer including but not limited to the following:

- i) Removal of bends, kinks, twists etc. for parts damaged during transport and handling.
- ii) Cutting, chipping, filling, grinding, etc. if required for preparation and finishing of site connections.
- iii) Reaming of holes for use of higher size rivet or bolt if required.
- iv) Refabrication of parts damaged beyond repair during transport and handling or refabrication of parts, which are incorrectly fabricated.
- v) Fabrication of parts omitted during fabrication by error, or subsequently found necessary.
- vi) Drilling of holes which are either not drilled at all or are drilled in incorrect location during fabrication.
- vii) Carry out tests in accordance with this specification.

2.02.00 Work by Others

No work under this Specification will be provided for by any agency other than the Contractor unless specifically mentioned elsewhere in the contract.

2.03.00 Codes and Standards

All work under this Specification shall, unless specified otherwise, conform to the latest revisions and/or replacements of the following or any other Indian Standard Specification and codes of Practice of equivalent:

IS: 800 - Code of practice for general construction in steel.

IS: 456 - Code of practice for main or reinforced concrete.

2.04.00 Conformity with Designs

The Contractor will erect the entire fabricated steel structure, align all the members, complete all field connections and grout the foundations all as per the provisions of this specification and the sequence and the design criteria laid down by the Engineer. All work shall conform to the provisions of this specification and /or instructions of the engineer. The testing and acceptance of the erected structures shall be in accordance with the provisions of this Specifications and/or the instructions of the Engineer.

2.05.00 Material



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 294 of 361

2.05.01 General

All fabricated steel structures and connection materials shall be supplied by the Contractor to the site. The Contractor shall take delivery from railway wagons or trucks at site, and unload the materials and perform all formalities like checking of materials and attend to insurance matters in accordance with Sub-Clause 2.01.00 and as specified hereinbefore.

2.05.02 Materials to conform to Indian standards

All materials required to be supplied by the Contractor under this contract shall conform to the relevant Indian Standard specifications.

2.06.00 Storage of Materials

2.06.01 General

All material shall be so stored as to prevent deterioration and to ensure the preservation of their quality and fitness for use in the works. Any material which has been deteriorated or damaged beyond repairs and has become unfit for use shall be removed immediately from the site, failing which, the engineer shall be at liberty to get the materials removed by agency and the cost incurred thereof shall be realised from the Contractor's dues.

2.06.02 Yard

The Contractor will have to establish a suitable yard in an approved location at site for storing the fabricated steel structures and other raw steel materials such as structural sections and plates as required. The yard shall have facilities like drainage, lighting, and suitable access for large cranes, trailers, and other heavy equipments. The yard shall be fenced all around with security arrangement and shall be of sufficiently large area to permit systematic storage of the fabricated steel structures without overcrowding and with suitable access for cranes, trailers and other equipment for use in erection work in proper sequence in accordance with the approved Programme of work.

The Tenderer must visit the site prior to submission of his tender to acquaint himself with the availability of land and the development necessary by way of filling, drainage, access roads, fences, sheds etc. all of which shall be carried out by the Contractor at his own cost as directed by the Engineer.

2.06.03 Covered Store

All field connection materials, paints, cement etc. shall be stored on well designed racks and platforms off the ground in a properly covered store building to be built at the cost of the Contractor.

2.07.00 Quality Control



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 295 of 361

The contractor shall establish and maintain quality control procedures for different items of work and materials as may be directed by the Engineer to assure compliance with the provisions of the Contract and shall submit the records of the same to the Engineer. The quality control operation shall include but not be limited to the Following items of work :

- i) Erection: Lines, levels, grades, plumbs, joint characteristics including tightness of bolts.
- ii) Grouting: Cleaning and roughness of foundation, quality of materials used for grouting, admixtures, consistency, and strength of grout.
- iii) Painting: Preparation of surface for painting, quality of primers and paints, thinners, application and uniformity of coats.

2.08.00 Taking Delivery

The Contractor shall take delivery of fabricated structural steel and necessary connection materials from railhead/trucks as may be necessary and as directed by the Engineer. He shall check, unload; transport the materials to his stores for proper storing at his own cost. The Contractor shall submit claims to insurance or other authorities and pursue the same in case of loss or damage during transit and handling and all loss thereof shall be borne by him.

The Contractor shall also take all precautions against damage of the materials in his custody after taking delivery and till the same are erected in place and accepted. The Contractor shall salvage, collect, and deliver all the packing materials to the Owner free of charge.

3.00.00 WORKMANSHIP

3.01.00 Erection

3.01.01 Plant and Equipment

The suitability and adequacy of all erection tools and plant and equipment proposed to be used shall be thoroughly verified. They shall be efficient, dependable, in good working condition and shall have the approval of the Engineer.

3.01.02 Method and sequence of erection

The method and sequence of erection shall have the prior approval of the Engineer. The Contractor shall arrange for most economical method and sequence available to him consistent with the drawings and specifications and other relevant stipulations of the contract.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 296 of 361

3.01.03 Temporary Bracing

Unless adequate bracing is included as a part of the permanent framing, the erector during erection shall install, free of cost to the Owner, temporary guys and bracings where needed to secure the framing against loads such as wind or seismic forces comparable in intensity to that for which the structure has been designed, acting upon exposed framing as well as loads due to erection equipment and erection operations.

If additional temporary guys are required to resist wind or seismic forces acting upon components of the finished structure installed by others during the course of the erection of the steel framing, arrangement for their installation by the erector shall be made free of cost to the Owner.

The requirement of temporary bracings and guys shall cease when the structural steel is once located, plumbed, levelled, aligned, and grouted within the tolerances permitted under the specification and guyed and braced to the satisfaction of the Engineer.

The temporary guys, braces, false work, and cribbing shall not be the property of the Owner and they may be removed immediately upon completion of the steel erection.

3.01.04 Temporary Floors for Buildings

It shall be the responsibility of the Contractor to provide free of cost planking and to cover such floors during the work in progress as may be required by any Act of Parliament and/or bylaws of state, Municipal or other local authorities.

3.01.05 Setting Out

Positioning and levelling of all steelwork, plumbing of stanchions and placing of every part of the structure with accuracy shall be in accordance with the approved Drawings and to the satisfaction of the Engineer. For heavy columns, etc. the Contractor shall set proper screed bars to maintain proper level. No extra payment shall be made for this.

Each tier of column shall be plumbed and maintained in a true vertical position subject to the limits of tolerance under this Specification. No permanent field connections by riveting, bolting or shall be carried out until proper alignment and plumbing has been attained.

3.01.06 Field Riveting

All rivets shall be heated and driven with pneumatic tools. Hand passing or "throwing" of rivets are desirable. Any other method of conveying hot rivets



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 297 of 361

from the furnace to the driving point must be approved by the engineer. No-cold rivets shall be driven. All other requirements of riveting including quality and acceptance criteria shall be in accordance with the relevant portions of the Specification for Fabrication of Structural Steelwork of the Project.

3.01.07

Field Bolting

All relevant Portions in respect of bolted construction of the Specification for Fabrication of Structural Steelwork applicable to the Project shall also be applicable for field bolting in addition to the following:

Bolts shall be inserted in such a way so that they may remain in position under gravity even before fixing the nut. Bolted parts shall fit solidly together when assembled and shall not be separated by gaskets or any other interposed compressible materials. When assembled, all joint surfaces, including those adjacent to the washers shall be free of scales except tight mill scales. They shall be free of dirt, loose scales, burns, and other defects that would prevent solid seating of the parts. Contact surfaces within friction type joints shall be free of oil, paint, lacquer, or galvanizing.

All high tensile bolts shall be tightened to provide, when all fasteners in the joint are tight, the required minimum bolt tension by any of the following methods.

a) Turn-of-nut Method

When the turn-of-nut method is used to provide the bolt tension, there shall first be enough bolts brought to a "snug tight" condition to ensure that the parts of the Joint are brought into good contact with each other. 'Snug tight' is defined as the tightness attained by a few impacts of an impact wrench or the full effort of a man using an ordinary spud wrench. Following this initial operation, bolts shall be placed in any remaining holes in the connection and brought to snug tightness. All bolts in the joint shall then be tightened additionally by the applicable amount of nut rotation specified in Table-I with tightening progressing systematically from the most rigid part of the joint to its free edges. During this operation there shall be no rotation of the part not turned by the wrench.

TABLE-I

Bolts length not
exceeding 8 times
dia or 200 mm

Bolt length
exceeding 8 times
dia or 200 mm

Remarks



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 298 of 361

1/2 turn

2/3 turn

Nut rotation is relative to bolt regardless of the element (nut or bolt) being turned.
Tolerance on rotation-30° over or under.

Bolts may be installed without hardened washers when tightening is done by the turn -of-nut -method. However, normal washers shall be used.

Bolts tightened by the turn-of-nut method may have the outer face of the match-marked with the protruding bolt point before final tightening, thus affording the inspector visual means of noting the actual nut rotation. Such marks can be made by the wrench operator by suitable means after the bolts have been brought up snug tight.

b) Torque Wrench Tightening

When torque wrenches are used to provide the bolt tensions, the bolts shall be tightened to the torques specified in TABLE-II (See Note below the Table). Nuts shall be in tightening motion when torque is measured. When using torque wrenches to install several bolts in a single joint, the wrench shall be returned to touch up bolts previously tightened, which may have been loosened by the tightening of subsequent bolts, until all are tightened to the required tension.

TABLE-II

Nominal Bolt Diameter (mm) (Kg.M) of IS:1367	Torque to be applied for bolt class 8.8
20	59.94
22	81.63
24	103.73

Note: The above torque values are approximate for providing tensions of 14.7 T for 20 mm dia.; and 21.2 T for 24 mm dia. bolts under moderately lubricated condition. The torque wrench shall be calibrated at least once daily to find out the actual torque required to produce the above required tension in the bolt by placing it in a tension indicating device. These torques shall be applied for tightening the bolts on that day with the particular wrench.

In either of the above two methods, if required, for bolt entering and wrench



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 299 of 361

operation clearances, tightening may be done by turning the bolt while the nut is prevented from rotating.

Impact wrenches if used shall be of adequate capacity and sufficiently supplied with air to perform the required tightening of each bolt in approximately ten seconds. Holes for turned bolts to be inserted in the field shall be reamed in the field. All drilling and reaming for turned bolts shall be done only after the parts to be connected are assembled. Tolerances applicable in the fit of the bolts shall be in accordance with relevant Indian Standard Specifications. All other requirements regarding assembly and bolt tightening shall be in accordance with this sub clause.

3.01.08 Field Welding

All field assembly and welding shall be carried out in accordance with the requirements of the specification for fabrication work applicable to the project, excepting such provisions therein which manifestly apply to shop conditions only. Where the fabricated structural steel members have been delivered painted, the paint shall be removed before field welding for a distance of at least 50 mm on either side of the joints.

3.01.09 Holes, Cutting and Fitting

No cutting of sections, flanges, webs, cleats, rivets, bolts, welds etc. shall be done unless specifically approved and /or instructed by the Engineer.

The erector shall not cut, drill, or otherwise alter the work of other trades, unless such work is clearly specified in the Contract or directed by the Engineer. Wherever such work is obtain specified the Contractor shall obtain complete information as to size, location and number of alterations prior to carrying out any work. The Contractor shall not be entitled for any payment on account of any such work.

3.02.00 Drifting

Correction of minor misfits and reasonable amount of reaming and cutting of excess stock from rivets will be considered as permissible. For this, light drifting may be used to draw holes together and drills shall be used to enlarge holes as necessary to make connections. Reaming, that weakens the member or makes it impossible to fill the holes properly or to adjust accurately after reaming, shall not be allowed.

Any error in shop work which prevents the proper assembling and fitting of parts by moderate use of drift pins and reamers shall immediately be called to the attention of the Engineer and approval of the method of correction obtained. The use of gas cutting torches at erection site is prohibited.

3.03.00 Grouting of stanchion bases and bearings of beams and girders on stone,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 300 of 361

brick or concrete (Plain or reinforced)

Grouting shall be carried out with Ordinary Cement grout as described below:

The mix shall be one (1) part cement and one (1) part sand and just enough water to make it workable. The positions to be grouted shall be cleaned thoroughly with compressed air jet and wetted with water and any accumulated water shall be removed. These shall be placed under expert supervision, taking care to avoid air locks. Edges shall be finished properly. If the thickness of grout is 25 mm or more, two (2) parts of 6 mm down graded stone chips may be added to the above noted cement-sand grout mix, if required, by the Engineer or shown on the drawings.

No grouting shall be carried out until a sufficient number of bottom lengths of stanchions have been properly lined, leveled, and plumbed and sufficient floor beams are tied in position.

Whatever method of grouting is employed, the operation shall not be carried out until the steelwork has been finally levelled and plumbed, the stanchion bases being supported meanwhile by steel wedges, and immediately before grouting, the space under steel shall be thoroughly cleaned.

If required by the Engineer, certain admixtures like aluminium powder, "ironite" or equivalent, may be required to be added to the grout to enhance certain desirable properties of the grout. Approved non-shrink pre-mixed grout having required flowability and compressive strength may also be used with Engineer's approval.

3.04.00 Painting after Erection

Field painting shall only be done after the structure is erected, levelled, plumbed, aligned and grouted in its final position, tested and accepted by the Engineer. Normally, final painting shall be done only after the floor slabs are concreted and masonry walls are built. However, touch up painting, making good any damaged shop painting and completing any unfinished portion of the shop coat shall be carried out by the Contractor free of cost to the Owner. The materials and specification for such painting in the field shall be in accordance with the requirements of the specification for fabrication of structural steelwork applicable for the project.

Painting shall not be done in frosty or foggy weather or when humidity is such as to cause condensation on the surfaces to be painted. Before painting of steel, which is delivered unpainted, is commenced, all surfaces to be painted shall be dried and thoroughly cleaned from all loose scale and rust.

All field rivets, bolts, welds, and abrasions to the shop coat shall be spot painted with the same paint used for the shop coat. Where specified,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 301 of 361

surfaces, which will be in contact after site assembling, shall receive a coat of paint (in addition to the shop coat, if any) and shall be brought together while the paint is still wet.

Surface, which will be inaccessible after field assembly shall receive the full, specified protective treatment before Bolts and fabricated steel members who are galvanized or otherwise treated and steel members to be encased shall not be painted.

The final painting shall be of two coats of Synthetic Enamel painting or Aluminium paint of approved manufacture as per the approved "Schedule of Painting". The shades shall also be as per the approved schedule. Synthetic enamel paint shall conform to IS: 2932.

3.05.00 Final cleaning up

Upon completion of erection and before final acceptance of the work by the Engineer, the contractor shall remove free of cost all false work, rubbish and all Temporary Works resulting in connection with the performance of his work.

4.00.00 TESTING AND ACCEPTANCE CRITERIA

4.01.00 General

Loading tests shall be carried out on erected structures, if required by the Engineer, to check adequacy of fabrication and/or erection. Any structure or a part thereof found to be unsuitable for acceptance as a result of the test shall have to be dismantled and replaced with suitable member as per the Contract and no payment towards the cost of the dismantled portion and any connected work shall be made to the contractor. In course of dismantling, if any damage is done to any other parts of the structure or to any fixtures, the same shall be made good free of cost by the Contractor, to the satisfaction of the Engineer. The Cost of the tests specified hereinafter shall be borne by the Owner; but if the structure fails to pass the tests, the cost of the tests shall be recovered from the Contractor. Any extra claim due to loss of time, idle labour, etc. arising out of these testing operations shall not be entertained, however, only reasonable and appropriate time extensions will be allowed.

The structure or structural member under consideration shall be loaded with its actual dead load for as long a time as possible before testing and the tests shall be conducted as indicated in the following sub-clauses 4.01.01, 4.01.02 and 4.01.03. The method of testing and application of loading shall be as approved by the Engineer.

4.01.01 Stiffness Test



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 302 of 361

In this test, the structure or member shall be subjected, addition to its actual dead load, to a test load equal to 1.5 times the specified superimposed load, and this loading shall be maintained for 24 hours. The maximum deflection attained during the test shall be within the permissible limit. If, after removal of the test load, the member or structure does not show a recovery of at least 80 per cent of the maximum strain or deflection shown during 24 hours under load, the test shall be repeated. The structure or member shall be considered to have sufficient stiffness, provided that the recovery after this second test is not less than 90 per cent of the maximum increase in strain or deflection recorded during the second test.

4.01.02 Strength Test

The structure or structural member under consideration shall be subjected, in addition to its actual dead load, to a test load equal to the sum of the dead load and twice the specified superimposed load, and this load shall be maintained for 24 hours.

In the case of wind load, a load corresponding to twice the specified wind load shall be applied and maintained for 24 hours, either with or without the vertical test load for more severe condition in the member under consideration or the structure as a whole. Complete tests under both conditions may be necessary to verify the strength of the structure. The structure shall be deemed to have adequate strength if, during the test, no part fails and if on the removal of the test load, the structure shows a recovery of at least 20 per cent of the maximum deflection or strain recorded during the 24 hours under load.

4.01.03 Structure of same design

Where several structures are built to the same design and it is considered unnecessary to test all of them, one structure, as a prototype, shall be fully tested, as described in previous Sub-clauses, but in addition, during the first application of the test load, particular note shall be taken of the strain or deflection when the test load 1.5 times the specified superimposed load has been maintained for 24 hours. This information is required as a basis of comparison in any check test carried out on samples of the structure.

When a structure of the same type is selected for a check test, it shall be subjected, in addition to its actual dead load, to a superimposed test load, equal to 1.5 time the specified live load, in a manner and to an extent prescribed by the Engineer. This load shall be maintained for 24 hours, during which time, the maximum deflection shall be recorded. The check test shall be considered satisfactory, provided that the maximum strain or deflection recorded in the check test does not exceed by more than 20% of the maximum strain or deflection recorded at similar load in the test on the prototype.

4.01.04 Repair for subsequent test and use after strength tests



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 303 of 361

An actual structure which has passed the “Strength Test” as specified in Sub-clause 4.1.2 hereinbefore and is subsequently to be erected for use, shall be considered satisfactory for use after it has been strengthened by replacing any distorted members and has subsequently satisfied the 'Stiffness Test' as specified in Sub-clause 4.01.01 hereinbefore.

4.02.00

Tolerances

Some variation is to be expected in the finished dimensions of structural steel frames. Unless otherwise specified, such variations are deemed to be within the limits of good practice when they are not in excess of the cumulative effect of detailed erection clearances, fabricating tolerances for the finished parts and the rolling tolerances for the profile dimensions permitted under the Specifications for fabrication of structural steel work applicable to this Project and as specified below:

I. For Buildings Containing Cranes

Component	Description	Variation Allowed
1.	2.	3.
Main columns	a) shifting of column axis at foundation level with respect to building line	
	i) In longitudinal direction	i) ± 3.0 mm
	ii) In lateral direction	ii) ± 3.0 mm
	b) Deviation of both major column axis from vertical between foundation and other member connection levels:	
	i) For a column upto and including 10M height	i) ± 3.5 mm from true vertical
	ii) For a column greater than 10M but less than 40M height	ii) ± 3.5 mm from true vertical for any 10 M length measured between connection levels, but not more than ± 7 mm per 30m length.
	c) For adjacent pairs of columns	± 9.0 mm on true



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 304 of 361

	across the width of the building prior to placing of truss	span.
	d) For any individual column deviation of any bearing or resting level from levels shown on drawings.	± 3.0 mm
	e) For adjacent pairs of columns either across the width of building or longitudinally level difference allowed between bearing or seating	3.0 mm
Trusses	a) Deviation at centre of span of upper chord member from vertical plane running through centre of bottom chord.	1/1500 of the span or greater than 10mm whichever is the least.
Trusses	b) Lateral displacement of top chord at center of span from vertical plane running through center of supports.	1/250 of depth of truss or 20 mm which ever is the - least.
Crane Cirders	a) Difference in levels of crane rail measured between adjacent columns.	2.0 mm.
	b) Deviation to crane rail-gauge	± 3.0 mm
	c) Relative shifting of ends of adjacent crane rail in plan and elevation after thermite welding.	1.0 mm.
	d) Deviation of crane rail axis from centre line of web.	± 3.5 mm
Setting of Expansion gaps	At the time of setting of the expansion gaps, due regard shall be taken of the ambient temperature above or below 30°C. The coefficient of expansion or contraction shall be taken as 0.000012	



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 305 of 361

per °C per unit length.

iv) For Building without Cranes

The maximum tolerances for line and level of the steel work shall be ± 3.0 mm on any part of the structure. The structure shall not be Out of Plumb more than 3.5 mm on each lox section of height and not more than 7.0 mm per 30 m section.

These tolerances shall apply to all parts of the structure unless the drawings issued for erection purposes state otherwise.

4.03.00 Acceptance

Structures and members have passed the tests and conform to all requirements specified in the foregoing Sub-clause 4.01.00, 4.01.01, 4.01.02, 4.01.03 and 4.01.04 and other applicable provisions of this specification and are within the limits of tolerances specified in Sub-clause 4.02.00 and/or otherwise approved by the Engineer shall be treated as approved and accepted for the purpose of fulfillment of the provisions of this contract.

5.00.00 INFORMATION TO BE SUBMITTED

5.01.00 Before Tender

5.01.01 Tentative Programme

The Tenderer shall submit a tentative programme based on the information available in the Tender Document and visit to site indicating the structure-wise erection schedule proposed to be maintained by the Contractor to complete the job in time in accordance with the Contract.

5.01.02 Constructional Plant and Equipment, Tools, Temporary works & manpower A detailed list Of all constructional plant and equipment like cranes, derricks, winches, welding sets, erection tools etc. along with their make, model, present condition and location available with the Tenderer which he will be able to employ on the job to maintain the progress of work in accordance with the Contract shall be submitted along with the Tender. The total number of each category of experienced personnel like fitters, welders, riggers etc. that he will be able to employ on the job shall also be indicated.

5.01.03 Erection Yard

A site plan showing the layout and location of the erection yard proposed to be established by the tenderer shall also be attached with the tender indicating the storage space for fabricated steel materials, site-fabrication and repair shop, covered stores, offices, locations of erection equipments and other facilities. The Engineer shall have the right to modify the arrangement and location of



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 306 of 361

the proposed yard to suit site conditions and the Contractor shall comply with the same without any claim whatsoever.

5.02.00 After award of the Contract

After award of the contract, the Contractor shall submit the following:

5.02.01 Detailed Programme

The Contractor shall submit a detailed erection programme within a month of the award of the Contract for completion of the work in time in accordance with the Contract. This will show the target programme, with details of erection proposed to be carried out in each fortnight, details of major equipment required, and an assessment of required strength of various categories of workers in a proforma approved by the Engineer.

5.02.02 Fortnightly Progress Report

The Contractor shall submit fortnightly progress reports in triplicate to the Engineer showing along with necessary photographs, 125 mm x 90 mm size, and all details of actual achievements against the target programme specified in Sub-clause 5.02.01 above. Any shortfall in the achievement in a particular fortnight must be made up within the next fortnight. Along with this report, the Contractor shall also furnish details of fabricated materials in hand at site and the strength of his workers.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 307 of 361

SECTION - D

SUB-SECTION – D19

ROOF DECKING



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 308 of 361

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	SCOPE
2.00.00	MATERIALS
3.00.00	INSTALLATION
4.00.00	ACCEPTANCE CRITERIA
5.00.00	IS CODES
6.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 309 of 361

ROOF DECKING

1.00.00 Scope

This section of the specification covers the supply, fabrication and erection of profiled light gauge Metal Decks (coated and painted) as roof decking to the main plant building and any other area as indicated in the drawings.

2.00.00 Material

2.01.01 Roof of main plant TG and Deareator bay and bunker building consists of permanently colour coated (on exposed face) galvanized MS trough metal sheet decking plate of approved colour over roof purlins for cast-in-situ roof slab as per IS: 14246 and conform to class 3. Thickness of deck plate shall be minimum 0.8mm and minimum trough depth of 44 mm and centre to centre of the valley shall be 130mm with minimum yield strength of 250 Mpa. Silicon modified polyester paint shall be used for permanent coating over galvanized surface with minimum rate of galvanization 275 gm/sqm. DFT of permanent colour coating shall be 20 microns. It shall serve as permanent shuttering for cast-in-situ roof slab. It should have adequate strength to support weight of green concrete and imposed load during construction. The thickness of the deck plate shall however be designed suitably according to the spacing of roof purlins.

3.00.00 INSTALLATION

The Contractor shall furnish all labour, equipment and materials as required for the design, fabrication, coating, erection and fixing of the decking over purlins, painting and for the complete performance of the work in accordance with the construction drawings and as described herein.

The description, which follows, gives a general indication of the nature and extent of the work but is not necessarily exhaustive and does not purport to cover all the details/operations which will be necessary in order to carry out the work.

3.01.00 Detailed Design of Roof Decking

The Contractor, in conjunction with the manufacturer, shall be responsible for the detailing of the profiled decking, fittings and fixtures and shall submit with his tender particulars of the proposed manufacturer and of the particular product proposed for use. The detailing is to be based on typical details furnished by the Engineer. The Contractor shall submit to the Engineer, two copies of the general arrangement and detailed working drawings for the proposed design, together with all calculations necessary to verify the adequacy and completeness of the design & detailing of decking sheets,



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 310 of 361

fixtures, flashings and trims. After approval he shall supply further eight copies.

The Engineer will verify the correct interpretation of his requirements but may not necessarily check the design and details, and the Contractor shall be entirely responsible for the accuracy of the drawings and the correctness of the design and the suitability of the details. Manufacture of roof decking sheets shall not commence until the necessary approval of the Engineer has been obtained.

3.02.00 Erection & Fixing

3.02.01 Sequence of Manufacture/Erection

Cutting Schedules, delivery to site and stacking arrangements in store shall ensure that sheets are erected in a sequence which follows that for the manufacture. The decking sheets shall be erected using an arrangement of sheets and joints to conform with the requirements of this specification. Decking erection for each elevation or feature shall commence at one end only and proceed towards the other end, in order to ensure tight fitting laps.

3.02.02 Position and Location of Laps

Side and end laps of roof decking sheets shall be located and positioned in such a manner as to provide the maximum weather protection taking into account the direction of the prevailing wind.

The lines formed by horizontal laps and fixing shall where possible, be continuous and coincide with the edges of large openings in the roof.

3.02.03 Alignment of Sheets and Fixings

All roof decking sheets shall be fixed plumb and level with all fixings evenly spaced and accurately lined. All dirt and grease shall be removed from the surfaces of the sheets as the work proceeds.

3.02.04 Site Cutting

Approval must be obtained before the roof decking sheets are cut at site. Generally cutting of sheets to length will not be permitted, only special cutting and trimming for small openings shall be allowed. Where possible, site cut edges shall be concealed at laps.

3.02.05 Damaged Sheets

Distorted, blemished or water stained sheets and any other fittings shall not be used.

3.02.06 Laps



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 311 of 361

End laps and side laps to roof decking sheets shall be sufficiently large to ensure that the decking complies with the weather tightness and other requirements of this specification. The length of each decking sheet shall be adjusted so that the end laps shall bear on the purlins. In no case end laps shall not be less than 150 mm and side laps shall not be less than 53 mm.

3.02.07 End Lap Fixings

End lap fixings shall be located at least 25 mm from the end of each sheet.

3.02.08 Side Lap Fixings

The spacing of side lap fixings shall ensure compliance with this specification regarding tightness. The spacing of these fixing screws shall not exceed 500mm. The fixing shall be located in the bottom flat of the corrugation.

3.02.09 Holes

Holes in MS decking sheets shall be punched. In case holes are drilled holes, it is to be ensured that the holes do not go oversize due to the small thickness of the sheeting. All drilling swarf shall be removed from the surfaces of decking, supporting steel work, purlins etc.

3.02.10 Location and Spacing of Fixings

Fixings shall be accurately located in position in the centre of the corrugations to ensure that the heads of bolts, nuts and washers bear squarely down on the surface of the sheeting and are not located at the edge or on the joints in supporting purlins.

3.02.11 Fixings

The tenderer shall submit with his tender details of the proposed method for securing the roofing sheets to the metal purlins. The roof decking sheets are to be fixed to the roof purlins with hex washer head white zinc plated heat treated carbon steel self drilling / self tapping screws of minimum thread diameter of 5.6mm. These self drilling screws shall be drilled through the roofing sheets and purlins supporting the roofing sheets. These purlins shall be suitably spaced as per the requirement of roofing sheets and the roofing sheets shall not sag more than span/250 for the loads likely to be imposed during concreting and in future. The self-drilling screws are to be spaced at a maximum distance of 390mm centre to centre along the length of the purlins and top chord of truss. The screws are to be located preferably in the valley only and shall be installed in accordance with the manufacturer's recommendations using tools approved by the manufacturer which do not damage the coating of the decking sheets.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 312 of 361

3.03.00 Protection during Construction

Precautions shall be taken during the erection of the roof decking to ensure that partially erected decking are protected during inclement weather and damage at all times.

3.04.00 Damage

Any damage to coating & primer during transportation is to redone with the similar type of coating as per the manufacturer's specification at no extra cost to the Owner.

4.00.00 Acceptance Criteria

The installation shall present a neat appearance and shall be checked for water tightness. The following shall be checked :

- a) Side and end laps
- b) Absence of damage in the sheeting.
- c) Conformity of fixings with the approved design.

5.00.00 IS Codes

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

- IS : 513 - Specification for cold rolled carbon steel sheets.
- IS : 3618 - Specification for phosphate treatment of iron and steel for protection against corrosion.
- IS : 4431 - Specification for carbon & carbon manganese free cutting steel.
- IS : 1573 - Electroplated Coatings of zinc on iron and steel.

6.00.0 RATES AND MEASUREMENTS

6.01.00 Rates



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 313 of 361`

Rates shall be unit rate for complete item described in the Schedule of Items and shall include all wastage.

6.02.00

Method of Measurement

Roofing shall be measured for net area of the work done. Profiled sheeting (coated & painted) shall be measured in plan area of sheets and not girthed. No deduction shall be made for openings measuring up to 0.1 sq.m. in area. No extra shall be paid for extra labour in cutting and for wastage etc. in making opening and cutting to size.

No payments shall be made for laps.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 314 of 361

SECTION - D

SUB-SECTION – D20

FALSE FLOORING



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 315 of 361`

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	GENERAL
2.00.00	MATERIALS
3.00.00	INSTALLATION
4.00.00	ACCEPTANCE CRITERIA
5.00.00	IS CODES
6.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 316 of 361

FALSE FLOORING

1.00.00 General

This section of the specification covers the supply, fabrication and installation of false flooring system having PVC top finish particle board, GI supporting system, painting etc. as per schedule of items in the main plant building and any other area as indicated in the drawings.

The scope of contractor covers supply of all materials, fabrication & installation works required to be carried out for completion of false flooring in the area specified in the drawings.

2.00.00 MATERIAL

2.01.00 Supporting structure

Supporting pedestals shall be made of steel and will be of height as required. Supporting pedestal shall be truly vertical and located at distances to conform with size of floor panels and shall be equipped with locking devices to prevent disturbances of finished elevation. Base of pedestal shall have integral load dispersion plate of size 100x100x8mm to transmit the load evenly to the base floor. Adjustment of pedestal shall be provided by threaded vertical rod of 25mm diameter and elevating nut. The pedestal head shall provide positive interlocking of the steel grid channels supporting system and shall prevent lateral shifting.

The grid channels shall be made of galvanised steel of 40mm x 40mm x 3.15mm thick and shall be placed at 610mm centre to centre both ways to support floor panels in uniform levelled elevations. Nominal height of the false flooring system shall be 600 mm unless otherwise indicated. Pedestal head shall be equipped with conducting grounding pad if so desired by the Engineer

2.02.00 Floor Panels

The floor panels shall be made of fire resistant particle board, phenol formaldehyde bonded. Size of each panel shall be 610mm x 610mm with all panel edges finished to a tolerance of ± 0.2 mm. Floor panel shall have 2mm thick non-static PVC on top, 2mm thick hard PVC strip lipping on four edges and 26 G aluminium sheet fixed with araldite at bottom. Minimum thickness of the panel shall be 35mm, unless otherwise noted. All panels shall be completely interchangeable and easily removable with a suction lift tool. Panels shall be square within a tolerance of ± 0.25 mm on the diagonal. The floor panels shall be cut, wherever required for providing suitable outlets for cables and edges shall be lipped with hard PVC sheets.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 317 of 361

2.02.01 Strength

Each 610mm x 610 mm floor panel must be capable of withstanding the designed service load. The ultimate strength shall provide a safety factor of 3. The false flooring shall be capable of carrying a axial load of 800 kg and uniform load of 2000 kg/sq.m with maximum deflection of 1/350. If required by the Engineer, the samples shall be accepted only after carrying out load tests. The Engineer may relax the test requirements with concentrated load in case cabinets are not handled with castor fitting arrangement.

One additional pedestal shall be provided under floor stringer along front panel area of each control board for taking possible additional load that may occur from time to time.

2.02.02 Surface finish

All removable panels shall have the top surface finished with 2 mm thick flexible PVC flooring conforming to IS:3462 and shall be fixed to the surface with compatible high-creep resistant adhesive. The PVC floor tile shall be in single piece for each floor panel. Under side of panels shall also be painted with suitable epoxy or oil based paint.

2.02.03 Damaged Floor Panels

Distorted, blemished or stained floor panels shall not be used.

2.03.00 Skirting

Skirting shall be 150 mm high and 2 mm thick, completely matching with false flooring surface finish materials and shall be fixed to the wall surface as per manufacturer's installation instructions.

3.00.00 INSTALLATION

3.01.00 Base

The system shall be placed over a base of RCC floor slab and beams. Any grouting etc. that is necessary to fix the supporting structure shall be done.

The concrete sub floor shall be sealed with two coats of polyurethane paint to prevent moisture from coming in contact with cables and to minimise dust problem.

The floor panels and channels shall be completely interchangeable and remain in position without screwing or bolting under working/imposed loadings.

Any damage to the sub floor during installation of the false flooring system shall be made good by the contractor without any extra cost to the Owner. All steel surfaces are to be protected by two coats of polyurethane paint over a



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 318 of 361

compatible primer and any damage to the paint during installation shall be made good. In case the loads exerted by the weight of machines are above the stated characteristics of floor finish material, the floor shall be protected by overlaying hard board during installation of machine or equipment.

All installation work of the false flooring system shall be supervised by the manufacturer's authorised representative.

3.03.00 Painting

After fixing the false flooring supporting system the sub floor shall be given a coat of polyurethane paint.

3.04.00 Protection during Construction

All precautions shall be taken during the erection of the false flooring to ensure that partially erected flooring are protected and shall not be damaged before handing over to owner.

3.05.00 Damage

Any damage of coating to supporting system caused during transportation is to be redone with the similar type of coating as per the manufacturer's specification at no extra cost to the Owner.

4.00.00 ACCEPTANCE CRITERIA

The false flooring system shall only be accepted after completion of following checks :

- a. Level
- b. Alignment of joints
- c. Thickness of joints
- d. Surface finish
- e. Colour and texture
- f. Details of edges, junctions etc.
- g. Performance
- h. Criteria specified for strength.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 319 of 361

5.00.00

IS CODES

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the Engineer, shall be followed.

IS:5318 Laying of flexible sheet and flooring.

IS:3462 Flexible PVC flooring

IS:3087 Wood particle boards (medium density) for general purposes.

6.01.0

RATES AND MEASUREMENTS

6.01.00

Rates

Rates shall be unit rate for complete item described in the Schedule of Items and shall include, but not limited to, supply & installation of floor panels, supporting systems, paintings etc.

6.02.00

Method of Measurement

False flooring shall be measured in Sq.M for net area of the work done. No deduction shall be made for openings measuring up to 0.4 sq.m. in area. No extra shall be paid for extra labour in cutting and for wastage etc. in making opening and cutting to size.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL,SRUCTURAL
AND ARCHITECTUURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 320 of 361`

SECTION - D

SUB-SECTION – D21

BORED CAST-IN-SITU RCC PILES



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 321 of 361

CONTENTS

CLAUSE NO.	DESCRIPTION
-------------------	--------------------

1.00.00	SCOPE
---------	-------

2.00.00	GENERAL REQUIREMENTS
---------	----------------------

3.00.00	MATERIALS
---------	-----------

4.00.00	PILE INSTALLATION
---------	-------------------

5.00.0	SAMPLING, TESTING, AND QUALITY ASSURANCE
--------	--

6.00.00	PILE TESTING
---------	--------------

7.00.00	CODES AND STANDARDS
---------	---------------------

8.00.00	RATES AND MEASUREMENT
---------	-----------------------

ANNEXURE-A

ANNEXURE-B

ANNEXURE-C

ANNEXURE-D

TABLE

-

1



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 322 of 361

TECHNICAL SPECIFICATION FOR INSTALLATION OF BORED CAST-IN-SITU PILES

1.00.00 SCOPE

This specification covers the installation of bored cast-in-situ reinforced concrete vertical piles of specified load carrying capacity and diameter for various structures. This specification also covers carrying out initial and routine load tests on piles to assess their vertical, horizontal and pull out load carrying capacities.

2.00.00 GENERAL REQUIREMENT

2.01.00 This specification along with specific requirements under Annexure-A covers the technical requirements for piling work.

2.02.00 The work shall include supplying and providing necessary materials, mobilization of all necessary equipments (Annexure-B), providing necessary engineering supervision through qualified and technical personnel, skilled and unskilled labour, etc. as required to carryout the complete piling work, and submission of records as per schedule.

2.03.00 The Contractor shall carryout all works as mentioned in Scope above. All works shall be executed to the satisfaction of the Engineer.

2.04.00 Pile capacities in vertical compression, horizontal, pullout loads for various pile diameters are given in Annexure-A.

2.05.00 The Contractor shall confirm and guarantee the "Safe Load" capacities by conducting both initial and working load test on piles as mentioned in the specific requirements.

2.06.00 The Contractor shall submit along with tender documents his tender design of piles based on soil data furnished by the Owner along with this specification. The ultimate load capacity of a pile may be estimated using suitable static formula and the minimum factor of safety shall be 2.5. However, safe load carrying capacity shall be conformed and guaranteed by conducting initial and routine load tests.

2.07.00 In case of initial or routine load test piles, if the Contractor fails to establish the safe load capacity as per his design, the Owner has the right to either derate the pile capacity on prorata basis or insist the Contractor to modify the pile design, to achieve the desired safe load capacity at no extra cost to the Owner.

2.08.00 Derating is acceptable up to 90 percent. In such case, additional piles shall be installed as per the design requirements.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 323 of 361

- 2.09.00 The Owner shall decide whether to derate or modify the design based on the design considerations such as providing additional piles in the designed pile cap, provision for extending the pile cap size, etc.
- 2.10.00 In case the Owner decides to modify the design instead of derating the pile, the contractor shall carry out the same and install separate test piles and test the same to guarantee the safe load at no extra cost to the Owner. However no extra shall be charged for the additional test piles as well as testing of these piles as per agreed contract conditions.
- 2.11.00 In case of working piles, if the pile does not meet the guaranteed capacity or rejected due to any other reason, the Contractor shall install extra piles at no extra cost to the Owner. Further, the extra cost, due to the increase in the pile cap size if any, on account of extra piles, shall be borne by the Contractor.
- 2.12.00 It is essential that all equipment and instruments are properly calibrated both at commencement and immediately after the completion of tests so that they represent true values. Certificates to this effect from an approved institution shall be furnished to the Engineer. If the Engineer so desires the Contractor shall arrange for having the instruments tested at an approved laboratory at no extra cost to the Owner and the test report shall be submitted to the Engineer. If the Engineer desires to witness such tests Contractor shall arrange to conduct the test in his presence.
- 2.13.00 The Contractor shall make his own arrangements for locating the coordinates and position of piles as per drawings supplied to him and for determining the Reduced Levels (RL) of these locations with respect to the benchmark indicated by the Engineer. Two established reference lines in mutually perpendicular direction shall be indicated to the Contractor. The Contractor shall provide at site all the required survey instruments to the satisfaction of the Engineer so that the work can be carried out accurately according to specifications and drawings.
- 2.14.00 The contractor shall assure the quality of piling work including cleaning of pile bore, quality of concrete, integrity of piles, etc.
- 2.15.00 **AVAILABLE SUB-SOIL DATA**
An abstract of the sub soil data is furnished in the tender document. However, the detailed soil investigation report shall be made available for reference of the bidder, if so required, at the office of the Owner. The soil data furnished is in good faith and only for the guidance of the Bidder, to arrive at design parameters and construction methods.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 324 of 361

3.00.00 MATERIALS

3.01.00 General

All materials viz cement, steel, aggregates, water, etc. which are to be used for pile construction shall conform to relevant IS codes for properties, storage and handling of common building materials. However, aggregates more than 20 mm size shall not be used.

3.02.00 CONCRETE

Concrete shall be manufactured either by central batching plant or Ready Mix concrete. However, for initial test piles suitable method as approved by the Engineer may be used. Concrete shall conform to IS: 10262 & IS: 456.

3.02.01 Technical Specification for Cement Concrete (Plain and Reinforced) works along with IS: 2911 Part I/Sec 2 shall be followed for concrete works of piles. Use of plasticiser to control the water cement ratio shall be permitted on specific approval from the Engineer. Water cement ratio shall not be greater than 0.5.

3.02.02 Grade and minimum cement content
Minimum grade of concrete shall be as per Annexure-A conforming to IS: 456. Minimum cement content of 400 Kg/M³ of concrete shall be used for M-20 grade concrete.

3.02.03 Slump of concrete
The slump of concrete shall vary between 150 to 180 mm.

3.03.00 REINFORCEMENT

3.03.01 Longitudinal reinforcement in pile shall be high strength deformed steel bars conforming to IS: 1786 unless specified otherwise. Lateral reinforcement in pile shall be of mild steel conforming to IS: 432 Part-1 or HYSD bars as per IS: 1786.

3.03.02 The longitudinal reinforcement shall be provided considering the combination of vertical (compression and tension) and horizontal loads. However, the minimum longitudinal reinforcement shall be 0.4 percent of the sectional area calculated on the basis of nominal pile diameter. Minimum six numbers of bars shall be provided for longitudinal reinforcement. The diameter of longitudinal reinforcement bars shall not be less than 12mm. The stipulated minimum reinforcement shall be provided for the full length of pile.

3.03.03 The longitudinal reinforcement shall project 50 times its diameter above cut off level unless otherwise indicated.

3.03.04 The laterals shall be tied to the longitudinal reinforcement to maintain its shape and spacing. The laterals may be in the form of links or spirals. The minimum diameter



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 325 of 361

of the links or spirals shall be 6 mm and the spacing of the links or spiral shall not be less than 150 mm and in no case more than 250 mm.

3.03.05 Reinforcement cage shall be sufficiently rigid to withstand handling and installation without any deformation and damage. As far as possible number of joints (laps) in longitudinal reinforcement shall be minimum. In case the reinforcement cage is made up of more than one segment, these shall preferably be assembled before lowering into casing tube/pilebore by providing necessary laps as per IS: 456.

3.03.06 The minimum clear distance between the two adjacent main reinforcement bars shall normally be 100 mm for the full depth of cage.

3.03.07 The laps in the reinforcement shall be such that the full strength of the bar is effective across the joint and the reinforcement cage is of sound construction.

3.03.08 Laps shall be staggered as far as practicable and not more than 50% bars shall be lapped at a particular section. Lap joints shall be staggered by at least 1.3 times the lapped length (Centre to Centre).

3.03.09 Proper cover and central placement of the reinforcement cage in the pile bore shall be ensured by use of suitable concrete spacers or rollers, cast specifically for the purpose.

3.03.10 Minimum clear cover to the longitudinal reinforcement shall be 50 mm, unless otherwise mentioned.

3.03.11 Bundling of bars is not permitted.

4.00.00 PILE INSTALLATION

Installation of piles shall be carried out as per pile layout drawings, installation criteria, and the direction of the Engineer.

4.01.00 Equipment and Accessories

4.01.01 The equipment and accessories for installation of bored cast-in-situ piles shall be selected giving due consideration to the sub soil conditions, ground water conditions and the method of casting, etc. These shall be of standard type and shall have the approval of the Engineer.

4.01.02 List and details of equipment and accessories proposed to be used for the job shall be submitted along with the bid.

4.01.03 The capacity of the rig shall be adequate so as to reach the specified founding level.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 326 of 361

4.01.04 Provision shall be kept for chiselling within the pilebore, as specified elsewhere in this specification. Chiselling shall be carried out only with the approval of Engineer.

4.02.00 Installation Criteria

4.02.01 For determining the founding level of piles in soil as specified elsewhere, the Contractor shall have to perform Standard penetration test (SPT) as per IS: 2131 in a separate bore hole. The SPT shall be conducted at 1.0 m interval between the depths covering 5 metres each above and below the specified founding level. The bore shall be 100 mm diameter and method of boring shall conform to IS: 1892.

4.02.02 For determining founding level of piles in rock, as specified elsewhere socketing horizon shall be established by the Contractor by collecting rock cores of NX size in a separate borehole, and testing the same for uniaxial compressive strength (UCS). Cores shall be collected by double tube core barrel attached with diamond bit. Coring shall be done upto a depth as indicated in the "specific requirements." Coring in rock shall conform to IS: 6926.

4.02.03 In case it is not possible to test the cores so obtained for uniaxial compressive strength, cores shall be tested for point load strength index and correlated to obtain uniaxial compressive strength.

4.02.04 Number of boreholes for carrying out SPT in soil or uniaxial compressive strength in rock, shall vary from one in 100 to 150 piles or pile group of 150 Sqm depending on the site condition and as decided by the Engineer. However, at the location of initial load test piles, one such borehole shall be done.

4.02.05 A protocol between contractor and BHEL site shall be maintained regarding the strata at founding level. SPT value and UCS from the nearest borehole shall be indicated therein.

4.02.06 The founding level of the pile shall be decided based on the criteria elaborated in the specific requirements under Annexure-A. Concreting shall not be done until the above conditions for founding level are satisfied.

4.02.07 Approval of founding level by the Engineer shall in no way absolve the Contractor of his responsibility to guarantee the Safe load capacity of the piles as indicated in this document.

4.03.00 Control of position and alignment

4.03.01 Piles shall be installed as accurately vertical as possible. The permissible limits for deviation with respect to position and (inclination) alignment shall conform to IS: 2911 Part I/Sec. 2, which is reproduced below for ready reference.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 327 of 361

- a) The maximum deviation of vertical piles shall not exceed 1.5 per cent in alignment.
- b) Piles shall not deviate more than 75 mm or $D/4$ whichever is less (75mm or $D/10$ whichever is more in case of piles having diameter more than 750mm) from their designed position at the working level.

4.04.00 Boring

4.04.01 Boring operations shall be done by rotary or percussion type drilling rigs using reverse mud circulation (RMC) method. Rotary hydraulic pulley shall be preferred.

4.04.02 The Contractor shall satisfy himself about the suitability of the method to be adopted for site. If DMC (direct mud circulation) or RMC is used Bentonite slurry shall be pumped through drill rods by means of high-pressure pumps. The cutting tool shall have suitable ports for the bentonite slurry to flow out at high pressure. If on mobilisation, the Contractor fails to make a proper bore for any reason, the Contractor has to switchover to other boring methods as approved by the Engineer at no extra cost to the Owner.

4.04.03 Working level shall be above the cut off level. After the initial boring of about 1.0m a temporary guide casing of suitable length shall be lowered in the pile bore. The diameter of guide casing shall be of such diameter, so as to give the necessary finished diameter of the concrete pile. The centre line of guide casing shall be checked before continuing further boring. Guide casing shall be minimum of 1.0m length. Additional length of casing may be used depending on the condition of the strata, ground water level etc.

4.04.04 Use of drilling mud (bentonite slurry) for stabilizing the sides of the pile bore is necessary wherever subsoil is likely to collapse in the pile bore. Drilling mud to be used shall meet the requirement as given in Annexure-C.

4.04.05 The bentonite slurry and the cuttings, which are carried to the surface by the rising flow of the slurry, shall pass through settling tanks of adequate size to remove the sand and spoils from the slurry before the slurry is recirculated to the boring. The bentonite slurry mixing and recirculation plant shall be suitably designed and installed.

4.04.06 The bentonite slurry shall be maintained at 1.5m above the ground water level during boring operations and till the pile is concreted. When DMC or RMC method is used the bentonite slurry shall be under constant circulation till start of concreting.

4.04.07 The size of cutting tools shall not be less than the diameter of the pile by more than 75mm. However, the pile bore shall be of the specified size.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 328 of 361

4.05.00

Chiselling

4.05.01

Chiselling may be resorted to with the permission of the Engineer below the socketing horizon. The chiselling tool or bit shall be of adequate size and weight so as to reach the desired depth.

4.06.00

Cleaning of Pile bore

4.06.01

On completion of the pile bore upto the required depth, the bottom of the hole shall be cleaned very carefully before concreting work is taken up. Cleaning shall ensure that the pile bore is completely free from sludge/bored materials, debris of rock/boulder etc. Necessary checks shall be made as given in clause 5.0 to confirm the thorough cleaning of the pile bore.

4.06.02

Pile bore shall be cleaned by fresh drilling mud through tremie pipe after placing reinforcement and just before start of concreting.

4.06.03

Pile bore spoil along with used drilling mud shall be disposed off from site as directed by the Engineer.

4.06.04

Pile bore bottom shall be thoroughly cleaned to make it free from sludge or any foreign matter before and after placing the reinforcement cage.

4.07.00

Adjacent Structures

4.07.01

When working near existing structures care shall be taken to avoid any damage to such structures.

4.08.00

Concreting

4.08.01

The Contractor shall carry out concrete mix design in accordance with IS: 10262 and submit mix design calculations and get them approved from the Engineer well in advance for installation of piles. Adequate number of tests on cubes, etc. shall be carried out as mentioned in clause 5.0 to ensure concrete of the minimum specified strength in accordance with IS: 456 at requisite workability (slump).

4.08.02

Concreting shall not be done until the Engineer is satisfied that the bearing strata (soil/rock) met with at the termination level of pile.

4.08.03

The time interval between the completion of boring and placing of concrete shall not exceed 6 hrs. In case the time interval exceeds 6 hrs the pilebore shall be abandoned. However, the Engineer may allow concreting provided the Contractor extends the pile bore by 0.5 m beyond the proposed depth, and clean the pilebore. The entire cost of all operation and materials for this extra length shall be borne by the Contractor.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 329 of 361

- 4.08.04 Proper placement of the reinforcement cage to its full length shall be ensured before concreting.
- 4.08.05 Concreting shall be done by tremie method as specified by IS: 2911 (Part I /Sec.2). The level of drilling mud shall be maintained sufficiently above the ground water level.
- 4.08.06 The concreting operations shall not be taken up when the specific gravity of bottom slurry is more than 1.2 and sand content more than 7%. The drilling mud sample shall be collected from the bottom of pilebore as mentioned in clause 5.
- 4.08.07 Consistency of the drilling mud suspension shall be controlled throughout the concreting operations in order to keep the bore stabilized as well as to prevent concrete getting mixed up with the thicker suspension of the mud.
- 4.08.08 It shall be ensured that volume of concrete poured is at least equal to the theoretically computed volume of pile shaft being cast.
- 4.08.09 The temporary guide casing shall be withdrawn cautiously, after concreting is done upto the required level. While withdrawing the casing concrete shall not be disturbed.
- 4.09.00 Cut off level (COL)**
- 4.09.01 Cut off level of piles shall be as indicated in drawings released for construction or as indicated by the Engineer.
- 4.09.02 The top of concrete in pile shall be brought above the COL to remove all laitance and weak concrete and to ensure good concrete at COL for proper embedment in to pile cap.
- 4.09.03 When the pile cut off level is less than 1.0 metre below the working level, concrete shall be cast to the piling platform level to permit overflow of concrete for visual inspection. In case COL of pile is more than 1.0 metre below working level then concrete shall be cast to a minimum of one metre above COL.
- 4.10.00 Sequence of Piling**
- 4.10.01 Each pile shall be identified with a reference number.
- 4.10.02 The convenience of installation may be taken into account while scheduling the sequence of piling in a group. This scheduling shall avoid piles being bored close to other recently constructed piles.
- 4.11.00 Building up of Piles**



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 330 of 361

4.11.01 If any pile, already cast as per construction drawing, requires any extra casting due to any change in cut off level or the cast pile top level is less than the specified level or for any other reason, then the pile shall be built-up by using atleast one grade higher concrete than that used for concreting of the same pile, ensuring proper continuity with the existing concrete and to the satisfaction of the Engineer. Necessary reinforcement as per design requirement and suitable shuttering shall be provided before casting the concrete. Surrounding soil shall also be built up to the required level by proper compaction to ensure lateral capacity of the pile.

4.12.00 Breaking off of Piles

4.12.01 If any pile already cast, requires breaking due to lowering in cut off level or for any other reason, then the same shall be carried out, not before seven days of casting without affecting the quality of existing pile such as loosening, cracking etc. and to the satisfaction of the Engineer.

4.13.00 Preparation of Pile head

4.13.01 The soil surrounding the piles shall be excavated upto the bottom of the lean concrete below the pile cap, with provision for working space, sufficient enough to place shuttering, reinforcement, concreting and any other related operations.

4.13.02 The exposed part of concrete above the COL shall be removed/chipped off and made to a uniform level at COL, but not before seven days of casting of pile.

4.13.03 The projected reinforcement above COL shall be properly cleaned and bent to the required shape and level to be anchored into the pile cap.

4.13.04 The pile top shall be embedded into the pile cap by 50mm or clear cover to reinforcement, whichever is higher.

4.13.05 All loose material, like debris due to chipping/breaking of pile head to the desired level, shall be removed and disposed off as directed by the Engineer.

4.14.00 Rejection and Replacement of Defective Piles

4.14.01 The Engineer reserves the right to reject any pile which in his opinion is defective on account of load capacity, structural integrity, position, alignment, concrete quality etc. Piles that are defective shall be pulled out or left in place as judged convenient by the Engineer, without affecting the performance of adjacent piles. The Contractor shall install additional piles to substitute the defective piles as per the directions of the Engineer, at no extra cost to the Owner.

4.15.00 Recording of Piling Data



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 331 of 361

4.15.01 The Contractor shall record all the information during installation of piles. Typical data sheet for recording pile data shall be as shown in Appendix D of IS: 2911 Part I/Sec.2. The pile data shall also include all the details as in Annexure-D. On completion of each pile installation, pile record in triplicate shall be submitted to Engineer within two days of completion of concreting of the pile.

5.00.00 SAMPLING, TESTING AND QUALITY ASSURANCE

5.01.00 Facilities required for sampling and testing of materials, concrete, etc. in field and in laboratory should be provided by the Contractor. The Contractor shall carry out all sampling and testing in accordance with the relevant Indian Standards and this Specification. Where no specific testing procedure is mentioned the tests shall be carried out as per the prevalent accepted engineering practice and as per the directions of the Engineer. Tests shall be done in the presence of the Engineer or his authorized representative. In case the Engineer requires additional tests, the Contractor shall arrange to get these tests done and submit to the Engineer the test results in triplicate within three days after completion of any test.

5.02.00 The Contractor shall maintain records of all inspection and testing, which shall be made available to the Engineer. The Engineer at his discretion may waive some of the stipulations for small and unimportant concreting operations and other works.

5.03.00 Materials found unsuitable for acceptance shall be removed and replaced by the Contractor. The work done by this unsuitable material shall be redone as per specification requirements & and to the satisfaction of the Engineer at no extra cost to the Owner.

5.04.00 Quality Assurance Programme

- a) The Contractor shall submit and finalize a detailed Field Quality Assurance Programme within 30 days from the date of award of the contract, according to the requirements of this specification. This shall include setting up of a testing laboratory, arrangement of testing apparatus/equipment, deployment of qualified/experienced manpower, preparation of field quality plan, etc. On finalized field quality plan, the Owner shall identify, customer hold points, beyond which work shall not proceed without written approval from the Engineer. The testing apparatus/equipment installed in the field laboratory shall be calibrated/ corrected by the qualified persons as frequently as possible to give accurate testing results.
- b) Frequency of sampling and testing, etc. and Acceptance Criteria are given in Table - 1. The testing shall be done at field laboratory or any other laboratory approved by the Engineer. However, the testing frequencies set forth are the desirable minimum and the Engineer shall have the full authority to call for tests as frequently as he may deem necessary to satisfy himself that the materials and works comply with the appropriate specifications. The materials shall be tested to meet all the specified requirements before acceptance at manufacturers premises or at independent



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 332 of 361

government approved laboratory. Tests indicated in the table are for cross checking at site the conformity of the materials to some of the specifications.

5.05.00 Testing of Concrete

5.05.01 Concrete and other materials shall be tested for quality, strength and other properties. Details of testing shall be as specified under technical specification for Cement concrete (Plain and Reinforced).

5.05.02 One sample consisting of six test cubes shall be made from the concrete used in each test pile, three to be tested after 7 days and three after 28 days.

5.05.03 For working piles, minimum one sample consisting of six test cubes shall be made from the concrete for the first ten piles, three to be tested after 7 days and three after 28 days. Thereafter, minimum one sample consisting of three test cubes for every 10 piles shall be tested for the 7-days & 28-days cube strength.

5.05.04 In preparation of test cubes or specimens vibrators shall not be used.

5.05.05 Concrete shall be tested for slump at every 1-hour interval during concreting of piles.

5.05.06 The frequency of sampling and testing of concrete and materials shall be done as per technical specification for cement concrete (Plain & Reinforced).

5.05.07 The acceptance criteria shall be as mentioned in Table-1.

5.06.00 Testing for position and alignment

5.06.01 Each pile shall be checked for its position with respect to specified location. Each pile bore shall be checked for its alignment.

5.06.02 Permissible limits for deviation shall be as specified under clause no. 4.03.

5.07.00 Properties of Drilling mud

5.07.01 Properties of drilling mud shall be checked as per requirement under Annexure C. Prior to the commencement of piling work and thereafter minimum once in a week or as found necessary by the Engineer, one sample consisting of 3 specimens shall be tested. Acceptance criteria applicable are as specified else where with 5% variation. This relaxation is not applicable for properties of drilling mud before concreting.

5.07.02 Density of the drilling mud shall be checked in each pile before concreting.

5.08.00 Check for Pile bore



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 333 of 361

5.08.01 On completion of boring and cleaning the bottom of each pilebore shall be checked from the sample collected from near the bottom of pile bore or by any other methods as approved by the Engineer, to ensure that it is free from pilebore spoil/debris and any other loose material, before concreting. Concreting shall be done only after the approval of the Engineer.

5.08.02 For sampling of drilling mud from the pilebore the following method or any other suitable method shall be adopted.

a) A solid cone shall be lowered by a string to the bottom of pilebore. A sampler tube closed at top with a central hole (hollow cylinder) is lowered over the cone, and then a top cover shall be lowered over the cylinder. Care shall be taken for proper fittings of assembly to minimize the leakage while lifting the cone assembly to the ground surface. The slurry collected in the sampler tube shall be tested for density and sand content.

b) Use of borehole camera for checking the pile bore spoil and strata is acceptable on approval of the Engineer.

5.09.00 Pile Integrity test

5.09.01 Low strain integrity test shall be conducted on 50% of the jobs piles and on all test piles or as directed by Engineer. The system shall have the computer readout facility and report on the findings of this shall be furnished to the Owner. This test shall be used to identify the job piles for routine load test.

Piles shall be trimmed to cut off level or sound concrete level. No pile cap blindage work should be undertaken prior to this test. The cast in-situ piles should not be tested before 14 days of casting.

5.09.02 The test shall be undertaken by persons trained and experienced and capable of interpreting the results with specific regard to piling. This test is limited to testing the integrity of the shaft and is not intended to replace the use of static load testing.

5.09.03 Low Strain Integrity Test Methodology:

a) In this test, a low stress wave is set up in the pile shaft and is also known as Sonic Integrity or Sonic Echo test.

b) A small metal/hard rubber hammer is used to produce a light blow on top of the pile. The shock wave travelling down the length of the pile is reflected back from the toe of the pile and recorded through a suitable transducer/ accelerometer in a computer for subsequent analysis.

c) The primary shockwave, which travels down the length of the shaft, is reflected from the toe by the change in density between the concrete and sub strata. However, if the pile has any imperfections or discontinuities within



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 334 of 361

its length these will set up secondary reflections, which will be added to the return signal.

- d) By analysis of the captured signal and knowledge of the conditions of the ground, age of concrete, etc. a picture of the locations of pile shaft defects can be built up. The observed signals are amplified into digital display as velocity versus length records providing information on structural integrity of piles.
- e) The stress wave velocity and approximate pile lengths are provided as input for the integrity testing. The stress wave velocity is dependent on the Young's Modulus and mass density of pile concrete.
- f) More than one recording of signals shall be done until repeatability of signals is achieved on the same pile.
- g) The tests shall be conducted at 3-6 locations to cover the entire cross section of the pile.

6.00.00 PILE TESTING

Pile load test shall be carried out as per IS:2911 Part-4 (latest edition) or as directed by Engineer.

6.01.00 INITIAL LOAD TEST

Initial load test shall be carried out on separately cast piles for confirmation of estimated pile capacities and to fix a more accurate driving criteria viz. set/bow, total number of blows and approximate depth etc. of founding level. At least 2 nos. of tests shall be conducted for each mode (vertical compression, pull out and lateral). The maximum test load shall be as mentioned in bill of quantities.

6.02.00 ROUTINE LOAD TEST

Routine load tests shall be carried out on job (working) piles for 0.5% of total no. of piles (for each mode and type). Maximum test load shall be 1.5 times the design safe load capacity. Piles showing unsatisfactory results as per load test results shall be treated as defective piles. Defective piles shall be removed or left in place and replaced by additional piles as directed by Engineer at no extra cost to the owner. Any additional cost towards design implications, if any, due to above shall be born by the contractor.

7.00.00 CODES AND STANDARDS

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) Codes, unless specified otherwise. In case any particular aspect of work is not specifically covered by Indian Standard Codes, any other standard practice, as may be specified by the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 335 of 361

Engineer, shall be followed.

- IS: 432 - Specification for mild steel and medium tensile steel bars (Part 1 & 11) and hard drawn steel wire for concrete reinforcement.
- IS: 456 - Code of practice for plain and reinforced concrete.
- IS: 1200 - Measurement of Building and Civil Engineering works (Part 23) Piling.
- IS: 1786 - Code of practice for twisted steel high strength deformed bars for concrete reinforcement.
- IS: 1892 - Code of practice for Subsurface Investigation for foundation.
- IS: 2131 - Method of Standard Penetration Test for Soils
- IS: 2911 - Code of practice for design and construction of pile Part I/Sec 2 foundations - Bored cast-in-situ concrete piles.
- IS: 2911 - Code of practice for design and construction of pile Part IV foundation - Load test on piles.
- IS: 6926 - Code of practice for Diamond core Drilling for Site Investigation for River Valley Projects.
- IS: 10262 - Recommended guidelines for concrete mix design.

8.00.00 RATES AND MEASUREMENTS

The clauses below shall apply for item rate contracts only. They shall not be applicable to turnkey/lump sum Contracts.

8.01.00 Rates

8.01.01 The items of work in the schedule of items, describe the work in brief. The various items in schedule of items shall be read in conjunction with the corresponding sections in the Technical Specifications, including amendments, and additions, if any. For each item in schedule of items, the unit rate shall include for the activities covered in the description of the item as well as for all necessary operations described in the specification and specific requirements.

8.01.02 The unit rates shall include for minor details which are obviously and fairly intended, and which may not have been included in the description in these documents, but are essential for the satisfactory completion of the work. Unit rates shall also include for all safety measures as required by codal provisions, local regulations, acts, bye-laws, etc. and for execution of work to the satisfaction of the Engineer.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 336 of 361

- 8.01.03 The quoted rate for each item shall be inclusive of mobilization of all plant, equipment, scaffolding, labour, materials, skilled and unskilled labour, and demobilization after completion of work, supervision, establishing the level and coordinates at each work.
- 8.01.04 The quoted rate for piling for a particular diameter and capacity of pile shall remain valid for the actual lengths provided /to be provided irrespective of the minimum length specified elsewhere in this specification.
- 8.01.05 The quoted rate for piling as per description of item works shall be inclusive of providing all plant equipment, labour, materials, skilled and unskilled labour, making observations, establishing the ground level and coordinates at each location of pile by carrying levels from one established bench mark and distances from one set of grid lines furnished by the owner.
- 8.01.06 The quoted rate for piling shall be inclusive of bailing out all the pile bore spoil from the pilebore, keeping the borehole free from bored material/debris etc. and disposing the bored/chiselled material along with the drilling mud upto 2 Km. beyond plant boundary or as directed by Engineer, flushing the pile bore by fresh bentonite before concreting, collection of samples from bottom of pilebore, transporting to laboratory, testing and reporting of results.
- 8.01.07 The quoted rate for piling shall include shifting of plant and equipment from one pile location to another pile locations, providing temporary casing pipe and removal of the same after completing, concreting, supply of necessary materials, equipment and manpower, cost of boring by approved method as specified, circulation of bentonite slurry and cleaning of borehole free from sludge, as specified, etc.
- 8.01.08 The quoted rate for piling shall also include chiselling, if any, required for socketing the pile in rock.
- 8.01.09 The quoted rate for the piling shall include concreting by termite method, length of pile above COL, withdrawal of guide casing, cost for preparation of pile head and disposal of debris etc., resulting from breaking off of pile upto COL, upto a distance of 2 Km from the plant boundary or as directed by Engineer.
- 8.01.10 The quoted rate for piling shall also include providing reinforcement and its cleaning, straightening, cutting, bending, binding with annealed wire, welding, tackwelding, providing concrete cover blocks, spacers, placing the reinforcement cage in pile casing/bore and other cost of tools and plants, materials, labours, carting the steel from store to piling site and return of unused steel to the Owners storage point, etc.
- 8.02.11 Plasticiser/Admixture when used as directed by the Engineer shall be included in piling rates.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 337 of 361

- 8.01.12 The quoted rate for piling shall include for all quality assurance requirements, but not limited to providing for technical inspection, transportation of samples to laboratory, testing samples, maintaining and submitting all test records, etc.
- 8.01.13 The quoted rate for boring in separate borehole shall be inclusive of performing of SPT at regular intervals as specified and collecting rock cores from boreholes, upto the depth as specified shall be inclusive of transporting to laboratory, testing and reporting of the results.
- 8.01.14 Unit rate for low integrity test shall be inclusive of mobilization of the entire set of equipment, computer readout, printer, and equipment which may not have been included in the description but are essential for the satisfactory completion of the work as per internationally accepted practice. The rate quoted shall be inclusive of repeatability of test, preparation of pile top surface etc.
- 8.02.00 Measurement**
- 8.02.01 Piling length shall be measurement by linear measurement from pile cut-off level to the tip of pile in meters upto second place of decimal separately for each diameter and capacity of pile. The length of pile to be cast above cut off level, as per specification, and as approved by Engineer, shall be considered for cement reconciliation only. Theoretical diameter of piles shall be considered for reconciliation of cement consumption. No extra payment shall be made for the length from existing ground to cut-off level.
- 8.02.02 Reinforcement steel shall be measured for reconciliation purpose only and the measurement shall be done for providing and placing reinforcement in piles, by weight in tones, up to third place of decimal in the following manner:
- i) The weight shall be arrived at by multiplying the actual length measured alongwith standard hooks, rings or spirals, spacers, cranks, bends, authorized laps, etc. by sectional weight. These shall be submitted with supporting documents giving the schedule of bars with sketches. The sectional weight to be adopted shall be IS code's sectional weight. Nothing extra shall be payable to the contractor on account of difference in weight, if any, due to different methods adopted for issue and measurement.
 - ii) Standard hooks, cranks, bend, authorized laps, supports, hangers and chairs which are covered in approved bar bending schedule shall be measured in tones.
 - iii) Dowels, neither shown on the drawings nor instructed by the Engineer, but required for construction facilities shall not be measured.
- 8.02.03 Breaking off of piles, due to subsequent change in design cut off level, shall be measured separately. This shall be measured in cubic metres upto second place



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 338 of 361

of decimal. This will be payable only when the pile is cast and on the basis of written instruction of the Engineer for lowering of COL.

8.02.04 Measurements for the item of boring in a separate borehole shall be measured in metres from ground level upto the depth as specified, upto second place of decimal. Item of work of boring in soil and coring in rock shall be measured separately for the actual length of boring in soil and coring in rock.

8.02.05 The item for pile integrity test shall be measured in terms of no. of piles tested.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 339 of 361

ANNEXURE-A

Specific Requirements for Bored Cast-in-situ RCC Piles

- A1.0 Minimum cement concrete grade M-25
- Minimum cement content 400 Kg/M³

A1.1 Safe load

Diameter of Pile

Diameter of Pile (mm)	Vertical/ Compression (MT)	Horizontal/ Lateral (MX)	Pull out/Tension (MT)
*	*	*	*
*	*	*	*

A2. Installation criteria

The installed pile(s) shall satisfy the following criteria.

A2.1 In Soil/weathered Rock

- a) Minimum length of the pile shall be _____* m below COL.
- b) The pile shall be terminated after penetrating through the strata having SPT penetration less than ____* cm for ____* blows, for a minimum length of _____* times the diameter of the pile.

A2.2 In Rock

- a) Piles shall be installed and socketed into the rocks for a length (socketing length) equal to ____* times the pile diameter subject to a minimum of _____* meter below the socketing horizon.
- b) Socketing horizon shall consist of rock strata having minimum uniaxial compressive strength of _____* kg/sq.cm.

A3. Average cut-off level for tender design and initial load test can be assumed as _____* m below ground level.

A4. A protocol shall be signed between BHEL site and contractor regarding,

Strata at the founding depth

Installation criteria



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 340 of 361

Socketing depth

Density of bentonite before concreting

Slump of concrete.

Time interval between end of boring and start of concreting,

* Values shall be indicated separately depending upon subsoil strata of the site.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 341 of 361

ANNEXURE-B

List of Equipments

Sl.No	Description	Capacity No.
1.	Piling Rigs	
2.	Chisel	3 T min 6 T max
3.	High pressure Mud Pumps	10 HP min 25 HP max
4.	Bentonite mixing plants	
5.	Concrete batching plant	
6.	Soil testing equipments	

Note:

1. The no. and capacity of the piling equipment varies for each work.
2. Additional equipments shall be mobilized if required as per the directions of the Engineer to match the work schedule at no extra cost to the Owner.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 342 of 361

ANNEXURE-C

Bentonite suspension used for piling work shall satisfy the following requirements

- a) Liquid limit of bentonite when tested in accordance with IS: 2720(Part V) shall be more than 300 percent and less than 450 percent.
- b) Sand content of the bentonite powder shall not be greater than 7 percent.
- c) Bentonite solution should be made by mixing it with fresh water using pump for circulation. The density of the freshly prepared bentonite suspension shall be between 1.034 and 1.10 gm/ml depending upon the pile dimensions and type of soil in which the pile is to be installed. However, the density of bentonite suspension after mixing with deleterious materials in the pilebore may be upto 1.25 gm/ml.
- d) The Marsh viscosity when tested by a Marsh cone shall be between 30 to 60 seconds.
- e) The differential free swell shall be more than 540 percent.
- f) The pH value of the bentonite suspension shall be between 9 and 11.5.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 343 of 361

ANNEXURE-D

PILE DATA

1. Reference No. Location (Co-ordinates) _____ area.
2. Sequence of Piling
3. Pile diameter & Type
4. Working level (Platform level)
5. Cut off level (COL)
6. Actual length below COL
7. Pile termination level
8. Top of finished concrete level
9. Date and time of start and completion of boring.
10. Depth of Ground water table in the vicinity.
11. Type of soil at pile tip
12. Method of boring operation
13. Details of drilling mud as used:
 - i) Freshly supplied mud
 - Liquid limit -
 - Sand content -
 - Density -
 - Marsh viscosity -
 - Swelling index -
 - pH value -
 - ii) Contaminated mud
 - Density -
 - Sand content -



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 344 of 361

14. SPT* N values in soil (from the nearest bore hole).
+UCS** value in rock (from the nearest bore hole).

* Standard penetration Test
** Unconfined compression strength
15. Chiseling if any, from..... m to m
16. Date and time of start and completion of concreting.
17. Method of placing concrete
18. Concrete quantity
Actual

Theoretical
19. Ref. Number of test cubes
20. Grade and slump of concrete
21. Results of test cubes
22. Reinforcement details:
Main Reinforcement
No. _____
Dia. _____
Depth _____

Stirrups: Type
No. _____
Dia. _____
Spacing _____
23. Any other information regarding obstructions, delay and other interruption to the sequence of work.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 345 of 361

TABLE -1

FREQUENCY OF SAMPLING AND TESTING

Sl. No	Type of material work	Nature of Test/ characteristics	Method of Test & frequency	No. of test	Acceptance Criteria
1.	Pilebore size a) diameter b) length		Physical measurement	each pile	as per specification
2.	Founding level	to establish socketing horizon/ and or founding level & upto depth 5m below founding level.	in separate borehole meant for the purpose a) SPT in soils/ weathered rock b) Core & UCS value of rock	1 borehole for 100-150 piles or group of 150 Sqm	Annexure - B
3.	Bentonite (Mud) properties. a) Basic properties of bentonite before use. b) Contaminated mud from pile bore bottom before concreting	Liquid Limit, Marsh Viscosity, Specific gravity, sand content, swelling index, pH value. Density, sand content	in lab in lab	As per Cl. 5.7 Each Pile	As per Annexure C As per annexure C
4.	Position and Alignment	-	Physical or any Approved method	Each Pile	As per Cl. 4.3
5.	Cleaning of pilebore	-	As per Cl. 5.8	Each Pile	Pilebore be free from bored material cuttings debris/sludge
6.	Reinforcement (R/F) Spacing of longitudinal R/F cover laps binding of laterals		Physical inspection and measurement	each cage	As per approved design
7.	Concrete a) Workability b) Cubes	Slump cone test Compressive Strength test	Each pile As per spec.	As per Cl. 5.5 As per Cl. 5.5	As per specification. As per IS: 456
8.	Materials like aggregate, sand etc.	As per technical specification for concrete and relevant IS codes			
9.	Pile head		Physical	each pile	



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 346 of 361

SECTION - D

SUB-SECTION – D22

SITE LEVELLING AND GRADING



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 347 of 361

C O N T E N T

CLAUSE NO.	DESCRIPTION
1.00.00	GENERAL
2.00.00	SCOPE
3.00.00	MATERIALS
4.00.00	QUALITY CONTROL
5.00.00	EXECUTION
6.00.00	RATES AND MEASUREMENTS



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 348 of 361

**STANDARD TECHNICAL SPECIFICATION
FOR
SITE LEVELLING AND GRADING**

1.00 GENERAL

This specification cover the works to be carried out for “**Site Levelling and Grading Works including Slope Protection**” etc for the entire plant and associated areas. The specified formation level(s) shall be achieved either by excavation or by raising with controlled fill with excavated/borrowed earth as the case may be.

2.00 SCOPE

2.01 The scope include all works involved in levelling the site to the lines, grades, cross sections and dimensions as shown on the approved drawings and/or as directed by the engineer including site clearance, setting out, earth work in excavation, stacking, loading, transportation, unloading, dewatering, drainage, filling, watering, compaction, turfing on slopes (if required), lighting, disposal of residual/surplus earth etc. It also include supplying and providing all labour, materials, supervision, services, equipments, tools and plants, testing and all incidental items of work not shown or specified but reasonably implied or necessary for the completion of the work etc.

2.02 All tools and plants, equipments and machineries to be used in this work shall be of standard quality and manufactured by reputed concerns conforming to Indian Standard (IS) codes or equivalent thereof.

2.03 Work to be provided by the Contractor

The works to be provided by the contractor unless specified otherwise shall include but not be limited to the following.

a) Supplying and providing all labour, supervision, services including as required under statutory labour regulations, materials, equipments, tools and plants, approaches, transportation etc required for the completion of the work.

b) Preparation and submission of detailed scheme of all operations required for executing the work (material handling, placement, services, approaches etc) to the engineer for approval.

c) Carrying out sampling and testing on fill materials/fills to assess the quality/moisture content/degree of compaction and submission of the test results whenever required by the engineer.

d) Design, construction and maintenance of Magazine of proper capacity for storage of explosives for blasting work and removal of the same after completion of the work etc.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 349 of 361

2.04 Work to be provided by others

No work under this specification will be provided for by any agency other than the contractor unless specifically mentioned elsewhere in the contract.

2.05 Codes and Standards

All work shall be carried out as per this specification and shall conform to the latest revision and/or replacements of the following or any other Indian Standard (IS) codes unless specified otherwise.

IS: 1200 Methods of measurement of building and civil engineering works,
Part-1: Earthwork

IS: 2720 Method of test for soils (Relevant parts)

IS: 3764 Excavation work- Code of safety

IS: 4081 Safety code for blasting and related drilling operations

IS: 4701 Code of practice for earthwork on canals

IS: 6922 Criteria for safety and design of structures subject to underground
blasts

In case of conflict between this specification and those (IS codes) referred to herein, the former shall prevail. In case any particular aspect of work is not covered specifically by the specification or/and by the IS codes, any other standard practice as may be specified by the engineer shall be followed.

2.06 Conformity with Designs

The contractor shall carry out the work as per the approved drawings, specification and as directed by the engineer.

3.00 MATERIALS

All materials required for the work shall be of best variety and approved by the engineer.

3.01 Materials for Excavation

For the purpose of identifying the various strata met during the course of excavation, the following classification is to be followed.

a) Soil



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 350 of 361

It include all type of soil including laterite, moorum etc with/without any percentage of kankars which can be excavated by normal means such as shovel, pick axe, crow bar, spade etc and those which do not fall under **clause** 3.01 (b) and (c) etc.

b) Soft Rock

It include the rocks (including weathered rock) which are removable by splitting with the help of crow bar, pick axe, wedges, pavement breakers, pneumatic tools, hammers or such implements etc and not requiring blasting (for excavation) in the opinion of the engineer.

c) Hard Rock

It includes the rocks, which require blasting for excavation in the opinion of the engineer. Where blasting is prohibited for any reasons, the excavation shall be carried out by chiselling or any other method as approved by the engineer. The mere fact that the contractor resorts to blasting shall not classify the soft rock under hard rock.

However, the engineer's decision on the type of strata encountered during excavation shall be the final and binding on the contractor.

3.02 Materials for Filling

Any coarse grained or fine grained low plastic soil free from vegetation, roots, shingle, salts, organic matters, sod and any other harmful chemicals shall be used for filling. The contractor shall test the fill material to establish its suitability and submit the results to the engineer for approval. Fill material shall be got approved by the engineer. The following type of materials shall not be used for filling.

- a) Materials from swamps, marshes and bogs
- b) Expansive clays
- c) Peat, logs, sod and perishable materials
- d) Materials susceptible to combustion
- e) Any material or industrial and domestic produce which will adversely affect other materials of work
- f) Materials from prohibited areas

The earth available by cutting the high grounds within the project site and the materials (if) available from the road excavation or any other excavation under the same contract shall be used for filling depending upon its suitability as fill material. Filling with excavated rock (in the project site) shall be done only



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 351 of 361

with the written permission of the engineer in the following manner. The boulders shall be broken into pieces not exceeding 150mm size in any direction and mixed with fine materials consisting of decomposed rock, moorum or any approved earth to fill the voids as far as possible and the mixture shall then be used for filling. In case the earth required for filling is over and above the earth available from the compulsory excavations within the project area, then borrow areas for obtaining suitable fill material shall be arranged by the contractor himself from outside the plant boundary limits and all expenses including royalties, taxes, duties etc shall be borne by him. He shall obtain and submit the necessary clearances/permissions from the concerned authorities to the engineer for the borrow areas/materials acquired.

4.00 QUALITY CONTROL

All works shall conform to the lines, levels, grades, cross sections and dimensions shown on the approved drawings and/or as directed by the engineer. The contractor shall establish and maintain quality control for the various aspects of the work, method of construction, materials and equipments used etc. The quality control operation shall include but not be limited to the following.

Sl. No.	Activity	Check
1	Lines, levels & grades	a) By periodic surveys b) By establishing markers, boards etc
2	Filling	(a) On quality of fill material (b) On moisture content of fill material (c) On degree of compaction achieved

5.00 EXECUTION

The contractor shall prepare and submit the detailed drawings/schemes for excavation and filling works as proposed to be executed by him showing the dimensions as per the construction drawings and specification adding his proposal of approaches, dewatering (if any), drainage and compaction etc within 15 days of award of the contract to the engineer for approval.

5.01 Site Clearance



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 352 of 361

Before the commencement of earthwork, the entire area of cutting and filling shall be cleared of all trees, stumps, bushes, grasses, vegetation etc with their roots, fences, logs, rubbish, water, slush etc. It is not necessary to remove all the soil containing fine hair like roots but only the rather heavy mats are to be removed. Cutting of trees shall include trees having girth of any size and removing roots upto a depth of 600mm below the existing ground level or 300mm below the formation level whichever is deeper. After the removal of roots of trees, the pot holes formed shall be filled with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the engineer. The trees shall be cut in to suitable pieces as instructed by the engineer. Before earthwork is started, all the spoils, unserviceable materials and rubbish shall be burnt or removed and disposed off to the approved disposal area(s) as specified by the engineer. Useful materials, saleable timbers, fire woods etc shall be the property of owner and shall be stacked properly at the worksite in a manner as directed by the engineer.

5.02 Setting Out

On receiving the approval from the engineer with modifications and corrections if any, the contractor shall set out the work from the control points furnished by the engineer and fix permanent points and markers for the ease of periodic checking as the work proceeds. These permanent points and markers shall be fixed at the interval as prescribed by the engineer and shall be got checked and certified by the engineer after whom the contractor shall proceed with the work. It should be noted that this checking by the engineer prior to the start of the work will in no way relieve the contractor of his responsibility of carrying out the work to true lines, levels and grades as per the drawings and specification. If any errors are noticed in the contractor's work at any stage, the contractor at his own risk and cost shall rectify the same. The contractor shall take spot levels of the area (with respect to the bench mark/ available source as provided by the engineer) to be excavated or to be filled at an interval of not more than 10m or as directed by the engineer before starting any earth work and shall be submitted to the engineer for prior approval.

5.03 Excavation

Levelling by excavation shall be carried out where the existing ground levels are higher than the specified formation level. Excavation shall include removal of all materials whatever nature as may be and whether wet or dry shall be carried out exactly in accordance with the line, levels, grades and curves shown on the approved drawings and/or as directed by the engineer. All excavations shall be done to the minimum dimensions as required. The contractor shall obtain prior approval of the engineer for the method he proposes to adopt for excavation in different types of strata including dimensions, side slopes and dewatering if any, stacking or disposal etc. This approval however shall not in any way make the engineer responsible for any consequent loss or damage. The excavation must be carried out in the most expeditious and efficient manner. The work shall be carried out in a workmanlike manner without endangering the safety of nearby



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 353 of 361

structures/services or works and without causing hindrance to any other activities in the area. **Prior to starting the excavation, the ground level at the location shall be checked jointly with the engineer.**

The rough excavation may be carried up to a maximum depth of 150mm above the final formation level. The balance shall be excavated with special care and the final surface shall be compacted by rolling with 6 passes of 8 to 10 tonne roller. If directed by the engineer, soft and undesirable spots shall be removed even below the final level. The extra excavation shall be filled up with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the engineer. The contractor shall be paid for the extra excavation and filling at the appropriate items of work.

If the excavation is done to a depth greater than that shown on the drawing or as directed by the engineer due to the contractor's fault, the excess depth shall be filled up to the required level with good earth in 250mm layers (loose thickness) and compacted unless otherwise directed by the engineer at the own risk and cost of the contractor.

Suitable slope in cutting as per the requirements and as directed by the engineer shall be adopted to withhold the face of earth. The contractor shall be held responsible for any damage to any part of the work caused by the collapse of the side of excavations.

5.03.01 Excavation in Hard Rock

Excavation in hard rock shall normally be done with blasting. In case where blasting is prohibited for any reasons, the excavation shall be carried out by chiselling or any other approved method as directed by the engineer. Personnel deployed for rock excavation shall be protected from all hazards such as loose rock/boulder rolling down and from general slips of excavated surfaces.

5.03.02 Blasting

a) General

Storage, handling and use of explosives shall be governed by the current explosive rules/regulations laid down by the Central and the State Governments. The contractor shall ensure that these rules/regulations are strictly adhere to. The following instructions are also to be strictly followed and the instructions wherever found in variance with the above said rules/regulations, the former (instructions) shall be superseded with the later (above said rules/regulations).

No child under the age of 16 and no person who is in a state of intoxication shall be allowed to enter the premises where explosives are stored nor they shall be allowed to handle the explosives. The contractor shall obtain licence from the District Authorities for undertaking the blasting work as well as for obtaining and storing the explosives as per Explosives Rules, 1940 corrected upto date.



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 354 of 361

The contractor shall purchase the explosives, fuses, detonators etc only from a licensed dealer and shall be responsible for the safe custody and proper accounting of the explosive materials. The engineer or his authorized representative shall have the access to check the contractor's store of explosives and his accounts at any time. It is the full responsibility of the contractor to transport the explosives as and when required for the work in a safe manner to the work spot.

Further, the engineer may issue modifications, alterations and new instructions to the contractor from time to time. The contractor shall comply with the same without these being made a cause for any extra claim.

b) Materials

All materials such as explosives, detonators, fuses, tamping materials etc proposed to be used in the blasting operation shall have the prior approval of the engineer. Only explosives of approved make and strength are to be used. The fuses known as instantaneous fuse must not be used. The issue of fuse with only one protective coat is prohibited. The fuse shall be sufficiently water resistant as to be unaffected when immersed in water for 30 minutes. The rate of burning of the fuse shall be uniform and shall be not less than 4 seconds per inch of length with 10% tolerance on either side. Before use, the fuse shall be inspected. Moist, damaged or broken ones shall be discarded. When the fuses are in stock for long, the rate of burning of fuses shall be tested before use. The detonators shall be capable of giving an effective blasting of the explosives. Moist and damaged detonators shall be discarded.

c) Storage of Explosives

The current Explosive Rules shall govern the storage of explosives. Explosives shall be stored in a clean, dry and well-ventilated magazine to be specially built for the purpose. Under no circumstances should a magazine be erected within 400m of the actual work site or any source of fire. The space surrounding the magazine shall be fenced and the ground inside shall be kept clear and free from trees, bushes etc. The admission to this fenced space shall be through a single gate only and no person shall be allowed without the permission of the officer-in-charge. The clear space between the fence and the magazine shall not be less than 90m. The magazine shall be well drained. Two lightning conductors, one at each end shall be provided to the magazine. The lightning conductors shall be tested once in every year.

Explosives, fuses and detonators shall each be separately stored. Cases of explosives must be kept clear of the walls and floors for free circulation of air on all sides. Special care shall be taken to keep the floor free from any grains of explosives. Cases containing explosives shall not be opened inside the magazine and the explosives in open cases shall not be received into a magazine. Explosives which appear to be in a damaged or dangerous condition are not to be kept in any magazine but must be removed without delay to a safe



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 355 of 361

distance and be destroyed.

Artificial light, matches, inflammable materials, oily cotton, rag waste and articles liable to spontaneous ignition shall not be allowed inside the magazine. Illumination shall be obtained from an electric storage battery lantern. No smoking shall be allowed within 100m distance from any magazine.

Magazine shoes without nails shall be used while entering the magazine. The persons entering the magazine must put on the magazine shoes which shall be provided at the magazine for this purpose and should be careful

* not to put their feet on the clean floor unless the magazine shoes on.

* not to touch the magazine shoes on ground outside the clean floor.

* not to allow any dirt or grit to fall on the clean floor.

Persons with bare feet shall dip their feet in water before entering the magazine and then step directly from the tub to the clean floor. No person having article of steel or iron with/on him shall be allowed to enter the magazine. Workmen shall be examined before entering the magazine to check none of the prohibited articles are with them. A brush broom shall be kept in the lobby of the magazine for cleaning the magazine. Cleaning shall be done immediately after each occasion whenever the magazine is opened for receipt, delivery or inspection of the explosives.

The mallets, levers, wedges etc for opening the barrels or cases shall be of wood. The cases of explosives are to be carried by hand and shall not be rolled or dragged inside the magazine. Explosives which have been issued and returned to the magazine are to be issued first; otherwise those which have been stored long in the store are to be issued first. Neither the magazine shall be opened nor any person shall be allowed in the vicinity of the magazine during any dust storm or thunderstorm. All magazines shall be officially inspected at definite intervals and a record of such inspections shall be kept.

d) Carriage of Explosives

Detonators and explosives shall be transported separately to the blast site. Explosives shall be kept dry and away from direct rays of the sun, artificial lights, steam pipes or heated metal and other sources of heat. Before explosives are removed, each case or package shall be carefully examined to ascertain that it is properly closed and shows no sign of leakage.

No person except the driver shall be allowed to travel on the vehicle conveying explosives. No explosive shall be transported in a carriage or vessel unless all iron or steel therein the carriage or vessel which are likely to contact the package containing explosives are effectually covered with lead, leather, wood, cloth or any other suitable material. No light shall be carried on the vehicle carrying explosives and no operation connected with the loading, unloading and



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 356 of 361

handling of explosives shall be conducted after sunset.

e) Use of Explosives

The contractor shall appoint an agent who shall personally superintend the firing and all operations connected therewith. The contractor shall satisfy himself that the person so appointed is fully acquainted with his responsibilities.

Holes for charging the explosives shall be drilled with pneumatic drills and the drilling pattern shall be so planned that the rock pieces after blasting will be suitable for handling. The hole diameter shall be of such a size that the cartridges can easily pass down through them and any undue force is not required during charging. Charging operation shall be carried out by or under the personal supervision of the shot firer. Wrappings shall never be removed from the explosive cartridges. Only one cartridge at a time shall be inserted in a hole and wooden rods shall only be used for loading and stemming the shot holes. Only such quantities of explosives as are required for a particular work shall be brought to the work site. Should any surplus remain when all the holes have been charged shall be carefully removed to a point at least 300m away from the firing point.

The authorized shot firer himself shall make all the connections. The shot firing cable shall not be dragged along the ground to avoid any damage to the insulation. The shot firing cable shall be tested each time for its continuity and possible short circuiting. The shot firer shall always carry the exploder handle with him until he is ready to fire shots. The number of shots fired at a time shall not exceed the permissible limits. Before any blasting is carried out it shall be ensured that all workmen, vehicles and equipment on the site are cleared from an area of minimum 300m radius from the firing point or as required by the statutory regulations at least 10 minutes before the time of firing by sounding a warning siren and the area shall be encircled by red flags.

The explosives shall be fired by means of an electric detonator placed inside the cartridge. For simultaneous firing of a number of charges, the electric detonators shall be connected with the exploder through the shot firing cable in a simple series circuit. Due precautions shall be taken to keep the firing circuit insulated from the ground, bare wires, rails, pipes or any other path of stray current etc and keep the lead wires short circuited until it is ready to fire. Any kink in the detonator leading wire shall be avoided. For simultaneous firing of a large number of shot holes, use of cordtex may be done. An electric detonator attached to its side with adhesive tape shall initiate cordtex connecting wire or string. Blasting shall only be carried out at certain specified times to be agreed jointly by the contractor and the engineer.

At least five minutes after the blast has been fired in case of electric firing or as stipulated in the regulations, the authorized shot firer shall return to the blast area and inspect carefully the work and satisfy himself that all the charged holes have exploded. Cases of misfired unexploded charges shall be exploded by



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 357 of 361

drilling a parallel fresh hole at a distance of not less than 600mm from the misfired hole and by exploding a new charge. The authorized shot firer shall be present during the removal of debris as it may contain unexploded explosives near the misfired hole. The workmen shall not return to the site of firing until at least half an hour after firing.

Where blasting is to be carried out in proximity of other structures, controlled blasting by drilling shallow shot holes and proper muffling arrangements with steel plates loaded with sand bags etc shall be used on top of the blast holes to prevent the rock fragments from causing any damage to the adjacent structures and other properties. Adequate safety precautions as per building byelaws, safety codes, statutory regulations etc shall be taken during blasting operations.

5.03.04 Restrictions on Blasting

- a) Blasting which may disturb or endanger the stability, safety or quality of the adjacent structures/foundations shall not be permitted.
- b) Blasting within 200m of a permanent structure or construction work in progress shall not be permitted.
- c) Progressive blasting shall be limited to two third of the total remaining depth of excavation.
- d) No large scale blasting operations will be resorted to when the excavation reaches the last one metre and only small charge preferably black powder may be allowed so as not to shatter the parent rock.
- e) The last blast shall not be more than 0.50 m in depth.
- f) In rocky formations, at locations where specifically indicated or ordered in writing by the engineer, the use of explosives shall be discontinued and excavation shall be completed by chiselling or any other suitable method as approved by the engineer.

5.04 Sorting of Excavated Materials

The excavated material shall be carefully sorted for use in filling the areas in the project site by removing roots, grasses, organic matters and other objectionable materials and be sorted out into different types of materials for use and as directed by the engineer. The excavated material which is not considered fit for filling purpose shall be immediately removed and disposed at such a place and in such a manner as will be directed by the engineer. The material found unusable should be got approved by the engineer before actually disposing it off. The useful materials that cannot be used directly shall be heaped in separate area as stock piles. Stockpiles shall be of regular size as far as possible for ease of measurement. The materials heaped shall be utilised as and when required and as directed by the engineer. The cost of complete item of earthwork includes the cost of rehandling of the materials and temporarily heaped and reused.

5.05 Disposal of Surplus/ Waste Materials



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 358 of 361

Surplus and other waste materials shall be removed and disposed of from the construction site to the area demarcated by the engineer. No material shall be wasted unless approved by the engineer.

5.06 Earth Work in Filling

Levelling by raising with controlled fill of approved excavated/borrowed earth shall be carried out where the existing ground levels are lower than the specified formation level. After clearing site as per clause 5.01, the original ground shall be compacted by rolling subject to a minimum 6 passes of 8 to 10 tonne roller. The approved earth/fill material shall then be spread in horizontal layers not exceeding 300mm in compacted thickness. Each layer shall be watered and thoroughly compacted with proper moisture content and such equipments as may be required to obtain a minimum of 95% of its maximum dry density as determined by standard Proctor's test as per IS: 2720, part-VII. Moisture content of the fill material shall be controlled near optimum moisture content during compaction

The fill material shall be tested for its optimum moisture content and maximum dry density as per IS: 2720, part-VII. Moisture content shall be checked at the source of supply in accordance with IS:2720 part- II and if found less than that required for proper compaction, the same shall be made good either at the source or after spreading the soil in loose thickness for compaction. In the latter case, water shall be sprinkled directly from the hose line or from the truck-mounted water tank etc making due allowance for evaporation losses and the fill material be thoroughly mixed by means of harrows, rotary mixers or by any other suitable approved method until the layer is uniformly wet. **Flooding shall not be permitted for watering purpose under any circumstances.** If the material delivered is too wet, it shall then be dried by aeration and exposure to the sun till the moisture content is suitable for compaction. Should circumstances arise owing to wet weather the moisture content cannot be reduced to the required amount by the above procedure, the work on compaction shall be suspended. Clods or hard lumps of earth shall be broken to have a maximum size of 150mm when being placed in the layers before compaction. For each of the above tests on the fill material, one sample for every 10,000cu.m shall be tested. Additional samples shall be tested whenever there is a change of source or type of material.

Before start of filling, the contractor shall submit the engineer his proposal for the methodology to be adopted for compaction. The compaction equipments as approved by the engineer shall only be employed to compact the different type materials encountered during construction. If directed by the engineer, the contractor shall demonstrate the efficacy of the plant he intends to use by carrying out compaction trials. Moisture content of the fill material shall be controlled near optimum moisture content during compaction.

The compacted layer shall be tested for its dry density as per IS:2720, part-XXVIII or XXIX as directed by the engineer. Samples shall be taken at the rate of one sample for every 10,000sq.m area of each compacted layer. In addition



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 359 of 361

random checks shall be carried out in compacted layers by means of Proctor needle penetration test. Contractor shall submit all the test results to the engineer immediately after completion of the tests. A sample shall be deemed to have passed the test when the dry density of the compacted fill is equal to or more than 95% of its maximum dry density. When field density measurements reveal any soft areas in the fills, further compaction shall be carried out as directed by the engineer. If in spite of that, the specified compaction is not achieved, the material in the soft areas shall be replaced with approved material compacted to the density requirements and satisfaction of the engineer.

Subsequent layers shall be placed only after the finished layer has been tested and accepted by the engineer.

Where the filling is to be done across low swampy ground that will not support the weight of trucks or other hauling equipments, the lower part of the fill shall be constructed by dumping successive loads in a uniformly distributed layer of a thickness not greater than that necessary to support the hauling equipment while placing subsequent layers.

5.07 Dewatering and Drainage

It shall be ensured that the area to be excavated/filled shall be free from water. The contractor shall remove the water (if any) by pumping or by any other means as approved by the engineer. At all times, the surface of cutting/filling during execution shall be maintained at such a cross fall as will shed water and prevent ponding. All existing drains/channels (if any) in the work area shall be suitably diverted by the contractor before taking up any excavation or filling. These diversions shall be such that it shall ensure effective disposal of water without any accumulation or flooding within the project site and in adjoining areas.

5.08 Finishing Operations

Finishing operation shall include the work of shaping and dressing the excavated/filled ground to the required grades, levels, lines, side slopes, cross-sections and dimensions as shown on the approved drawings or as directed by the engineer.

5.09 Turfing

Turfing shall be provided at the slopes and other locations as shown on the drawings or as directed by the engineer. The turf shall be of approved quality of grass. The sod shall consist of dense, well rooted growth of permanent and desirable grasses indigenous to the locality where it is to be used and shall be practically free from weeds or other undesirable matter. The grass on the sod shall have a length of approximately 50mm and the sod shall be free of any debris. Thickness of the sod shall be as uniform as possible with 50 to 80mm of soil covering the grass roots depending on the nature of the sod so that all the



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 360 of 361

dense root system of the grasses are retained in the sod strip. The sods shall be cut in rectangular strips of uniform width not less than about 300mm x 250mm size but not so large so that it is convenient to handle and transport without damage.

The area to be sodded shall be previously constructed to the required slope and cross section. Prior to placing the sods, the slopes shall be **roughened** and wetted in order to have a satisfactory bond. The strips of sod shall be laid in close contact with each other and be tamped firmly in place so as to fill and close the joints between them. The turfing so laid shall be well watered and protected until final acceptance.

5.10 Approaches

The contractor shall provide proper approaches for workmen and inspection.

5.11 Lighting

Full scale lighting are to be provided if night work is permitted or directed by the engineer. If no night work is in progress, red warning lights should be provided at the edges of excavations and fills.

6.00 RATES AND MEASUREMENTS

6.01 Rates

a) The item of work in the schedule of quantities describe the work very briefly. The various items of the schedule of quantities shall be read in conjunction with the corresponding sections in the technical specification including amendments and additions if any. For each item in the schedule of quantities, the bidder's rate shall include all the activities covered in the description of the items as well as for all necessary operations in detail as described in the technical specification.

b) No claims shall be entertained if the details shown on the released for construction drawings differ in any way from those shown on the tender drawings.

c) The unit rate quoted shall include minor details which are obviously and fairly intended and which may not have been included in these documents but are essential for the satisfactory completion of the work.

a) The bidder's quoted rate shall be inclusive of supplying and providing all labour, men, materials, equipments, tools and plants, supervision, services, approaches, schemes etc.

6.02 Measurements



**TITLE: - 4x270 MW BHADRADRI TPS
SPECIFICATIONS FOR CIVIL, STRUCTURAL
AND ARCHITECTURAL WORKS FOR
POWER BLOCK CIVIL WORKS**

SPECIFICATION NO. PE-TS-411-600-C001

SECTION- D

REV.NO. 00 DATE: 09/04/2015

SHEET Page 361 of 361

Method of measurements are specified in the proceeding sections. Where not so specified, the latest version of IS:1200, Part-1 shall be applicable.

a) The length, breadth and depth shall be measured correct to the nearest centimetre if measurements are taken by tape. Rounding of numericals shall be as per relevant IS Codes. If the measurements are taken with staff and level, the levels shall be recorded correct to 5mm. The area and volume shall be worked out in square meter and cubic meter correct to the nearest of two decimal places.

b) For earth work in excavation, the ground levels shall be taken before and after completion of the work in the actually excavated area. The quantity of earth work in cutting shall be computed from these levels in cubic meter.

c) Where soft rock and hard rock are mixed, the measurement shall be done as follows. The two types of rock shall be stacked separately and measured in stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in the stacks. If the sum of net quantity of the two types of rock so arrived exceeds the total quantity of excavation then the quantity of each type of rock shall be worked out from the total quantity (from excavation) in the ratio of net quantities in stack measurements of the two types of rock. If stacking is not feasible, the method as suggested by the engineer shall be followed.

d) Where soil, soft rock and hard rock are mixed, the measurement shall be done as follows. The soft and hard rock shall be removed from the excavated material and stacked separately and measured in stacks. The net quantity of each type of rock shall be so arrived by applying a deduction of 50% for looseness/voids in stacks. The difference between the entire excavation and the sum of the quantities of soft and hard rocks so arrived shall be taken as soil.

e) For earth work in filling, the actual measurements of fill shall be calculated by taking levels of the original ground before start of the work but after site clearance and after compaction of fills. The quantity of earth work in filling shall be computed from these levels in cubic meter.

f) For turfing, the measurement shall be made on the finished work in square meter.




TABLE	
FACILITY	DESCRIPTION OF FACILITIES
1.0	MAIN PLANT AREA
1.1	SWITCH YARD
1.2	TRANSFORMER YARD
1.3	TURBINE BUILDING
1.4	BOILER
1.5	ESP
1.6	ESP CONTROL ROOM
1.7	CHIMNEY
1.8	SPACE FOR FGD
1.9	IA & SA COMPRESSOR HOUSE
2.0	WATER SYSTEM
2.1	RAW WATER RESERVOIR
2.2	RAW WATER PUMP HOUSE
2.3	PT PLANT
2.4	DM PLANT
2.5	NDCT
2.6	CW PUMP AREA
2.7	CW CHLORINATION PLANT FOR CW SYSTEM
2.8	CW TREATMENT PLANT FOR CW SYSTEM
2.9	DELETED
2.10	CLARIFIED WATER STORAGE TANK & PUMP HOUSE
2.11	EFFLUENT TREATMENT PLANT
2.12	CHEMICAL LAB
2.13	SEWAGE TREATMENT PLANT
2.14	DM TANKS & DM TRANSFER PUMPS
2.15	CONDENSATE STORAGE TANKS AND CONDENSER MAKE UP & BOILER FILL PUMPS
3.0	FUEL OIL SYSTEM
3.1	FUEL OIL UNLOADING TRENCH
3.2	FUEL OIL UNLOADING AND PRESSURISING PUMP HOUSE
3.3	FUEL OIL STORAGE TANK AREA
3.4	FUEL OIL FORWARDING PUMP HOUSE
4.0	COAL HANDLING PLANT
4.1	WAGON TIPPLER
4.2	CRUSHER HOUSE
4.3	CRUSHED COAL STOCKPILE
4.4	CHP CONTROL ROOM
4.5	STACKER RECLAIMER
4.6	TRANSFER POINT (TP)
4.7	PENT HOUSE (PH)
4.8	COAL BELT CONVEYOR
4.9	DUST SUPPRESSION PUMP HOUSE
5.0	ASH HANDLING PLANT
5.1	FLY ASH SILOS
5.2	ASH SLURRY PIMP HOUSE
5.3	ASH WATER PUMP HOUSE
5.4	AHP CLARIFIER
5.5	AHP VACUUM CUM COMPRESSOR HOUSE
5.6	AHP VACUUM PUMP HOUSE – ADDED
5.7	SILO UTILITY BUILDING
6.0	NON – PLANT BUILDING
6.1	ADMN. BUILDING
6.2	CANTEEN
6.3	FIRE STATION
6.4	MAIN GATE
6.5	SERVICE BUILDING
6.6	DELETED

LEGENDS:

- Area Boundary
- Road
- River, Stream
- DGPS Point
with MSL Level
in Metres
- Village
- Pipe/Cable Rack
-

NOTES:-

1. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.
2. ASH DYKE LOCATION CONSIDERED IN BLOCK-II AS PER DESEIN PLOT PLAN 111-29-0200 R1 DT. 31.12.14 RECD. VIDE MAIL DTD. 09.01.15.

FOR TENDER PURPOSE ONLY

CUSTOMER				TELANGANA STATE POWER GENERATION CO. LTD.	
CUSTOMER'S CONSULTANT				DESEIN CONSULTING ENGINEERS NEW DELHI	
JOB No. K27		STATUS PROPOSAL		4X270 MW MANUGURU TPP	
DISTRIBUTION		TO		BHARAT HEAVY ELECTRICALS LTD	
REV		DATE		DATE	
P01 15.01.15		ALTD RK		CHD LKJ	
APPD SPV		APPD SPV		APPD SPV	
1. WIND ROSE, ROADS & SPACES FOR FABRICATION YARD MARKED		2. FACILITIES 2.7, 2.8, 5.2, 5.3 & 5.4 RELOCATED		3. FACILITY 2.9 & 6.4 DELETED	
4. INCH LOCATIONS AND CH CHANNELS		5. DO BLOCKS, AIR WASHERS & CENTRAL		6. RAW RESERVOIR CAPACITY UPDATED.	
TITLE		PLOT PLAN		SCALE: 3000	
MPL C MSE I MAX E		DEPT. SIGN		DRAWING No. PE-DG-K27-100-M001	
SHEET 1 OF 1		REV P01		SIZE-A0	